

# The Chemical Formulary


A Collection of Valuable, Timely, Practical Commercial Formulae and Recipes for Making Thousands of Products in Many Fields of Industry

VOLUME VI

Editor-in-Chief

H. BENNET





1943

CHEMICAL PUBLISHING CO., INC. 212 FIFTH AVENUE New YORK 10, N. Y.

COPYRIGHT, 1943, BY H. BENNETT

145813

#### EDITOR-IN-CHIEF

#### H. BENNETT

#### BOARD OF EDITORS

Abbott, H. M. Baird, William D. Beretvas, H. M. Degering, Ed. F. De Ment, J. Dixon, T. G. Evans, H. A. Fellner, J. I. Forchheimer, Paul Fowler, Henry French, Dudley K. Fromm, F. Greenbaum, F. R. Gutkin, S. S. Harriman, Benjamin R. Hecht, M. H. Hershey, J. Willard Hinterleitner, Ernest J. Hofmann, M. P. Holman, Emmette R. Jacobson, C. A. Jones, Hilton Ira Kilbourne, Jr., F. L. Kingman, W. A. Klein, Hugo Kneeland, D. R. Leistner, W. E. Lermer, H. B. Levitt, Leonard S. Liger, Andrew W. Lowen, L. Maglio, M. Martin Mark, H.

Century Stearic Acid Candle Wks., Inc American Aniline Products, Inc. Nox-Rust Corp. Purdue University The Mineralogist Pratt Institute S. B. Penick Co. Block Drug Co. F. N. Chemical Mfg. Co. Agfa Ansco Co. Chemical Consultant Polytechnic Inst. of Puerto Rico McNeil Laboratories Falk & Co. Agfa Ansco Co. Atlas Mineral Products Co. McPherson College U. S. War Production Board C. O. Bartlett & Snow Co. Turco Products, Inc. West Virginia University Hizone Products Co. Xylos Rubber Co. Paper Consultant Charles Bruning Co., Inc. Bates Mfg. Co. Vulcan Proofing Co. Celluplastic Corp. Glyco Products Co., Inc. Battelle Memorial Institute United States Rubber Co. St. John's University Polytechnic Institute of Brooklyn

Marlies, Charles A. Marquardt, J. C. Mathers, Frank C. Matlin, D. R. McGreal, Martin E. Mendelsohn, Simon Mertle, J. S. Metro. Francis G. Munch, James C. Olsen, Allan B. Oesterreich, Kurt Orthmann, August C. Ott, Ludwig F. Quait, R. L. Rasch, Carl H. Ratay, Stephen Rázim, W. Wendel Rice, H. L. Robertson, G. Ross Robson, J. T. Rooney, John T. Rudd, J. F. Rutstein, Leo Schnidman, Louis Schulman, William Schuyler, W. H. Seymour, R. B. Shoub, H. Louis and Earl, P. Siever, Charles M. Silleck, C. F. Simpson, J. E. Sklarew, Samuel Sobel, M. Merlub Stewart, Jeffrey R. Thorp, C. E. Tormey, H. J. Van Heeden, Arthur Weingart, G. W. Werner, Jesse Werthan, S. Williams, H. R. Zabel, Herman W.

Cornell University Indiana University Hydroponics Consultant St. John's University Consulting Chemist Internat'l Photo-Engravers' Union Chemical Consultant Temple University H. M. Storms Co. Duro-Test Corp. Orthmann Laboratories, Inc. Titeflex Metal Hose Co. Limestone Prod. Corp. of America Riverside Chemical Co., Inc. Chemist U. S. Army Medical Corps Plastics Chemist University of California Ferro Enamel Corp. Spencer Lens Co. Rudd Lacquer Corp. Rutstein Laboratory & Library Rochester Gas & Elec. Corp. L. Sonneborn & Sons, Inc. Bucknell University Monsanto Chemical Co. Shoub Laboratories Consulting Pharmacist C. J. Osborn Co. Chemical Consultant Ralph L. Evans Associates Virginia-Carolina Chem. Corp. Stewart Research Laboratory Armour Research Foundation St. Bonaventure College Consulting Chemist Pyrotechnic Consultant General Aniline & Film Corp. N. J. Zinc Co. Fusion Engineering Co. Kansas State College

College of the City of New York

#### PREFACE

Chemistry as taught in our schools and colleges is confined to synthesis, analysis and engineering—and properly so. It is part of the proper foundation for the education of the chemist.

Many a chemist on entering an industry soon finds that the bulk of the products manufactured by his concern are not synthetic or definite chemical compounds but are mixtures, blends or highly complex compounds of which he knows little or nothing. The literature in this field, if any, may be meagre, scattered or antiquated.

Even chemists, with years of experience in one or more industries, spend considerable time and effort in acquainting themselves on entering a new field. Consulting chemists, similarly, have problems brought to them from industries foreign to them. A definite need has existed for an up-to-date compilation of formulae for chemical compounding and treatment. Since the fields to be covered are many and varied, an editorial board was formed, composed of chemists and engineers in many industries.

Many publications, laboratories, manufacturing companies and individuals have been drawn upon to obtain the latest and best information. It is felt that the formulae given in this volume will save chemists and allied workers much time and effort.


Manufacturers and sellers of chemicals will find in these formulae new uses for their products. Non-chemical executives, professional men and others, who may be interested, will gain from this volume a "speaking acquaintance" with products which they may be using, trying, or with which they are in contact.

It often happens that two individuals using the same ingredients in the same formula get different results. This may be the result of slight deviations or unfamiliarity with the intricacies of a new technique. Accordingly, repeated experiments may be necessary to get the best results. Although many of the formulae given are being used commercially many have been taken from patent specifications and the literature. Since these sources are often subject to various errors and omissions, due regard must be given to this factor. Wherever possible it is advisable to consult with other chemists or technical workers regarding commercial production. This will save time and money and avoid "headaches."

It is seldom that any formula will give exactly the results which one requires. Formulae are useful as starting points from which to work out one's own ideas. Formulae very often give us ideas which may help us in our specific problems. In a compilation of this kind errors of omission, commission and printing may occur. We shall be glad to receive any constructive criticism in this, our first attempt.

To the layman, it is suggested that he arrange for the services of a chemist or technical worker familiar with the specific field in which he is interested. Although this involves an expense it will insure quicker and better formulation without wastage of time and materials.

H. BENNETT



#### PREFACE TO VOLUME VI

Additional new formulae have been gathered to compile a sixth volume of the Chemical Formulary—an addition which will broaden and bring up-to-date the contents of volumes I, II, III, IV and V. Because the board of editors feels that information of this nature, to be most helpful, should be released as soon as possible and since we have had hundreds of inquiries as to when Volume VI would be ready, an early publication date was decided upon.

Special elementary formulae of direct and indirect military interest have been included. A chapter on substitutes for scarce materials is an innovation which may

be of interest and use to many.

Schools and colleges in increasing numbers seem to find it advisable to use the *Chemical Formulary* as an aid in promoting a practical interest in chemistry. By its use, students learn to make cosmetics, inks, polishes, insecticides, paints and countless other products. The result is that chemistry becomes an extremely interesting practical and useful subject. This interest often continues even when the students reach the theoretical or more difficult phases of this subject.

Since some mature users of this book have not had the good fortune to have had previous training or experience in the art of chemical compounding, the simple introductory chapter of directions and advice has been repeated. This chapter should be studied carefully by all beginners (and some more experienced workers) and some of the preparations given therein should be made before attempting to duplicate the more complex formulae in the succeeding chapters.


An enlarged directory of sources of chemicals and supplies has been added. This should prove useful in locating new as well as old materials and products.

It is a sincere pleasure to acknowledge the valuable assistance of the members of the board of editors and others who have given of their time and knowledge in contributing the special formulae which have made this volume possible.

H. BENNETT

#### NOTE

All the formulae in volumes I, II, III, IV, V and VI (except in the introduction) are different. Thus, if you do not find what you are looking for in this volume, you may find it in one of the others.



# TABLE OF CONTENTS

																PAGE
Preface		•	•	•		•	•		•	•	•	•		•	•	vii
PREFACE	TO Vo	LUM	e V	Ι			a					•				ix
ABBREVIA	ATIONS						•					•				xix
I.	INTRO	DUCT	ION		•		•		٠.							1
II.	Adhe	SIVES														19
11.	1. V Flee "Ce sive sive Adh hesi Glu Wa 2. V Ruh Alk mer "Vi Cen "Hy tum hesi mer Cen	Water wible lloph; End of the sive; End of the sive; Timesive; Eng Gland Water bear ali-Pat; Varament; Varament; transfer cen Cove; It; I neent;	r "S Glanne livelo n Pe e; M Littl lue; r "I Cem e" ( Ce em e Co Lum Pip	lues " A ppe aste Aeta nogr e G Ins nso nent f A um Cem eent; npo ino oe-I	; I Adhee Adh; Draph Craph lue; Circum dhee; Oi dhee Cent; Wo sitin us Leak	esive nesive ry F an S ers' Ber nent e" 1-W Sive; ment Ni: Ni: Ceme Ther odjo g C Adh Cer	; Ce; Seaste Sea	Solonoscoloristas de la colorista de la colori	ent; ent; ent; ent; ent; ent; ent; ent;	Tr.	ansp ; Pl; of S Past ton ary d-P esiv Rub nent tain ient La id t Pa	pare ywo deal; ywo deal; Ce; Clu Pass rooffre; Cer L; Rimin o V ste; Cem	nt od Pr slas le; ste; Ce Boa Ce ross Adh ubb atin Voo R eent	Adhhadhaessur Sa Ac Tuk Nor Memen s-Ha desive er-B ag Ac do Co oofin ; Syr	t;-t;riig-	19
	Gla Pap nesi Adh	ic R ss to er to um lesive vas er.	Me Al Putte; C	tal ( umi ty; <del>l</del> as-	Cem num Cau Tigl	ent; Ad ilkin nt V	Chi hesi g C	loro ve; com; e Se	pren "Ba posi eal;	ie to akeli tion : Vac	Me te" Couun	tal A Put ork n T	Adh ty; to ube	esive Mag Meta Sea	e; g- al l;	
III.	Win	AGES les; S s; Fr	tab uit,	Ve	egeta	able	ors;	Fla d B	vors	s; No Ju	on-A ices	alcol ; S	holi tora	c Fla ige (	i- of	32

PAGE 40

#### IV. COSMETICS AND DRUGS

Cosmetic Creams; Cold Cream; "Nourishing" Creams; Liquid Cream; Medicated Cream; Antiseptic Cream; Foundation Cream; Vanishing Cream; Beauty Mask; Skin Protectives; Blemish Covering Cream; Hand Lotion; Face Lotion; Astringent; Baby Skin Oil; Sunburn Preparations; Liquid Powder; Face Powder; Sun Tans; Rouge; Lip-Stick; Eye Lotion; Mascara; Nail Lacquer; Nail Wax; Nail Polish Remover; Bath Salt; Deodorants; Foaming Bath Powder; Baby Powder; Aromatic Waters; Synthetic Flower Perfumes: Solidified Perfume: Cosmetic Stockings; Hair "Tonic"; Hair Lacquer; Hair Cream; Wave-Sets; Permanent Waving Compounds; Kinky Hair Straightener; Hair Waving Pads; Hair Dyes; Hair Dye Remover; Shampoo; Depilatories; Brushless Shaving Cream; After Shave Lotion; Tooth Paste; Tooth Powder; Denture Cleaner; Gum Massage Lotion; Mouth Wash; Throat Gargle; Nasal Preparations; Ear Drops; Eye Preparations; Toothache Drops; Poultice; Poison-Gas Protectives; Ointment Base; Ringworm and Athlete's Foot Remedies; Dermatitis Preparations; Poison-Ivy Remedies; Calamine Lotion; Burn Treatments; Sulfanilamide and Sulfathiazole Preparations; Corn Remedies; Salves; Acne Lotion; Scabies Treatments; Suppositories; Liniments; Hay-Fever; Asthma and Hiccup Treatments; Pectin Preparations; Enteric Coatings: Tablet Binders: Polishes and Lubricants: Prophylactic Capsule; Activated Carbon Tablet; Improved Aspirin Tablet; Antiacid and Anthelmintic Tablets; Cod Liver Oil, Mineral Oil and Pine Needle Oil Emulsions: Cocoa Butter Substitute: Barium X-Rav Meal; Quick-Setting Plaster of Paris; Waterproof Bandage; Adhesive Tape Remover; Hemostatic; Mothproofing; Mosquito and other Insect Repellents and Bite Remedies; Silverfish Poison; Cesspool Deodorant; Disinfectants; Antiseptics; Embalming Preparations; Iodized Oils; Special Pharmaceuticals.

#### V. Emulsions

84

Santowax; Synthetic Wax; Paraffin Wax; Candelilla Wax; Carnauba Wax; Fruit-Coating; Agricultural Spray; Plant Growth Stimulant; Acid Stable; Salt Stable; Sulfathiazole; Anise Oil; Castor Oil; Kerosene; Toluol; Mineral Oil; Sesame Oil; Die-Lubricating Copper Naphthenate; Lime Stable; Benzene; Synthetic Resin;

PAGE	Cumar; Natural Resin; Resin-Wax; Rosin; Cleaning Base; Waterproofing; Lacquer; Soluble and Miscible Oils; Demulsifiers.	
95	FARM AND GARDEN SPECIALTIES	VI.
119	FOOD PRODUCTS	VII.
	Candies; Fruit Candies; Marshmallow; Chewing-Gum Base; Fudge Sauce and Icing; Bread; Noodles; Doughnut Glaze; Cup-Cakes; Pie-Dough; Waffle-Mix; Cake Icings; Pie; Fruit Purees; Ice-Cream; Artificial Cream; Cream Neutralizer; Butter, High Melting; Smoked Cheese; Process Cheese Spreads; Italian Cheeses; Cheddar Cheese; Cream Cheese; Cheese Mold Control; Smoked Poultry; Poultry Pickle; Meat Curing Brine; Army Ration; Dill Pickles; Free-Flowing Salt; Artificial Cinnamon; Curry Powder; Spice Oils; Mayonnaise; Salad Dressings; Fruit Bars; Fruit Cereal; Preserve Thickener; Fruit Juice Clarifier; Sulphured Fruits; Nuts, Preparing; Sauerkraut; Marking Foods and Beverages.	
. 151		VIII.
	Tanning: Vegetable; Chrome; Preparing Sheepskins; Dehairing Powder; Fat Liquor; Deglazing; Degreasing; Waterproofing; Dyeing; Coloring and Finishing; Flu-	
• ;	orescent Leather; Artificial Leather; Bleaching and Dyeing Feathers; Horsehair and Bristles; Sterilizing; Bleaching; Softening; Straightening; Lustering (Glazing) and Carroting for Furs.	
;	Carbon Paper; Typewriter Ribbons; Stamp-Pad; Meat- Stamping. Printing Inks: Aqueous, Thermosetting	IX.
<b>-</b> ; -	Heliogravure; Rotogravure; Textile; Intaglio; Thermoplastic (Raised); White; Indelible; Marking; Invisible Textile; Silk-Screen; Fluorescent; Glass; Glass Crayon	
<b>-</b> S	Textile; Silk-Screen, Findrescent, Class, Glass Grayon; Textile Crayon; Cattle Marking Crayon; Metal Etching; Fluorescent Crayon; Erasable Crayon; Tailor's Crayon; Magic Writing Pad; Stencil-Sheet; Ink Eradicator	

	P.	AGE.
		182
X.	Lubricants: Wood and Fiber; Driving Journal; Diesel Lubricants: Wood and Fiber; Driving Journal; Glass Engine; Chassis; Gyroscope Bearing; Dental; Glass Mold; Die Member; Drawing Die; Metal Working; Non-Gumming; Strip Steel Rolling; Pipe-Thread; Anti-Freeze; Rustproofing Grease; Stop-Cock; Hydraulic Fluids; Belt Dressing; Cutting Oils; Soluble Oils; Flushing Oil; Slushing Oil; Sticky Oil; Drying Oil; Harness Oil; Well Drilling Fluids; Dubbing (Leather); Petroleum Jelly; Bleaching Oils and Fats.	
	- CONCERNICATION	188
XI.	C Duogonting, Hillorescent, Otaco.	
	Acid Resistant Flux; Infra-Red Absoluting, Adhesions; Ce-	
	ment Floor; Wall; Glazed Brick. The Artificial Mar-	
	Fire-Brick; Cement; Refractiones. Stone: Plaster: Quick ble; Chemically Resistant Machinable. Plaster: Quick Setting;	
	ble; Chemically Resistant Machinable. Pauck Setting; Drying; Building; Fluorescent. Cement: Quick Setting. Concrete: Quick Set-	
	Drying; Building; Fluorescent. Commerce Quick Set- Light Weight; Retarded Setting. Concrete: Quick Set- Light Weight; Retarded Setting. Fluorescent. Floor Hardeners.	
	Light Weight; Retarded Setting. Concrete. Quick String; Porous; Coating; Fluorescent Floor Hardeners.  Miscellaneous: Roofing Compositions; Furnace Patch-	
	ing; Repairing Textured Walls.	
		19
XII	- Cuntago Treatments, Libring	
	Magnesium Die Casting Surface Treasmony, Silver; Stainless Steel and Nickel Alloys; Dyeing Silver; Brass Bronze, Phos-	
	Aluminum; Coloring Aluminum, Brass Bronze, Lead phor Bronze, Chromium, Lead, Nickel, Copper, Lead phor Bronze, Chromium, Bronze Powder Effect; Bright	, -
	Nickel Silver, 1111, 21110, Blooms Rluing: Blackening	;
	Cleaning Lead; Stripping Solutions, Stripping Solut	•
	Copper, Brass, Molybdenum Bronze, Cadmida, Vickel, Platinur	á
	Gold, Iron, Lead, Aluminum, Zinc, Works, and Tin Plating; Plating Non-Conductors; Electrand Tin Plating; Provention: Rust Removers; Tar	0
	and Tin Plating; Plating Roll Conductory, Polishing; Corrosion Prevention; Rust Removers; Tar	`
	nish Inhibitors; Casting Molds, Cole Binders, Solderin	g,
	nish Inhibitors; Casting Moids, Colo Bladers; Solderin ing and Tempering; Carburizing; Solders; Solderin Brazing and Welding Fluxes; Welding Rods; Anodizing Brazing and Welding Fluxes; Welding Rods; Harder and Fluxe Alloys; Harder	g
	Brazing and Welding Fluxes, Woltan Alloys; Harder Aluminum; Electrical Contact and Fuse Alloys; Harder Aluminum; Tin Follows Metal Regring; Tin Follows	1- 1-
	ing Copper; Lead Shot. Porous Metal Bearing. Cutting	ng
	ing Copper; Lead Shot. Porous Metal Bearing, Gold Colored, Magnet, Dental Alloys; Cutting Bearing, Gold Colored, Magnet, Dental Alloys; Cutting Cold Steel; Descaling; Passivation; Reclaiming Gold Steel; Passivation; Reclaiming Gold Steel; Passivation;	ld
	Cold Steel; Descaining, Lassivation, and Type Metal Scrap.	
	and Typo Alectronic	

PAGE 254

XIII. PAINT, VARNISH, LACQUER AND OTHER COATINGS .

Paints: Traffic; Fire-Retardant; Waterproof; Chemical Resisting (Alkali, Acid, Salt); Metal Priming; Metal Finishing; Heat Resistant; Aluminum; Galvanized Iron; Tin; Rust Preventive; Ship-Bottom; Naval; Canvas: Wood Tank: Deck: Asbestos: Shingle: House (Exterior and Interior); Fume Proof; Wood Priming; Flat; Self Priming; Glossy; Cement; Stipple; White Lead; Architectural; Blackout; Camouflage; Luminous; Calcimine Coater; Masking. Painting: Farm Implements; Floors; Plywood; Plaster Statues; Over Tar; Asphalt and Creosote; Linoleum; Golf Balls; Glass Phonograph Records; Damp Surfaces. Pigments: Camouflage; Fluorescent; Enamel; Suspending. Enamels: Porcelain Patching; Floor; Wall; Non-Yellowing; Outdoor; Insulating; Gloss; Automobile; Semi-Gloss. Water Paints: Shellac; Silicate; Resin Emulsion; White Wash; Casein. Varnishes: Bodying; Vehicle; Metal; Floor; Mixing; Phenolic Resin; Oiticica; Quick Drying; Furniture, Rubbing; Baking; Spar; Flat; Paper; Casket; Piano; Shellac. Coatings: Alcohol Resistant; Beer Can; Pipe; Metal; Air-Filter; Electric Cable; Wrinkle; Concrete; Anti-Corrosive; Pre-Painting; Wood. Oils: Paint; Grinding; Bodied; Limed Rosin; Honey; Gloss. Finishes: Limed Oak; Fumed Oak; Weathered Wood; Frosted; Suede (Flock); Wrinkle. Lacquers: Oxidized Brass; Wood; Rubbing; Furniture; Fluorescent; Glass Fiber; Glue; Spraying; Pigmented; Airplane; Paper; Artificial Leather; Pyroxylin; Polyvinyl Acetal Acetate; Nitro-Starch; Cellulose Acetate; Ethyl Cellulose; Finger-Nail; Solvent Resistant; Thinners (Solvents); Plasticizer. Miscellaneous: Removers (Paint; Varnish); Crack-Filler; Wood Sealer; Preserving Fence Posts and Adobe: Fireproof Plaster; Plaster Primer; Abrasive Surface; Pipe Thread Compound; Decalcomania; Transparent Films; Driers; Shellac Substitute; Dibutyl Phthalate Substitute.

XIV. PAPER.

Grease-Proof; Alkali-Resistant; Waterproof; Moisture-Proof; Insect Proof; Pest Proof; Casein Coating; Emulsion Coating; Sizing; Fluorescent; Waxed; Adhesive; Milk Container; Translucent; Board; Stereotype Mat; Softener; Deciphering Charred.

333

		PAGE
XV.	Photography	339
XVI.	Polishes and Abrasives	39 )
XVII.	Pyrotechnics and Explosives	418
XVIII.	Rubber: From Plants; Powdered; Preserving; Reconditioning; Gears; Substitutes; Reclaiming; Artificial Latex; Stabilizer; Golf-Ball Cover; Increasing Adhesion of; Tack Elimination of. Resins: Opaque; Polystyrene; Water-White; Synthetic; Varnish; Can Coating; Adhesive; Heat Stable; Rainproofing. Plastics: Cheap; Self-Hardening; Ethyl Cellulose; Cellulose; Luminous; Optical Lens; Wall Board Coating; Molding; Phonograph Record; Electrical Conducting; Styrene; Phenolic; Shellac Injection Wood. Waxes: Cable Impregnating; Insulating; Sticky; Synthetic; Hard; Slow Burning; Thread; Dental; Carving; Inlay; Engravers; Jewelers; Modeling; Coating. Miscellaneous: Brake-Block; Brake Lining Impregnant; Shoe Filler; Shoe Stiffener; Synthetic Brewers' Pitch; Stuffing Box Packing; Neoprene Gasket; Fiber Board; Flooring Composition; Dental	431
	Impression Composition; Increasing Softening Point of	

PAGE

448

XIX. SOAPS AND CLEANERS . Soap: Transparent; Soft; Liquid; Pectin; Waste Fat; Saddle; Anti-Perspiration; Fluorescent; Pad: Pumice; Soapless; Acid; Non-Gelling; Mechanic's; Hand; Abrasive; Waterless; Laundry. Stain Removers: Household: Dry Cleaners; Non-Inflammable; Acriflavin; Argyrol; Grease; Balsam; Tincture of Benzoin; Carbon; Cement; Chocolate; Cocoa; Coffee; Dye; Fish Oil: Fruit: Gentian Violet; Glue; Grass; Oil; Ichthyol; Indelible Pencil: Printing, Writing, Marking, India Ink; Iodine; Rust; Lacquer; Nail Polish; Lime Soap; Medicine; Mercurochrome; Methylene Blue; Mildew; Mud; Ointment; Paint; Perspiration; Picric Acid; Prontosil; Clay; Tar; Rouge; Scarlet Red; Scorch; Shoe Polish; Silver; Smoke; Tannin; Tea; Verdigris; Water; Textile Mill. Laundry: Bluing; Bleaching; Starch; Gloss. Cleaners: Rug; Shoe; Glove; Dish; Glass; Laboratory Apparatus; Bottle; Window; Dairy Utensil; Porcelein; Marble; Paint; Metal; Mildew; Furniture; Woodwork; Wall; Brush; Floor; Degreasing; Boiler-Tube; Rifle; Cannon; Aircraft; Automobile; Windshield; Engine Carbon; Rust; Watch.

XX. TEXTILES AND FIBERS .

496

Rotproofing; Mothproofing; Mildew Proofing; Fire-proofing; Waterproofing; Crushproofing; Scrooping; Weighting; Stiffening; Non-Sticking; Preserving; Glazing; Refinishing; Immunizing; Non-Shrinking; Metal Coating; Paraffin Coating; Kierboiling; Fluorescent; Conditioning. Identification of: Fibers; Dyes. Sizings: Rayon; Nylon; Thermoplastic; Duck. Desizing: Lustering; Delustering; Bleaching; Scouring; Lubricating; Artificial Velvet. Dyeing: Black-Out; Vegetable; Logwood; Vat; Khaki; Fugitive; Synthetic Wool; Cotton; Bristles. Printing: Paste; Plush; Cotton; Lacquer; Resist; Thickener. Fibers: Making from Casein, Straw; Retting; Softening; Separating.

XXI. MISCELLANEOUS

529

Fireproofing Straw; Water System; Anti-Leak; Anti-Corrosion; Descaling; Anti-Freeze; Stencil Film; Adhesion Prevention; Electrical Resistance; Dielectric Insulation; Electrolytes; Condenser; Dry Cell; Gas Plug; Revivifing Spent Gas Oxide; Non-Dusting Coal; Coloring Coal; Flare Illuminant; Kerosene (Illuminating) Improver; Frosting (Electric Bulb Inside); Engine Carbon Remover; Hydraulic Fluids; Anti-Mist Compounds;

PAGE Acoustic Filler; Protection Against War Chemicals; Air-Raid Glass Protection; Incendiary Bomb Extinguishers; Gun Recoil Fluid; Picture Transfer Fluid; Mimeograph Roll Moistener; Printing Press Static Eliminator; Preventing Printing Offset; Transparentizing Small Animals; Yeast Nutrient; Mash Sterilizer; Culture Medium; Mold Prevention; Killing Algae; Heating Mixture: Boiler Compounds: Water Clarifier. Softener: Well-Drilling Mud; Modeling Composition; Artificial Fish Bait; Temperature Indicating Paper, Solutions; pH Indicator; Printing Plate Activator; Water Resistant Alkali Silicate; Clear Starch Solution; Syrupy Gasoline; Wax Beakers; Artificial Perspiration; Dyeing Ivory Nut, Pearl Buttons; Artificial Gems; Fluorescent Gems: Artificially Fluorescent Minerals, Sand, Stone: Fluorescent Flag, Prospecting Screen, Smoke Thief Detector, Fingerprint Powder, Animals, Mustache, Teeth, Eyes; Dental Investment Composition; Imitation Meerschaum; Stylus; Feather Preservative. XXII Substitutes 554 Chemicals; Cork; Drugs; Dyes; Gums; Metals; Minerals; Oils; Resins; Rubber; Wax. TABLES . 579 References and Acknowledgmen 586 TRADE NAME CHEMICALS 588 CHEMICALS AND SUPPLIES: WHERE TO BUY THEM . 589 SELLERS OF CHEMICALS AND SUPPLIES . 603 Where to Buy Chemicals Outside of United States 613 INDEX 615USEFUL REFERENCE BOOKS . 636

# ABBREVIATIONS

amp
amp./dm <sup>2</sup> amperes per square decimeter
amp./sq. ftamperes per square foot
annydranhydrous
avoiravoirdupois
BéBaumé
b.pboiling point
CCentigrade
°Cdegrees Centigrade
cc. cubic centimeter
c.dcurrent density
cmcentimeter cm <sup>3</sup> cubic centimeter
cm <sup>3</sup> cubic centimeter
concconcentrated
c.pchemically pure
cpscentipoises
cu. ftcubic foot
cu. incubic inch
cwthundredweight
ddensity
dildilute
dm decimeter
dm decimeter dm <sup>2</sup> square decimeter
drdram
EEngler
FFahrenheit
°F degrees Fahrenheit
f.f.cfree from chlorine
f.f.p.afree from prussic acid
fl. drfluid dram
fl. ozfluid ounce
f.pfreezing point
ftfoot
ft.2square foot
ggram
galgallon
grgrain
hl hectoliter
hrhour
ininch
kgkilogram
1liter
lbpound
liqliquid
mmeter
min minute
ml milliliter—cubic centimer
mmmillimeter
m.p
N normal N.F National Formulary
N.FNational Formulary
ozounce
pHhydrogen-ion concentration
p.p.mparts per million
xix

ptpint
pwtpennyweight
q.sa quantity sufficient to make
gtquart
r.p.mrevolutions per minute
S.A.ESociety of Automotive Engineers
sec second
spspirits
sp. grspecific gravity
sq. dmsquare decimeter
tech technical
tinc tincture
trtincture
TwTwaddell
U.S.P United States Pharmacopeia
vvolt
viscviscosity
volvolume
wtweight
S. Ostano

#### CHAPTER I

#### INTRODUCTION

At the suggestion of a number of teachers of chemistry and home economics

the following introductory matter has been included.

The contents of this section are written in a simple way so that anyone, regardless of technical education or experience, can start making simple products without any complicated or expensive machinery. For commercial

productions, however, suitable equipment is necessary.

Chemical specialties en masse are composed of pigments, gums, resins, solvents, oils, greases, fats, waxes, emulsifying agents, water, chemicals of great diversity, dyestuffs, and perfumes. To compound certain of these with some of the others requires certain definite and well-studied procedure, any departure from which will inevitably result in failure. The successful steps are given with the formulas. Follow them explicitly. If the directions require are given with the formulas. Follow them explicitly. If the directions require that A should be added to B, carry this out literally, and not in reverse fashion. In making an emulsion, the job is often quite as tricky as the making of mayonnaise. In making mayonnaise, you add the oil to the egg, slowly, with constant and even and regular stirring. If you do it correctly, you get mayonnaise. If you depart from any of these details: if you add the egg to the oil, or pour the oil in too quickly, or fail to stir regularly, the result is a complete disappointment. The same disappointment might be expected if the prescribed exceedure of any other formula is violated. procedure of any other formula is violated.

The next point in importance is the scrupulous use of the proper ingredients. The next point in importance is the scrupillous use of the proper ingredients. Substitutions are sure to result in inferior quality, if not in complete failure. Use what the formula calls for. If a cheaper product is desired, do not obtain it by substituting a cheaper material for the one prescribed: resort to a different formula. Not infrequently a formula will call for some ingredient which is difficult to obtain: in such cases, either reject the formula or substitute a similar material only after preliminary experiment demonstrates its usability. There is a limit to which this rule may reasonably be extended. In some interaces the substitution of an equivalent ingredient may locitimately. some instances the substitution of an equivalent ingredient may legitimately be made. For example: when the formula calls for white wax (beeswax), yellow wax can be used, if the color of the finished product is a matter of secondary importance. Yellow beeswax can often replace white beeswax, making due allowance for color: but paraffin will not replace beeswax, even though its

light color recommends it above yellow beeswax.

And this leads to the third point: the use of good quality ingredients, and ingredients of the correct quality. Ordinary lanolin is not the same thing as anhydrous lanolin: the replacement of one for the other, weight for weight, will give discouragingly different results. Use exactly what the formula calls for: if you are unacquainted with the material and a doubt arises as to just what is meant, discard the formula and use one that you understand. Buy your materials from reliable sources. Many ingredients are obtainable in a number of different grades: if the formula does not designate the grade, it is understood that the best grade is to be used. Remember that a formula and the directions can tell you only a part of the story. Some skill is often required to attain success. Practice with a small batch in such cases until you are sure of your technique. Many instances can be cited. If the formula calls for steeping your technique, many instances can be cited. If the formula cans for steeping quince seed for 30 minutes in cold water, your duplication of this procedure may produce a mucilage of too thin a consistency. The originator of the formula may have used a fresher grade of seed, or his conception of what "cold" water means may be different from yours. You should have a feeling for the right degree of mucilaginousness, and if steeping the seed for 30 minutes fails to produce it, steep them longer until you get the right kind of mucilage.

If you do not know what the right kind is, you will have to experiment until you find out. Hence the recomme dation to make small experimental batches until successful results are arrived at. Another case is the use of dyestuffs for coloring lotions, and the like. Dyes vary in strength: they are all very powerful in tinting value: it is not always easy to state in quantitative terms how much to use. You must establish the quantity by carefully adding minute quantities until you have the desired tint. Gum tragacanth is one of those products which can give much trouble. It varies widely in solubility and bodying power: the quantity prescribed in the formula may be entirely unsuitable for your grade of tragacanth. Hence a correction is necessary, which can only be made after experiments to determine how much to correct.

In short, if you are completely inexperienced, you can profit greatly by gaining some experience through recourse to experiment. Such products as mouth washes, hair tonics, astringent lotions, need little or no experience, because they are as a rule merely mixtures of simple liquid and solid ingredients, the latter dissolving without difficulty and the whole being a clear solution that is ready for use when mixed. On the other hand, face creams, tooth pastes, lubricating greases, wax polishes, etc., which require relatively elaborate procedure and which depend for their usability on a definite final viscosity, must be made with the exercise of some skill, and not infrequently some experience.

Figuring

Some prefer proportions expressed by weight, volume or in terms of percentages. In different industries and foreign countries various systems of weights and measures are used. For this reason no one set of units could be satisfactory for everyone. Thus divers formulae appear with different units in accordance with their sources of origin. In some cases, parts instead of percentages or weight or volume is designated. On the pages preceding the index, tables of weights and measures are given. These are of use in changing from one system to another. The following examples illustrate typical units:

	Ink for Mark	ing Glass	
Glycerin	40	Ammonium Sulphate	10
Barium Sulphate	15	Oxalic Acid	8
Ammonium Bifluoride	15	Water	12

Here no units are mentioned. When such is the case it is standard practice to use parts by weight, using the same system throughout. Thus here we may use ounces or grams as desired. But if ounces are used for one item then ounces must be the unit for all the other items in the particular formula.

	T. ICVIDIO	z Giue	
Glue, Powdered	30.9 %	Glycerin	5.15%
Sorbitol (85%)	15.45%	Water	48.5 %
Where no units of	weight or volume	but percentages	are given then forge

Where no units of weight or volume but percentages are given then forget the percentages and use the same instructions as given under Example No. 1. Example No. 3

Petrolatum	16 parts	Benzoic Acid	1 part
Coconut Oil Salicylic Acid	12 parts	Chlorthymol	1 part

The same instructions as given under Example No. 1 apply to Example No. 3.

It is not wise in many cases to make up too large a quantity of material until one has first made a number of small batches to first master the necessary technique and also to see whether it is suitable for the particular outlet for which it is intended. Since, in many cases, a formula may be given in proportions as made up on a commercial factory scale, it is advisable to reduce the proportions accordingly. Thus, taking the following formula:

Example No. 4

	*	Neutral Clean	nsing Cream		
	Mineral Oil	80 lb.	Water		90 lb.
	Spermaceti	30 lb.	Glycerin		10 lb.
	Glyceryl Monostearate	e 24 lb.	Perfume		to suit
	Here, instead of pound	is, grams may	be used. Thus	this formula	would then
36	ad:	10 17			

Mineral Oil	80 g.	Water	90 g.
Spermaceti	30 g.	Glycerin	10 g.
Spermaceu	00 g.		10 8.
Glyceryl Monostearate	24 g.	Perfume	to suit
Reduction in hulk may a	lso be obtain	ned by taking th	e same fractional part
or portion of each ingredien	t in a form	la Thus in the f	ollowing formula:
or portion of each mercuich	o in a rormic	na. inas m one i	ono wing rounding.
Example No. 5			
	Vinegar F	ace Lotion	•
Acetic Acid (80%)	20	Alcohol	440
	<b>2</b> 0	Water	500
Glycerin		water	500
Perfume	20		_
We can divide each amo	unt by ten	and the finished	bulk is only 1/10th of
the original formula. Thus	it hogomoge		
the original formula. Thus	it becomes.	47 7 7	44
Acetic Acid (80%)	2	Alcohol	
Glycerin	$\frac{2}{2}$	Water	. 50
	ก		
Perfume			
	Appa	ratus	

For most preparations pots, pans, china and glassware, such as is used in every household, will be satisfactory. For making fine mixtures and emulsions a "malted-milk" mixer or egg-beater is necessary. For weighing, a small, low priced scale should be purchased from a laboratory supply house. For measuring of fluids, glass graduates or measuring glasses may be purchased from your local druggist. Where a thermometer is necessary a chemical thermometer should be obtained from a druggist or chemical supply house.

Methods

To better understand the products which you intend making, it is advisable that you read the complete section covering such products. Very often an important idea is thus gotten. You may learn different methods that may be used and also avoid errors which many beginners are prone to make.

Containers for Compounding Where discoloration or contamination is to be avoided (as in light colored, or food and drug products) it is best to use enameled or earthenware vessels. Aluminum, as well, is highly desirable in such cases but it should not be used with alkalies as the latter dissolve and corrode this metal.

Heating To avoid overheating, it is advisable to use a double boiler when temperatures below 212° F. (temperature of boiling water) will suffice. If a double boiler is not at hand, any pot may be filled with water and the vessel containing the ingredients to be heated is placed therein. The pot may then be heated by any flame without fear of overheating. The water in the pot, however, should be really with the pot, however, should be really with the pot. be replenished from time to time as necessary—it must not be allowed to "go dry." To get uniform higher temperatures, oil, grease or wax is used in the outer container in place of water. Here of course care must be taken to stop heating when thick fumes are given off as these are inflammable. When higher uniform temperatures are necessary, molten lead may be used as a heating medium. Of course, where materials melt uniformly and stirring is possible, direct heating over an even force is provincible. direct heating over an open flame is permissible.

Where instructions indicate working at a certain temperature, it is important that the proper temperature be attained—not by guesswork, but by the use of a thermometer. Deviations from indicated temperatures will usually

result in spoiled preparations. Temperature Measurements

In Great Britain and the United States, the Fahrenheit scale of temperature measurement is used. The temperature of boiling water is 212° Fahrenheit (212° F.); the temperature of melting ice is 32° Fahrenheit (32° F.).

In scientific work and in most foreign countries the Centigrade scale is used. On this scale of temperature measurement, the temperature of boiling water is 100 degrees Centigrade (100° C.) and the temperature of melting ice is 0 degrees Centigrade (0° C.).

The temperature of liquids is measured by a glass thermometer. The latter is inserted as deeply as possible in the liquid and is moved about until the temperature remains steady. It takes a little time for the glass of the thermometer to come to the temperatures of the liquid. The thermometer should not be placed against the bottom or side of the container, but near the center of the liquid in the vessel. Since the glass of the bulb of the thermometer is very thin, it can be broken easily by striking it against any hard surface. A cold thermometer should be warmed gradually (by holding over the surface of a hot liquid) before immersion. Similiarly the hot thermometer when taken out should not be put into cold water suddenly. A sharp change in temperature will often crack the glass.

Ordinary solution (e.g. sugar in water) is hastened by stirring and warming. Where the ingredients are not corrosive, a clean stick, bone or composition fork or spoon is used as a mixing device. These may also be used for mixing thick or spoon is used as a mixing device. These may also be used for mixing thick or spoon is used as a mixing device. These may also be used for mixing thick or spoon is used as a mixing device. These may also be used for mixing thick or spoon is used as a mixing device. These may also be used for mixing thick or spoon is used as a mixing device. These may also be used for mixing thick or spoon is used as a mixing device. These may also be used for mixing thick or spoon is used as a mixing device. These may also be used for mixing thick or spoon is used as a mixing device. These may also be used for mixing thick or spoon is used as a mixing device. These may also be used for mixing thick or spoon is used as a mixing device. These may also be used for mixing thick or spoon is used as a mixing device. These may also be used for mixing thick or spoon is used as a mixing device. These may also be used for mixing thick or spoon is used as a mixing device. These may also be used for mixing thick or spoon is used as a mixing device.

When dirt or undissolved particles are present in a liquid, they are removed by settling or filtering. In the former the solution is allowed to stand and if the particles are heavier than the liquid they will gradually sink to the bottom. The upper liquid may be poured or siphoned off carefully and in some cases is then of sufficient clarity to be used. If, however, the particles do not settle out then of sufficient clarity to be used. If, however, the particles do not settle out then of sufficient clarity to be used. If the particles are coarse they may be filtered or they must be filtered off. If the particles are very small particles then strained through muslin or other cloth. If they are very small particles then scarse filter paper filters rapidly but will not, of course, take out extremely fine Coarse filter paper filters rapidly but will not, of course, take out extremely fine particles. For the latter, it is necessary to use a very fine grade of filter paper. In extreme cases even this paper may not be fine enough. Here it will be necessary to add to the liquid 1-3% of infusorial earth or magnesium carbonate. The sary to add to the liquid 1-3% of infusorial earth or magnesium carbonate. The sary to add to the liquid 1-3% of infusorial earth or magnesium carbonate, able to take the first portions of the filtered liquid and pour them through the filter again as they may develop cloudiness in standing.

Decolorizing

The most commonly used decolorizer is decolorizing carbon. The latter is added to the liquid to the extent of 1-5% and heated with stirring for ½ hour to added to the liquid to the extent of 1-15% and heated with stirring for ½ hour to added to the liquid to the extent of 1-15% and heated with stirring for ½ hour to added to the liquid to the extent of 1-15% and heated with stirring for ½ hour to added to the liquid to the extent of 1-15% and heated with stirring for ½ hour to added to the liquid to the extent of 1-15% and heated with stirring for ½ hour to added to the liquid to the extent of 1-5% and heated with stirring for ½ hour to added to the liquid to the extent of 1-5% and heated with stirring for ½ hour to added to the liquid to the extent of 1-5% and heated with stirring for ½ hour to added to the liquid to the extent of 1-5% and heated with stirring for ½ hour to added to the liquid to the extent of 1-5% and heated with stirring for ½ hour to added to the liquid to the extent of 1-5% and heated with stirring for ½ hour to added to the liquid to the extent of 1-5% and heated with stirring for ½ hour to added to the liquid to the extent of 1-5% and heated with stirring for ½ hour to added to the liquid to the extent of 1-5% and heated with stirring for ½ hour to added to the liquid to the extent of 1-5% and heated with stirring for ½ hour to added to the liquid to the extent of 1-5% and heated with stirring for ½ hour to added to the liquid to the extent of 1-5% and heated with stirring for ½ hour to added to the liquid to the extent of 1-5% and heated with stirring for ½ hour to added to the liquid to the extent of 1-5% and heated with stirring for ½ hour to added to the liquid to the extent of 1-5% and heated with stirring for ½ hour to added to the liquid to the extent of 1-5% and heated with stirring for ½ hour to added to the liquid to the extent of 1-5% and heated with stirring for 1-2% and heated with stirring for 1-2% and heated with stirring for 1-2% and heated with stirring for

Pulverizing and Grinding

Large masses or lumps are first broken up by wrapping in a clean cloth and placing between two boards and pounding with a hammer. The smaller pieces are then pounded again to reduce their size. Finer grinding is done in a mortar with a pestle.

Spoilage and Loss

All containers should be closed when not in use to prevent evaporation or contamination by dust; also because, in some cases, air affects the material adversely. Many materials attack or corrode the metal containers in which they adversely. Many materials attack or corrode the metal containers in which they are received. This is particularly true of liquids. The latter, therefore, should be transferred to glass bottles which should be as full as possible. Corks should be covered with aluminum foil (or dipped in melted paraffin wax when alkalies are present).

Materials such as glue, gums, oilve oil or other vegetable or animal products may ferment or become rancid. This produces discoloration or unpleasant odors. To avoid this, suitable antiseptics or preservatives must be used. Too great stress cannot be placed on cleanliness. All containers must be cleaned thoroughly before use to avoid various complications.

Weighing and Measuring

Since, in most cases, small quantities are to be weighed, it is necessary to get a light scale. Heavy scales should not be used for weighing small amounts as they are not accurate for this type of weighing.

For measuring volume (liquids) measuring glasses or cylinders (graduates) should be used. Since this glassware cracks when heated or cooled suddenly it should not be subjected to sudden changes of temperature.

Caution

Some chemicals are corrosive and poisonous. In many cases they are labeled

as such. As a precautionary measure, it is advised not to smell bottles directly, but only to sniff a few inches from the cork or stopper. Always work in a well ventilated room when handling poisonous or unknown chemicals. If anything is spilled, it should be wiped off and washed away at once.

Where to Buy Chemicals and Apparatus

Many chemicals and most glassware can be purchased from your druggist. A list of suppliers of all products will be found at the end of this book.

ADVICE

This book is the result of co-operation of many chemists and engineers who have given freely of their time and knowledge. It is their business to act as consultants and, for a fee, to give advice on technical matters. As publishers, we do not maintain a laboratory or consulting service to compete with them.

Please, therefore, do not ask us for advice or opinions, but confer with a

chemist in your vicinity.

Extra Reading

Keep up with new developments of new materials and methods by reading technical magazines. Many technical publications are listed under references in the back section of this book.

Calculating Costs

Purchases of raw materials, in small quantities, are naturally higher in price than when bought in large quantities. Commercial prices, as given in the trade papers and catalogs of manufacturers, are for quantities such as barrels, drums or sacks. For example, a pound of epsom salts, bought at retail, may cost 10 or 15 cents. In barrel lots its price today is about 2 to 3 cents per pound.

Typical Costing Calculation Formula for Beer- or Milk Pipe Cleaner

Soda Ash Sodium Perborate

25 lb. @ .02½ per lb. = \$0.63 75 lb. @ .16 per lb. = 12.00

Total 100 lb. Total \$12.63 If 100 lb. cost \$12.63, 1 lb. will cost \$12.63 divided by 100 or about \$0.126 per

lb. for raw materials, assuming no loss.

Always weigh the amount of finished product and use this weight in calculating costs. Most compounding results in some loss of material because of spillage, sticking to apparatus, evaporation, etc. Costs of making experimental lots are always high and should not be used for figuring costs. To meet competition, it is necessary to buy in larger units and costs should be based on the latter.

Elementary Preparations

The recipes that follow have been gotten up in a very simple way. Only one of each type is given so as to avoid confusion. These have been selected because of their importance and because they can be made readily.

The succeeding chapters go into greater detail and give many different types and modifications of these and other recipes for home and commercial

use.

Cleansing Creams

Cleansing creams as the name implies serve as skin cleaners. Their basic ingredients are oils and waxes which are rubbed into the skin. When wiped off they carry off dirt and dead skin. The liquefying type of cleansing cream contains no water and melts or liquefies when rubbed on the skin. To suit different climates and likes and dislikes harder or softer products can be made.

Cleansing Cream (Liquefying)

Melt together with stirring in an aluminum or enamelled dish and allow to cool. Then stir in a dash of perfume oil. Allow to stand until a haziness appears and then pour into jars, which should be allowed to stand undisturbed over night.

Cold Creams

The most important facial cream is cold cream. This type of cream consists of a mineral oil and wax which are emulsified in water with a little borax or glycosterin. The function of a cold cream is to furnish a greasy film which takes up dirt and waste tissue which are removed when the skin is wiped thoroughly. Many modifications of this basic cream are enountered in stores. They vary in color, odor, and

in claims but, essentially, they are no more useful than this simple cream. The latest type of cold cream is the non-greasy cold cream which is of particular interest because it is non-alkaline and therefore non-irritating to sensitive skins.

Cold Cream

Liquid Petrolatum (White 52 g. Mineral Oil) White Beeswax 14 g.

Heat the above in an aluminum or enamelled double boiler (the water in the outer pot should be brought to a boil). In a separate aluminum or enamelled pot dissolve.

Borax 33 c.c. Water and bring this to a boil. Add this in a thin stream, to the melted wax, while stirring vigorously in one direction only, to the melted wax mixture. Use a fork for stirring. When the mixture turns to a smooth thin cream, immerse the bottom of the thermometer in it from time to time, stirring continuously. When the temperature drops to 140° F. add ½ c.c. of perfume oil and continue stirring until the temperature drops to 120° F. At this point pour into jars where the cream will "set" after a while. If a harder cream is desired, reduce the amount of liquid petrolatum. If a softer cream is wanted increase it.

Cold Cream (Non-Greasy) White Paraffin Wax 11/4 oz. Petrolatum (Vaseline) 1½ oz. Glycosterin or Glyceryl 21/4 oz.

Monostearate Liquid Petrolatum (White

Mineral Oil) Heat the above in an aluminum or enamelled double boiler (the water in the outer pot should be boiling). Stir until clear. To this slowly add, while stirring vigorously with a fork,

Water (boiling) Continue stirring until smooth and then add with stirring, a little perfume oil. Pour into jars at 110-130° F. and cover the jars as soon as possible.

Vanishing Creams

Vanishing creams are non-greasy creams, soapy in nature. Some are white and others have a very beautiful pearly appearance. This type of cream depends on its soapiness for its

cleansing character and is useful as a powder base.

Vanishing Cream

Stearic Acid 18 oz. Melt the above in an aluminum or enamelled double boiler (the water in the outer pot must be boiling). To the above add, in a thin stream, while stirring vigorously with a fork, the following boiling solution made in an aluminum or enamelled pot:

Potassium Carbonate 1/4 oz. Glycerin 6½ oz. Water lb.

Continue stirring until the temperature falls to 135° F., then stir in a little perfume oil and stir from time to time until cold. Allow to stand over night and stir again the next day. Pack into jars which should be closed tightly.

Hand Lotions

Hand lotions are usually clear or milky liquids or salves which are useful in protecting the skin from roughness and redness because of exposure to cold, hot water, soap and other materials. "Chapped" hands are a common occurrence. The use of a good hand lotion keeps the skin smooth, soft, and in a normally healthy condition. The lotion is best applied at night, rather freely, and cotton gloves may be worn to prevent soiling. During the day it should be put on sparingly and the excess wiped off.

Hand Lotion (Salve)

Boric Acid 1 oz. Glycerin 6 oz.

Warm the above in an aluminum or enamelled dish and stir with a clean wooden stick until dissolved (clear). Then allow to cool and work into the following mixture with a potato masher, or rounded stick, adding only a little of the above liquid at a time to the mixture below and not adding a further portion until it is fully absorbed.

Lanolin Petrolatum or "Vaseline" If it is desired to impart a pleasant odor to this lotion a little perfume may be added and worked in.

Hand Lotion (Milky Liquid) Lanolin 1/4 teaspoonful Glycosterin or Glyceryl Monostearate

Tincture of

1 0%.

Benzoin 2 oz. Witch Hazel 25 oz.

Melt the first two items together in an aluminum or enamelled double boiler. If no double boiler is at hand improvise one by standing the dish in a small pot containing boiling water. When the mixture becomes clear remove from the double boiler and add slowly, while stirring vigorously with a fork or stick, the tincture of benzoin and then the witch hazel. Continue stirring until cool and then put into one or two large bottles and shake vigorously. The finished lotion is a beautiful milky liquid comparable to the best hand lotions on the market sold at high prices.

Brushless Shaving Creams

Brushless or latherless shaving creams are soapy in nature and do not require lathering or water. The formula given below is of the latest type being free from alkali and non-irritating. It should be borne in mind, however, that certain beards are not softened by this type of cream and require the old-fashioned lathering shaving cream.

Brushless Shaving Cream
White Mineral Oil 10 oz.
Glycosterin or Glyceryl
Monostearate 10 oz.
Water 50 oz.

Heat the first two ingredients together in a pyrex or enamelled dish to 150° F. and into this run slowly, while stirring with a fork, the water which has been heated to boiling. Allow to cool to 105° F. and while stirring add a few drops of perfume oil. Continue stirring until cold.

Mouth Washes

Mouth washes and oral antiseptics are of practically negligible value. Many, however, insist on their use because of their refreshing taste and deodorizing value.

Mouth Wash

Benzoic Acid
Tincture of Rhatany
Alcohol
Peppermint Oil
Just shake together in a dry bottle
until it is dissolved and it is ready.
A teaspoonful is used to a small wineglassful of water.

•

Tooth Powders

Tooth powders depend for their cleansing action on soap and mild abrasives such as precipitated chalk and magnesium carbonate. The antiseptic present is practically of no value. The flavoring ingredients mask the taste of the soap and give the user's mouth a pleasant after-taste.

Tooth Powder	
Magnesium Carbonate	420 g.
Precipitated Chalk	565 g.
Sodium Perborate	55 g.
Sodium Bicarbonate	45 g.
Soap, Powdered White	50 g.
Sugar, Powdered	90 g.
Wintergreen Oil	8 cc
Cinnamon Oil	2 cc.
Menthol	1 g.

Dissolve the last three ingredients together and then rub well into the sugar. Add the soap and perborate mixing in well. Add the chalk with good mixing and then the sodium bicarbonate and magnesium carbonate. Mix thoroughly and sift through a fine wire screen. Keep dry.

Foot Powders

Foot powders consist of a filler such as talc or starch with or without an antiseptic or deodorizer. In the following formula the perborates liberate oxygen when in contact with perspiration which tends to destroy unpleasant odors. The talc acts as a lubricant and prevents friction and chafing.

Foot Powder

Sodium Perborate 3 oz. Zinc Peroxide 2 oz. Talc 15 oz.

Shake together thoroughly in a dry container until uniformly mixed. This powder must be kept dry or it will spoil.

Liniments

Liniments usually consist of an oil and an irritant such as methyl salicylate or turpentine. The oil acts as a solvent and tempering agent for the irritant. The irritant produces a rush of blood and warmth which is often slightly helpful.

Liniment, Sore Muscle
Olive Oil 6 fl. oz.
Methyl Salicylate 3 fl. oz.
Shake together and keep in a well
stoppered bottle. Apply externally but
do not apply to chafed or cut skin.

cover.

Chest-Rubs

In spite of the fact that chest-rubs practically useless countless sufferers use them. Their action is similar to that of liniments and they differ only in that they are in the form of a salve.

"Chest-Rub" Salve Yellow Petrolatum or Yellow Vaseline lb. Paraffin Wax 1 07. 2 12 OZ. Eucalyptus Oil fl. oz. Menthol 1/8 fl. oz. Cassia Oil ½ fl. oz. Turpentine Melt the vaseline and paraffin wax together in a double boiler and then add the menthol. Remove from the heat, stir, and cool a little; then stir in the oils, turpentine, and acid. When

Insect Repellents

it begins to thicken pour into tins and

Preparations of this type may irritate sensitive skins. Moreover, they will not always work. Psychologically they often are helpful, even though they may not keep insects away, because they give one confidence of protection.

Mosquito Repelling Oil 2 fl. oz. Cedar Oil 4 fl. oz. Citronella Oil Spirits of Camphor 8 fl. oz. Just shake together in a dry bottle and it is ready for use. This preparation may be smeared on the skin as often as is necessary to repel mosquitoes and other insects.

Fly Sprays

Fly sprays usually consist of deodorized kerosene, perfuming material, and an active insecticide. In some cases they merely stun the flies who may later recover and begin buzzing again.

Fly Spray Deodorized Kerosene 89 fl. oz. 1 fl. oz. Methyl Salicylate Pyrethrum Powder 10 oz. Mix thoroughly by stirring from time to time; allow to stand covered over night and then filter through

muslin. Caution: This spray is inflammable and should not be used near open

flames.

Deodorant Spray (For public buildings, sick-rooms,

lavatories, etc.) 2 oz. Pine Needle Oil 2 oz. Formaldehyde \*Acetone 6 oz. 20 oz.

\*Isopropyl Alcohol One ounce of the above is mixed with a pint of water for spraying.

Cresol Disinfectant

25½ g. †Caustic Soda Water 140 cc.

Dissolve the above in a pyrex or enamelled dish and warm it. To this add slowly the following warmed mixture:

†Cresylic Acid 500 cc. Rosin 170 g. Stir until dissolved and add water to make 1000 cc.

#### Ant Poison

Sugar 1 lb. Water 1 qt. Arsenate of Soda 125 g. Boil and stir until uniform; strain through muslin; add a spoonful of

Bedbug Exterminator \*Kerosene 90 fl. oz. Clove Oil 5 fl. oz. §Cresol 1 fl. oz. Pine Oil 4 fl. oz. Simply shake and bottle.

Mothproofing Fluid (Non-Staining) Sodium Aluminum Silico-

fluoride 12 02. Water 98 oz. 1/2 OZ. Glycerin Sulfatate (Wetting Agent) 1/4 oz. Stir until dissolved.

Fly Paper

Rosin 32 oz. Rosin Oil 20 oz. Castor Oil 8 oz.

Heat the above in an aluminum or enamelled pot on a gas stove with stirring until all the rosin has melted and dissolved. While hot pour on firm paper sheets of suitable size which have been brushed with soap water just before coating. Smooth out the coating with a long knife or piece of thin flat wood and allow to cool. If a

Inflammable. † Do not get this on skin as it is corrosive. Poison.

§ Corrosive to skin.

heavier coating is desirable increase the amount of rosin used. Similarly a thinner coating is gotten by reducing the amount of rosin. The finished paper should be laid flat and not exnosed to undue heat.

Household Baking Powder
Bicarbonate of Soda 28 oz.
Mono Calcium Phosphate 35 oz.
Corn Starch 27 oz.
Mix the above powders thoroughly
in a dry can by shaking and rolling
for a half hour. Pack into dry airtight tins as moisture will cause
lumping.

Malted Milk Powder
Malt Extract, Powdered 5 oz.
Skim Milk, Powdered 2 oz.
Sugar, Powdered 3 oz.
Mix thoroughly by shaking and rolling in a dry can. Pack in an air-tight container.

Cocoa Malt Powder Corn Sugar oz. Malt, Powdered, Mild 19 oz. 12½ oz. Skim Milk, Powdered 13 Cocoa oz. Vanillin oz. 3/8 Salt, Powdered oz. Mix thoroughly and then run through a fine wire sieve.

Sweet Cocoa Powder
Cocoa 17½ oz.
Sugar, Powdered 32½ oz.
Vanillin ¾ g.
Mix thoroughly and sift.

Pure Lemon Extract
Lemon Oil U.S.P. 6½ fl. oz.
Alcohol 121½ fl. oz.
Shake together in a gallon jug till
dissolved.

Artificial Vanilla Flavor ¾ oz. Vanillin 1/4 oz. Coumarin pt. Alcohol Stir the above in a glass or china pitcher until dissolved. Then stir in the following solution which has been made by stirring in another pitcher. 12 Sugar oz. 5¼ pt. Water pt. Glycerin Color brown by adding sufficient "burnt" sugar coloring.

Canary Bird Food Yolk of Eggs, Dried and	
Chopped	2 oz.
Poppy Heads (Coarse Powder)	1 oz.
Cuttlefish Bone (Coarse	1 02,
Powder) Granulated Sugar	1 oz. 2 oz.
Soda Crackers, Powdered Mix well together.	8 oz.

Writing Ink (Blue-Black)
Naphthol Blue Black 1 oz.
Gum Arabic, Powdered ½ oz.
Carbolic Acid ¼ oz.
Water 1 gal.
Stir together in a glass or enamelled vessel until dissolved.

Laundry Marking Ink (Indelible) A. Soda Ash 1 oz. Gum Arabic. Powdered 1 oz. Water 10 fl. oz. Stir the above until dissolved. B. Silver Nitrate Gum, Arabic Powdered 4 oz. 2 oz. Lampblack Water 40 fl. oz.

Stir this in a glass or porcelain dish until dissolved. Do not expose this to strong light or it will spoil. Finally pour into a brown glass bottle. In using these solutions wet the cloth with solution A and allow to dry. Then write on it with solution B using a quill pen.

 Marking Crayon (Green)

 Ceresin
 8 oz.

 Carnauba Wax
 7 oz.

 Paraffin Wax
 4 oz.

 Beeswax
 1 oz.

 Talc
 10 oz.

 Chrome Green
 3 oz.

Melt the first four ingredients in any container and then add the last two slowly while stirring. Remove from the heat and continue stirring until thickening begins. Then pour into molds. If other color crayons are desired, other pigments may be used. For example for black, use carbon or bone-black; for blue, Prussian blue; for red, orange chrome yellow.

Antique Coloring for Copper
Copper Nitrate 4 oz.
Acetic Acid 1 oz.
Water 2 oz.
Dissolve by stirring together in a

glass or porcelain vessel. Pack in glass

To Use: Wet the copper to be colored and apply the above solution hot.

Blue-Black Finish on Steel

a. Place object in molten sodium nitrate (700-800° F.) for 2-3 minutes. Remove and allow to cool somewhat; wash in hot water; dry and oil with mineral or linseed oil.

b. Place in following solution for 15

minutes:

Inutes:
Copper Sulphate
Iron Chloride
I lb.
Hydrochloric Acid
Vac.
Nitric Acid
Vater
I gal.
Then allow to dwy for soverel bours

Then allow to dry for several hours; place in above solution again for 15 min.; remove and dry for 10 hours. Place in boiling water for ½ hour; dry and scratch brush very lightly. Oil with mineral or linseed oil and wipe dry.

Rust Prevention Compound
Lanolin 1 oz.
\*Naphtha 2 oz.

Mix until dissolved.

The metal to be protected is cleaned with a dry cloth and then coated with the above composition.

Metal Polish

 Naphtha
 62
 oz.

 Oleic Acid
 ½
 oz.

 Abrasive
 7
 oz.

 Triethanolamine Oleate
 ½
 oz.

 Ammonia (26°)
 1
 oz.

 Water
 1
 gal.

In one container mix together the naphtha and oleic acid to a clear solution. Dissolve the triethanolamine oleate in water separately, stir in the abrasive, if it is of a clay type, and then add the naphtha solution. Stir the resulting mixture at a high speed until a uniform creamy emulsion results. Then add the ammonia and mix well, but do not agitate as vigorously as before.

Glass Etching Fluid
Hot Water 12 fl. oz.
†Ammonium Bifluoride 15 oz.
Oxalic Acid 8 oz.
Ammonium Sulfate 10 oz.
Glycerin 40 oz.
Barium Sulfate 15 oz.

Warm the washed glass slightly before writing on it with this fluid. Allow the fluid to act on the glass for about two minutes.

Leather Preservative Neatsfoot Oil (Cold

Pressed) 10 oz. Castor Oil 10 oz. Just shake together.

This is an excellent preservative for leather book bindings, luggage and other leather goods.

White Shoe Dressing
Lithopone 19 oz.
Titanium Dioxide 1 oz.
Shellac (Bleached) 3 oz.
Ammonium Hydroxide 4 fl. oz.
Water 25 fl. oz.
Alcohol 25 fl. oz.
Glycerin 1 oz.

Dissolve the last four ingredients by mixing in a porcelain vessel. When dissolved stir in the first two pigments. Keep in stoppered bottles and shake before using.

Waterproofing for Shoes
Wool Grease 8 oz.
Dark Petrolatum 4 oz.
Paraffin Wax 4 oz.
Melt together in any container.
Apply this grease warm but never hotter than the hand can bear.

Polishes

Polishes are usually used to restore the original lustre and finish of a smooth surface. As a secondary purpose they are expected to clean the surface and also to prevent corrosion or deterioration. There is no one polish which will give good results on all surfaces.

Most polishes depend on oil or wax for their lustering or polishing properties. Oil polishes are applied easily but the surfaces on which they are used attract dust and show finger marks. Wax polishes are more difficult to apply but are more lasting.

Oil or wax polishes are of two types: waterless and with water. The former are clear or translucent and the latter are milky in appearance.

For use on metals abrasives of various kinds such as tripoli, silica dust or infusorial earth are incorporated to grind away oxide films or corrosion products present.

<sup>\*</sup> Inflammable—keep away from flames.

Shoe Polish (Black) Carnauba Wax 5½ oz. Crude Montan Wax 5½ oz. Melt together in a double boiler (the water in outer container should be at a boil) then stir in the follow-
ing melted and dissolved mixture:
Stearic Acid 2 oz.
Nigrosine Base 1 oz.
Then stir in
Ceresin 15 oz.
Remove all flames and run in slowly.
while stirring
Turpentine 90 fl. oz.
Allow mixture to cool to 105° F. and
pour into air-tight tins which should
be allowed to stand undisturbed over

Auto Polish (Clear Oil Type) Paraffin (Mineral) Oil 5 pt. Raw Linseed Oil pt. ½ pt. China Wood Oil \*Benzol ¼ pt. ¼ pt. Kerosene Amvl Acetate 1 tbsp. Shake together in a glass jug and keep stoppered.

night.

Auto and Floor Wax (Pas	ste T	ype)
Yellow Beeswax	1	oz.
Ceresin	$2\frac{1}{2}$	oz.
Carnauba Wax	$4\frac{1}{2}$	oz.
Montan Wax	$1\frac{1}{4}$	oz.
*Naphtha or Mineral		
<b>Špirits</b>	1	pt.
*Turpentine	2	oz.
Pine Oil	1/2	oz.
Melt the waxes together	in a	double
boiler. Turn off the heat a	and 1	un ir
the last three ingradients	in s	a thir

Melt the waxes together in a double boiler. Turn off the heat and run in the last three ingredients in a thin stream and stir with a fork. Pour into cans; cover and allow to stand undisturbed overnight.

Furniture Polish (Oil and Wax Type)
Thin Paraffin (Mineral
Oil 1 pt.
Carnauba Wax, Powdered ½ oz.
Ceresin Wax ½ oz.
Heat together until all of the wax
is melted. Allow to cool and pour into
bottles before mixture turns cloudy.

Polishing Wax (Liquid)
Beeswax, Yellow 1 oz.
Ceresin Wax 4 oz.
Melt together and then cool to 130°
F.; turn off all flames and stir in slowly.

\*Turpentine 17 fl. oz.
Pine Oil ½ fl. oz.
Pour into cans or bottles which are closed tightly to prevent evaporation.

Floor Oil
Mineral Oil 46 fl. oz.
Beeswax ½ oz.
Carnauba Wax 1 oz.
Heat together in double boiler until dissolved (clear). Turn off flame and stir in
\*Turpentine 3 fl. oz.

Lubricants

Lubricants in the form of oils or greases are used to prevent friction and wearing of parts which rub together. Lubricants must be chosen to fit specific uses. They consist of oils and fats often compounded with soaps and other unctuous materials. For heavy duty heavy oils or greases are used and light oils for light duty.

Gun Lubricant
White Petrolatum 15 oz.
Bone Oil (Acid Free) 5 oz.
Warm gently and mix together.

Graphite Grease
Ceresin 7 oz.
Tallow 7 oz.
Warm together and gradually work
in, with a stick

Graphite 3 oz. Stir until uniform and pack in tins when thickening begins.

Penetrating Oil
(For freeing rusted bolts, screws, etc.)
Kerosene 2 oz.
Thin Mineral Oil 7 oz.
Secondary Butyl Alcohol 1 oz.
Shake together and keep in a stoppered bottle.

Molding Material
White Glue 13 lb.
Rosin 13 lb.
Raw Linseed Oil 1/3 qt.
Glycerin 1 qt.
Whiting 19 lb.

This mixture is prepared by cooking the white glue until it is dissolved. Then cook separately the rosin and raw linseed oil until they are dissolved. Add the rosin, oil, and glycerin to the cooked glue, stirring in the whiting until the mass makes up to

<sup>\*</sup> Inflammable-Keep away from flames.

<sup>\*</sup> Inflammable.

the consistency of putty. Keep the

mixture hot.

Place this putty mass in the die, pressing it firmly into the same and allowing it to cool slightly before removing. The finished product is ready to use within a few hours after removal. Suitable colors can be added to secure brown, red, black or other color.

In applying ornaments made of this composition to a wood surface, they are first steamed to make them flexible; in this condition they can be glued to the wood surface easily and securely. They can be bent to any shape, and no nails are required for

applying them.

#### Grafting Wax

Wool Grease	11	oz.
Rosin	22	oz.
Paraffin Wax	6	oz.
Beeswax	4	OZ.
Japan Wax	1	OZ.
Rosin Oil	9	oz.
Pine Oil	1	oz.
Walt tarathan matil alann	n-n-d	***

Melt together until clear and pour into tins. This composition can be made thinner by increasing the amount of rosin oil and thicker by decreasing it.

#### Candles

Paraffin Wax		30	oz.
Stearic Acid		$17\frac{1}{2}$	OZ.
Beeswax			oz.
Melt together			
If colored candles	s are des	ired a	pinch
of any oil solubl			
this stage. Pour		ical mo	lds in
which wicks are	hung.		

#### Adhesives

Adhesives are sticky substances used to unite two surfaces. Adhesives are specifically called glues, pastes, cements, mucilages, lutes, etc. For different uses different types are required.

Wall Patching Plaster

Plaster of Paris

Dextrin

Pumice Powder

Mix thoroughly by shaking and rolling in a dry container. Keep away from moisture.

Cement Floor Hardener
Magnesium Fluosilicate 1 lb.
Water 15 pt.
Mix until dissolved.

In using this, the cement should first be washed with clean water and then drenched with the above solution.

Paperhanger's Paste

Use a cheap grade of rye or wheat flour, mix thoroughly with cold water to about the consistency of dough or a little thinner, being careful to remove all lumps. Stir in a tablespoonful of powdered alum to a quart of flour, then pour in boiling water, stirring rapidly until the flour is thoroughly cooked. Let this cool before using and thin with cold water.

a. White or Fish Glue
Cold Water
b. Venice Turpentine
c. Rye Flour
Cold Water
d Boiling Water
64 floor
65 cold Water
66 floor
66 floor
67 cold Water

d. Boiling Water 64 fl. oz. Soak the 4 oz. of glue in the cold water for 4 hours. Dissolve on a water bath (glue-pot) and while hot stir in the Venice turpentine. Make up c into a batter free from lumps and pour into d. Stir briskly, and finally add the glue solution. This makes a very strong paste, and it will adhere to a painted surface, owing to the Venice turpentine in its composition.

Aquarium Cement

Litharge 10 oz.
Plaster of Paris 10 oz.
Powdered Rosin 1 oz.
Dry White Sand 10 oz.

Boiled Linseed Oil Sufficent Mix all together in the dry state, and make into a stiff putty with the

oil when wanted for use.

Do not fill the aquarium for three days after cementing. This cement hardens under water, and will stick to wood, stone, metal, or glass, and, as it resists the action of sea-water, it is useful for marine aquaria. The linseed oil may have an addition of drier to the putty made up four or five hours before use, but after standing fifteen hours, however, it loses its strength when in the mass.

Wood Dough Plastic

\*Collodion 86 g. Ester Gum, Powdered 9 g. Wood Flour 30 g.

Allow first two ingredients to stand until dissolved, stirring from time to time. Then while stirring add the wood flour a little at a time until

<sup>\*</sup> Inflammable.

uniform. This product can be made softer by adding more collodion.

#### Putty

Whiting 80 oz.
Raw Linseed Oil 16 oz.
Rub together until smooth. Keep in closed container.

Wood Floor Bleach

Sodium Metasilicate 90 oz.
Sodium Perborate 10 oz.
Mix thoroughly and keep dry in a closed can. Use 1 pound to a gallon of boiling water. Mop or brush on the floor, allow to stand \(^{1}{2}\) hour, then rub off and rinse well with water.

\* Paint Remover

Benzol	5 pt.
Ethyl Acetate	3 pt.
Butyl Acetate	2 pt.
Paraffin Wax	½ lb.
Stir together until di	ssolved.

Soaps and Cleaners

Soaps are made from a fat or fatty acid and an alkali. They lather and produce a foam which entraps dirt and grease which is washed away with water. There are numerous kinds of soaps depending on the uses to which they are to be put.

Cleaners consist of solvent such as naphtha with or without a soap. Abrasive cleaners are soap pastes containing powdered pumice, stone, silica, etc.

Liquid Soap (Concentrated)

Water 11 oz. †Caustic Potash (Solid) 1 oz. Glycerin 4 oz. Red Oil (Oleic Acid) 4 oz.

Dissolve the caustic in water, add the glycerin and bring to a boil in an enamelled pot. Remove from heat, add the red oil slowly while stirring. If a more neutral soap is wanted, use a little more red oil.

Saddle Soap

Beeswax	-		5	oz.	
†Caustic Potash		(	8.0	oz.	
Water		5	8	oz.	
Boil for 5 minutes	while	sti	crii	ıg. I	1
another vessel heat					
Castile Soap			1.6	oz.	
Water			8	oz.	

\* Inflammable. † Do not get on skin as it is corrosive. Mix the two with good stirring; remove from heat and add

Turpentine 12 oz.

while stirring.

Mechanics Hand Soap Paste
Water 1.8 qt.
White Soap Chips 1.5 lb.
Glycerin 2.4 oz.
Borax 6 oz.
Dry Sodium Carbonate 3 oz.
Coarse Pumice Powder 2.2 lb.
Safrol enough to scent

Dissolve the soap in % of the water by heat. Dissolve the last three in the rest of the water. Pour the two solutions together and stir well. When it begins to thicken, sift in the pumice, stirring constantly till thick, then pour into cans. Vary amount of water, for heavier or softer paste (water cannot be added to the finished soap).

Dry Cleaning Fluid
Glycol Oleate 2 fl. oz.
Carbon Tetrachloride 60 fl. oz.
Varnoline (Naphtha) 20 fl. oz.
Benzine 18 fl. oz.
An excellent cleaner that will not injure the finest fabrics.

Wall Paper Cleaner

THAIL LAPOL CICALICE		
Whiting		lb.
Magnesia Calcined	2	lb.
Fuller's Earth		lb.
Pumice Powder	12	
Lemenone or Citronella Oil	4	OZ.
Mix well together.		

Household Cleaner

Soap Powder

Soda Ash

Trisodium Phosphate
Finely Ground Silica

Mix well and put up in the usual containers.

Window Cleanser

		windo	w Ciea	nse	C.	
	Castile	Soap				OZ.
	Water				5	oz.
	Chalk				4	oz.
	French	Chalk				oz.
	Tripoli	Powder	•		2	oz.
	Petrole	um Spi:	rits			oz.
	Mix w	ell and	pack	in	tight	con
ta	ainers.		_			

Straw Hat Cleaner
Sponge the hat with a solution of
Sodium Hyposulphite 10 oz.
Glycerin 5 oz.

Alcohol Water Lay aside in a damp pl	10 oz. 75 oz. ace for 24
hours and then apply	_
Citric Acid	2 oz.
Alcohol	10 oz.
Water	90 oz.
Press with a moderately	y hot iron
after stiffening with gum	water if
necessary.	

#### Grease, Oil, Faint & Lacquer Spot Remover

Alconol	ı uz.
Ethyl Acetate	2 oz.
Butyl Acetate	2 oz.
Toluol	2 oz.
Carbon Tetrachloride	3 oz.
Place garment with spot	over a piece
of clean paper or cloth an	nd wet with
the above fluid; rub with	clean cloth
toward center of spot. I	Jse a clean
section of cloth for rubbin	ig and clean
paper or cloth for each ap	plication of
the fluid. The above pro	duct is in-
flammable and should be	kept away
from flames. Use of clear	ners of this
type should be out-of-door:	s or in well-
ventilated rooms as the	fumes are
toxic.	

#### Paint Brush Cleaner

Mix (1)			
Kerosene	2	pt.	
Oleic Acid	1	pt.	
Mix (2)			
Strong Liquid Ammonia,			
28%	1/4	pt.	
Denatured Alcohol	1/4	pt.	
Slowly stir 2 into 1 until	as	mooth	
mixture results. To clean	ı bı	ushes,	
pour into a can and stand t	he b	rushes	
in it overnight. In the morn	ing,	, wash	

#### Rust & Ink Remover

Immerse portion of fabric with rust or ink spot alternately in Solution A and B, rinsing with water after each immersion.

Solution A Ammonium Sulphide Solution

out with warm water.

Water	19	oz.
Solution B *Oxalic Acid Water		oz.

1 oz.

Javelle Water (Laundry	Bleach)
Bleaching Powder	2 oz.
Soda Ash	2 oz.
Water	5 gal.
# Theiremone	

Mix well until reaction is completed. Allow to settle overnight and siphon off the clear liquid.

Laundry Blue (Liquid)
Prussian Blue 1 oz.
Distilled Water 32 oz.
\*Oxalic Acid 4 oz.
Dissolve by mixing in a crock or wooden tub.

"Glassine" Paper
Paper is coated with or dipped in
the following solution and then hung
up to dry.

Gum Copal 10 oz.
Alcohol 30 fl. oz.
Castor Oil 1 fl. oz.

Dissolve by letting stand overnight in a covered jar and stirring the next day.

Waterproofing Paper and Fibreboard The following composition and method of application will render uncalendered paper, fibreboard, and similar porous material waterproof and proof against the passage or penetration of water.

Paraffin (Melting Point about 130° F.) 22.5 oz.

Trihydroxyethylamine

 Stearate
 3.0 oz.

 Water
 74.5 oz.

The paraffin wax is melted and the stearate added to same. The water is then heated to nearly boiling and then vigorously agitated with a suitable mechanical stirring device while the above mixture of melted wax and emulsifier is slowly added. This mixture is cooled while it is stirred.

The paper or fibreboard is coated on the side which is to be in contact with water. This is then quickly heated to the melting point of the wax, which then coalesces into a continuous film that does not soak into the paper which is preferentially wetted by the water. This method works most effectively on paper pulp moulded containers and possesses the advantages of being much cheaper than dipping in melted paraffin as only about a tenth as much paraffin is needed. In addition, the outside of the container is not greasy, and can be printed upon after treatment which is not the case when treated with melted wax.

Waterproofing Liquid
Paraffin Wax % oz,
\* Poison.

Gum Dammar	11/5	oz.
Pure Rubber	1/8	oz.
Benzol	13	oz.
Carbon Tetrachloride		

to make 1 gal.
Dissolve rubber in benzol; add other ingredients and allow to dissolve. (Inflammable.)

The above is suitable for wearing apparel and wood. It is applied by brushing on two or more coats, allowing each to dry before applying another coating. Apply outdoors as vapors are inflammable and toxic.

Waterproofing Heavy Canvas
Raw Linseed Oil 1 gal.
Beeswax, Crude 13 oz.
White Lead 1 lb.
Rosin 12 oz.

Heat the above, while stirring, until all lumps are gone and apply warm to upper side of canvas; wetting the canvas with a sponge on the underside before applying.

Cement Waterproofing Chinawood Oil Fatty

Acids 10 oz.
Paraffin Wax 10 oz.
Kerosene 2½ gal.
Stir until dissolved. This is painted or sprayed on cement walls, which must be dry.

Oil and Greaseproofing Paper and Fibreboard

This solution applied by brush, spray, or dipping will leave a thin film which is impervious to oils and grease. Applied to paper or fibre containers, it will enable them to retain oils and greases. All the following ingredients are by weight:

 Starch
 6.6 oz.

 Caustic Soda
 0.1 oz.

 Glycerin
 2.0 oz.

 Sugar
 0.6 oz.

 Water
 90.5 oz.

 Sodium Salicylate
 0.2 oz.

The caustic soda is dissolved in the water and then the starch is made into a thick paste by adding a portion of this solution. This paste is then added to the water. This mixture is placed in a water jacket and heated to about 85° C. until all the starch granules have broken and the temperature maintained for about half an hour longer. The other substances are then added and thoroughly mixed and the composition is completed and ready for application. A smaller water

content may be used if applied hot and a thicker coating will result. Two coats will result in a very considerable resistance to oil penetration.

Fireproof Paper
Ammonium Sulphate 8 oz.
Boric Acid 3 oz.
Borax 1% oz.
Water 100 fl. oz.
Mix together in a gallon jug, by shaking, until dissolved.

The paper to be treated is dipped into this solution in a pan, until uniformly saturated. It is then taken out and hung up to dry. Wrinkles can be prevented by drying between cloths in a press.

Fireproofing Canvas
Ammonium Phosphate 1 lb.
Ammonium Chloride 2 lb.
Water ½ gal.
Impregnate with above; squeeze out excess and dry. Washing or exposure

to rain will remove fireproofing salts.

Fireproofing Light Fabrics
Borax 10 oz.
Boric Acid 8 oz.
Water 1 gal.
Impregnate; squeeze and dry.
Fabrics so impregnated must be treated again after washing or exposure to rain as the fireproofing salts wash out easily.

Dry Fire Extinguisher

Ammonium Sulphate 15 oz.
Sodium Bicarbonate 9 oz.
Ammonium Phosphate 1 oz.
Red Ochre 2 oz.
Silex 23 oz.

Use powdered materials only; mix well and pass through a fine sieve. Pack in tight containers to prevent "lumping."

Fire Extinguishing Liquid
Carbon Tetrachloride 95 oz.
Solvent Naphtha 5 oz.
The inclusion of the naphtha minimizes production of toxic fumes when extinguishing fires.

Fire Kindler
Rosin or Pitch 10 oz.
Sawdust 10 or more oz.
Melt, mix, and cast in forms.

Solidified Gasoline
\*Gasoline ½ gal.
\*Infiammable.

White Soap (Fine Shaved) 12 oz.
Water 1 pt.
Household Ammonia 5 oz.
Heat the water, add soap, mix and when cool add the ammonia. Then slowly work in the gasoline to form semi-solid mass.

Boiler Compound
Soda Ash 87 oz. from ti
Trisodium Phosphate 10 oz. starch 1 oz. alcohol
Tannic Acid 2 oz. bought
Use powdered materials, mixing alcohol.

well and then pass through a fine sieve.

#### Anti-Freezes

The materials listed below are the basic ingredients used in all good antifreeze liquids. Of these, alcohol is the only one that evaporates. Radiators containing alcohol should be tested from time to time to be sure of protection. A hydrometer for testing alcohol solution strength can be bought from sellers of denatured alcohol.

Anti-Freeze Liquids

Pints of anti-freeze per	r gan. or	water for	protection	all:	
	_	+10° F.	0° F.	—10° F.	-20° F.
Denatured Alcohol 180° p	roof	3.4	4.9	6.5	8.3
Denatured Alcohol 188° p	roof	3.3	4.7	6.0	7.7
Glycerin 95%		$\cdot 3.3$	5.3	7.1	9.0
Radiator Glycerin 60%		10.0	18.7	39.0	106.5
Ethylene Glycol 95%		2.7	4.0	5.1	6.5
Specific gravity for pre	otection	at:			
+	10° F.	0° F.	-10° F.	-20° F.	-30° F.
Denatured Alcohol (	0.968	0.959	0.950	0.942	0.921
Glycerin	1.090	1.112	1.131	1.147	1.158
Ethylene Glycol	1.038	1.048	1.056	1.064	1.069

Soldering Flux (Non-corrosive)
Rosin, Powdered 1 oz.
Denatured Alcohol 4 oz.
Soak overnight and mix well.

Photographic Solutions
Developing Solution
Stock Solution A

Dissolve the following, separately, in glass or enamel dishes.

Pyro 4 oz.

Sodium Bisulphite, Pure Potassium Bromide 280 gr. Distilled Water 5tock Solution B Sodium Sulphite, Pure Sodium Carbonate, Pure 5 oz.

Distilled Water 64 oz.
To use take the following proportions:

Stock Solution A2 oz.Stock Solution B2 oz.Distilled Water16 oz.

At a temperature of 65° F. this developer requires about 8 minutes.

Acid Hardening Fixing Bath
A. Sodium Hyposulphite 32 oz.
Distilled Water 8 oz.

Stir until dissolved and then add the following chemicals in the order given below, stirring each until dissolved:

B. Distilled Water (Warm) 2½ oz. Sodium Suiphite, Pure ½ oz. Acetic Acid (28%),

Pure 1½ oz. 1½ oz.

Potassium Alum Powder ½ oz. Add Solution B to A and store in dark bottles away from light.

### CHAPTER Two

## ADHESIVES

AOTIFOLIS ADTIES	TTTTC	l CI	17.00
AQUEOUS ADHES	IVES	Glue	17.00
Flexible Glues		Waste Roller Composi- tion	42.50
Formula No. 1		Water	39.60
For general bindery use		Zinc Oxide	.90
waste roller composition:			.80
Glue	20.80	No. 6	
Glycerin	16.60	For general bindery use	
Waste Roller Composi-		Glue	22.60
tion	9.80	Diethylene Glycol	22.10
Water	52.50	Water	55.00
Beta Naphthol	.15	Beta Naphthol	.15
Terpineol	.15	Terpineol	.15
No. 2		No. 7	
For use on gathering,	stitching,	For use on gathering,	stitching.
and covering machines:	36.30	and covering machines:	0010011111191
Glue Glycerin	30.30 16.60	Glue	36.30
Water	46.80	Glycerin	8.30
Beta Naphthol	.15	Diethylene Glycol	8.30
Terpineol	.15	Water	46.80
No. 3	.10	Beta Naphthol	.15
For use on Perfect Bir	ding Ma-	Terpineol	.15
chine:	iding 1414		.10
Glue	39.90	No. 8	
Glycerin	33.30	Tablet composition:	00.70
Water	26.50	Glue	26.50
Beta Naphthol	.15	Glycerin	13.25
Terpineol	.15	Diethylene Glycol	13.25
No. 4		Water	$46.70 \\ .15$
Tablet composition:		Beta Naphthol	.15
Glue	26.50	Terpineol	.10
Glycerin	26.50	No. 9	
Water	46.70	For general bindery use	<b>:</b> :
Beta Naphthol	.15	Glue	22.60
Terpineol	.15	Sorbitol Syrup	20.50
No. 5		Water	56.60
Tablet composition	utilizing	Beta Naphthol	.15
waste roller composition	:	Terpineol	.15
	1	17	

No. 10	
For use on gathering	, stitching,
and covering machines:	
Glue	36.40
Sorbitol Syrup	16.60
Water	46.70
Beta Naphthol	.15
Terpineol	.15
No. 11	
Tablet composition:	
Glue	26.50
Sorbitol Syrup	26.50
Water	46.70
Beta Naphthol	.15
Terpineol	.15
No. 12	
For gluing-off large, the	hick books
previous to rounding and	
Glue	22.50
Sorbitol Syrup	25.90
Water	51.30
Beta Naphthol	.15
Terpineol	.15
Terpineor No. 19	.10

No. 13
For bookbinders, telephone books:
Gelatin 35.0
Glycerin 14.0
Glucose 5.0
Phenol 0.4
Water 45.6

Add glycerin and glucose to water. Mix gelatin into solution. Let stand in the cold for several hours. Heat to 140° F. and maintain at that temperature till all the gelatin is dissolved. When clear, add phenol. Pour into suitable forms and allow to cool.

This glue is melted when needed. Water may be added to suit requirements.

Insolubilizing Glue and Casein (Patented)
Glue

Glue
20

	O 4000	
Glue		20
Water		30

When the water has been absorbed by the glue, glycerine formal (10) and 10 per cent sulfuric acid (1) are added. After curing this product at 50°-70° C. it is insoluble in boiling water following a preliminary soaking of three hours in cold water.

Casein	
Water	30
Glycerin Formal	2.4
Sulphuric Acid (10%)	1
Casein	10

This mixture after thorough mixing may be pressed into a mold and cured at 50°-100° C. to form a water resistant product.

Other acids than sulfuric acid may be used and the results will depend upon the pH of the mixture. In general a low pH results in faster curing and lower curing temperatures.

Shoe Ce	ement
Glue, Viscous Ca	rpen-
ter's	1.00
Glycerin	0.30
Acetic Acid	0.04
Water	0.50 - 0.60
Apply warm.	

Transparent	t Colorless	Adh	esive
British	Patent 52	5,620	
Gelatin		1	lb.
Water		11/2	gal.
Potassium	Chlorate		
(26° Bé.	Solution)	0.15	gal.
Boric Acid			lb.

"Cellophane" Adhes	sive
Gum Arabic	$16\frac{1}{2}$
Aquaresin	30
Water	50
Formaldehyde	$4\frac{1}{2}$

Envelope Adhesive
The gum used by the United

States Government on postage stamps is probably one of the best that could be used not only for envelopes but for labels as well. It will stick to almost any surface, and is prepared with:

Gum Arabic 1
Starch 1
Sugar 4
Water, sufficient to give the desired consistency.

The gum arabic is first dissolved in some water, the sugar added, then the starch, after which the mixture is boiled for a few minutes in order to dissolve the starch, after which it is thinned down to the desired consistency. To cut the expense, dextrine may be substituted for the gum arabic, glucose for the sugar, and boric acid added to preserve and help stiffen the paste.

Mucilage for Secret Message Envelopes and Stamps

Mucilage for sealing letters and documents, or for use in stamps and revenue tags which shows the effects of tampering and steaming is prepared by adding beta-methylumbelliferone to ordinary paper mucilage or glue base. When the stamp or seal has been tampered with, or an attempt to steam open has been made, tell-tale traces of the attempt will be seen by a bright blue coloration on the paper or about the stamp which can only be seen in ultraviolet light and not in white light.

Plywood Adhesive			
Australian	Patent 1	10,458	
Formula	No. 1	No. 2	
Casein	100	100	
Urea	15	$15\frac{1}{2}$	
Water	460	480	

_			15
_	Formaldehyde Trisodium	$7\frac{1}{2}$	8
	Phosphate		4
	Oil and Vapo Australian Pa		
	Water		10
	Turkey-Red Oi	1	11
	Caustic Potash	.1	1
	Graphite		15
	Chalk		40
	Asbestos		10
	Barytes		10
	-		
	Neutral 7		
	U. S. Paten		
	Casein (18% so		100.0
	Ammonium Flu		90.0
	Sodium Boropho	osphate	5.0
	Glycerin		0.6
	Water		4.4
	Dilute with wat	er as desi	ırea.
	Dry 1 Formula U. S. Paten Sugar Starch Citric Acid	a No. 1 t 2,204,38 55 — 43.5—	34 45 % 53.5% 1.5%
	U. S. 2,5	231,000	100
	STORAN		1141

Starch	43.5-53.5%
Citric Acid	1.5%
No. 2	2
U. S. 2,23	1,050
Starch	100
Lactic Acid	25
Sodium Chlorate	1
Heat to 110° C.	until soluble in
hot water.	

Metal Container Sealin	g Dope
British Patent 517,0	037
Barytes	10.1
Asbestine	5.0
Gum Karaya	0.3
Colloidal Clay	1.9
Glue	4.5
Glycerin	2.5

200

20	THE CHEMICA
Casein	1.8
Ammonia (28%)	0.7
Rubber Latex (Se	
Vulcanized Rubb	
(Solids)	5.0
Water	66.2
Viscous Wate Sticky I	iquid
Sodium Alginate	50
Solution)	50
Abopon (Sodium	) 50
Borophosphate	
Mix together to	body stiekings
rial having great ind "length."	oody, stickiness
Gasket I	Paste
Formula	
Potash Soap	18.25%
Glycerin	4.6 %
Water	2 %
Castor Oil, Bodie	d to
Make	100 %
Heat gradually	with mixing to
250° F. to get a sr	
Continue stirring v	
100° F. and then p	
No.	

Soap	20%
Water	2%
Glycerin	5%
Blown Castor Oil, to	
Make	100%
No. 3	,
Potash Soap	20%
Diglycol Laurate	5%
Glycerin	5%
Castor Oil, Blown	59%
Heat and mix at 25	0° F. until

uniform. Stop and heat and mix until it cools to 100° F. and package.

Adhesive for	Window	Glass
Gum Arabic		18
Water		52
Glycerin		30

Dissolve the gum arabic in water and add the glycerin

na add one Sirecting	
Paper to Glass Adh	esive
Water	150
Zinc Chloride	2
Glycerin	10
Cassava Flour or	

121/6

Tapioca

Mix thoroughly and heat to boiling, stirring vigorously, all the time, during the heating. If tapioca is in lumps, the mixture should soak overnight before heating. Other starches and flour can be used in place of the cassava and tapioca. but the products are much poorer in quality.

#### Hot Enamel Lithographer's Adhesive Formula No. 1

Soak 400 g, gelatin in 500 ml. water and heat until dissolved. Add 66 ml. water, 30 ml. concentrated hydrochloric acid and 4 g. pepsin. Heat 10-15 hours at 45° then to 90° to inactivate the pepsin, and add alcoholic solution of thymol. Final mixture shows pH 4.1 and can be kept indefinitely. For enameling, 375 g. of suspension is mixed with 13.5 g. ammonium dichromate and 1200 ml, water, The enamel is transparent and has good adhesive properties.

#### No. 2

From 20 to 25 ml. of a 10% solution of aluminum sulfate is added to a 1:6 solution of bone glue in water. The mixture is neutralized with a lime solution.

Carton Sealing Glue	
White Corn Dextrin	
(Medium Viscosity)	35.0
Borax	5-0

Sodium Hydroxide (25%)	3.0
Formaldehyde	0.3
Water	56.7

Mix the dextrin in 45 parts of cold water till free of lumps. Heat to 180° F. In balance of water dissolve the borax. Add borax solution to dextrin solution; finish with the caustic and formaldehyde.

For most work this glue will stand considerable dilution.

#### Tube Glue

For reels, tubes, cones and similar material:

Canary Corn Dextrin	50.0
Borax	5.0
Caustic Soda (25%)	2.0
Formaldehyde	0.3
Water	42.7

Warm water, as dextrin is being added. By the time all the dextrin is added the solution should be at 180° F. Keep stirring till free of lumps. Then sift in the borax and maintain the heat and the stirring till all the borax is dissolved. Finish with the caustic and formaldehyde.

### Stripping Glue

I'ul paper box maxing.	
White British Gum	28.0
Borax	5.0
Phenol	0.3
Caustic Soda (30%)	1.8
Water	64.9

Dissolve the gum in the water. Heat to 180° F. Add the borax, whenol, and caustic.

Envelope Gum—Heavy I	Paper
Canary Tapioca Dextrin	65.0
Glucose	5.0
Glycerin or Glycol	1.0
Formaldehyde	0.2
Water	28.8
Procedure as for envelope	paste.

Envelope Gum—Kraft P	aper
Canary Tapioca Dextrin	60.0
Glucose	5.0
Phosphoric Acid (80%)	1.0
Formaldehyde	0.2
Water	33.8

Heat water, add dextrin while stirring. At the end of dextrin addition the temperature should be 190° F. Maintain temperature till free of lumps. Add glucose and cool to 110° F. Add formaldehyde and phosphoric acid.

## Bottle Labelling Glue Formula No. 1 Capary Corp or Tanioca

Canaly Colli of Lapioca	
Dextrin	52.0
Glucose	22.5
Formaldehyde	0.3
Water	25.2

Add glucose to water and heat. Add dextrin while heating. When dextrin is all added the temperature should be 180° F. Continue heating while stirring till the solution is clear. Cool, finish with formaldehyde.

This glue is suitable for automatic labeling machines. For hand work dilute with water.

#### No. 2

Iceproof type—suitable for beer and soda bottles kept in ice water:

Sago Starch	32.0
Caustic Soda (25%)	18.0
Nitric Acid	11.0
Phenol	0.3
Water	38.7

Heat water to 130° F. Add starch and stir till smooth. Add small amounts of caustic till mass is smooth and opaque. Quickly add balance of caustic. Stir till uniform. Discontinue stirring for five hours. Add acid till just neutral. Finish with phenol.

Bench Paste	
Soft tacky paste for be	nch work:
White Corn Dextrin	24.0
Chlorinated Starch	4.0
Glucose	20.0
Borax	3.5
Phenol	0.2
Water	48.3

Mix glucose, corn, dextrin, and chlorinated starch in cold water. When smooth heat to 180° F. then dissolve in it the borax and phenol. Draw off in containers and age two weeks before using.

Library Paste	
White Potato Dextrin	25.0
Glucose	22.0
Borax	5.0
Phenol	0.4
Water	47.6
Mix glucose and dextrin	in the
1. T OOK 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1	on from

Mix glucose and dextrin in the water warmed to 110° F. When free of lumps raise temperature to 180° F. When the solution is clear, add the borax and phenol.

Non-Warp Glue

For high grade boxes, loose leaf pad covers, etc.:

Low Grade Gelatin 30.0

Glycerin 10.0
Glucose 25.0
Phenol 0.4
Water 34.6
Prepare as flexible glue.

#### Adhesive

For fixing mirrors to microscopes and other scientific instruments:
Gelatin (Medium Grade) 30.0
Glycerin 14.0
Phenol 0.4
Water 55.6
Prepare as flexible glue. Use

warm.

rightwiap dide	
Formula No. 1	
Canary Tapioca Dextrin	40.0
Glucose	10.0
Borax	5.0
Caustic Soda (25%)	1.0
Formaldehyde	0.3
Water	43.7

Tightwran Glue

Dissolve the dextrin and glucose in the water. Heat to 180° F. Dissolve the borax in the solution. Finish with the caustic soda and formaldehyde.

This glue is slow drying and very tacky.

No. 2	
Canary Corn Dextrin	
(Completely converted	
high viscosity)	36.0
Glucose	10.0
Glycerin or Glycol	4.0
Caustic Soda (25%)	1.0
Formaldehyde	0.3
Water	48.7
Method of manufacture	same as

Envelope Paste
Canary Tapioca Dextrin
(Completely con-

above.

(Completely converted) 60.0 Formaldehyde 0.3 Water 39.7

Heat water, add dextrin while stirring. At the end of the dextrin addition, the temperature should be 190° F. Maintain temperature till free of lumps. Cool, add formaldehyde. More concentrated pastes can be made if desired.

#### WATER INSOLUBLE ADHESIVES

TATALLINE A TIN	
Acid Soluble Oil Well	Cement
Portland Cement	1
Calcium Carbonate,	
Precipitated	1

Acid Resisting Cement
Sulphur 95
Polybutene Vistanex 5

Acid Proof Cement— Silicate Type

A cement capable of setting in the cold to a hard infusible mortar, resistant to acids at all concentrations and temperature; not resistant to boiling water or alkali.

Mix thoroughly 2 parts powder to 1 part binder, with allowable variations to obtain a desirable troweling consistency. Setting time 20 minutes to 1 hour.

#### A. Powder

Filler: 93 to 97
 Silica or pulverized quartz, 50 to 325 mesh, preferably.

2. Setting Agent: 3 to 7

a) Aryl or alkal-aryl sulfo chlorides such as benzene sulfochloride, p-toluene sulfochloride, etc.

or b) Silico fluorides, such as sodium silico fluoride, etc.

or c) Mixtures of a) and b)

#### B. Binder

Sodium or potassium silicate water glass, 30° to 40° Baume

Acid Proof Cement— Synthetic Resin Type

A cement capable of setting in the cold to a hard, infusible mortar, resistant to acids except the highly oxidizing ones, oils, solvents, greases, water and mild alkalies of temperatures up to 300 to 200 degrees Fahrenheit.

Mix thoroughly 2 to 2.5 parts powder to 1 part binder to obtain desirable troweling consistency. Setting time at 70° C. is under 1 hour. Final cure within a day.

#### A. Powder

- 1. Filler: 93 to 96
  - a) Silica preferably 50 to 325 mesh
- or b) Carbon preferably 50 to 325 mesh

2. Setting Agent: 4 to 7

Aromatic sulfonic acids, such as benzene sulfonic acid, p-toluene sulfonic acid, etc.

#### B. Binder

- A phenol-formaldehyde, or homologues of these two products, reacted by means of an acid or alkaline catalyst, and arrested at a stage wherein the partially polymerized resin has a viscosity of 25 to 70 seconds at 25° C. in a Gardner-Holt tube: 75
- 2. Glycerin: 10
- 3. Water: 15

#### Water and Alkali Resistant Adhesive

This adhesive is specially useful for bonding a dry surface to a wet sub-surface, and in maintaining adhesion where exposed to water and alkali.

Formula No. 1	
Para-Coumarone Resin	27.8
Hard (M.P. 100-115°	
C.) 90%	
Soft (M.P. 20–30° C.)	
10%	
Portland Cement, Finely	
ground and quick set-	
ting	57.2
Asbestos or Asbestine	-4.6
Solvent (Water miscible)	10.4
Acetone 20%	
Methyl Ethyl Ketone	
80%	
No. 2	
Phenol-Aldehyde Resin	28.5

(In liquid stage)

Portland Cement, Finely ground 57.5 Asbestos or Asbestine 4.5 Solvent (Water miscible) 10.5 Cellosolve 15% Ethyl Alcohol 85%	"Nylon" Adhesives (for obtaining good anchorage between Nylon fabric and rubber or synthetic rubber coatings) Saturate fabric with solutions of Hexamethylene Diisocyanate
Water and Acid Resistant Glue for Plywood This is valuable in that it utilizes waste from phenol-formaldehyde molding wastes. It develops a bond stronger than the wood itself.  A. Glue Cold Setting Water Soluble Urea Form- aldehyde Resin S8 Water 29 Finely Ground Bake- lite Waste 13 (C stage phenol-formaldehyde resin) This may be spread on one surface. On the other surface the hardening agent is spread and pressure is applied to the contacting surfaces 'til cured. B. Hardening Agent This may be organo phosphate esters or ammonium salts such as the chloride, thio cyanate, nitrate.  Waterproof Adhesive Gutta Percha Pine Tar Pitch 100	Monomethylene Diisocyanate
Boat Plug Compound Portland Cement 75 Lanolin or Sublan 25 This is plugged into holes in boats, with or without oakum or rags to keep out water.  Vacuum Holding Wax Adhesive Beeswax 10 Rosin 10	2 Nitropropane 4 pt.  Methyl Ethyl Ketone 4 pt.  Toluol 1 pt.  Butyl Acetate 1 pt.  No. 3  For Polyvinyl Chloride Surfaces Solution A  Hycar OR 100  Zinc Oxide 2½  Butyl 8  Dissolve one pound of stock in

ethylene dichloride and dilute to form one gallon.

#### Solution B

Hycar OR	100
Zinc Oxide	$2\frac{1}{2}$
Sulphur	3

Dissolve one pound of stock in ethylene dichloride and dilute to

form one gallon.

Mix equal parts of A and B when ready for use. Add 10% benzyl alcohol. This cement gives films which are tacky for long periods of time. Cure: 5 hours at 158° F.

#### No. 4

	Hycar OR	15.20
	Dibutyl Phthalate	4.90
	Cumar P 25	4.90
	Whiting	15.15
	Iron Oxide, Black	3.60
	Iron Oxide, Yellow	3.60
	Zinc Oxide	3.60
	Sulphur	0.35
	Nitroethane	18.90
	Methyl Ethyl Ketone	14.90
	Ethyl Acetate	14.90
A	dd before use:	

Captax Mill Hycar 20-30 minutes; add sulphur, pigments and filler. Mill together for 3-5 minutes. Soak stock in nitroethane for at least 1 hour followed by mixing and adding of dibutyl phthalate and cumar.

0.27

Thin this heavy paste with rest of solvents while mixing thoroughly. Add the Captax as a 10% solution in methyl ethyl ketone before using.

#### Nitrocellulose Cement 8.7 Nitrocellulose (15 sec.) 4.0 Camphor 37.8 Acetone Butyl Acetate 44.0 5.0 Methanol 0.5 Nigrosin (Dye)

Instrument Cross-Ha	ir Cen	nent
Pyroxylin (5–6 sec.)	30	g.
Acetone	100	cc.
Amyl Acetate	42	cc.
Butyl Acetate	18	cc.
Ethyl Acetate	15	cc.
Theop (Plasticizer)	$\frac{1}{2}$	cc.
Ethyl Abietate	1	cc.

#### Dental Cement

This is used in dentistry by mixing, just before use, 1 g. of the powder and 0.2 cc. of the liquid:

Zinc Acetate	0.1
Zinc Stearate	1.0
Zinc Oxide	70.0
Rosin (Water White)	28.5

Powder the rosin, incorporate an equal weight of zinc oxide until thoroughly mixed; sift through a 100 mesh sieve. Regrind the unsieved material with more zinc oxide and sift again, repeating the process until all passes through the sieve. Mix the other zinc salts with zinc oxide and pass through a 100 mesh sieve.

85 cc. Eugenol Cottonseed Oil 15 cc.

Temporary Dental Cement Zinc oxide U.S.P. is mixed with just enough eugenol U.S.P. to make it plastic and workable.

#### RUBBER CEMENT FOR PAPER

Masticated

Rubber 8 g. 100 cc. Solvent Standard

Viscous

Oil No. 32 3 g. or more

The solvent may be of variable composition according to conflicting requirements of safety and expense. For a fire-proof solvent use 80 cc. of carbon tetrachloride and

20 cc. of light petroleum thinner. For a fire-resistant product of low hazard, use 50–50 proportions of tetrachloride and thinner. For a cheap solvent regardless of fire hazard, use straight petroleum solvents, which will be satisfactory mechanically. Commercial light "rubber solvents" are available; these contain relatively large fractions of the aromatic solvents benzene and possibly toluene.

The viscous oil gives the product a tacky character, permitting easier stripping. Rosin is often used instead. Varying proportions should be tried to give the desired degree of tackiness.

If only common crepe rubber, not sticky to the touch, is available instead of the relative tacky masticated product, it will be necessary to use a mechanical stirrer for some hours to break down the jelly-like structure obtained by such a formula.

#### Rubber Sole Cement

This cement hot vulcanizes rubber soles to leather without bonding with gutta percha.

zon Baron Pozona.	
Synthetic Rubber	100
Lampblack	80
Rosin	20
Stearic Acid	<b>2</b>
Zinc Oxide	1
Sulphur	2.6
Tetramethylthiuram	
Disulphide	0.3
1-Mercaptobenzothiazole	1.2

Fiber Container Adhesive (Thermoplastic Adhesive) U. S. Patent 2,259,490 Polymerized Vinyl Acetate 70 Dammar 30 Melt together and apply above 300° F. This retains its adhesiveness at high temperatures.

Hycar (Butadine Rubber) Cement Hycar OR Compound 1.6 lb. Methyl Ethyl Ketone 0.7 gal. Chlorobenzene 0.3 gal.

General Purpose Air Curing
"Hyear" Cement
High Tensile Strength

	A	$\mathbf{B}$
Hycar OR	100	100
Channel Black	35	35
Catalpo "X"	15	15
Zinc Oxide	5	5
Agerite Resin	5	5
Nevoll	30	25
Cumar P25	25	26
Sulphur	4	-
Butyl 8	********	8
Dissolve each part	t separa	itely in:
Chlorobenzene		70
2 Nitropropane		20
Methyl Ethyl Ket	one	10
Use same weight 1	er gall	on.

To use, add equal volumes of A and B.

#### THERMOSETTING CEMENTS

Formula No. 1

The use of Glyceryl Phthalate is suggested to replace shellac in alcoholic phenol-formaldehyde thermosetting cements for lamp and radio tube bases. Less glyceryl phthalate is required than shellac and it gives better thermoplastic effects before heat setting.

No. 2 Canadian Patent 395,145 hyl Cellulose 62

Ethyl Cellulose	62.0
Alcohol	11.6
Ethyl Acetate	10.0
Dibutyl Phthalate	12.4
Carnauba Wax	4.0

		1	
Pressure Sensitive Adhes	sive	tains polymerized meta	crylic acid
Nitrocellulose	35	100, ortho-dibutyl phtha	
Flexalyn (Diglycol		chlorinated rubber 10-40	
Abietate)	45		
Dibutyl Phthalate	25	Cellulose Acetate Con	npositing
		Cement	apostoring
Adhesive, Bitumen to Ru	hher	Acetone	3
British Patent 521,401		Ethyl Lactate	í
Rubber, Powdered	50	Emyl Dactate	
Petroleum Bitumen	900	Callulaid to Wood on Cla	th Comont
		Celluloid to Wood or Clo	
Heat and digest until dis	ssorved.	Transparent pyroxylin	
Then add a solution of	10	scrap	30 lb.
Zinc Oleate	10	Acetone	16 gal.
Light Hydrocarbon Oil	100	Butyl Acetate	4 gal.
Mix well until uniform.			•
		Luminous Laminating	
Wood Joining Adhesiv	e	British Patent 530	),065
Celluloid	1	Acetone	100 cc.
Butyl Acetate	5	Cellulose Acetate	10 g.
-		Calcium Sulphide,	
Wood Laminating Adhes	sive	Luminescent	20 g.
U. S. Patent 2,290,833		Use between two sheet	ts of trans-
Formula No. 1		parent cellulose acetate.	
Microcrystalline Wax	10		•
Rosin	13	CHEAP BELTING	PASTE
Oxidized Asphalt	77	Black Treacle	
No. 2		(Molasses)	2 lb.
Oxidized Asphalt	80	Rosin, Powdered	½ lb.
Nuba Rosin No. 2	20	Whiting	$\frac{3}{4}$ lb.
11404 100011 110. 2		Black Soot	2 oz.
Laminating Adhesive		Mix thoroughly and	
		inside the belt.	ab a mono
U. S. Patent 2,229,028	100	mside one bett.	
Zein	275	ASPHALT ROOFING	CEMENT
Alcohol (95%)	10		
Benzol		(A Troweling Asphalt Co	
Castor Oil	10 5	Asphalt, Cutback	66
Formaldehyde		Slate Flour	16
Dip sheets in above solution		"Short Fiber" Asbesto	
and heat under pressure to la	minate.	"Long Fiber" Asbesto	s 7
		The materials are ad	
Laminating and Stiffening A	dhesive	order given, using a hoe	and mortar
U. S. Patent 2,120,054		box or mechanical mixin	g. The first
An adhesive which may		three ingredients should	d be well
in laminating and coating fa	brics to	mixed before adding the	"long fiber"
produce a permanent stiffn	ess not	asbestos. All materials s	hould be at
affected by washing or ironi	ng con-	room temperature. The	ratio of re-

agents may be varied in accordance with the grade of asphalt used.

#### CEMENT FOR PIPE LEAKS

A modified glycerin-litharge cement that is water-proof, resistant to fairly high temperatures and that sets under water may be used to repair leaks in pipes. To prepare this compound for use, equal parts of cement and litharge are thoroughly mixed together and then a volume of glycerin equal to half the volume of the mixed powders is added and the whole thoroughly mixed with a spatula or similar flat-blade tool.

When repairing a leaky pipe, the hole is filled with the cement and bound in place with cheese cloth, then a quantity of the cement is daubed on the cloth wrapping and the whole is tightly bound with iron wire.

Although the powders may be mixed ready for use, the glycerin should be added only when the cement is needed for immediate use.

#### Metal Thread Connection Compound

Graphite	20
Rheolan (Special Pitch)	20
White Lead	120
Mineral Oil (SAE 60)	20
Petrolatum	20-30

Stone Table Repair Cement
Mix litharge and manganese dioxide to match color of table top.
Add glycerin until a soft putty is
formed and mix thoroughly and apply at once. This sets within an
hour.

This cement is useful on pipe joints, caulking seams in stones or metal and sealing in sight glasses, etc. Adhesive for Polythenes to Metal or Ceramics

British Patent 544,359
Polythene 1-2
Cyclorubber 1
Hot roll together and apply hot

Chloroprene to Metal Adhesive U. S. Patent 2,227,991

Chloroprene (30% Chlorine) 100
Sulphur 50
Dibutyl Phthalate 75
Accelerator 3
Magnesium Oxide 10
Lead Oxide 10

Joint Seal for Liquid Cooled Engines N-Butyl Methacrylate

Polymer 40–46 Toluene 54–60

47.5

200-400

#### FLEXIBLE ADHESIVE, NON STICKY METAL FINISH Formula No. 1

Asphalt

Gasoline

F. Rosin	47.5
Paraffin Wax (M.P.	
175° F.)	5.0
Calcium Carbonate	100.0
Gasoline	200-400.0
No. 2	
Rosin	50
Gilsonite	25
Petropol	25
Calcium Carbonate	100

#### CEMENT FOR GLASS OR METAL

The following composition has a very low viscosity when melted and can be pressed into a thin film which will have excellent adherence when cold:

Paraffin Wax	95
Piccolyte Resin	5

## WATERPROGF CEMENT FOR GLASS TO GLASS

Grind surface for better adhesion. Coat surfaces with 50° Bé Sodium silicate and apply 10 lb. pressure for 24 hours. Dry in oven 4 hours at 50° C. followed by four additional hours at 105° C. Immerse overnight in 5% Acetic acid.

#### Sealing Composition British Patent 517,037 Formula No. 1

This composition is most suitable for food containers comprising a body of one or more layers of a fibrous material and a metallic end.

Barytes	10.1
Asbestine	5.0
Gum Karaya	0.3
Bentonite	1.9
Glue	4.5
Glycerin	2.5
Casein	1.8
Ammonia (28%)	0.7
Rubber Latex (Solid Basis	2.0
Vulcanized Rubber Latex	5.0
Water	66.2

No. 2 French Patent 853.364

	,	
"Celluloid"	2.5	g.
Acetone	7	1.
Pigment	20	kg.
Vinyl Resin	80	g.

## ADHESIVE FOR TISSUE PAPER TO ALUMINUM

For geological survey and other types of map work, base maps are very often printed on thin sheets of aluminum. Topographic maps of this type require the names of rivers, towns, etc. to be printed on thin tissue paper which is then fastened to the base map at the proper spot by an adhesive. It is very important in work of this kind that the tissue paper does not tear off, become wrinkled or discolored, so that photoreproduction is not made difficult or impossible.

Flexo Wax C Light 40 g. Turpentine 57 cc.

The wax is melted in a porcelain dish, the turpentine is added and the solution mixed well and bottled. It solidifies on cooling, forming a tacky wax which can be remelted for use.

"Bakelite" Putty
"Bakelite" Lacquer 100
Barytes, Kaolin or
Graphite 200–280
Apply and heat at 80–100° C. for 12 hours.

#### Putty, Acid Resistant German Patent 702,739

Water glass (sodium oxide 20, silicon dioxide 60, water 20%) 2 parts, sodium fluosilicate 8.5 parts, clay 1.5 parts, and quartz flour 70 parts. The size of the quartz particle depends on the purpose of the putty.

## Putty for Joining Magnesium French Patent 850,700 Linseed Oil 28 Manganese Borate 1 Strontium Chromate 28 Strontium Fluoride 28 Magnesium Oxide 15

#### ASPHALT CAULKING MATERIAL

Asphalt	50
Powdered Clay	16
Slate Flour	34

The asphalt is melted, then the solids are added with stirring. The product may then be used by pouring into the desired crevice or may be allowed to solidify and may be melted and used as needed.

Fastening Cork to Metal

In fastening cork to iron and brass, even when these are lacquered, a good sealing wax containing shellac will be found to serve the purpose nicely. Wax prepared with rosin is not suitable. The cork surface is painted with the melted sealing wax. The surface of the metal is heated with a spirit flame entirely free from soot, until the sealing wax melts when pressed upon the metal surface. The wax is held in the flame until it burns, and it is then applied to the hot surface of the metal. The cork surface painted with sealing wax is now held in the flame, and as soon as the wax begins to melt, the cork is pressed firmly on the metallic surface bearing the wax.

Gas Tight Valve Seal	
British Patent 540,352	
Vermiculite	40
Grease	50
Mica or Tale	10

Vacuum Tube Vitreous Se	al
U. S. Patent 2,223,031	
Silica	28
Sodium Silicate	53
Ferric Oxide	19

Attaching Canvas to Walls
Before attaching ordinary canvas,
muslin or burlap to plaster walls,
the painter must first see to it that
the plaster is smooth, clean and dry.
Cracks should be dug out in the approved wedge-shaped manner and
filled with patching plaster. All
dents and surface imperfections
must be brought up level after a
preliminary size or primer has been
applied over the entire wall and allowed to dry. Spackle may be used

over the primer to provide a smooth, even surface. After sanding down the walls and dusting them thoroughly, a coat of white lead and lead mixing oil paint should be put on. This paint is made by mixing white lead with an equal volume of lead mixing oil.

When the paint is dry and hard, the adhesive should be applied. This adhesive is sometimes made of white lead (heavy paste) and good spar varnish but many painters and decorators prefer a white lead and lead mixing oil combination—about two gallons of the oil to the hundred pounds of lead. This heavy-bodied paint is spread evenly over the wall with an ordinary wide wall brush.

Before the adhesive sets up, the fabric-canvas, muslin, burlap, etc. —is hung, much in the manner of wall paper. In large public rooms or halls, when it is necessary to work from scaffolds, the canvas is first rolled on rug or linoleum poles, then hoisted to the scaffold. The top edge of the cloth is fastened at the top of the wall, using strips of wood nailed so as to hold the canvas in place. Then the roll of cloth is dropped so the lower edge reaches the bottom of the wall. The canvas is then pressed firmly to the white lead cement, using a stiff smoothing brush or some other suitable implement. All air bubbles and wrinkles should be very carefully worked out to the edges of the fabric.

With one vertical strip of fabric in place, the next strip is cemented to the wall in the same manner, the edge of this second strip overlapping the edge of the first strip by two to four inches, preparatory to producing a tight butted joint. After allowing sufficient time for the cement to partly set, a straightedge is held against the center of the overlapped joint and, using a very sharp blade, the double-lapped joint is cut through to the plaster.

### Cement (Household) or Celluloid Adhesive

A waterproof cement for making repairs on many different materials (it is especially good for leather) is easily and cheaply made by dissolving celluloid in "Cellosolve," amyl acetate, or ethyl acetate, or a similar moderately high-boiling solvent. Use about one part of celluloid to two parts of solvent. A few days are generally necessary for the solution to form and the material, during making and storing, must be kept in tightly closed vessels. Many different easily available objects will furnish celluloid, e.g., tooth brush handles, parasol handles, some of the "horn" spectacle frames, some novelties, as balls, cards, etc. Some produce clear and some opaque cements, and many different colors are available. This cement is similar to various "household" cements marketed in metal tubes.

Flypaper Ribbon	
Rubber	10
Rapeseed Oil	8
Wool Fat	<b>2</b>
Honey	1
Benzol	79

Dissolve rubber in benzol. Mix honey with the wool fat and this mixture with the rapeseed oil. Add the honey, wool fat, and oil mixture to the rubber solution. Distill off the benzol and spread the residue on properly sized paper.

## Flypaper Sheets Rosin 50 Blown Castor Oil 50 Melt rosin in oil by heating in a steam jacketed kettle; spread on properly sized paper.

Flypaper Adhesive Formula No. 1	
	~~
Rosin	52
Pine Oil	15
Rosin Oil	15
Thin Mineral Lubricating	
Oil	15
Glyceryl Bori-Borate	
("Aguaresin")	2
Glycerin	1
No. 2	
1. Rosin "H"	54
2. Mineral Oil (d. 0.885-	
0.900)	25
3. Rapeseed or Castor Oil	11
4. Gum Mastic	5
5. Paraffin Wax	3
6. Gutta Percha	2
2, 3, and 4 are warmed tog	gether

former.		
	No. 3	
Rubber		4
Rosin		60
Oleic Acid		34

and mixed until dissolved. Do the

same to 1 and 6 and then add to the

Dissolve the rubber in the oleic acid with heat. Add the rosin and heat until it is melted. Mix well and spread hot on paper.

#### CHAPTER THREE

#### BEVERAGES

Grape Wine

Measure out 1 quart clean Concord grapes in a cup. Place these in a 1 gallon jug and add a sugar solution composed of 3 to  $3\frac{1}{2}$  pounds of sugar, depending on what sweetness is wanted. For a medium wine, use 1 quart of water and  $3\frac{1}{4}$  pounds of sugar dissolved therein. Now pour this over the grapes in the jug, add a small piece of a yeast cake dissolved in 1 cup of water, and fill the jug to within 4-5 inches of the top. Next shake the jug to mix the grapes, water, sugar water, and yeast and then tie a piece of cloth over the top of the jug to keep out gnats, and let it ferment. Do not stopper the jug during fermentation. After about 3-4 weeks the fermentation has about ceased, if the jug and contents have been kept in a warm place. Next, strain off the grapes, press out the remaining juice and pomace and let work or ferment for another 2 weeks. At the end of this time filter or strain through a double folded cloth, bottle, and set away to age. At the end of 5–6 months nearly a full gallon of ruby red grape wine will be ready.

#### Golden Dynamite or Cornmeal Wine

Place 1 lb. of yellow commeal in a crock and add 1 gallon of water. Squeeze out the juice of 3 lemons and 3 oranges and add to the crock. Now add 1 lb. of ground raisins, 4

lb. of sugar, and 1 yeast cake. Set aside in a warm place to ferment and stir once a day for at least 30 days. Strain at the end of this time, and bottle. This makes a very potent, powerful wine.

#### Mint Wine

Mint Leaves 1 qt.
Juice and Pulp of 3 Oranges
Juice and Pulp of 3 Lemons

Mash all the above together, add 1 quart of warm water and let set over night—or 24 hours.

Now add 4 lb. of sugar, 3 more quarts of water, ½ of a yeast cake and set away to ferment. After about 4 to 5 weeks when the fermentation is complete, and no more bubbles are seen rising in the mixture, strain and bottle. This makes a light amber colored, mint flavored wine.

#### Stabilizing Alcoholic Beverages U. S. Patent 2,075,653

Non-distilled alcoholic beverages, particularly wines, are stabilized against hazes due to iron, aluminum, copper and calcium by addition of 0.1–1 gal. of soluble sodium phosphite. The liquor is agitated, and the precipitate which has appeared in about 12–18 hours later is removed by filtration.

General Formula for Flavors Terpeneless Oil 3/8 fl. oz.

fl. oz.

fl. oz.

3

 $\frac{1}{\frac{1}{4}}$ 

91

10

6

For usual purposes, 2 fl. oz. can

be used per gal. of syrup.	oz. can
the state of the s	
Non-Alcoholic Flavo	
U. S. Patent 2,180,93  Lemon Flavor	52
Lemon Oil	5
Monoethylglycerin	95
Orange Flavor	, 50
Sweet Orange Oil	5
Diethyl Glycerin	95
$Imitation\ Vanilla\ Flau$	vor
Vanillin 1½	$_{2}^{\prime }$ oz.
Coumarin ½	4 oz.
Monoethylglycerin 10	OZ.
Caramel 1	OZ.
Water, To make 1	gal.
Vanilla Bean Flavor	
Mix 30 parts of monoeth	nylglyc-
erin with 70 parts of water	
this diluted solvent as a men	
for the percolation of vanill	
Imitation Raspberry Fl	$rac{avor}{96}$
Monoethylglycerin Orris Concrete	$\frac{1}{2}$
Benzyl Acetate	$9^{72}$
Vanillin	1/s
Rhodinol	1/8
Ionone	1/4
Amyl Butyrate	2
Ethyl Pelargonate	$1\frac{1}{2}$
Ethyl Benzoate	$\frac{1}{2}$
Amyl Acetate	4
Raspberry Juice	40
$Imitation\ Banana\ Flav$	
Ethyl Pelargonate	$2\frac{1}{2}$
Ethyl Butyrate	$3\frac{1}{4}$
Amyl Butyrate	$11\frac{1}{4}$
Ethyl Acetate	$2\frac{3}{4}$
Amyl Acetate	12

Sweet Orange Oil

Amly Valerianate

Diethyl Glycerin

Lavender Flowers Oil

(essential)

Distilled Water

Alcohol

#### Apple Juice

Select sound firm-ripe autumn or winter apples.

Wash carefully.

Crush apples in grinder.

Press in barrel or hydraulic press. Strain juice through muslin or cheesecloth.

Heat juice promptly and rapidly to 170°-175° F. in upper part of double boiler.

Without cooling, fill immediately, into fruit enamel-lined cans, or into hot sterile glass jars, hot crown-closure bottles, or hot screw-top glass jugs, taking care to remove foam and to fill each container completely.

Close each container immediately.
Invert cans or place bottles or jars on their sides for 3 to 5 minutes.

Place in hot water (160°-165°F.) and cool with running water.

#### Grape Juice

Select, preferably, fully ripe Concord, or Concord type grapes. Catawba and Ives also give excellent products.

Wash carefully.

Remove grapes from stems.

Crush grapes in grape crusher.

Heat crushed grapes to 140°-145° F. in upper part of double boiler.

Press hot grapes in barrel press or hydraulic press.

Strain juice through muslin or cheesecloth.

Heat juice rapidly to 170°-175° F. in upper part of double boiler.

Without cooling, fill immediately into large hot fruit jars or hot screwtop glass jugs taking care to remove foam and to fill each container completely.

Close each container immediately.

Invert container or lay on side for three to five minutes. Place in water at 160°-165° F., and cool bottle in running water.

Allow to stand in cool cellar 3 or more months.

Carefully siphon supernatant juice from sediment, and pass juice from bottom (containing sediment) through heavy muslin cloth.

Heat juice rapidly to 170° F. in

upper part of double boiler.

Without cooling, fill immediately into hot, sterile fruit jars, hot crown-closure bottles, or hot screw-top glass jugs, taking care to remove the foam and to fill each container completely.

Close immediately and cool as directed above.

Cherry Juice—Cold Pressed
Use sound, fully ripe, Montmorency or English Morello cherries or a mixture of the two varieties.

Wash carefully.

Crush cherries in grape crusher. Press in barrel-press or hydraulic press.

Strain juice through muslin or cheesecloth.

Heat juice promptly and rapidly to 170° F. in upper part of double boiler.

Without cooling, fill immediately into fruit-enamel-lined cans, or into hot, sterile, glass jars, hot crown-closure bottles, or hot screw-top glass jugs, taking care to remove foam and to fill each container completely.

Close each container immediately, invert or place on side for three to five minutes. Place in water at 160°-165° F., and

Cool with running water.

Cherry Juice—Hot Pressed

Use sound, fully ripe, Montmorency or English Morello cherries or a mixture of the two varieties.

Wash carefully.

Crush cherries in grape crusher.

Heat crushed cherries to 175°–180° F. in upper part of double boiler.

Press hot cherries in barrel press or hydraulic press.

Strain juice through muslin or cheesecloth.

Heat juice promptly and rapidly to 170° F. in upper part of double boiler.

Without cooling, fill immediately into fruit-enamel-lined cans, or into hot, sterile, glass jars, hot crown-closure bottles, or hot screw-top glass jugs, taking care to remove foam and to fill each container completely.

Close each container immediately.
Cool as directed above.

Raspberry Juice

This procedure may be followed for the making and preservation of red, black and purple raspberries, loganberries, blackberries, youngberries, boysenberries and dewberries.

Select soft, ripe fruit, preferably of a highly colored and flavored variety.

Wash carefully.

Mix with granulated sugar, using 10 parts fruit to 1 part sugar by weight.

Fill into heavily paraffined paperboard cartons or fruit-enamel-lined tin cans.

Close containers.

Freeze in locker plant or farm freezer, and store until needed.

Without opening containers thaw in a refrigerator or at room temperature before a fan.

Immediately after thawing, press in barrel-press or hydraulic press. (See alternate method.)

Strain juice through muslin or cheesecloth.

Heat juice promptly and rapidly to 170-172° F. in upper part of double boiler.

Without cooling, fill immediately into fruit-enamel-lined cans, or into hot, sterile, glass jars, hot crown-closure bottles, or screw-top glass jugs, taking care to remove foam and to fill each container completely.

Close each container immediately. Invert or turn containers on side. Air cool for three to five minutes, then place in warm water 150° F., and

Cool with running water.

#### Alternate Method for Pulpy Juice

If pulpy berry juice is desired, the thawed juice may be passed through a collander or a taper screw press to separate the seeds and more solid parts.

Heat juice promptly and rapidly to 180°-185° F., in the upper part of a double boiler and continue as directed for pressed juice.

Because of difficulty of removing the air from the juice, it will not retain its quality as well as pressed juice, but may be used satisfactorily in fruit juice blends.

#### Plum Juice

Select soft, ripe fruit, preferably of a highly colored and flavored

variety. Press (undried) prunes may be used.

Wash carefully.

Pit and cut in halves.

Mix well with granulated sugar, using 10 parts of fruit to 1 part sugar by weight.

Fill into heavily paraffined paperboard cartons or fruit-enamel-lined tin caps.

Close containers.

Freeze in locker plant or farm freezer and store until needed.

Thaw, without opening containers, in a refrigerator or before a fan.

Immediately after thawing, crush in grape crusher.

Press in barrel-press or hydraulic press.

Strain juice through cheese cloth. Heat juice promptly and rapidly to 170°–175° F. in upper part of double boiler.

Without cooling, fill immediately into fruit-enamel-lined cans, or into hot sterile glass jars, hot crown-closure bottles or screw-top glass jugs, taking care to remove foam and to fill each container completely.

Close each container immediately.
Invert or place container on side.
Air cool three to five minutes.

Place in hot water at 160°-165° F. then cool as directed above.

## Blended Fruit Juices Apple Berry

Most berry juices are too strong to be palatable unless they are either sweetened and diluted with water or blended with a bland juice, such as that of the apple. The exact proportion of any berry juice to use will depend upon its acidity and amount of flavor. In the case of highly flavored berries, such as black raspberries, three to four parts of apple juice may be used with one of raspberry juice. If the berry juice is milder in flavor, two parts of berry juice to one part of apple juice may be a satisfactory proportion.

Blending of the preserved juices may be done just before use, or preserved (canned or frozen) berry juices may be blended with either freshly prepared or preserved apple juice and the product pasteurized as directed below. Apple juice may be added to the thawing berries (see section on berry juices) and pressed with the berries. The latter method will result in the greatest yield from the berries.

Blend juices to give pleasing flavor.

Sweeten with sugar, if a sweeter juice is desired.

Heat juice rapidly to 170°-180° F. in upper part of double boiler.

Without cooling, fill immediately into fruit-enamel-lined cans, or into hot, sterile, glass jars, hot crownclosure bottles, or hot screw top glass jugs taking care to remove foam and fill each container completely.

Close each container immediately. Invert or place container on its side. Air cool for three to five minutes. Place in water at 160°-165° F.

Cool with running water.

 $Apple\ Cherry$ 

The juice of sour cherries (Montmorency, English Morello and Early Richmond) is too intense and tart for consumption without sweetening, and dilution with water or blending with apple juice. Two parts of apple juice should be blended with

one part of hot pressed cherry juice. Cold pressed cherry juice should be blended with an equal amount of apple juice.

The blended juice should be pasteurized in the same manner as the

apple-berry blend.

 $Apple\ Plum$ 

The juice of most varieties of plums is too strong for consumption without dilution with water or blending with apple juice. As a rule, plum juices should be blended with an equal volume of apple juice. The blended juice should be pasteurized in the same manner as the appleberry juice blend.

#### Tomato Juice

Select fully red ripe tomatoes.

Wash thoroughly and remove all green, yellow, black and rotted areas. Cut out stem end.

Quarter tomatoes, and heat to boiling.

Strain through a sieve, collander or tapered screw press or any other type of screening device. The finer screens give a smoother juice.

Add salt, approximately 1 tea-

spoon per pint.

Heat rapidly to 190°-200° F. in the upper part of a double boiler or in a kettle with continued stirring.

Without cooling, fill immediately into hot sterile glass jars, hot crown closure bottles or tin cans, taking care to remove foam and to fill each container completely.

Close each container immediately and place in hot water at 190° F. and hold for five minutes.

nd noid for live infinites

Remove containers, cool.

Tomato Juice Blends, or Cocktails

Tomato juice blends or cocktails of delightful flavor may be prepared by mixing with various vegetable juices. After blending they are preserved by the methods as described for tomato juice. A few satisfactory blends are as follows:

Four parts tomato juice and one

part sauerkraut juice.

Four parts tomato juice and one part celery sauerkraut juice.

Tomato juice with five per cent

turnip juice.

Tomato juice with two to three

per cent beet juice.

The beet juice may also be added to the first combination to give a deeper red color to the cocktail.

If sauerkraut juice is not available, vinegar or lemon juice may be used but they do not impart the same flavor.

#### Sauerkraut Juice

Excess sauerkraut juice is nearly always present in vats or barrels of sauerkraut. This juice contains approximately the same nutritive qualities that are present in kraut including from one to two per cent of digestible organic acid.

Kraut juice may be obtained from the bottoms of barrels of kraut made in the home or from vats of kraut made by commercial packers.

Heat the juice to 160°-165° F. in the upper part of a double boiler or in a kettle stirring continuously.

Without cooling fill immediately into hot sterile crown closure bottles, glass jars or tin cans taking care to fill each container completely.

Close each container immediately and invert to air cool three to five

minutes. Place in warm water, 150° F. and add running water to cool.

#### Rhubarb Juice

Select tender and juicy stalks of rhubarb. Red varieties give the best color.

Wash thoroughly and drain excess water.

Cut in pieces four to six inches long.

Cook until tender, but not until mushy.

Press in a barrel type press while hot, using muslin cloth or fine pore press cloth.

Sweeten if desired. One pound per

gallon is usually sufficient.

Heat to 165°-170° F. in an aluminum or white enamel kettle, stirring continually.

Without cooling, fill immediately into fruit-enamel-lined tin cans, hot sterile glass jars or hot crown closure bottles, taking care to remove foam and to fill each container completely.

Close each container immediately, invert it or turn on its side and cool for three to five minutes.

Place in warm water 155° F. and add running water to cool.

#### Alternate Procedure

After washing and cutting the rhubarb as directed above it may be mixed with sugar ten to one, placed in fruit-enamel-lined tin cans or heavily paraffined paperboard container for freezing.

Place in a sharp freezer or in a cold storage locker and freeze.

At a later date, thaw.

Extract the juice, sweeten and preserve as directed above.

#### Carrot Juice

Select large, well formed carrots. Wash, peel and remove green parts.

Shred and extract the juice in a centrifugal extractor.

Three different procedures may be used for preserving the juice.

First Method—Freezing

The extracted juice may be placed in heavily paraffined paperboard containers and frozen in a sharp freezer or locker cold storage plant.

Second Method—Acidification

The carrot juice may be mixed in equal quantities with high acid sauerkraut juice.

After blending, heat rapidly to 190°-195° F. in double boiler or kettle, stirring continuously.

Without cooling, fill immediately into hot sterile glass jars, hot crown closure bottles or tin cans, taking care to remove foam and to fill each container completely.

Close each container immediately and place in hot water at 190° F. and hold for five minutes.

Cool by running in cold water.

#### Third Method

The carrot juice may be sterilized in a pressure cooker.

Heat juice to 160°-170° F. Fill into glass jars or tin cans. Sterilize in a pressure cooker at 10 pounds pressure for 30 minutes. When pressure is released, glass jars should be tightly sealed.

Air cool.

Other Vegetable Juices—Celery. Beet, Turnips Various vegetable juices are nutritious and flavorable and blend very well with each other as well as with tomato juice. The centrifugal extractor or similar device is required to extract fresh juice from the hard vegetables.

Wash, trim and extract juice.

Three different procedures may be used for preserving these juices.

#### First Method—Freezing

The extracted juice may be placed in heavily paraffined paperboard containers and frozen in a sharp freezer or locker cold storage plant.

#### Second Method—Acidification

The vegetable juice may be mixed with one-half the quantity of high acid sauerkraut juice.

After blending, heat rapidly to 190°-195° F. in a double boiler or kettle, with continued stirring.

Without cooling, fill immediately into hot sterile glass jars, hot crown closure bottles or tin cans, taking care to remove foam and to fill each container completely.

Close each container immediately and place in hot water at 190° F.

and hold for five minutes.

Cool by running in cold water

#### Third Method

The vegetable juice may be sterilized in a pressure cooker.

Heat juice to 160°-170° F. Fill into glass jars or tin cans. Sterilize in a pressure cooker at ten pounds pressure for 30 minutes. When pressure is released, glass jars should be tightly sealed.

Air cool.

### STORAGE OF FRUIT AND VEGETABLE JUICES

Regardless of the care taken in preparation and preservation of fruit and vegetable byproducts, they will slowly deteriorate in quality over a period of time particularly if kept in a fairly warm place. This loss of quality may be reduced to a minimum by storage at low temperature, for example in a cold dry cellar.

Prepared Orange Beverage Sugar 64 lb. Salt 2 oz. Powdered Orange
Juice 2 lb. 8 oz.
Citric Acid 1 lb. 8 oz.
California Orange
Oil 2 oz.
Orange Color, Pure
Food 3 oz.

Place 48 lb. of sugar, salt, powdered orange juice and citric acid in machine bowl and blend thoroughly. Blend 16 lb. of sugar, orange oil and color carefully and add to first mixture. Use additional sugar as required.

Mix well and sift through fine sieve. One pound produces one gallon or more of beverage.

#### CHAPTER FOUR

#### COSMETICS AND DRUGS

#### Cosmetic Creams

	Formula	No. 1	$^2$	3	4
	(1. Sorbitol Syrup	2.5	3.9	5.0	2.5
Α.	2. Potassium Carbonate 3. Potassium Hydroxide 4. Triethanolamine	0.9 **	0.8	0.9 **	1.7
	5. Water 6. Preservative *	$77.8 \\ 0.15$	$74.5 \\ 0.15$	$   \begin{array}{c}     50.0 \\     0.15   \end{array} $	$72.5 \\ 0.15$
	"Moldex". 0.7 to 1.0.				
	7. Stearic Acid 8. Lanolin 9. Mineral Oil (65/75)	$15.0 \\ 0.5 \\ 2.0$	15.4 $1.2$ $1.5$	6.0 0.5 35.3	4.0 $2.0$ $15.0$
В.	10. Sorbitan Mono-oleate 11. Mannitan Monostearate 12. Spermaceti	2.0	0.8 — 1.5	2.0	2.0
C	13. Perfume	0.2	0.2	0.2	0.2

Warm (A) and (B) separately to 75–80° C.

Add (B) to (A) slowly and with thorough agitation.

Add (C) at 50° C.

Note: Stir No. 1 and No. 2 intermittently and when body has increased, turn over by hand. No. 1 cream may be poured directly into jars at 58° C. No. 4 cream must be passed through colloid mill or homogenizer while

still fluid.

No. 3 cream should be stirred until cold, set aside over night and remixed the following morning.

No. 1-Vanishing Cream

No. 2-Hand Cream

No. 3—All Purpose Cream

No. 4—Liquid Cream

Modifications

For modification of the above formulas, the following will serve as guides:

Brushless Shaving Cream: Formula No. 2. Increase the potassium hydroxide to 1.3 parts.

40

Foundation Cream: Formula No. 2. Add 2% titanium dioxide.

Powder Cream: Formula No. 2. Add 5% titanium dioxide and color lakes.

Emollient Skin Cream: Formula No. 3. Increase lanolin to 5% or as required.

Liquid Cleanser: Formula No. 4.

Hand Lotion: Formula No. 4. Reduce mineral oil to not over 5%, increasing water by like percentage.

Liquid Powder Base: Formula No. 4. Reduce mineral oil to 5% as

above.

Hair Dressing: Formula No. 4.

Simple Cold (	Cream
White Beeswax	1 oz.
Paraffin Wax	2 dr.
Light Mineral Oil	4 fl. oz.
Water	3 fl. oz.
Borax	25 gr.
Perfume	q. s.

Melt the first three ingredients together. Add the borax dissolved in the water at 70° C. Stir until thick. Perfume may be worked in before mixture becomes too thick.

Vitamin Cold Creat	m	
Niacin	10	
Pantothenic Acid	10	g.
Distilled Water	<b>2</b> 0	
Lanolin (Anhydrous)	40	g.
Whipped White Petrola-		
tum Jelly	30	g.

"Nourishing" Cream	
Formula No. 1	
Beeswax	18
Raisin Seed Oil	30
Olive Oil, Odorless	16
Lanolin	<b>2</b>
Cetyl Alcohol	<b>2</b>
Cholesterol	0.1
Water	30.9
Borax	1.0
No. 2	

A special nourishing cream contains 7.5 cetyl stearate, 7.5 cetyl al-

cohol, 5 glycerin, 10 absorption base, 9.7 white vaseline, 0.5 vitamin F, 15 lauryl sulfonate, water 54.5.

#### Honey Cream

6.5 diethylene glycol myristate, 18 lanolin, 41 absorption base, 14 cucumber seed oil, 2 cetyl alcohol, 2 myristyl alcohol, 3 honey, 13.5 water or rose water.

Dermal Cream	
Water, Distilled	74.0
Sesame Oil	20.0
Citrus Pectin	5.0
Citric Acid	1.0

Citric Acid	1.0
Liquid Crear	
Formula No.	
Stearic Acid	3.0
Raisin Seed Oil	10.0
Liquid Paraffin	10.0
Triethanolamine	1.5
Water	<b>75.5</b>
Preservative	Sufficient
No. 2	
Propylene Glycol	
Laurate	15.0
Raisin Seed Oil	30.0
Water	55.0
Preservative	Sufficient
No. 3	
Glyceryl Monostea-	

rate

14

-			
Avocado Pear Oil	12	Aluminum Chloride,	
Cetyl Alcohol	1	Hydrated Crystals	12
Water	70	Water To mak	e 100
Glycerin	3		
Preservative	Sufficient	A	
No. 4		Antiseptic Cream	
Propylene Glycol		Emulgor A (Polymerized	
Stearate	15	Glycol Ester)	10.0
Avocado Pear Oil	5	Stearic Acid	10.0
Raisin Seed Oil	5	Paraffin Wax	15.0
Water	70	Mineral Oil	15.0
Glycerin	5	Petrolatum	10.0
Preservative	Sufficient	Oxy-Quinoline Sulfate	0.2
No. 5		Water To mak	e 100
Diethylene Glycol			
Monolaurate	16.0	Town Jeties Com	
Liquid Paraffin	8.0	Foundation Cream	
Raisin Seed Oil	8.0	Lanolin Concentrate	01/
Water	68.0	(Parachol)	$3\frac{1}{4}$
Preservative	Sufficient	Lanolin	6
No. 6	Samoioni	A Cocoa Butter	5
29 mineral oil, 6 isop	ronanolamine	Cetyl Alcohol	15
oleate, 64.5 distilled v		Glyceryl Stearate	
perfume.	vasci ana o.o	(Mono)	30
No. 7		Melt to 70° C.	
Falba Absorption B	ase 15.0	n ( Water	41
Liquid Paraffin	20.0	B Heat to 70° C.	
Raisin Seed Oil	23.0	Add A to B and agitate un	til cool
Water	42.0	Perfume to suit.	022 00021
44 500T	12.0	i ciramo os saro.	
Marine Commission of the Commi	-	77 : 1:	
Salt Containing Cost	netic Cream	Vanishing Cream	070
Polymerized Glycol		Stearic Acid	25.0
Stearate	10	Spermaceti	5.0
Stearic Acid	10	Aminomethylpropanediol	1.5
Paraffin Wax	15	Glycerin	8.0
Mineral Oil	15	Water	60.5
Petrolatum	10	The aminomethylpropa	
Sodium Chloride	6	glycerin, and water are hea	
Water	o make 100	gether to about 75° C. (16	
		while the stearic acid and s	
Manager of the public of the second s		ceti are heated in another co	
Aluminum Chlorid		When both mixtures are at the	
Polymerized Glycol		temperature and homogeneous	
Stearate	15	stearic acid-spermaceti mix	
Spermaceti	5	slowly and thoroughly stirr	ed into
Glycerin	3	the aqueous solution. The te	
0.0		•	

ture must be maintained at approximately 75° C. throughout this operation. After the acid-wax melt has all been added, heating is discontinued. However, vigorous stirring is maintained until the mixture thickens at which point the stirring should be slowed down and changed to a kneading action. Like all stearate creams, it should be allowed to stand overnight and then thoroughly remixed.

Beauty Mask	
Bentonite	10.0
Alcohol	10.0
Purified Kaolin	35.0
Glycerin	13.0
Tragacanth (Mucilage)	20.0
Water	10.9
Perfume	1.0
Methyl-p-hydrobenzoate	0.1
Skin Protectives Formula No. 1	
Beeswax	5.0
Glyceryl Monostearate	12.5
Hydrous Wool Fat	5.0
Sodium Silicate	5.0
Ammonium Hydroxide	
(10% sol.)	0.5
Petrolatum	72.5
ml	. :. :.

The ammonium hydroxide is incorporated to prevent the precipitation of the sodium silicate. The above formula with 5% latex gives a product which produces a rubberlike film on the skin. The base is melted, the latex added with stirring and the mixture stirred constantly until it congeals.

No. 2	
Beeswax	10.0
Hydrous Wool Fat	5.0
Glyceryl Monostearate	12.5
Stearic Acid	2.0
Petrolatum	75.5

This cream has a pH of 5.4 and is recommended where there is prolonged contact of the hands with soapy water.

No. 3	
Beeswax	10.0
Hydrous Wool Fat	5.0
Sulfonated Olive Oil	
(75%)	10.0
Petrolatum	75.0

This cream is useful to waterproof the skin when there is prolonged contact with water.

The following is a non-greasy preparation which dries on the skin and does not rub off. Its use is indicated for dry work as a protection against dust-borne irritants or where workers must guard against soiling the materials or objects with which they are working.

No. 4	
Glyceryl Monostearate	12.0
Beeswax	12.0
Hydrous Wool Fat	6.0
Cholesterol	1.0
Sodium Silicate	5.0
Ammonium Hydroxide	
(10% sol.)	0.5
Water	63.5

Melt together the white wax, glyceryl monostearate, the wool fat and cholesterol. Heat the water to the same temperature as the wax mixture and add the sodium silicate and ammonium hydroxide solutions. Stir the aqueous solution into the wax mixture and continue stirring until it congeals.

No. 5	
Glycosterin	40 g.
Diglycol Laurate,	
Neutral	90 g.
Triple Pressed Stearic	
$\mathbf{Acid}$	180 g.
Glycerin	60 g.

Sulfatate (2% Solu-	
tion) 100	cc.
Methyl Cellulose (5%	
Solution) 150	cc.
Water 350	cc.
Perfume 5	cc.
This girres a reary smooth	hand

This gives a very smooth hand cream which is not greasy but softens the skin and minimizes the absorption of grease, oil or dirt.

#### No. 6

Stearic Acid	2	OZ.
White Beeswax	1	oz.
Petrolatum	$2\frac{1}{2}$	oz.
Mineral Oil	$1\frac{1}{2}$	OZ.
Melt and emulsify wit		
heated Triethanola-	•	
mine	4	dr.
Boiling Water, To		
make	24	oz.
Then incorporate Mag	5-	
nesium Stearate	2	oz.

No. 7 No. 8

Mixture of Cetyl and		
Stearyl Alcohols		
Containing Sulfated		
Derivatives	12	2
Liquid Petrolatum	12	12
Lanolin, Anhydrous	6	6
Water, Distilled	70	70
Perfume, To suit		
Cetyl and Stearyl		

Alcohols To suit 10

Heat together all constituents except perfume over a water bath until emulsified and stir until cold, working in the perfume. It is not necessary to run through a homogenizer but the latter procedure improves the product. A preservative should be incorporated unless the cream is to be used immediately. For various consistencies, paraffin wax may be substituted for lanolin and the proportions altered accord-

ingly. A suitable mild organic acid might be added to the water phase to adjust the pH to that of normal skins.

Cover Paint for Skin Discolorations
So-called cover paints used to conceal and blend the white, pigmentfree skin spots characteristic of
vitigilo (acquired leukoderma) can
also be used to temporarily cover
other smooth skin blemishes, scars
or marks. Moreover, such products,
if properly made, can also be useful
to soften and blend the often sharp
sunburn lines so frequently seen at
the end of the summer season.

it cita of the sammer	ECERCIT.	
Zinc Oxide	45	g.
Prepared Calamine	45	g.
Glycerin	4-16	cc.
Rose Water, To make	e 500	cc.

To this is added, drop by drop, sufficient ichthyol to cause the paint to match or blend with the surrounding skin. Usually from 10 to 60 drops are needed, and the addition should be made carefully, since success of the paint depends on the closeness of the match obtained. Face powder may be applied after using this concealing paint.

#### Hand Lotion Formula No. 1

Formula No. 1	
Stearic Acid	4.0
Cetyl Alcohol	1.0
Butyl Stearate	3.0
Amino-methyl-propaned	iol 0.8
Quince Seed	0.5
Water	90.7

As required

A thick cream is made from all of the above ingredients except the quince seed, preservative and half the amount of water specified, using the technique described for the vanishing cream.

Preservative

The quince seed is soaked overnight with the rest of the water and the preservative, strained, and the resulting "mucilage" is stirred into the cream. The lotion thickens considerably after standing several days and may be thinned with water as desired. Perfume is usually added as a highly concentrated solution in specially denatured alcohol, in the last stages of manufacture.

No 2

- (O. M		
Stearic Acid	1.75	g.
Glycerin	1.00	cc.

Cholesterol Base

(Parachol) 0.50 g. Cetyl Alcohol 0.50 g. Triethanolamine 0.15 cc.

Alcohol (15%) To

make 100.00 cc.

Allow the stearic acid and the triethanolamine to react until the reaction is complete (about 20 minutes). Add the cholestrol, cetyl alcohol and glycerin (which must have been brought to the same temperature as the other ingredients), and when this mixture is melted, gradually stir in the 15% alcohol (also warmed to the same temperature). Stir till cool. Perfume as desired.

The value of this lotion lies in the fact that the emulsion is permanent without any tendency to break down. In addition, the lotion will take a variety of dermatologically important medicaments such as calamine, zinc oxide, kaolin, phenol, salievlic acid, boric acid and any of the alkalies within reason.

Facial Astringent German Patent 700,229

Gum Arabic 20 g. Sodium Perborate 5 g. Soap, Powdered  $3\frac{1}{2}$  g.

Dissolve	before	use	in		
Water				15	1.

Skin Lotions U. S. Patent 1,631,384 Formula No. 1

Pure Citrus Pectin 1 0z. Tincture of Benzoin 1 fl. oz Glycerin

4 oz. No. 2 Pure Citrus Pectin 8 Tincture of Benzoin 20 Glycol 100 Boric Acid Water 850 No. 3 Citrus Pectin 0.9 Diethylene Glycol 10.0 Tincture of Benzoin 2.0 Boric Acid 04 Water 86.7 No. 4

Zinc Oxide 5.0 Talc 5.0Sodium Borate 5.0 Menthol 1.4

Alcohol 15.6 Bentonite (6% Lime water suspension) 100.0

Lotion for Blotched Skin Orange Water (or

Rose Water) fl. oz. 2 Extract of Witch

Hazel

fl. oz. Magnesium Sulphate ½ oz. Borax 1/4 OZ.

(Wash face with soap and hot water, then apply lotion at bedtime.)

Baby Skin Oils Formula No. 1 Olive Oil, Best Deodorized 80 Almond Oil 20 Oil-Soluble Rose Perfume To suit

No. 2	
Raisin Seed Oil	60
Avocado Pear Oil	20
Olive Oil, Deodorized	20
Perfume	To suit
These products are pro-	epared by
simple mixing.	

Sunburn Preventative	
Salol	10
Cold Cream	90

Sun Protective	Lotion	
Butylcinnamoyl		
Pyruvate	0.5	cc.
Dihydropyrone	30.0	cc.
Alcohol	30.0	cc.
Water, To make	100.0	cc.

Glenn's Liquid Powder	
Colloidal Kaolin	7
Titanium Dioxide	5
Bentonite	5
Water	78
Glycerin	5
Pigment To s	suit

#### Face Powders

For the coloration of face powders the eve of the artist is necessary. The colors must not be glaring, but delicate. Various dyestuffs which may be used have already been mentioned and here is a general outline of the method of working. Either a stock of diluted color is made up in calcium carbonate (precipitated chalk) or talc, or the dyestuff is separately ground into part of the talc necessary for formulation, before adding it to the rest of the mixture. This permits much better mixing; it would be asking for trouble to add undiluted color directly to the mill.

Face Powder	
(Medium Peach Colo	or)
Talc	65.00
Purified Kaolin	20.00
Magnesium Carbonate	6.00
Titanium Dioxide	4.00
- m - m - m - m - m - m - m - m - m - m	

Titanium Dioxide 4.00
Magnesium Stearate 3.00
Perfume 0.50
Ochre 1.45
Brilliant Pink Lake

(Eosine Type) 0.05

Here the ochre and the pink lake are separately mixed with a portion (known weight) of the tale and, when a sample from either grinding, rubbed out on a white paper card, shows no streakiness or color spots, they can be mixed together. The final color mixing is then rubbed out evenly on to a card which is retained for matching when dealing with later consignments of the same shade. The color is then added to complete the mixture, which should be milling during the time that the color is being prepared.

Certain colorists find it easier to work with stock solid "solutions." There is little doubt that this is the best method to employ when matching is being carried out. "Nude" for example may be made up as follows:

Nude Shade Powder
Precipitated Chalk 69.25
Golden Ochre 30.00
Tetrabromofluorescein

Lake 0.75 and then 7.5 to 10 per cent, or whatever is required to give the right depth, is added to the white face powder batch which is separately prepared.

#### Color Stocks

Stocks of all the colorist's dyes may be prepared in 25 per cent mix-

tures with calcium carbonate. The above shade would then be made by using 120 parts of 25 per cent ochre "solution" and 3 parts of 25 per cent tetrabromofluorescein lake "solution." The powderman and the colorman must work together however on these points in order to control the amount of calcium carbonate in the final product.

Burnt sienna is often used in conjunction with eosine and ochre for the formation of brunette and sunburn shade powders. Baby powders are often very delicately tinted and perfumed, the perfume oil and color lake or pigment being rubbed out carefully in a portion of the talc before adding it to the bulk mixing.

Sun tans are made by numerous different procedures but the coloring matter, usually a pigment brown mixture, is ground up in petrolatum and then added to the prepared oil which may have something like a nut oil base. Oil soluble dyestuffs are often employed. Artificial sun tan liquids (not oils) are made up by using basic dvestuffs in very small proportions. Owing to the fact that dyestuffs used must be perfectly dissolved, the colorist works with very dilute solutions, usually 0.5 to 0.1 per cent in spirits or water. For example here is a kind of artificial tan used for theatrical purposes:

Theatrical Sun Tan Color
Bismarck Brown R
(1% Solution in water) 80.0
Methyl Violet 4B
(1% Solution in water) 1.5
Methylene Blue 2B
(1% Solution in water) 1.0
Glycerin 6.0

Alcohol	11.0
Perfume	0.5

Fluorescent Rouge and Face Powder
Fluorescent rouge and face powder for theatrical work is made by
using a base of barium sulfate or
magnesium oxide and adding a
phosphor to color the rouge. Phosphors may be zinc beryllium silicate
or the fluorescent organic dyes.

Ordinary petrolatum when applied to the face gives a bright bluish fluorescence suited to theatrical application. Lanolin and other grease-like substances may also serve in this capacity.

Rouges for compacts require brilliant red lakes and carmine may be supplemented by an eosine lake, or the latter may be used alone. An example is:

Compact Rouge	
Talc	36
Zinc Oxide	20
Kaolin	20
Zinc Stearate	5
Bromo Acid Lake	11
Petrolatum, Heavy	3
Gum Tragacanth (1%	
Solution)	3
Perfume	2

In this case the color lake may be rubbed out in the petrolatum and perfume oil, and then mixed with a portion of the talc before adding to the mass. The object of the tragacanth and liquid petrolatum, of course, is to enable the powder to set in a compact mass. It will be noticed that here much more color is required than has been mentioned in examples of other types of cosmetics; this may be explained by the fact that usually four or five times more color is required when

using lake colors as compared to pure dyestuffs.

#### Liquid "Lip-Stick" U. S. Patent 2,230,063 Formula No. 1

Formula No. 1	
Ethyl Cellulose	3.1%
Ethyl Alcohol	68.4%
Petroleum Ether	20.0%
Hydrogenated Methyl	,
Abietate	7.5%
Rhodamine	1.0%
No. 2	, ,
Ethyl Cellulose	3.06%
Bleached Wax-Free	7
Shellac	4.94%
Ethyl Alcohol	65.00%
Petroleum Ether	14.66%
Hydrogenated Methyl	, , ,
Abietate	12.00%
Fuchsine	0.3 %
Saccharin	0.04%
No. 3	, , ,
Ethyl Cellulose	3.5%
Ethyl Alcohol	90.7%
Castor Oil	5.0%
Tetra-bromo Eosine	0.8%
No. 4	7.
Ethyl Cellulose	3.0%
Bleached Wax-Free	, ,
Shellac	2.5%
Methyl Abietate	7.5%
Petroleum Ether	11.0%
Ethyl Alcohol	77.0%
Oil-Red O	1.0%

Accessory agents may be added, such as perfumes, preservatives, anti-oxidants, etc. The preparations are preferably clear and transparent and are of a viscosity ranging between 3 and 5 hundred centipoises, while best results are obtained in a range between 20 and 50 centipoises.

#### Fluorescent Lipstick

For most theatrical purposes the lipstick ordinarily used will fluoresce

brightly under ultraviolet light.

Coco Butter or Lipstick Base 100
Fluorescent Dye up to 5
Physiologically harmless dyes
should be used. Various shades may
be obtained by mixing the dyes.

#### Coloring Lipsticks

Lipsticks formulae vary widely, but the simplest way of explaining the procedure of coloring is by an example:

xample:	
(a) Castor Oil	45.5
(b) Beeswax	25.0
(c) Peanut Oil	15.0
(d) Paraffin	7.5
(e) Lanolin	1.5
(f) Perfume	1.0
(g) Oil Red	2.0
(h) Tetrabromofluorescein	2.5

The castor oil is heated to 55° C and the tetrabromofluorescein dissolved in it. The oil soluble red is then dissolved and the whole thoroughly incorporated; (b), (d) and (e) are then mixed and melted together. The peanut oil (c) is then added, followed by the color and castor oil, and finally the perfume. The whole is well milled and then run into cooled molds to set.

Another type of procedure is as follows:

TOHOWS.	
Lanolin	11
White Carnauba Wax	12
White Beeswax	20
Spermaceti	1
are melted together and	
fluorescein derivative is	dissolved
in:	

Castor Oil 37
Oleyl Alcohol 9
Propylene Glycol 8
Cetyl Alcohol 2

at 50° C., and sieved before adding

to the wax melt. Thorough agitation follows and the mass is then run into molds to set.

When hydrocarbons are used as a basis for a lipstick, which is a common practice, castor oil cannot be used in normal formulation. On this account another solvent for the dyestuff must be employed. Butyl stearate may then be used and the presence of a binder such as triethanolamine is then necessitated. Eosine reacts with the fatty acids present in the lipstick and produces a combined bromo acid and thus the color does not bleed in use. A lake usually is four or five times weaker than the dvestuff itself and consequently allowances must be made in such cases, and also the lake substratum naturally tends to harden the stick and this factor must also be regulated. The bright orange and yellow lipsticks which give a red color when applied to the lips are perhaps a puzzle to the uninitiated. This double color effect is accomplished by the use of the free acid of eosine.

It must be pointed out that when using artificial dyestuffs, the color, in every case should be full batch strength, *i.e.*, it must contain no salt or diluent.

Eve Lotions Formula No. 1 Sodium Chloride 5 gr. Borax 4 gr. Sodium Bicarbonate 2 gr. Distilled Water, To 1 fl. oz. make No. 2 Mercuric Oxycyanide 1 gr. 6 fl. oz. Distilled Water Dilute with equal amount of warm water for use.

No. 3

Boric Acid . 8 gr.
Zinc Sulphate . ½ gr.
Distilled Water 1 fl. oz.
Dilute with equal amount of warm water for use.

Liquid Mascara

Liquid mascara consists of Tr. benzoin 20, ester gum 2, castor oil 1, lampblack 14 and alcohol 23 parts each.

## Nail Lacquer U. S. Patent 2,215,898 Formula No. 1 Solids

Nitro-Cellulose		
$(\frac{1}{2} \sec.)$	132	
Ethyl Cellulose	16	
Tricresylphosphate	24	
Liquid Resin "Hercolyn"		
(Dihydro Methyl		
Abietate)	34	
Alkyd Resin		
("Glyptal")	50	
Solvent		
Denatured Alcohol	83.5	
Xylol	21	
Ethyl Acetate	260	
Butyl Acetate	113	
Amyl Acetate	112	
No. 2		
Solids		
Nitro-Cellulose		
$(\frac{1}{2} \text{ sec.})$	121	
Nitro-Cellulose		
(20–30 sec.)	10	
Ethyl Cellulose	15	
Gum Camphor	20	
"Santolite" (Toluene		
Sulfonamideform-		
aldehyde)	39	
"Hercolyn"	10	
Dibutylphthalate	15	
Sodium Lauryl Sulfate	7	

Solvent	
Butyl Acetate	190
Ethyl Acetate	140
Ethyl Alcohol	140
Monethyl Ether of	
Ethylene Glycol	80
Toluol	57
No. 3	•
Ethyl Acetate	50.0
Butyl Acetate	20.0
Diethyl Phthalate	15.0
Camphor	4.5
Nitrocellulose Lacquer	10.0
Color, e.g., Eosine	0.5
7 - 9-7	0.0

Eosine is usually dissolved in the ethyl acetate, although many processes involve direct solution in a portion of the nitrocellulose lacquer. Matt types of varnishes are often produced by adding inert white or colored pigments in definite amounts; color lakes may be employed here. The fluorescein range is probably the only color group of importance in this section of the industry although various other colors are used for certain jobs.

No. 4	
Rosin, WW	7
Alcohol	68
Butyl Acetate	68
Ethyl Lactate	1
Nitrocellulose Film Scrap	-
(Washed)	15
Glycol Ricinoleate	1

Management of the second secon	
Liquid Nail Wax	
Petrolatum	. 5
Paraffin Wax	10
Ethyl Acetate	10
Chloroform or Deodorized	
Kerosene	175
Perfume, To suit	7.75
Mix together with gentle he	at un
dissolved	

#### Fluorescent Nail Polish

Many of the lacquer polishes contain organic dyes which fluoresce brightly under ultraviolet light and are therefore suited to theatrical work.

By adding eosine, uranine, or other fluorescent dye to a lacquer base in concentration of from 0.2 to 0.5 per cent, a luminous lacquer may be made which can be applied to the fingernails.

#### Nail Varnish Removers U. S. Patent 2,197,630

Emulsified compositions containing a blown or sulphonated vegetable oil, a nitrocellulose solvent and an activated clay are proposed as combined varnish removers, nail cleaners and cuticle softeners.

F,01	rmula No. 1		
Sulphonate	d Olive Oil	10.0	g.
Caustic Sod	a (10%)	1.0	
Butyl Acets	ite	15.0	
Acetone		15.0	g.
Titanium O	xide	0.5	
Bentonite		2.0	
Water	To make		
	No. 2		
Linseed Oil		5.0	g.

	- · · ·			
Linseed Oil			5.0	ø.
Caustic Sod	la (10	0%)	8.0	
Butyl Acets	ıte		15.0	
Acetone			15.0	
Titanium O	xide		1.0	
Tin Oxide			1.0	
Bentonite			2.0	
Water	To	make	100	ec

The proportion of caustic soda in each case is intended to give a final pH of 7.5 to 10. In making up the emulsion it is advisable to leave the bentonite in contact with about 20 per cent of the total water for about twelve hours in order to become hydrated. Pigment and polishing in-

gredients (e.g., tin oxide) are then added, followed by the oil, solvent, alkali and the balance of the water. It is claimed for these emollient emulsions that they prevent colored nail varnish from running under the nails or on to the cuticle in course of removal. They have a whitening effect on the underside of the nails. Properly prepared emulsions on these lines should not settle or break.

#### Bath Salts

Bath salts are made in a variety of colors and ways; a simple example is given here to show the lines on which they are prepared:

Sodium Sesquicarbonate 99.0 Perfume 0.5 Color 0.5

The color may be applied in two chief ways; either the crystals are immersed in strong solution of the dye (in water or spirits), or the color is sprayed on whilst mixing is taking place. In the first case the crystals are finally centrifuged and allowed to dry before being packed. The basic dyestuffs are usually employed and these are water or spirit soluble. An example showing how a water dye solution is prepared for this purpose is:

Tangerine
Chrysoidine R Crystals 2
Glycerin 150
Distilled Water 848

The dyestuff, of course, must be carefully dissolved in water not exceeding 60° C. and this is particularly important for auramine which is used for lemon shades. Other colors commonly employed are Acridine Orange R, Safranine GR, Methyl Violets and Basic Greens.

Besides basic colors the fast oil colors are used in spirit solutions. When using these it is a common practice to add a small amount of a resin or ester gum to the spirit solution. On evaporation of the spirit, the small amount of gum is left in a very thin coating all over the surface of the crystals. This holds the color without being sticky. A spraying solution is made up as follows:

116116016	
Auramine Base	3
Ester Gum or Spirit Solu	ble
Resin	10
Industrial Alcohol	987
	1000

All the oil colors mentioned earlier are applicable by this process.

#### Perspiration Deodorant Formula No. 1

Liquid	
Aluminum Chloride	8.0
Aluminum Sulphate	5.0
Borax	0.5
Water	86.5
No. 2	

# Cream Triple Pressed Stearic Acid Diglycol Laurate, Neutral Fir Balsam Needle Oil Water Glycerin 3.5

This cream neutralizes body and perspiration odors for men.

17
11
72
80
20



1458/3

52	THE CHE	MICA	L FORMULARY		
	o. 5		No. 4	-	
Aluminum Phe	enolsulfo-		Calamine		250
nate	20.	.00	Starch		500
Perfumed Spir	it, N.F. 50.	00	Boric Acid		200
Lavender Oil		25	Zinc Stearate		50
Ethyl Acetate		50	These powders, or varia	ati	
Distilled Water			them, are prepared by sim		
	To make 100.	00	ing.	-1· -	-
Hygienic Dec	dorant Powde	r	AROMATIC WATE	R	S
	Hygienic Deodorant Powder Australian Patent 109,904		Cherry Laurel Water		
Zinc Oxide		3.0	True Fruit Extract of		
Boric Acid	-	1.8	Wild Cherry	R	OZ.
Chalk, French		7.0	Bitter Almond Oil		dr.
Zinc Stearate		1.0	Water to make		gal.
Benzoic Acid		1.0	Filter through Magnesia		
Aluminum Chl		0.1			0
Sodium Bicarb		).1	the second control of the control of		
Perfume, To su			Orange Flower Wat	er	
,			Orange Flower Essence	8	oz.
Tarming I	oth Dowdon		Water, To make		gal.
Bicarbonate of	Bath Powder	00	Filter through Magnesia	1	oz.
Tartaric Acid		80			
Starch		20			
Saponin		3	Rose Water		
	olor To quit	0	Rose Essence	4	OZ.
Perfume and C	olor, 10 sult		Water (Lukewarm), To		
			make		gal.
	Powders		Filter through Magnesia	1	oz.
	ıla No. 1		Black of the company		
Boric Acid		00	Peppermint Water		
Starch		00	Peppermint Oil		dr.
Purified Talc, '		00	Water, To make		gal.
	0. 2	-	Filter through Mag-		0
Boric Acid		00		1/2	oz.
Zinc Oxide	· -	00		, 2	
Kaolin		00			
Magnesium Ste		50	Essences for the Above A	roı	matic
Purified Talc		50	Waters		
	o. 3		Orange Flower Esser		
Purified Talc		00	Neroli Oil	-	dr.
Kaolin		00	Alcohol	1	pt.
Magnesium Ste		50	Rose Essence		
Boric Acid		00	Rose Oil *		dr.
Starch	1.	50	Alcohol	1	pt.

\* Rose geranium oil may be used, being cheaper than the natural rose oil.

The second secon			
Synthetic Lavender O	il	Ethyl Acetate	0.6 cc.
Ethyl Amyl Ketone	1	Alcohol (95%)	50.00 cc.
Benzylidene Acetone	1	Water, To make	100.00 cc.
Citronellal	4	*	
Geranyl Acetate	5	Solid Perfumes (No	
Coumarin	4	Formula No	
Linalyl Acetate	30	Japan Wax	20 g.
Linalol	20	White Beeswax	20 g.
Linalyl Isobutyrate	5	Diethyl Phthalate	40 ml.
Terpinyl Acetate	10	Perfume Oil	20 ml.
Rosemary Oil	5	No. 2	
Spike Oil	10	Melt 4.5% of stearin	, add 0.5 part
Trichlorphenylmethyl		of sodium carbonate a	nd 95% Eau
Carbinyl Acetate	2	de Cologne and heat d	luring 1 hour
Benzoin R	$\bar{2}$	in an autoclave. When	nearly cool,
Benzyl Cinnamate	$\frac{2}{2}$	pour into molds.	
Civet	$\bar{1}$	G G. 7	•
	-	Cosmetic Stock	
Synthetic Geranium O	il	Formula No	
Citronellol	15	Methyl Cellulose	0.5
Geraniol	27	Gum Arabic	0.1
Phenylethyl Alcohol	15	Titanium Dioxide	2.0
Diphenyl Öxide	5	Zinc Oxide	0.1
Geranyl Isobutyrate	5	Precipitated Chalk	10.0
Rhodinol	15	Zinc Stearate	1.0
Benzophenone	2	Talc	0.4
Geranyl Propionate	5	Bentonite	2.0
Geranyl Formate	5	Alcohol	8.0
Aldehyde $C_9$ (10%)	1	"Aguaresin"	4.0
Palmarosa Oil	5	"Sulfatate"	0.5
	Ū	Water	68.0
Synthetic Bergamot Oi	il .	Dye and Pigment, T	o suit
Linalyl Acetate	40	No. 2	
Terpinyl Acetate	15	Precipitated Chalk	20
Linalol	10	Zinc Stearate	<b>2</b>
Terpinyl Isobutyrate	4	Talc	8
Geranyl Methyl Ether	4	* Bentonite	20
Methyl Anthranilate	10	Sodium Bicarbonate	1
Citronellyl Acetate	10	Alcohol	10
Limonene	4	"Glycopon 50"	10
Aldehyde $C_8$ (10%)	1	"Protoflex"	6
Aldehyde $C_{12}$ (1%)	$\tilde{2}$	Water	124
Chlorophyll, To color	q.s.	Dye and Pigment, To. 3	o suit
Perfume for Deodorant Cr	ream	Stearyl alcohol, 100	grams; La-

0.25 cc.

0.06 cc.

Rose Oil

Clove Oil

Stearyl alcohol, 100 grams; Lanette wax SX, 20 grams; liquid paraffin, B.P., s.g. 0.89, 150 ml.; water,

754 THE CH	EMICA	L FORMULARY	NATURE   IIII
distilled, 500 ml.; powdered	mix-	Kaolin	3
ture, 50 grams; water, distilled		Zinc Stearate	2
ml.; preservative perfume, q.s		Glycerin	3
other formula consists of: Dis		Witch Hazel Extract	10
stearate, 10 grams; titanium		Orange-Flower Water	68
ide, 3 grams; colloidal kaol		Color and Perfume, as	
grams; water, about 200 gran		required	
No. 4		No. 7	
Bentonite	9		
Precipitated Chalk	11	Cream	
Magnesium Silicate	5	Paraffin Oil	1
Aquaresin (Glycol Bori-		Glyceryl Mono-Stearate	6
Borate)	6	Distilled Water	48
Protoflex	8	Titanium Dioxide plus	
Water	68	Earth Pigments	21
Diglycol Stearate	1	$\operatorname{Talc}$	9
Dye or Pigment, To suit		Perfume, To suit	
No. 5		No. 8	
Vanishing Cream	62	Powder Cream	
Gum Solution (Tragacanth,		Vanishing Cream	70
Karaya, etc.)	2	Talc	24
Titanium Dioxide	1	Titanium Dioxide	6
China Clay, Colloidal	3	Color and Perfume, as	·
Face Powder Base (Suntan,	1	required	
etc.)	12		
Glycerin or Substitute	5	No. 9	
Water	15	Powder	
The pigments need to be care		Titanium Dioxide	3.00
and thoroughly dispersed. The		Zinc Oxide	20.00
product is best run through a		Talc	65.06
or similar mill. Naturally, muc		Zinc Stearate	4.00
depend upon the weight of the		Precipitated Chalk	6.00
ments used, the consistency of		Color and Perfume, as	
cream, and other variable factor		required	
In so far as possible, earth of		No. 10	
are preferred because of their nature and freedom from blee		Lotion	
The selection of earths is a wide		Bismarck Brown (1% So-	
and practically any shade de		lution)	79.0
can now be obtained with then		Methyl Violet (½% Solu-	
dicious use of organic lakes wil		tion)	3.0
life and brightness to the tints.		Methylene Blue ( $\frac{1}{2}$ % So-	
No. 6		lution)	2.0
Liquid Powder	1	Glycerin	5.0
Zinc Oxide	6	Alcohol	10.5
Precipitated Chalk	8	Perfume	0.5
1 Colpitatou Ollain	5	2 ci i dillo	U.U

19.0

Hair "Tonics"	
Formula No. 1	
Isopropyl Alcohol	70.0
Propylene Glycol	5.0
Eau de Cologne	5.0
Cholesterin	0.5
Perfume	0.5

Dissolve all the ingredients except water in isopropyl alcohol, add the water last.

Distilled Water

#### No. 2

Gum Benzoin	2	dr.
Castor Oil	4	oz.
Alcohol	1	qt.
Shake well together, t	hen	add
Lavender Oil	1	dr.
Bergamot Oil	1	dr.
Clove Oil	30	drops
Rosemary Oil	30	drops
Lemon Oil	30	drops
Neroli Oil	30	drops
Tincture of Can-		
tharides	$\frac{1}{2}$	oz.
Shake well to cut the		

#### No. 3

Il biondo Dio (Italian "Hair Tonie")

101110		
Castor Oil	1	pt.
Jamaica Rum	$\frac{1}{2}$	pt.
Shake well; use immediate	ely	afte

hair has been shampooed and is perfectly dry. For many years this has been a favorite tonic in parts of Italy.

#### Hair Lacquer Formula No. 1

Elastolac	20-35%
Water or Alcohol	80-65%
Perfume, To suit	- 100

This product gives a soft sheen to the hair and does not become brittle. The more alcohol used in the formula, the faster the rate of drying.

#### No. 2

Ten parts of orange shellac is dissolved with 2 parts borax in 70 parts of water, to which 20-30 parts of eau de cologne is added. If a gold effect is desired, powdered aluminum bronze may be added.

#### Cheap Hair Cream

White Wax	10
Paraffin Oil	130
Distilled Water	15
Borax	1

Perfume, To suit

Melt the wax in 50 parts of paraffin oil. Place in a mortar and stir in the remainder of the liquid paraffin. Add the distilled water in which the borax has been dissolved and stir the cream formed consistently until cold.

#### Hair Fixatives Formula No. 1

96.00
3.00
1.00
98.50
1.00
0.50
96.00
2.00
0.25
1.75

### Permanent Wave Solutions

i oring it or i		
Sulphonated Castor Oil	8	oz.
Ammonia	20	oz.
Sodium Pyrophosphate	2	ΟZ.
Sodium Bisulphite	8	oz.
Potassium Pyrosulphite	12	oz.
Sodium Sulphite	12	oz.
Water	428	oz.

0			
8 oz.			
3  oz.			
16 oz.			
16 oz.			
16 oz.			
5 oz.			
156 oz.			
Permanent Wave Creams			
(Cream Paste Type)			
Formula No. 1			
1			
9.40			
1.70			
0.10			

Water 37.30
B. Sodium Sulfite 9.50
 Ammonium Carbonate 4.70
 Ammonia (28° Bé.) 2.00
 Water 30.30

A. Glycosterin 10.00
Lanolin 2.00
Glycerin 0.72
Water 40.00
B. Permosalt 7.85
Ammonia (28° Bé.) 7.53
Water 31.90

Melt the Glycosterin and lanolin together, heat to about 160–170° F. Add the water, or water and Wetanol (wetting agent) heated to the same temperature and stir to about 100° F. or a little lower. At the same time, mix Group B cold and add to Group A mixture at 100° F. or lower, slowly with thorough agitation. Both these materials will give a heavy fluid emulsion which will set overnight into cream form which can be packed in jars or tubes.

No. 3
Ammonia (28° Bé.) 20
Caustic Soda 1
Sodium Sulphite 10
Water 89

Dissolve above by mixing.

Melt together
Parachol 40
Lanolin 40

Add the water solution to the above, a little at a time, mixing each portion until well absorbed.

# STABILIZATION OF FINGER WAVE CONCENTRATES

In finger wave concentrates using gum karaya, difficulty is experienced in keeping the gum from settling to the bottom and caking into a hard mass which is difficult to redissolve. This can be overcome by the addition of Diglycol Laurate to the gum-alcohol mixture, giving a uniform dispersion of the gum which will dilute easily in water. Diglycol Laurate gives added gloss to the hair and prevents flaking of the gum on drying. The following formula is suggested:

Gum Karaya 3
Diglycol Laurate  $1-1\frac{1}{2}$ Alcohol 1-2Increasing the gum content gives

a paste suitable for tubes.

Kinky or Wavy Hair Straightener
British Patent 543,066

Sodium Sulphide 20 g.
Caustic Soda 2 g.
Soda Ash 2 g.
Triethanolamine 4 g.
Water 1 l.

Hair Waving Pad Heat Generating Composition

Formula No. 1 British Patent 531,250 Mercurous Chloride

Sodium Nitrate 5
Aluminum, Powdered 10
Before use, moisten with 1% of

1

ammonium or stannous chloride.

#### No. 2

A sheet of fibrous material is impregnated with a 40% copper chloride solution and dried and a sheet of aluminum foil is used with a solution of

Ammonium Chloride	6.7
Ammonium Nitrate	28.6
Sodium Salicylate	8.3
Water	56.4
No. 3	
U. S. Patent 2,261,221	
Aluminum	4.0
Potassium Chlorate	1.5
Cuprous Oxide	1.0
Benzene Sulfonic Acid	0.6

Hair Dyeing Soap British Patent 524,293

Eighty grams of para-aminophenol is mixed with 75 grams of soda ash and 100 grams of the methyl tauride of oleic acid, and converted into a paste with 75 grams of water. This paste is milled with 675 grams of toilet soap chips with a fatty acid content of 75 to 80 per cent. The homogeneously milled product is plodded and cut to shape. The product dipped into a 2 per cent solution of hydrogen peroxide and applied to the hair—e.g., by rubbing—is stated to give a reddish-brown shade.

Solid Hair Dye Block
British Patent 524,293

Methyl p-Phenylene
Diamine Sulphate 120 g.
Ammonia (25%) 65 g.
Fullers' Earth 40 g.
Water 50 g.
Mix together until uniform; then
mill with soap (75–80% fatty acid),
760 g.

The hair is first moistened with 2% hydrogen peroxide and treated with above is dyed brown-black.

#### Removing Hair Dye U. S. Patent 2,149,319

A dye-removing composition is formed of 3% of 40° Baumé nitric acid, 1% hydrochloric acid, 1% oxalic acid, 1% of acetic ether, 0.02% of cholesterol, 3% of diethylene glycol, 1% of sodium formaldehydesulfoxylate and 89.98% of water.

Coal Tar Shampoo

A liquid tar shampoo may be made from 66 grams coconut oil, 78 cc. cottonseed oil, 36 grams stearic acid, 10 cc. rectified oil of tar, 42 grams potassium hydroxide, 9 grams potassium carbonate, 42 cc. alcohol, 10 grams purified talc and sufficient water to make 1000 cc. The fats are melted and heated to 82° C.; the alkalies are dissolved in 100 cc. distilled water and added. Finally, the alcohol containing the coal tar is added and the whole heated until saponification is complete. When cold, add distilled water to measure 1000 cc.

Blond Hair Rinse	
Tincture of Rhubarb	40
Alcohol	70
Propylene Glycol	10
Perfume, To suit	
Water, To make	1000
Depilatories	
· Formula No. 1	
Barium Sulfide	30 g.
Atropine	5 g.
Spermaceti	100 g.
Distilled Water	200 g.
White Petrolatum Jelly	300 g.

This cream can be used as a depilatory or can be applied every day for 20 minutes to stop the growth of unwanted bair

No. 2	
Strontium Sulphide	1
Chalk, Precipitated	2
Tale, Powdered	5
Zinc Oxide	5

Mix well and pack in moisture proof containers. Before use, make into a paste, with water, and leave on skin for about five minutes.

> No. 3 U. S. Patent 2,202,829

Rosin	50
Mineral Oil	25
Beeswax	3

Brushless Shaving Cream Formula No. 1 Stearic Acid (Triple Pressed) 900 Lanolin 160 Glycopon S 60 Mineral Oil 180 Triethanolamine 51 Borax 54 Water 2600 Perfume

Melt the stearic acid, add the lanolin, Glycopon S and mineral oil and bring the temperature to about 70° C. Heat the water, triethanolamine, and borax in a separate container to boiling. Now add the first mixture to the second with vigorous stirring until a smooth emulsion is obtained. Add the perfume and stir gently until cool.

No. 2	
Stearic Acid	35
Cottonseed Oil	18
Anhydrous Ammonium	
Laurate	7.5
Glycerin	12
Water	100

This produces a very smooth cream, of good consistency. It spreads easily and washes off the razor blade readily.

No. 3		
Stearic Acid	70	g.
Cottonseed Oil	30	g.
Diglycol Laurate	5	g.
Anhydrous Ammonium		
Stearate	15	g.
Glycerin	25	
Sulfatate (2% Solution)	55	cc.
Water	200	cc.

This produces a cream which spreads readily, washes off the razor blade easily and remains moist on the face.

No. 4	
Sodium Stearate (Soap)	4.0
Stearic Acid	14.2
Spermaceti	3.8
Mineral Oil	7.5
Water	70.5

#### After Shaving Lotion Formula No. 1

(especially for users of electric shavers: disinfectant, refreshing, improving resistance of skin.)

Glycerin	5	ec.
Tannic Acid	5	gr.
Menthol	1	gr.
Alcohol, Diluted		

To make 100 cc.

No. 2	
Water, Distilled	85.0
Glycerin	10.0
Citrus Pectin	2.0
Alcohol	2.0
Boric Acid	0.5
Zinc Sulpho Phenolate	0.2
Rose Oil	0.3

Electric	Razor	Shave	Lotion
Alcohol		W. 19	70.0
Lecithin			0.5

Wetting Ag	gent (Wetanol)	1.0
Witch Haz	el Extract	28.0
Perfume	Sufficient Qua	ntity

#### Tooth Paste Formula No. 1

Citrus Pectin	3.0%
Glycerin (28° Bé.)	71.5%
Water, Distilled	25.0%
Citrie Acid	0.5%
Mix 58% of this jelly	with 42%
of titanium dioxide.	

#### No. 2

Citrus Pectin	8.0%
Glycerin (28° Bé.)	10.0%
Water, Distilled	81.0%
Citric Acid	1.0%

Mix 50% of this jelly with 48% titanium dioxide and 2% peppermint oil.

#### No. 3

Tragacanth	1.0%
Citrus Pectin	5.0%
Glycerin (28° Bé.)	30.0%
Water, Distilled	63.0%
Citric Acid	1.0%

Mix 36% of the solution with 37% titanium dioxide, 22% Pepsin U.S.P., 8.3% invert syrup and 2% Menthol.

#### No. 4

Tragacanth	1.5%
Pectin	5.0%
Glycerin (28° Bé.)	30.0%
Water, Distilled	61.0%
Invert Syrup	2.5%
Mix 39% of this	solution wit

20% Pepsin U.S.P., 8.39% titanium dioxide and 2% Peppermint Oil.

#### No. 5

Mix 50% of the formula 2 with 30% titanium dioxide, 16% fine kaolin, 2% saponin-acetate and 2% Peppermint Oil.

Glycerin Free Tootl	h Paste	es
Formula No.		
Methyl Cellulose (4%	Stock	
Solution)		20
Cold Water		34
Mineral Oil (Cosmetic	c Grad	
Precipitated Chalk	0.200	32
Magnesium Carbonat	ie.	10
Perfume		1
No. 2		_
Precipitated Chalk	46.75	lb.
Bentonite	3.75	
Gum Tragacanth Mu		
lage (5%)	3.75	lb.
Mineral Oil	1.50	lb.
Saccharine	0.50	OZ.
Flavoring Oil	5.00	lb.
Water	45.00	
The method of manuf	acture	is t

The method of manufacture is to take about one-third of the water, then add the chalk mixed with the binder (absorbent clay or bentonite) slowly, so that the mass remains smooth. Then add the gum tragacanth mucilage and saccharin dissolved in a little of the water. Afterwards incorporate the flavor and the lubricant (mineral oil).

# No. 3 Precipitated Chalk Hard Soap Soluble Saccharin Heavy Mineral Oil Sorbitol Syrup (Yumidol) No. 3 552.00 g. 60.00 g. 0.25 g. 25.00 cc.

Inexpensive Tooth Powder
Precipitated Chalk
(Very Fine) 200 g.
Orris Root (Powdered) 20 g.
Common Salt (Pulverized) 10 g.
Sodium Bicarbonate 20 g.
Menthol Crystals (Pulverized) 2 g.
Mix all the above ingredients and

flavor with 10-20 drops of oil of wintergreen or oil of peppermint. Keep this mixture in a dry place and use it on a dry toothbrush for best results.

Tooth Powder for Pyorrhea
Sodium Perborate 10.00 g.
Sodium Benzoate 2.50 g.
Sodium Bicarbonate 0.50 g.
Menthol, To suit

Tooth Powder for False Teeth Mix together 10 parts of calcium carbonate, 2 parts of sodium perborate, 2 parts of sodium bicarbonate, 2 parts of tricalcium phosphate and 2 cc. of oil of cinnamon.

Denture Cleaner
Canadian Patent 391,039
Citric Acid (Saturated
Solution) 1
Isopropyl Alcohol 15
Mix with water for use.

 $\begin{array}{c|c} \text{Lotion for Massaging Gums} \\ \text{Zinc Chloride} \\ \text{Zinc Iodide} \\ \text{Tincture of Iodine} \\ \text{Distilled Water} \\ \end{array} \begin{array}{c} 1.0 \text{ g.} \\ 10.0 \text{ g.} \\ 0.5 \text{ g.} \\ \end{array}$ 

Mouth Lotion
Water, Distilled 84
Citrus Pectin 5
Citric Acid 1
Peppermint Oil 10

Mouth	Wash	
Citric Acid	0.1	g.
Tartaric Acid	0.1	g.
Benzoic Acid	0.1	g.
Borie Acid	2.0	g.
Glucose	0.5	g.
Glycerin	10.0	g.

Chlorothymol	0.033	g.
Eucalyptol	0.1	ec.
Thymol	0.07	g.
Menthol	0.045	g.
Alcohol	25.0	cc.
Distilled Water,		
To make	100.0	cc.

Soapy Mouth Wash	
Powdered Neutral Soap	20.0
Glycerin	90.0
Peppermint Oil	6.0
Wintergreen Oil	2.5
Cinnamon Oil	1.0
Clove Oil	0.5
Alcohol	300.0
Distilled Water	580.0

Astringent Mouth Wash Formula No. 1 Sodium Bicarbonate 12.5 Borax 12.5 Zinc Chloride 1.5 Menthol 0.25Alcohol 25.0Glycerin 50.0 Cinnamon Water 200.0 No. 2 Quinine Hydrochloride 1/2 Urea 4 Glycerin 25

Water, Distilled, To make 100 Flavor and color to suit. Adjust pH, with caustic soda to about 7.

Throat Gargle

To 75 cc. of 95% ethyl alcohol (not the denatured variety) add 45 cc. of water. Then, with stirring, add 5.4 grams of ground ferric chloride, hexahydrate. When solution is effected add 45 grams of potassium chlorate and 200 cc. of water. Next add 240 cc. of glycerin and enough water to make 1000 cc. total volume. Mix well.

Dosage: 2 tablespoonfuls in half a glass of water and gargle at intervals of one hour.

Ephedrine	Spray	
Ephedrine Hydro-	•	
chloride	4	gr.
Sodium Chloride	2	gr.
Water, To make	1	fl. oz.

Sourdin Chioride	∠ gr.
Water, To make	1 fl. oz.
terrories and the second and the sec	
Buffered Ephedrine No	ose Drops
Ephedrine Sulphate	0.5
Potassium Phosphate	
Monobasic	0.5
Sodium Phosphate	
Dibasic	0.5
Potassium Chloride	0.15
Sodium Chloride	0.15
Dextrose, Anhydrous	0.9969
Preserved Water,	

To make 100 cc. If a one per cent solution of ephedrine sulphate is desired, the amount of dextrose in the above formula is reduced to 0.7867 g., and for a two per cent solution the dextrose is reduced to 0.3663 g. The quantities in the above formula must be weighed accurately on an analytical balance and made up to the indicated volume in a volumetric flask in order to obtain the desired tonicity and pH values. In addition the chemicals used must be of the highest purity.

Antiseptic Snuff	
Sulfathiazole	10
Magnesium Carbonate	90
This is used to prevent see	condary
nasal infections.	

Ear Drops			
Formula No.	1		
Salicylic Acid	4	gr.	
Alcohol, Denatured	1	fl. oz.	
Dilute with 10-20 par	ts v	water fo	)1
use.			

No. 2			
Phenol, Liquefied	12	mi	n.
Glycerin, To make	1	fl.	oz.
Do not mix this wat	er.		

Eye Drops	
Boric Acid	10 gr.
Zinc Sulphate	1 gr.
Adrenaline Solution	
(1–1000)	30 min.
Distilled Water, To	
make	1 fl. oz.
No. 2	
Silver Protein	40 gr.
Distilled Water	1 fl. oz.
No. 3	
Atropine Sulphate	2 gr.
Distilled Water	1 fl. oz.
No. 4	
Soluble Fluorescein	2 gr.
Distilled Water	1 fl. oz.

Alkaline Eye Ointment	
Sodium Borate	1
Sodium Bicarbonate	2
Wool Fat	10
Distilled Water	10
White Petrolatum	80

Eye-Wash		
Boric Acid	16.2	g.
Zinc Sulphate	0.8	g.
Glycerin	15.4	cc.
Distilled Water	740.0	cc.

Toothache Dro	ops
Clove Oil	12
Camphor	6
Chloroform	6
Phenol	2
Menthol	2
Cinnamon Oil	3
Apply to cavity.	

Antiphlogistic Poul	tice
British Patent 521,	215
Aluminum, Powdered	2-5
Copper Sulphate,	
Anhydrous	2-6
Sodium Chloride	1-4
Silica	0.2 - 13

Poison-Gas Ointment	
Eucalyptol	5
Ichthyol	0.8
Olive Oil	45
Calcium Hydroxide	50
(Saturated Solution)	

Mustard Gas Itch	Ointment
Benzyl Alcohol	50
Stearic Acid	30
Glycerin	10
Pontocaine	1
Menthol	1

Protective	Against	Mustard	Gas
Glycerin			3
Gelatin			2
Water			3

This is applied to feet of animals in contaminated gregs. To render it waterproof, it is treated with formaldehyde after application.

Tear Gas Cleaner	for	Skin
Alcohol (50%)		96
Sodium Sulphite		4

Air Raid Abrasion	Antiseptic
Potassium Iodide	640 gr.
Iodine	200 gr.
Distilled Water	1 fl. oz.
Glycerin, To make	20 fl. oz.
Grind the potassiun	m iodide to
7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7	

Grind the potassium iodide to a fine powder, add the iodine, mix, add the water and make up to volume with glycerin.

This solution may be used full strength or half strength. In the lat-

ter case it is diluted with glycerin, never with water.

The preparation is used to paint on abrasions. It may also be used to pour into wounds instead of sulfanilamide, or to swab out wounds which cannot be excised.

Ointment Base	
Formula No. 1	
Glyceryl Monostearate	15
Cetyl Alcohol	15
Glycerin	35
Diethylene Glycol	35
The inquedients are best	- L

The ingredients are heated together until all of the solid particles are melted and it is then stirred slowly until cool. This formula can be modified by incorporating water into each ointment as indicated in the parentheses below. The amount of water added is governed by the consistency of the finished ointment.

This base is compatible with the following medication:

Phenol, 2 per cent (42% water in final ointment).

Rectified Oil of Birch Tar, 10 per cent (30% water in final ointment).

Sulfur, 15 per cent (37% water in final ointment).

Ammoniated Mercury, 10 per cent (45% water in final ointment).

Coal Tar, 5 per cent (32% water in final ointment).

Burrow's Solution, 10 per cent (no water added to final ointment).

Balsam of Peru, 10 per cent (12% water in final ointment).

#### No. 2

Glyceryl Monostearate	10	g.
Glycerin	25	g.
Bentonite	2	g.

Distilled Water, To

make 100 g. The bentonite is mixed with 50 cc. of distilled water and stirred into a uniform magma. The glyceryl monostearate is melted in the glycerin on a water-bath and added to the magma, warmed to the same temperature and more distilled water added to make the product weigh 100 g. It is then stirred until cool.

Emulsified Ointment Base
Sodium Lauryl Sulphate 0.5
Cetyl Alcohol 8.0
Cocoa Butter 6.5
Petrolatum, White 20.0
Water 65.0

Water content has been retained at a fifty per cent ratio in ointment emulsions in which medication is added. There is no reason other than that this water ratio is a convenient amount to work with and gives satisfactory results. The following chemicals have been incorporated in this emulsion system, either separately, or combined in varying percentages:

Salicylic acid 3%/c Benzoic acid 6%.

Juniper tar (Oil of cade) 10%/c Salicylic acid 3%.

Coal tar 5%.

Kaolin 10%/c Sulfur precipitated 10%.

Ammoniated mercury 5% and 10%.

Sulfur precipitated 10%.

Phenol 2%.

Sulfathiazole 1%.

Balsam Peru 10%/c Sulfur precipitated 10%.

Salicylic acid 2%/c Sulfur precipitated 5%.

Calamine 8%.

Emulsion Ointment Base Propylene Glycol 6.00 Water 1.92 Wetanol (Wetting Agent) 0.25 Petrolatum, White 91.83

Germicidal Emulsion Base
U. S. Patent 2,281,249
O-Phenylphenol 24
Sulfonated Castor Oil 36–136
(Partially neutralized)

A 5% emulsion of this, with water, gives a pH above 7.

Ointment for Dry and Rough Skin

A compound ointment specified for use in the treatment of excessively dry skin conditions and for promoting exceptionally rapid healing of abraded skin contains the essential unsaturated fatty acids, together with lecithin, cholesterol and other synergistically acting ingredients.

Lecithin 7.0
Anhydrous Lanolin 35.0
"Vitamin F" Concentrate 11.5
Special Lard 46.0
Peppermint Oil 0.5

To this base, sun-bleached beeswax may be added to procure satisfactory stiffening of the product. About 10 per cent of beeswax seems to give the most desirable consistency.

#### Ringworm Treatment Formula No. 1

Twenty (20) grains (1.3 g.) of salicylic acid is dissolved in one ounce (32 cc.) of alcohol, and this lotion is applied repeatedly. A dram (4 cc.) of glycerin will prevent toorapid evaporation; a minim or two of rose water will impart a pleasing odor.

No. 2

Salicylic Acid	1.0	g.
Benzoic Acid	1.0	g.
Alcohol (90%)	30.0	cc.

Apply twice daily with a cotton-

wrapped match.

For the dry, horny type, Whitfield's ointment should be used:

#### No. 3

Benzoic Acid	<b>2</b> .0 g.
Salicylic Acid	1.0 g.
Wool Fat	1.6 g.
White Petrolatum	30.0 g.

Both of these remedies should be used long after the last traces of the

disease have disappeared.

A case of eczema of the hand, of 15 years' duration, cleared up in six weeks after the patient was instructed to scrape the ringworminfected toenails with the edge of a glass slide, following a hot potassium permanganate foot bath. The allergic manifestations of mycotic infections of the feet are almost always on the hands, and are more resistant than the original focus. The great majority of hand lesions are dermatophytids (fungus-free) and should be treated with soothing remedies while the feet are undergoing active treatment.

The hands should be soaked in Burrow's solution, 1 to 10 in warm water, for one hour, three times daily. Overnight and between soakings, this combination should be applied to the hands: Burrow's solution, 10 parts; anhydrous lanolin, 20 parts; Lassar's paste, 30 parts. The feet should be soaked in a potassium permanganate solution (5 grains to a basin of hot water) for 30 minutes. Whitfield's ointment should be used between the toes

overnight.

#### No. 4

Petrolatum	190
Melt and Add:	
Benzoic Acid	32

FORMULARY	
Salicylic Acid	14
Mix till dissolved	i.
When nearly coo	l add:
Phenol	$^2$
Thymol	$^2$
Mix	
Stir till cool	
Pass through an o	ointment mill.
No.	5
Itching Feet (	Whit field's)
Ointm	ent
Salicylic Acid	15 gr.
Benzoic Acid	25 gr.
Soft Petrolatum	2 dr.
Cocoanut Oil q. s.	
Apply at night f	or a week, then
omit treatment for	a week and re-
peat if necessary.	
No.	6
Camphor	1–3 g.

Camphor 1-3 g.
Phenol U. S. P. (Melted) 3 g.
Rub together in a mortar until
uniform. Do not apply to wet skin
for then it is caustic.

#### No. 7

To:	
Ethyl Alcohol	50%
Water	50%
Add: (Based on amou	nt of above
mixture)	
Salicylic Acid	6%
Benzoic Acid	12%

# Apply once or twice a day after washing.

## Skin Coating to Prevent Dermatitis U. S. Patent 2,249,523

	F	'ormu	la N	Vo. 1	
Cellul	ose	Trib	utyr	ate	1
Butyl	$\operatorname{St}$	earate	•		3
Heat	to	160°	C.	while	stirring
11 (	٦	1:		7 *	c 1

# slowly. On cooling a gel is formed. No. 2 Collulose A cotate Steprete

Centitiose Acetate Stearate	T
Butyl Stearate	2
Cottonseed Oil	2

Zinc Oxide 2

Impetigo Lotio	n		
Boric Acid		gr.	
Zinc Sulfate	1	gr.	
Saturated solution of			
Sulfanilamide in			
freshly distilled			
water, To make	1	fl.	oz.

Dermatological Cream	
Glyceryl Monostearate	10
Glycerin	25
Bentonite	2
Distilled Water, To make	100
The suggested procedure	is t

sprinkle the bentonite on 50 parts of distilled water, and, after it has become thoroughly wetted, to stir the mixture until a uniform magma results. The glyceryl monostearate is melted in the glycerin on a waterbath, and the mixture is added to the magma, warmed to the same temperature, together with sufficient distilled water to bring to the required weight. The cream is then stirred until cold. The bentonite can be preserved, if desired, and used in the form of a 7 per cent magma. Creams containing boric acid, tannic acid, iodine, sulphur, benzoic acid, calamine, ichthammol, and potassium iodide, respectively, were prepared using this basis, and appeared to be satisfactory.

Poison-Ivy Protective	
Ferrous Sulfate	30
Water	250
Alcohol	250
Glycerin	25

Poison Ivy Treatment	
Formula No. 1	
Tannie Acid U.S.P. 2	g.
	g.

The above is dissolved in one pint of water. Apply solution, when cold, to parts affected, with cupped hand once every two hours for about a half a day. The application of this solution will remove the itch instantly, and the postules will be removed overnight.

#### No. 2

This ointment should be thickly applied to exposed parts, such as the hands and face, if necessary, before contact with poison ivy. Clothes must be removed after exposure before the ointment is washed off, otherwise the unprotected skin may be exposed to clothes which have been contaminated. Tools and instruments or clothing which have been used in cutting poison ivy must be decontaminated before being used again. Decontamination can be effected by washing clothes or immersing tools for 15 to 20 minutes in a 1% solution of calcium hypochlorite.

111011001	
No. 3	
Castor Oil	21.5
Olive Oil	21.5
Lanolin, Anhydrous	21.5
Diglycol Stearate	12.9
Paraffin, Refined	8.6
Boric Acid	2.0
Sodium Perborate	10.0
Duponol WA, Pure	2.0
No. 4	
Cetyl Alcohol	35.1
Stearyl Alcohol	5.3
Ceresin	3.5
Castor Oil	20.8
Mineral Oil	21.9
Duponol WA, Pure	1.7
Sodium Perborate	10.0
Boric Acid	1.7

Keep in closed containers.

Calamine Lotion		
Prepared Calamine	150	g.
Bentonite	20	g.
Water, To make	1000	cc.

Mix the bentonite with 800 cc. of water, agitate well and frequently and allow to stand 12 hours or more. Thoroughly incorporate the calamine with about one-tenth of the bentonite sol and gradually incorporate the remainder of the sol in small portions at a time until the mixture is complete. Finally add enough water to make 1000 cc. and shake well.

#### Burn Treatments Formula No. 1

30 m

20.0

Claracrin

Glycerin	30 g.
Distilled Water	70 cc.
Brilliant Green	0.1 g.
No. 2	
Tannic Acid Jelly	
Tannie Acid	10
Glycerin	10
Tragacanth	3
Euflavine	0.1
Water, To make	100
· No. 3	
Silver Nitrate	0.5
Glycerin	10
Tragacanth	3
Activated Charcoal,	
Powdered	15
Water, To make	100
No. 4	
Aluminum Naphthol	
Disulphonate	2
Ichthyol	4
Liquefied Phenol	2
Wool Fat	62
Yellow Petrolatum	30

Burn Jelly Formula No. 1 Tannic Acid

Proflavine Sulphate or	
Methyl Violet	0.1
Procaine	2.0
Glycerin-Tragacanth	
Base, To make	100.0
Glycerin-Tragacanth	Base
Glycerin	10.1
Pulv. Tragacanth	2.0
Distilled Water, To	
make	100.0
No. 2	
Tannic Acid (10% Solu	1-
tion)	32
Polymerized Glycol Ole	eate 2
Warm together and mix	
persed.	
1	

#### Sulfanilamide Ointment Formula No. 1

(a) Dissolve 10 parts of sulfanilamide in 25 parts of nearly boiling water; filter. (b) To 4 parts of sodium alginate add 75 parts of boiling water and then strain the resulting mucilage through fine gauze. Mix the sulfanilamide solution and the sodium alginate while hot, and stir until cool. (c) Add 16 parts of anhydrous wool fat, 1 part of sodium chloride dissolved in 4 parts of water, and 78 parts of white petrolatum base to the sulfanilamide-sodium alginate combination and mix until smooth.

#### No. 2

- 1. Dissolve 10 parts of sulfanilamide in 25 parts of almost boiling water and filter.
- 2. Add to 100 parts hot starch solution.
- 3. Cool and add 15 parts of hydrous wool fat and 50 parts of petrolatum.

#### Sulfanilamide Paste

To make 1000 g. of paste, 8 g. of sulfanilamide and 75 g. of medicinal

pectin are rubbed with 180 g. of glycerin. To this is added, at once and with sufficient stirring, a hot solution of benzoic acid in 735 g. of Ringer's Solution. Emulsify with hand homogenizer or with mortar and pestle.

No. 2

Five per cent of the powdered drug in a base consisting either of equal parts of zinc oxide and liquid petrolatum or of equal parts of iodoform and liquid petrolatum.

Sulfanilamide Thro	at Spra	ay
Sulfanilamide	1.7	
Alcohol (90%)	7.5	cc.
Acetone	7.5	cc.
Glycerine, To make	100.0	cc.

Sulfanilamide Emulsion
Powdered Sulfanilamide 175 gr.
Cod Liver Oil 4 fl. oz.
Oleic Acid 36 min.
Solution of Calcium
Hydroxide, To

Sulfathiazole Emulsion
Sulfathiazole (Finely
powdered) 5
Triethanolamine 2
Distilled Water 24
White Beeswax 5
Liquid Petrolatum 64

Melt the beeswax in the liquid petrolatum on a water bath. Mix the triethanolamine with the water and heat to the same temperature as the petrolatum-wax mixture. Mix the sulfathiazole with the triethanolamine solution and add the petrolatum-wax mixture, stir vigorously until a creamy emulsion is obtained.

Wounds and ulcers are packed

with gauze which has been soaked in the emulsion. The preparation keeps the walls of the cavity oiled, preventing the adherence of clothing or lymph. Loose packing over the emulsion-soaked gauze permits constant drainage and the packing need not be removed for several days. It is readily removed with little discomfort to the patient.

Sulfathiazole Ointment	,
Formula No. 1	
Cold Cream	70
Absorption Base (Para-	
chol)	25
Sulfathiazole	5
No. 2	
Lanolin, Anhydrous	47.5
Sulfathiazole, Finely	
divided	5.0
Vanishing Cream	47.5
Mar 1 1	

Melt the lanolin and add the vanishing cream slowly with adequate beating, so as to produce a good, fluffy cream. Add the very finely divided sulfathiazole and continue beating until a uniform mixture is obtained. If the mixture is not readily emulsified, add three or four drops of ethanolamine and continue the beating.

This ointment is particularly adapted to various skin irritations, eczema, and similar skin disturbances.

No. 3

Stearic Acid 35

Triethanolamine 5

Glycerin 10

Lanolin, Anhydrous 250

Powdered Sulfathiazole 25

Distilled Water, To make 50

Melt the stearic acid and lanolic

Melt the stearic acid and lanolin and use portion of water, add glycerin and triethanolamine and add to the melted stearic acid and lanolin. Allow to cool to about 35-40° C. Rub sulfathiazole in mortar with water and add to the ointment base under mechanical, constant stirring.

#### Foot Corn Ointment

Benzoic Acid	1.0
Lanolin	44.5
Salicylic Acid	5.0
Sulfathiazole	5.0
Vanishing Cream	44.5

Warm the lanolin and vanishing cream together and beat in a finely pulverized mixture of the benzoic acid, salicylic acid, and sulfathiazole. When all the ingredients have been added, continue to beat until a good, fluffy cream is obtained. This cream is particularly useful for soft corns between the toes and similar foot irritations.

# Cod Liver Oil Ointment Cod Liver Oil U.S.P. 45% Paraffin Wax 7% Stearic Acid U.S.P. 20% Cetyl Alcohol 3%

Lanolin Hydrous, To make 100%

Weigh the cod liver oil and lanolin and heat, melt paraffin wax, stearic acid and cetyl alcohol and pour the molten waxes at a temperature of 70° C. into the cod liver oil and lanolin at 70° C. Stir until cooled to room temperature and put through ointment mill.

#### Dhobie Itch Ointments Formula No. 1

Formula No. 1	
Salicylic Acid	4
Bismuth Subnitrate	10
Mercury Salicylate	4
Eucalyptus Oil	10
Lanolin or Petrolatum	100

No. 2	
Resorcin	2 dr.
Salicylic Acid	10 gr.
Lanolin	$4  \mathrm{dr}$ .
Petrolatum	4 dr.

#### Zinc Peroxide Ointment

Zinc Peroxide 10 g. Glyceryl Monostearate 3 g. Peanut Oil, To make 100 g.

The oil is heated at 150° C. in a hot-air oven and cooled to normal temperature. The glyceryl monostearate is added and the mixture heated to 130° C. for 1 hour. After cooling to normal temperature the peroxide is incorporated with the mixture in a sterile mortar by sifting through sterile muslin under aseptic conditions. The suspension is stored in sterile glass-stoppered bottles capped with sterile parchment paper.

#### Allantoin Ointment

Petrolatum	45
Chlorthymol	0.15
Paraffin Wax	6
Stearic Acid	6
Allantoin	2
Lanolin, Hydrous, To	
make	100

#### Analgesic Salve

Menthol	15
Methyl Salicylate	15
Hydrous Lanolin	70
Melt together and mix well.	

#### Acne Lotion Formula No. 1

Alcohol (90%)	50.00
Ether	50.00
Rhodinol (ex Geranium)	0.10
Methyl Cinnamate	0.02
Phenylethyl Alcohol	0.10

	AND THE RESIDENCE OF THE PROPERTY OF THE PARTY OF THE PAR		
_	No. 2		
	Menthol	(	0.10
	Ti-Tree Oil	2	2.50
	Alcohol	60	0.00
	Propylene Glycol	24	1.70
	Sodium Hexametaphos	- -	
	phate		00.5
	Sulfonated Olive Oil	7	7.70
	Water	250	00.0
	Caraway Water	50	00.0
	Witch Hazel Extract	100	00.0
	Scabies Ointmen	ita	
	Formula No. 1		
	Benzyl Benzoate	200	ee.
	Lanette Wax S or Ami		с.
	nostearin	10	C)
	Water	800	
	No. 2	000	
	Benzyl Benzoate	200	cc.
	Glyceryl Monostearate		g.
			cc.
	11 0000		- 0

	Seabie	es Su	lph	ır S	oap	
Sulph					•	18
Soap,						$\epsilon_2$
~	7.1	1		*	241.12	

Mix well and work in a little mucilage of acacia and water. Roll out the mass and cut into 60 gr. tablets and dry quickly at room temperature.

#### Scabies Treatments

For infants and young children the following formula may be used:

#### Formula No. 1

Precipitated Sulfur	1/2 dr.
Zinc Oxide Powder	½ dr.
Petrolatum	1 oz.

In older children, the strengths of the powders may be increased. Six applications for three nights and three mornings are usually found satisfactory.

In adults, the following formula may be applied for three nights only, its action being rapid and effective, but not to be used in excess:

#### No. 2

2.0. 2		
Betanaphthol	$\frac{1}{2}$	dr.
Sublimed Sulfur		dr.
Peruvian Balsam and		
Petrolatum, of equal		
parts sufficient to		
make	1	oz.

#### No. 3

Five to fifteen per cent alcoholic solutions of Peruvian balsam or a 40% aqueous solution of sodium thiosulfate may also be used. Following the latter by 15 minutes, however, a 4% solution of hydrochloric acid must be applied and both solutions reapplied one hour later. An 18% bland sulfur soap paste is effective.

#### No. 4

Another mixture to be painted over the body with a soft brush consists of:

Benzyl Benzoate	50
Liniment of Soft Scap	65
Alcohol (90%)	30
Distilled Water	5

#### No. 5

A lotion of benzyl benzoate is composed of equal parts of soft soap, isopropyl alcohol and benzyl benzoate. About 150 grams of the lotion are required for each patient.

#### Head Lice Treatment Formula No. 1

Use 15 per cent of Lethane (n butyl-carbitol-thiocyanate) in deodorized purified kerosene. One treatment applied to the head without a towel covering kills nits and lice immediately. The head is not to be shampooed for a few days.

#### No. 2

Lauryl Thiocyanate	25
Mineral Oil. Refined	50

Scurf Pomade		
Salicylic Acid	30	gr.
Borax	15	gr.
Soft Paraffin Wax	1	OZ.
Balsam of Peru	30	gr.
Cinnamon Oil		drops
Bergamot Oil	10	drops
Mix.		

#### Treatment for "Swimming Pool Ear"

Fungous infection of the external ear may be prevented by instilling a few drops of
Boric Acid 2 g.
Mercury Bichloride
(1:1000) 8 cc.
Alcohol, To make 30 cc.

after swimming.

#### Suppositories Formula No. 1 Extract of Belladonna 0.05 g. Cocoa Butter 0.40 g. Sugar of Milk 2.00 g. No. 2 White Wax 2.50 g. Hard Paraffin Wax 5.00 g. Wool Fat 5.00 g. 35.00 g. Spermaceti Liquid Paraffin, To make 100.00 g. No. 3 Cocoa Butter 65 35 Stearic Acid No. 4 2 Cocoa Butter Chloral Hydrate 1 Lactose

Soothing Massage Oil

Olive Oil or Almond Oil

5 g.

5 g.

20 g.

75 g.

Eucalyptol

Spermaceti

Camphor

#### Liniment of Soft Soap (Tincture of Green Soap)

Soft Soap U.S.P. 650 g. Cedar Leaf Oil 20 cc. Alcohol, To make 1000 cc.

#### Healing Rubbing Alcohol Compound

To a pint of any good grade of rubbing alcohol add:

Phenol (88%) 5 drops
Glycerin 5 drops
Castor Oil 5 drops
Shake thoroughly, and use for tired muscles of the feet and limbs, and hands. This is especially good

#### Aromatic Liniment Formula No. 1

10 oz.

for chapped and rough hands.

Camphor

Certaforacia	4.0 02	
Menthol	4 oz	
Thyme Oil	4 oz.	
Sassafras Oil	4 oz.	
Tincture of Myrrh	6 oz.	
Tincture of Capsicum	6 oz.	
Chloroform	5 oz	
Alcohol 2 to	-	
No. 2	-/2 1/4	•
Methyl Salicylate	5.0	)
Cedar Leaf Oil	1.0	
Sassafras Oil	1.0	
Hemlock Oil	1.0	
Chloroform	5.0	
Tincture of Opium	5.0	
Spirit of Camphor	5.0	
Rectified Turpentine	3.0	
Tincture of Capsicum	3.0	
Alcohol	71.0	
No. 3	0.0	
Ground Capsicum	8.0	
Soft Soap	5.0	
Camphor	3.0	
Eugenol	0.5	
Methyl Salicylate	2.0	)

Sassafras Oil	1.0
Soap Liniment	30.0
Alcohol	50.5
Trto the consistence	fl

Macerate the capsicum, soft soap, camphor and soap liniment for ten days. Filter and add to the rest of the ingredients.

12.5
12.5
12.5
12.5
100.0

Liniment
30.0
10.0
0.5
32.5
5.0
100.0

ıt
26.5
26.5
100.0

Athletic Rub	
Methyl Salicylate	2.0
Witch Hazel	50.0
Alcohol, To make	100.0

Acetone Liniment	
Methyl Salicylate	4.0
Peppermint Oil	0.5
Sassafras Oil	0.4
Chloroform	10.0
Soap Liniment, To make	100.0

Hay Fever Treatment
Formula No. 1
Potassium Chloride 7.5 g.
Distilled Water,

To make 100 cc.
Take 1 teaspoonful three times daily.

#### No. 2

After years of suffering with this malady, doubtless from rag weed pollen, the contributor of this note has tried numerous remedies without avail, but has discovered that, by taking into the system extra amounts of common salt the flow of mucus is greatly reduced if not entirely arrested.

It seems that the loss of salt to the system during the summer months, as well as during the hay fever period, reduces the resistance to pollen attack. For an adult weighing between 130 and 150 pounds, about 1 gram (15 grains) of salt in a glass of water morning and evening, produces a marked effect.

*Note:* The Editor would like to hear, from those who try the above remedy, as to its efficacy.

#### Asthma Treatment Methyl Atropine Nitrate, or Bromide 0.14 Papaverine 0.08 Sodium Nitrate 0.08 Adrenalin 0.05 Lactic Acid 2.50 Glycerin 10.00 Distilled Water, To make 100.00

#### Treatment of Hiccup

Such simple measures as holding the breath, pressing on the abdomen, a series of deep breaths or rebreathing from a paper bag, traction on the tongue, pressure on the ensiform cartilage, or inhalation of aromatic spirits of ammonia, will often relieve hiccup. In a stout person, after a heavy meal, the tendency to hiccup is relieved by bending back in ger

the chair so as to give more space in the upper abdomen.

A simple carminative, such as:

Menthol 8 gr. (0.5 g.)

Compound Spirit
Ammonia
Spirit of Chloroform
form
Tincture of Gin-

Two teaspoonfuls in water, taken as strong as possible, is of value, or a few drops of oil of cloves or cajuput on sugar.

If hiccup is due to gastric irritation and does not respond to simple measures, washing out the stomach and the use of an alkaline powder will be effective.

Therapeutical Pectin Dressing Dissolve 2% flake pectin in distilled water and shake the solution occasionally for 24 hours. Then autoclave during 15 minutes at 20 lb. and keep sealed until used. Float the pectin-solution with a bulb syringe onto gauze until saturation. Cover the infected burn or wound with this dressing and remoisten every 4–8 hours. Burns are usually healed within 8 days.

Uses and Treatment of Pectin
Pectin has many valuable properties indicating its use for various
therapeutic and cosmetic compositions. In every treatment of this material, special care has to be taken
of clotting. Pectin should therefore
never be contacted with water in
dry state. It must preliminarily be
moistened with small quantities of
alcohol and then carefully comminuted in a mortar whilst gradually
increasing the additions of water.

The swollen mass is heated on a water bath. If an addition of glycerin is provided for, it should be comminuted with the alcohol moistened pectin in the mortar before adding water. Glycerin may be replaced by glycol, diethylene-glycol, etc.

If aqueous pectin solutions are added with alcohol, a jelly is formed when the amount of alcohol attains 40%; a much smaller quantity of alcohol is required to bring about gelation if the pectin solution already contains glycerin.

Pectin has the property of stimulating the papillary glands thus increasing the salivary exerction and is therefore suggested as an addition to toothpastes.

#### Pectin Jellies

Pectin jellies are prepared by moistening the required quantity of pectin with a small amount of alcohol, adding acidulated water and stirring the mixture in the cold. The rest of the water is then slowly added and the whole mass is heated on a water bath, whilst pouring in the rest of the alcohol. The mixture congeals after cooling. Water may separate out from the softer jellies on standing. This "bleeding" is prevented by the addition of small amounts of tragacanth or Galagum.

Formulas for pectin jellies, suitable for carriers of pharmaceutical and cosmetic compositions:

# Formula No. 1 Stiff Cutting Jelly

Stiff Cutting Jelly	
Pectin	1.5
Water	65.0
Glycerin	2.5
Alcohol (92%)	0.00
Citric Acid	1.0

No. 2	
Pectin	4
Glycerin	30
Water	80
Citric Acid	1
No. 3	
Semi-Fluid Jelly	
Pectin	0.9
Glycerin	18.0
Water	53.6
Alcohol (92%)	27.0
Citric Acid	0.5
No. 4	
Pectin	1.3
Tincture of Benzoin	1.0
Glycerin	96.4
Citric Acid	0.5
Lime Oil	0.8

Sugarless Sweetener
Tragacanth, Powdered 2.50 g.
Alcohol, To suit
Chloroform 0.25 cc.
Soluble Saccharin 0.25 g.
Distilled Water, To
make 100.00 cc.

#### Enteric Coating Base

Monostearin is being used as a replacement for shellac for enteric coatings. Monostearin is insoluble in water, but readily emulsifies and breaks down in the system in contact with alkalies.

Enteric	Coatings	(Pill	and	Tablet)
	Formul	a No	. 1	

HIRITA TAO. T	
20	g.
ite, Arsenic-	
30	g.
30	cc.
cohol, To -	
100	cc.
No. 2	
22.5	g.
	20 ite, Arsenic- 30 30 cohol, To

2.5 g.

Stearic Acid

Alcoholic Solution of		
Shellac (10%)	10.0	
Use at temperature at	which	shel-
lac is fluid		

coo ao ocmperantre ao	will slie!-
lac is fluid.	
No. 3	
Shellac	25%
Ammonia Water	$37\frac{1}{2}\%$
Alcohol	$37\frac{1}{2}\%$
No. 4	,
Peptonized Keratin	1 g.
Spirit of Ammonia	6 cc.
(with a few drops of	
water)	
Apply warm.	
No. 5	
${f Mastic}$	25%
Methylpropylketone	75%
Sprinkle dried coating	with mag-
nesium stearate.	_
37 0	

contract of co.		
No. 6		
Cetyl Alcohol	10	g.
Mastic	10	g.
Acetone	100	cc.

No. 7

Myristic acid, 68%; "Opal" wax, 25%; castor oil, 2%; cholesterol, 1% and sodium taurocholate, 4%. This coating prevents tablets from disintegrating in the stomach for at least 6 hours but is a coating which will dissolve in the intestines in from ½ to 2 hours. The fatty acids in the mixture are not digested by stomach juices but form diffusible suspensions with the bile salts in the intestines contrary to the old theory.

#### Binder for Yeast and Other Tablets

Yumidol (Sorbitol syrup) is being used very successfully as a binder for yeast and similar tablets. The necessary amount of Yumidol is weighed out and mixed with 50% of yeast. It is then screened through 40 mesh, and the remaining

yeast added and screened again. It is aged 16–20 hours in air tight containers and screened again after aging prior to compression. No heating or drying operation is necessary. The specific amount of Yumidol required as binder can only be determined by specific formulation but, in general, about 2½% is used, based on the weight of the yeast or other material to be made into tablet form.

# Polishing or Pharmaceutical Tablets, Pills, Etc.

Pharmaceutical tablets are generally polished by tumbling with a mixture of natural waxes in a suitable solvent such as acetone. This mixture of natural waxes can be replaced by glyceryl tristearate which will not spot or discolor colored or black coatings. In this connection anhydrous ethyl acetate or deodorized naphtha are suggested as solvents.

#### Tablet Making Lubricant

Add 1-4 oz. glyceryl tristearate per 100 lb. of granulation to prevent sticking to dies.

# Medical Prophylactic (Preventive) Capsules

Mercuric Cyanide	0.075
Levigated Calomel	25.000
Anhydrous Lanolin	15.000
Yellow Soft Paraffin	
Wax	27.500
Mineral Oil, Refined	27.500

All ingredients and mixing apparatus must be dry. Mill between stone rollers. Pack into capsules of 36 grains.

5.000

Acrawax

# Activated Carbon (Medicinal) Tablets

Activated Carbon	200
Tragacanth, Powdered	8
Sugar	195
Water	68

	-
Synthetic (Medicinal)	Coal Tar
Anthracene	1.10
Naphthalene	10.90
Phenanthrene	4.00
Carbazole	2.30
Picolene	0.58
Pyridin	0.58
Quinolin	0.58
Phenol	0.70
Cresol	0.75

Universal Poison Antidote Activated Carbon 2 Magnesium Oxide 1

Use in teaspoonful doses in small glass of water.

Tannie Acid

#### Improved Aspirin U. S. Patent 2,134,714

O. W. Latter Myromy err		
Aspirin	20	
Saccharin	1/2	
Stareh	4	
Tincture of Vanilla	4	

This composition has an improved taste and increased rate of absorption when taken.

Anti Acid Stomach Tablets
Sugar 1 lb.
Calcium Carbonate ½ lb.

Peppermint Essence

Mix sugar and carbonate with one and one half pints of water and boil until mass will set on a cold spoon. Cool and add one fourth ounce of essence of peppermint while stirring is still possible. Spread thin over a flat pan and cut into \(^1\)4 in. cubes.

Anthelmintic Tablet	
U. S. Patent 2,282,290	
Phenothiazine	80
Starch	8
Sodium Bicarbonate	5
Tartaric Acid	4
Sodium Choleate	2
Phenolphthalein	1

Cod Liver Oil Emulsion
Cod Liver Oil 50
Gum Arabic 3
Gum Tragacanth 34
Irish Moss 1
Calcium Glycerophosphate 1
Glycerin 6
Water 38

Dissolve arabic in 9 parts of water while heating to 145° F. When dissolved, cool to 90° F. Disperse tragacanth in 9 parts of water while heating to 180° F. When well dispersed, cool to below 90° F., add to arabic solution. Make up a 10% Irish moss solution, boil thoroughly, then pass through homogenizer after straining and cool. Take aliquot equivalent to above percentage and add to gum solution. With stirring, add glycerin, then glycerophosphate and, finally, the oil in a small stream. Do not add oil so that "lakes" are formed on the surface; add just sufficient for the body of the mixture to take up.

When thoroughly mixed, homogenize at a total pressure of about 2500 lb., with the greater pressure, about 2000 lb., on the first valve.

After homogenization let set for a few hours to effect readjustment; then stir slightly and bottle.

Mineral	Oil Emulsion	(Laxative)
Heavy	Mineral Oil	45.0
Acacia	. Gum	2

51.9
0.5
0.1
0.5

Add to oil—acacia mixture. Mix thoroughly and pass through homogenizer at 2500 lb.

Pine Needle Oil En	nulsion
Pine Needle Oil	12 oz.
Methyl Cellulose	$2\frac{1}{2}$ oz.
Water	6 qt.
Preservative	•
(Moldex), To suit	
Color, To suit	

Cacao Butter Substitutes Formula No. 1	
Lanolin	6
Spermaceti	3
Olive Oil	1
No. 2	
Paraffin Wax	1
Lanolin	1
Olive Oil	1
No. 3	_
Lanolin	9
Stearin	1
Triethanolamine Stearate	3
No. 4	Ü
Beeswax, Sunbleached 2.	5
Paraffin Wax, Hard 5.	
Lanolin 5.	
Spermaceti 35.	
Mineral Oil U.S.P. 100.	-
Willieral Oil U.S.F. 100.	·U

Nux Vomica Extract, Substitute for Strychnine Hydrochloride 8 gr.
Burnt Sugar 12 min.
Alcohol (90%) 192 min.
Distilled Water, To make 1 fl. oz.
The preparation has the same

strychnine and alcoholic content as the official liquid extract and if necessary it can be diluted satisfactorily with alcohol to produce a substitute for the tineture. If it is prepared in bulk and kept for any length of time prior to use, filtration is usually necessary, although this does not have any appreciable effect upon its color.

#### Barium X-Ray Meal

Two types of x-ray films are required to rule out cancer or ulcer of the stomach: (1) A thick barium suspension, to completely fill out the stomach and outline the greater and lesser curvatures; and (2) a thin suspension to delineate the gastric rugae. By use of this new, inexpensive preparation (which can be made anywhere), both views are shown on one film, thus saving time and films.

#### Formula No. 1

Seven ounces of water are stirred thoroughly with 20 grams of a mixture containing 4 parts of barium sulfate, 1 part of gum acacia, 1 part cocoa, and 1 part granulated sugar, by volume. The meal is taken and films are made as usual; no compression is needed.

#### No. 2

Methyl Cellulose 350 gr. Water 16 fl. oz.

Shake well and let stand overnight.

Rub down

Barium Sulphate 2.5 lb. Water 5–10 lb.

Then add the above mucilage and

Sodium Benzoate 40 gr. Add flavor to suit.

Fast Setting Plaster of Paris
Use a solution of:
Sodium Chloride 10 g.
Potassium Chloride 10 g.
Water (50° C.) 500 cc.

Quick Painless Remover for Surgical Dressings Solution No. 1

Pure White (72%) Olive

Oil Soap Flakes 100 g. Alcohol (95%) 300 g.

Distilled Water, To make 1000 cc.

No. 2

Same diluted as follows: 1 part in 3 parts distilled water.

First soak the adhering dressing by gently pouring a small quantity of Solution 1. Leave on a few minutes. Rinse by pouring on Solution 2. The dressing comes off easily without pain.

#### Acné Salve

Cade Oil 5 g.
Balsam Peru 8 g.
White Petrolatum Jelly 87 g.
Mix and whip to make a light
"mousse."

Athlete's Foot Salve
Colloidal Sulfur
Boric Acid
Almond Oil
Whipped Anhydrous Lanolin
Rose Water

Athlete's Foot Salve

6 12.5 g.

65.0 g.

Sore Throat Tablets
Potassium Chlorate 10.000 g.
Sugar 80.000 g.
Borax 8.000 g.
Eucalyptol 0.125 g.
Thymol 0.500 g.
Menthol 0.025 g.

Add glycerin and distilled water to make a paste. Mold and dry. For 200 tablets.

#### Waterproof Dressings and Bandages British Patent 448,742

Dissolve 1 polymerized acrylic acid ethylester in 4 acetone, methylene chloride mixture. Add to the solution a small quantity of dibutylphthalate (up to 5%). Pour the solution on a hard surface bearing a layer of fibrous material and allow to evaporate while in contact with the fibrous material.

#### Adhesive Tape Remover

A composition for removing plasters and adhesive tape from the skin comprises a mixture of preferably pure carbon tetrachloride with not more than 40%, preferably not more than 20%, of white oil. The mixture may contain up to 10% of alcohol.

#### Hemostatic Preparation British Patent 490,432

Mix 300 cc. of a 10% aqueous solution of a polyvinyl-alcohol with 50 cc. of an aqueous solution of iron chloride containing 80% FeCl<sub>3</sub>. 6H<sub>2</sub>O. Add 1000 cc. of a mixture of equal volumes of sterile 96% alcohol and water. Allow the solution thus obtained to flow slowly into 2700 cc. of 96% sterile alcohol whilst stirring vigorously. The yellowish precipitated powder is filtered off, washed with ethyl acetate and dried in vacuo at ordinary temperature.

Moth Proofing Solution	
Magnesium Silico Fluoride	1.5
Butyl "Carbitol"	5.0
Santomerse S	0.5

Wat	er, T	o ma	ke		100.0
Adju	ist to	pН			6.5
	3%	bу	weight	on	woolen
goods.					

Mosquito Repeller	ıt	
Formula No. 1		
Castor Oil	10	oz.
Thyme Oil	1	oz.
Pyrethrum Powder	1	ΟZ.
No. 2		
Citronella Oil	5	g.
Clove Oil		g.
Eucalyptus Oil		g.
Alcohol	255	g.
No. 3		
Dihydropyrone		cc.
Alcohol	95	cc.
No. 4		
Phenol		2
Pennyroyal Oil		4
Spirits of Camphor		6
Tar Oil		6
Lard Oil		12
No. 5		
Old offering Old	1 fl.	
Opanio	1 fl.	
O C C C C C C C C C C C C C C C C C C C	$_{2}^{\prime}$ fl.	oz.
No. 6	~~~	
U. S. Patent 2,293,	255	F0
Butyl "Carbitol" Aceta	te	50
Ethyl "Carbitol"		15
Corn Oil		7
Alcohol		28

#### Remedy for Insect Stings Formula No. 1

Dilute ammonia water or a paste made with Sodium Bicarbonate, followed with Zinc Oxide, Lime Water, or Calamine Lotion.

#### No. 2

Rub bites briskly with absorbent cotton saturated with Chloroform 100

Diglycol Laurate

Marked relief is gotten, even many hours after the bites have been received.

Silverfish Insecticide
Oatmeal (Ground to
Flour) 100
White Arsenic 8
Granulated Sugar 5
Salt 2½

Mix together dry, the oatmeal, white arsenic, sugar, and salt. Moisten the mass and mix thoroughly to bind the substances together. Then thoroughly dry the bait to prevent mold, and work it into small bits so that it can be scattered easily.

One level tablespoon of sodium fluoride powder can be substituted for the white arsenic in the above formula. If the substitution is made, simply mix the materials thoroughly, but do not add moisture.

Anti-Midge Preparation

To avoid discomfort from midges or gnats when working or walking in the open, the following glycerincontaining preparation may be applied to the exposed parts of the body as a preventive measure:

Glycerin 1 dr.
Tineture of Wormwood 3 dr.
Thymol 1 gr.
Cologne Water, To make 2 oz.

Those who have been bitten by these or other insects, will find that the preparation given below offers a means of soothing the bites:

Phenol 15 gr.
Glycerin ½ oz.
Rose Water, To make 4 oz.

Perfume for Hypochlorite Sprays Formula No. 1 Synthetic Neroli 1.0 g.

Synthetic Neroli 1.0 g. Cetyl Alcohol 1.5 g.

Carbon Tetrachloride 10.0 cc. Sulphonated Castor Oil 15.0 cc. Water, To make 100.0 cc. No. 2 Synthetic Musk 1.0 g. Cetyl Alcohol 1.5 g. Carbon Tetrachloride 10.0 cc. Sulphonated Castor Oil 15.0 cc. Water, To make 100.0 cc. One cc. of either 1 or 2 is added to 100 cc. of 10% Sodium Hypochlorite Solution.

Cesspool Deodorant and	
Germicide	
Formula No. 1	
Dowacide A (Antiseptic)	17
Aluminum Chloride	10
Paraformaldehyde	2
Hydrated Lime	66
Pine Oil	5
No. 2	
Aluminum Chlorida 50)	

Aluminum Chloride 50
Formaldehyde 100
Water 300
Pine Oil 50
Sorbitol Monolaurate 50
Mix together with vigorous sti

Mix together with vigorous stirring.

100
5
2
2

Saponified Cresol Disinfectant
Water 200 cc.
Cresol 500 cc.
Sodium Oleate 240 g.
Heat with stirring to 65° C. until
dissolved, Cool and add

Water, To make 1 l.
Mix until uniform.

Disinfectant and Bleach	n Powder
U. S. Patent 2,121	,501
Calcium Hypochlorite	15 - 20
Tartaric Acid	3-10
Sodium Chloride	45-80
Sodium Acetate, Anhy-	-
drous	2-10
Sodium Chromate	0.1-1
Borax	0-22

Disinfectant Emulsion
U. S. Patent 2,289,476
Orthophenyl Phenol 10–40%
Terpene Ether 15%
Sulphonated Castor
Oil, To make 100%

Disinfecting Infected Shoes Fungi-infected shoes can be inexpensively and effectively sterilized by spraying a 37% solution of formaldehyde into the shoes on three nights in succession.

Non-Alcoholic Iodine	Antiseptic
Iodine	1.000
Calcium Iodide	0.044
Potassium Iodide	0.048
Sodium Iodide	1.104

This is more penetrating and less irritating than tincture of iodine. A 3% solution of the above in water is recommended.

Mild Tincture of Iodine	U.S.P.
Iodine	20 g.
Sodium Iodide	24 g.
Diluted Alcohol, To	
make 10	000 cc.

Antiformin Type Antiseptic Anhydrous Soda Ash 100 g. Distilled Water, To vield 1000 cc.

Saturate this solution with chlorine gas, under the pressure available with the compressed gas in commercial cylinders.

#### Antiseptic

Alcohol (95%)	525.00	cc.
Acetone	100.00	cc.
Cresol, U.S.P.	5.00	cc.
Mercuric Chloride	0.70	g.
Eosin Y	0.60	
Acid Fuchsin	0.08	
Water, To make	1000.00	

Alcohol and acetone alone will kill 96 per cent of bacteria on the skin surface, and acetone is also a fat solvent. Cresol (tricresol) and mercuric chloride kill 98 per cent of such bacteria. The eosin and fuchsin are added as dyes, so that the antisepticized surface will be plainly visible. Such an antiseptic is quickdrying, quick-acting, is not injurious to the skin (unless the patient is allowed to lie in a puddle of it), to the operating room personnel, or to linens, and is capable of sustained action. If tax-free alcohol cannot be obtained, ordinary rubbing alcohol may be used (the pharmacist will recompute the formula to compensate for the weaker strength of the alcohol). It is an interesting fact that 50 to 70 per cent alcohol will kill organisms more quickly than will the 90 per cent strength.

#### Embalming Fluid

Sodium Nitrate	1 lb.)
Methanol	$ \begin{array}{c c} 1 & \text{pt.} \\ 5 & \text{pt.} \end{array} $
Water	5 pt.
Sodium Acetate	2 lb.)
Methanol	$ \begin{array}{c c} 1 & \text{pt.} \\ 5 & \text{pt.} \end{array} B $
Glycerin	5 pt.
Water	13 pt.

Formaldehyde Counter-	Odor
Patchouli Oil	10
Sassafras Oil	50
Methyl Salicylate	50
Eucalyptus Oil	50

Ointment for Embal	lmers' Eczema
Salicylic Acid	2.0 dr.
Phenol	$1.5  \mathrm{dr}.$
Zinc Ointment	4.0 oz.

Maggot Repellent for Embalm	ning
Kerosene	4
Turpentine	2
Carbon Tetrachloride	1
Methyl Salicylate	1
Use on cotton and plug the	nos-
trils.	

#### Iodized Oils

This method is applicable to all vegetable and animal oils, which contain unsaturated fatty acids.

At first the free fatty acids are removed, as they are very detrimental. This is accomplished by taking 1000 grams of the oil, vegetable or animal oil with about 2000 cc. of denatured alcohol and then N/2 sodium-hydroxide and a few drops of phenolphthalein. The addition of the N/2 sodium hydroxide is continued until it imparts a pink color to the alcohol. This is now mechanically stirred. Should this pink color disappear, more N/2 sodium hydroxide is added. The amount of sodium hydroxide will depend on the degree of acidity of the vegetable or animal oil.

The oil is then allowed to settle, the alcohol is syphoned off and two liters of water is added and stirred for a few minutes. This frees the oil from the alcohol. The oil is allowed to separate and floats on top. The water is now syphoned off by means of suction. Another two liter portion is now added to the oil and stirred again for a few minutes. It is allowed to settle, and the water is

again syphoned off. To this purified oil, any oil solvent, such as chloroform, ethylenedichloride, carbon tetrachloride, or ether may be added.

The second step comprises the preparation of the iodizing and chlorinating agent in aqueous solution. This is prepared in the follow-

ing way:

In 720 cc. of distilled water 357 grams of potassium iodide is dissolved and 239 grams of potassium iodate is added to this cold solution; 720 cc. of concentrated hydrochloric acid U.S.P. is added with mechanical, vigorous stirring in one rapid stream. A dark precipitate of iodine monochloride is first formed, which on continued stirring will go in solution. The stirring should be continued until the solution has a dark reddish color.

This iodizing and chlorinating solution is now cooled to about 15 degrees C. and is now ready for use.

The third step comprises the actual introduction of iodine and chlorine into the purified oil, by means of this aqueous solution of iodine monochloride. The iodizing solution is mechanically stirred and well cooled with ice and water. Now the purified oil, dissolved in an organic solvent is added in a thin stream to the iodizing solution with vigorous stirring. Care should be taken that the temperature remains between 20-25° C. After all of the oil has been added, stirring for about ten minutes will completely iodize the oil. The remaining iodine monochloride solution has lost all of its color and is faintly yellow or almost water white.

Upon allowing the iodized oil to stand, it will settle to the bottom, as

the specific gravity is greater than that of water, and the supernatant aqueous portion is syphoned off and at this stage, some more solvent may be added to facilitate the washing of the oil. This oil solution is now washed in a wide mouth bottle with running water, until all of the hydrochloric acid is removed. This can be established by the addition of a few drops of bromthymol blue, which will give a yellow color if mineral acid is still present, but a blue color if all of the acid has been removed. This usually takes several hours. The fourth step:

Now the oil solution is separated from water as much as possible, then 750 cc. of denatured alcohol is added, and stirred mechanically. To this is then added alcoholic sodium hydroxide, until a pink color remains with phenolphthalein. When this is the case, it is allowed to settle. The alcohol is syphoned off. Then the iodized oil is washed with water, until the pink color to phenolphthalein disappears and the wash water has lost its soapy appearance.

Then the oily layer is separated from the water, and is dried with sodium sulfate, treated with activated charcoal, stirred and filtered. The solution should be brilliantly clear and of a light yellow color. Then it is placed in a round flask and the organic solvent removed by distillation in a vacuum, at first without heat, then later it is placed in a controlled water bath and the temperature is maintained at about 55 degrees C. After about six to eight hours distillation, all of the solvent is removed and a nice yellow viscous iodized oil, remains behind, which contains about 27.5% of iodine and 7.5% chlorine.

## CALCIUM IODOXYBENZOIC ACID

4800 grams of anthranilic acid and 13,200 cc. of conc. hydrochloric acid to which 6000 grams of chopped ice has been added, are mixed, then 6000 grams of water is added and the entire mixture is stirred mechanically and cooled very thoroughly with ice and salt. When the temperature has gone to about 5 degrees C., a solution of 2540 grams of sodium nitrite dissolved in 4200 cc. of water, is added slowly. Care should be taken that the temperature does not rise too much, so that no nitric oxide is formed. The solution is tested with potassium iodide starch paper, which indicates the presence of free sodium nitrite by a blue iodine starch reaction. So long as this test is negative, the addition of the sodium nitrite solution is continued. When a blue iodine starch color appears on the paper, which on continued stirring of the solution still is present, the diazotization is finished. About 150 grams of talcum is added and the solution filtered. To the clear diazo solution, 7270 grams of potassium iodide dissolved in 9600 grams of water, is added in a slow stream to the diazo solution under stirring. When all the iodide solution is added, careful and slow heating is started by means of steam, heating the water outside the container of the diazo and iodide solution. The reaction, which has already begun in the cold, proceeds and evolution of nitrogen gas occurs and at first the benzoic diazo iodide

is formed as a black mass, which as the heating proceeds goes over into the ortho iodobenzoic acid. The heating is continued until the outside water is boiling and kept boiling for several hours. Then it is allowed to cool overnight, filtered and washed with water and then emulsified with a solution of 500 grams of sodium bisulfite in 5 liters of water, which removes all the free iodine. Then the iodobenzoic acid is placed on a tray and dried. Approximate yield 6085 grams.

6085 grams of iodobenzoic acid, finely powdered, is suspended in 7,100 cc. of conc. sulphuric acid and 50,700 cc. of water, heated to about 85 degrees C. and now 7100 grams of potassium bromate is added in portions of 300-500 grams under constant stirring. This process is continued for several hours and the bromine vapors, which are formed are carried off by means of an exhaust fan. After about six hours of heating it is allowed to cool overnight and filtered and washed with cold water and allowed to dry. It is important that the crude iodoxybenzoic acid should be completely dry. Yield about 5500–6000 of crude iodoxybenzoic acid.

These 6000 grams of iodoxybenzoic acid are extracted with 5000 cc. of denatured alcohol, which removes the coloring matter and the unoxidized iodobenzoic acid, filtered off, which will give about 5000 grams of fairly pure iodoxybenzoic acid, which is dried and finely powdered then suspended in 14,000 cc. of water, heated to about 40 degrees C. Twenty per cent ammonia is added slowly, about 2400 cc. of it are needed, then 200 grams

of Darco (decolorizing carbon) is added and the solution is filtered.

To the clear, yellow solution of ammonium-iodoxybenzoate, a solution of 1332 grams of calcium chloride U.S.P. in 2000 cc. of water is rapidly added. All of a sudden the calcium iodoxybenzoate comes out as a white solid cake, which is allowed to cool, by standing overnight, then filtered off and emulsified with about 5,000–6,000 cc. of ice cold water, filtered and placed on trays and allowed to dry on exposure to air. White hard pieces of calcium iodoxybenzoate, yield about 5 kilos.

#### GOLD SODIUM THIOSULFATE (Pharmaceutical)

Thirty grams of gold chloride (light) are dissolved in 25 cc. of water and put into a dropping funnel. 105 grams of sodium thiosulfate are dissolved in 120 cc. of water. The solution is filtered and agitated by means of a small electric stirrer. The gold chloride is added gradually a few drops at a time, then stirred until the yellow color disappears, when a few more drops of gold chloride are added. The solution assumes a milky white appearance, due to the precipitated sulphur and colloidal sulphur and gives a strong odor of sulphur dioxide. The addition of gold chloride lasts for about half an hour and the stirring is continued for some time. Then this milky liquid is filtered once to free it from the precipitated sulphur. After filtration however, it still possesses a milky white appearance due to the colloidal finely sus-

nended sulphur. This colloidal sulphur is removed later on. This milky white fluid is then stirred and while being stirred, receives an addition of two and half its volume of 95% of alcohol. A white precipitate is obtained after a little stirring. The addition of 95% alcohol causes a precipitation of the gold sodium thiosulfate, which is very readily soluble in water, but insoluble in alcohol. At the same time the colloidal sulfur is precipitated by the alcohol. This white precipitate is then dissolved in as little water as possible, the solution filtered (and in this way freed from the colloidal sulfur) and the clear filtrate reprecipitated with 95% alcohol; the white crystalline precipitate can be redissolved and reprecipitated as before to obtain a perfectly pure compound.

#### Preparation of Fatty Acids of Cod Liver Oil

One gallon of U.S.P. Cod Liver Oil, is placed in a 5 gallon Pyrex flask. To this is added one gallon and a half of denatured alcohol No. 1, and to this is added a solution of potassium hydroxide in water made in the following way: 2 lb. of potassium hydroxide is dissolved in 2 pints of water, and this saturated solution is added, while still hot, to the mixture of cod liver oil and al-

cohol. This is then placed in a boiling water bath and heated on a reflux condenser until saponification is completed. This can be tested by adding a small amount to water and if a clear solution occurs, saponification is complete.

To this is now added hydrochloric acid (concentrated) until Congo paper turns red, then one gallon of ethylene dichloride is added and water is added. The ethylene dichloride brings the liberated acids in solution, and as the specific gravity of ethylene dichloride is high, the fatty acids in ethylene dichloride will settle down and it then can be washed by a constant stream of tap water, until all of the hydrochloric acid is removed. This is checked with silver nitrate solution, allowing for the chloride test as contained in ordinary tap water as control.

The ethylene dichloride solution of the fatty acids are then separated from the water by syphoning, and dried with anhydrous sodium sulfate and filtered. The sparkling clear solution of fatty acids in ethylene dichloride is now placed in a round bottom flask and distilled, in vacuo, until no ethylene dichloride distills over. The residue consists of very pure fatty acids of cod liver oil absolutely clear.

#### CHAPTER FIVE

#### EMULSIONS

## Santowax Emulsions Formula No. 1

50.00	g.
3.10	g.
50.00	g.
0.94	g.
400.00	g.
	50.00 3.10 50.00 0.94 400.00

Dissolve Santowax and stearic acid in turpentine, heating to about 85° C. Dissolve triethanolamine in 100 grams of soft water and heat to 85° C. Add the solution of triethanolamine to the hot turpentine solution with rapid mixing. Mix for about two minutes, then add 300 grams of soft water at room temperature. Continue to mix for ten minutes or more. This gives a smooth, fairly fluid, creamy-white suspension. Follow the same procedure with the formula given below.

No. 2		
Santowax M or		
Santowax 9523	50.00	g.
Turpentine	50.00	g.
Stearic Acid	2.00	g.
Triethanolamine	1.23	g.
Water	400.00	g.

Synthetic Wax Emulsion	
Acrawax	10
Ethanolamine Oleate	1
Water	84
TT 11 07 1000 0 111 1	

Heat to 95–100° C. with vigorous mixing. Continue mixing until temperature drops to 75° C. Then add Methyl Ethyl Ketone 5

raramii wax isii	10181011	
Diglycol Stearate	10 )	4
Paraffin Wax	40 }	$\mathbf{A}$
Water	250	
Granulated Sugar	$0.5  \}$	В
Ammonia (26° Bé.)	1	
Melt A and add B	(warm	ed to

Paraffin Way Emulsion

Melt A and add B (warmed to 40° C.) with vigorous stirring.

#### Candelilla Wax Emulsions Formula No. 1

Candelilla Wax	60
Myristic Acid	15
Emulsifier S489	19
Water, To make	375

This gives a very translucent, almost clear emulsion which dries to a transparent film.

#### No. 2

Candelilla Wax	60
Myristic Acid	13
Morpholine	10
Water, To make	375

This produces a very thin emulsion which is translucent and dries to a transparent film.

#### No 3

110.0	
Refined Candelilla Wax	60
Myristic Acid	13
Emulsifier S489	10
Water, To make	375

This gives a dark but very translucent, thin emulsion with high wax content, which dries to a transparent film.

No. 4	
Candelilla Wax	60
Oleic Acid	16
Morpholine	8
Water, To make	375
Very thin translucent	and dries

Very thin, translucent and dries to a transparent film.

No. 5	
Candelilla Wax	40
Abietic	8
Isopropanol	10
Ammonia	15
Borax	1
Water, To make	400

This gives a thin, amber emulsion, translucent, which dries to a transparent film.

No. 6	
Candelilla Wax	30
Flexo Wax C	10
Oleic Acid	8
Ammonia	15
Butanol	10
Water, To make	400

This gives a translucent, thin emulsion which dries to a transparent film.

No. 7	
Candelilla Wax	20
Flexo Wax C	10
Oleic Acid	11
Morpholine	4
Water, To make	225

#### Carnauba Wax Emulsions

Formula No. 1	
Carnauba Wax	60
Myristic Acid	16
Oleic Acid	4
Emulsifier S489	19
Water, To make	375

This gives a very clear, light colored emulsion, almost transparent and which dries to a transparent film.

No. 2	
Carnauba Wax	60
Oleic Acid	16
Morpholine	11.5
Water, To make	375

This makes a very light colored, translucent emulsion of low viscosity which dries to a transparent film with good gloss.

No. 3	
Carnauba Wax	60
Linseed Oil Fatty Acids	13
Emulsifier S489	17
Water, To make	375

This gives a very thin, almost transparent emulsion which dries to a transparent film with good brightness.

# Fruit Coating Wax Emulsions Formula No. 1 Paraffin Wax 168.0 Beeswax 42.0 Oleic Acid 22.0 Sodium Bicarbonate 6.6 Sodium Chloride 2.2 Water 599.2

It is necessary that the soap be formed simultaneously with the first stage of emulsification by the addition of the alkali, in a minimum amount of water, to a wax. These emulsions will readily coat fruits and vegetables with nonwaxy surfaces; but spreading agents are necessary when they are used for waxy fruits. Alkyl naphthalenesulfonates are suitable spreading agents and also inhibit breaking of the emulsions.

# No. 2 U. S. Patent 2,153,487 Caustic Soda 6 Triethanolamine 20 Stearic Acid 42 Paraffin Wax 165

Carnauba Wax	55
Shellac	100
Water	2000
Dilute above before use	
No. 3	
U. S. Patent 2,019,7	58
Paraffin Wax	553
Carnauba Wax	68
Cottonseed Oil	98
Oleic Acid	183
Triethanolamine	98
Water (Containing	
Soda Ash)	to suit
It is necessary that the	soap be
formed simultaneously with	the first
stage of emulsification by t	he addi-
tion of the alkali, in a n	ninimum
amount of water, to a mi	xture of
fatty materials.	

Agricultural Emulsion S <sub>1</sub> U. S. Patent 2,258,83	
Formula No. 1	
Glyceryl Oleate	2
Oil Soluble Nicotine	
Compound	5
White Mineral Oil	93
Water, To suit	
No. 2	
Glyceryl Oleate	1.5
Aluminum Oleate	2.0
Nicotine	2.0
Naphthenic Acid	3.1
White Mineral Oil	91.4
Water, To suit	

Plant Growth Regul	lation Emulsion
Indoleacetic Acid	$0.3  \mathrm{mg}$ .
Lanolin	50 g.
Soap Flakes	5.0 g.
Water	100 cc.
Melt lanolin and n	nix in indoleace-
tic acid; dissolve so	ap in water and
mix vigorously.	- No. 1
Agar	0.25 g.

may be dissolved in the water (used for soap solution) if desired.

Dilute the above to 1000 cc. with water for use.

Acia wax Emulsions	
Polymerized Glycol	
Distearate	5
Candelilla Wax	20
Phosphoric Acid (85%)	5
Water (Boiling)	70

Another acid emulsion is made of the following materials, in the proportions shown:

Polymerized Glycol	
Distearate	15
Monostearate of Glycerin	15
Paraffin Wax	6
Hydrochloric Acid	9
Water	55

Acid Oil Emulsi	ions
Polymerized Glycol	
Dilaurate	15
Oleic Acid	5
Mineral Oil	30
Hydrochloric Acid	6
Water	44
A 41 1 1	

Another mineral oil emulsion is made of the following formula:

Polymerized Glycol	
Dilaurate	15
Oleic Acid	5
Mineral Oil	30
Sodium Chloride (10%	
Solution)	50

In the above formula the sodium chloride solution may be replaced by a solution of tartaric acid, say, of concentration 10%. Also the mineral oil, may be replaced by other oily materials as, for example, by toluene, pine oil, a fatty vegetable oil, kerosene or naphtha, the proportion of water being decreased somewhat if necessary to give desired stability.

# Emulsions With Acids, Salts and Hard Water

to be emulsified, by heating to about 50° C. The salt, acid, etc. are dissolved in the water which is added at about 50° C. to the oil, EMULGOR-A mixture and stirred rapidly. All the emulsions are fluid with the exception of the These emulsions are made by dissolving the EMULGOR-A (Glaurin and Oleic Acid where necessary) in the oil paraffin wax emulsion, which is a paste.

Material to Be E	Emulsified	Electrolytes		Water	Water Emulgor-A Oleic Acid Glaurin	Oleic Acid	Glaurin
Amyl Acetate	50.00	Boric Acid	1.8	38.2	10		
Cottonseed Oil	41.15	300 parts per million calcium car-					
		bonate contained in water used.		41.15	11.8	5.9	
Mineral Oil	30.00	Acetic Acid (Glacial)	್ತಾ	45	15	ಸಂ	
Mineral Oil	30.00	Aluminum Chloride (14% solution)	5	45	15	5	
Mineral Oil	40.00	Citric Acid	4	36	10	10	
Mineral Oil	31.6	Formic Acid	2.3	39.85	10.5	5.25	10.5
Mineral Oil	30.0	Hydrochloric Acid (22° Bé)	9	44	10		10
Mineral Oil	30.0	Oxyquinoline Sulphate	0.2	49.8	15	ນ	
Mineral Oil	31.6	Phosphoric Acid (85%)	2.4	39.75	10.5	5.25	10.5
Mineral Oil	30.0	Sodium Chloride	2.5	47.5	20		
Mineral Oil	31.6	Sulphuric Acid (Conc.)	2.15	40	10.5	5.25	10.5
Mineral Oil	40.0	Tartaric Acid	4.5	40.5	10	52	5
Paraffin Wax	30.0	Aluminum Acetate (28% solution)	30	20	10	5	ಸ
Pine Oil	32.0	Sodium Chloride	2.35	44.45	21.2		
Pine Oil	31.3	Hydrochloric Acid (22° Bé)	6.25	41.6	18.75	2.1	
Toluol	33.3	Sodium Chloride	2.22	42.25	17.75	4.45	
Toluol	30.0	Hydrochloric Acid (22° Bé)	9	44	20		

Emulsion Containing	Lime
Polymerized Glycol	
Stearo-Oleate	10
Mineral Oil	20
Paraffin Wax	20
Lime	5
Stearic Acid	12
Water, To make	100

#### Sulfathiazole Emulsion

Sulfathiazole 5%, triethanolamine 2%, distilled water 24%, white beeswax 5% and paraffin 64%. The sulfathiazole is stirred into a heated mixture of the triethanolamine and water, to which is added the melted beeswax-paraffin mixture. Vigorous stirring produces the proper product.

Anise Oil Emulsion	
Anise Oil	10
Tincture of Quillaia	5
Water	100

Castor Oil Emulsion
Sodium Hydroxide 9.8 gr.
Water 25 oz.
Castor Oil 6 lb. 5 oz.
Sodium Benzoate 100.5 gr.
Triethanolamine 288 min.

Run through colloid mill after flavoring mix with lemon and vanilla and sweetening with saccharine to suit.

Kerosene-Pine	Oil Emulsion
Kerosene	40-60 %
Pine Oil	0-20 %
Aerosol OT	5-6.5%
Oleic Acid	6-6.5%
Water	35–50 %

Mineral Oil Emulsion	1
White Mineral Oil	43.0
Stearic Acid	5.1
Aminomethylpropanediol	1.9
Water	50.0

The acid is melted in the oil at a temperature of about 65° C. The oil-acid mixture is poured into the water solution with agitation and the emulsion is stirred occasionally while it cools.

# Pectin in Emulsions (Sesame Oil)

Various emulsions may be prepared with pectin. For oil emulsions a pectin concentration of 3-5% is required. Vigorous stirring of an acidified 5% pectin solution with 20% sesame-oil yields a stable viscous emulsion which readily disperses when poured into water. If such emulsions are homogenized and prevented from desiccation, they will remain stable for years. Dispersed systems consisting of pectin solutions and paraffin-oils are excellent cosmetics and skin protectors. Pectin solutions are not sticky, quick drying and form a protective layer on the skin.

Copper Naphthenate Emul	sion
1. Copper Naphthenate	10
2. Ammonium Linoleate	
(B585)	20
3. Water	70
Melt 1 and stir in hot mixt	ure of
2 and 3.	

Benzyl Benzoate Emulsic	on
Methyl Cellulose	
(Medium Viscosity)	1
Benzyl Benzoate	25
Water	74
Toluol Emulsions	
Polymerized Glycol	
Dilaurate	20
Toluol	30
Hydrochloric Acid	6
TTT - 4	4.4

Another toluol formula i	s the fol-
lowing:	
Polymerized Glycol	
Dilaurate	10.2
Diglycol Monolaurate	6.7
Toluol	44.5
Water	38.6
17 0000	00.0
Acid Pine Oil Emuls	sion
Polymerized Glycol	
Dilaurate	10
Pine Oil	40
Diglycol Monoleate	7
Oxalic Acid	2
Water	41
Benzene Emulsion	1
Glyceryl Mono Oleo	
Laurate	14
Benzene	88
Water	50
Flexalyn (Synthetic R	esin)
Emulsions	•
Formula No. 1 No.	2 No. 3
Flexalyn (80%	
solids in	
Xylene) 41.25 47.5	47.22
Duponol ME	
Dry 0.33	
Triethanola-	
mine 0.6	37
Potassium	
Hydroxide	0.27
TTY GLONIGO	0.27

Formula No. 1 requires the use of a colloid mill. The Duponol ME is added with stirring to warm water (40–50° C.). When solution is complete, Flexalyn solution is added with continued stirring. The spontaneous semi-emulsion thus formed is passed through a colloid mill, forming a stable low-viscosity emul-

58.42 50.5

1.33

1.13

0.88

Oleic Acid

Oil

Water

Sulfated Castor

sion with an average particle size of 85% to 100% under 5 microns, and a pH of 6.7 to 7.5.

Spontaneous emulsion of Flexalyn solution may be prepared with either Formula No. 2 or No. 3 above, providing the following procedure is followed. With either formula, the oleic acid required is carefully stirred into the Flexalyn solution; ½ the amount of water required is mixed with either the triethanolamine in Formula No. 2, or potassium hydroxide and sulfated castor oil in Formula No. 3. The oleic acid-Flexalyn solution is then added slowly to this water phase with vigorous agitation (highspeed propeller-type stirrers have been found satisfactory.) This produces a spontaneous emulsion, which is allowed to stir for approximately 30-45 minutes, and the remaining water slowly added. After addition of the water is completed, the emulsion is allowed to stir for about 1/2 hour before using.

Vinyl Resin Emulsion
U. S. Patent 2,238,956
Copolymerized Vinyl
Chloride and
Acetate 25
Methyl n-Amyl
Ketone 45
Toluene 30
Water 33 1/3
Alkanol B 1 1/5

Dissolve resin in solvents and mix vigorously with water solution of Alkanol B. Then pass through a colloid mill.

- Cumar Emulsion		
Cumar	44	lb.
Water	36	lb.
Soap "A"	2	lb.

# Soap "A" Rosin 4 lb. Caustic Potash 200 cc. Water 500 cc. Alcohol 200 cc.

To make Soap "A," melt rosin, heat to 180° F. Then combine caustic potash, water and alcohol, heat to 160° F. and add to the melted rosin. Stir.

To make cumar emulsion, combine Cumar, water and Soap "A," heat mixture to 200° and run through colloid mill or high speed agitator.

### Natural Resin Emulsion

Elemi	70.3	lb.
Batavia Dammar	7.7	lb.
Oleic Acid	11.0	lb.
Triethanolamine	4.0	lb.
Water	210.0	lb.

Melt the Elemi and add the Dammar. Keep the mixture at about 125° C. until it is homogeneous. Put the mixture in a boiling water bath. Add the oleic acid and then the triethanolamine, making use of vigorous stirring as additions are made. Heat the water to boiling and add it slowly to the mixture, still using vigorous agitation. Continue the agitation until the emulsion has cooled.

A milky white emulsion is formed which yields a clear, tacky film.

# Resin-Wax Emulsions Formula No. 1

Batavia Dammar	12.5	lb.
Beeswax	12.5	lb.
Morpholine	1.0	lb.
Stearic Acid	-1.5	lb.
Water	100	lb.

Melt the beeswax and add the Dammar, stirring until the mixture is homogeneous. Stir into this mixture the morpholine and the stearic acid. Add this mixture slowly with stirring to the water which has been heated to about 85–95° C.

This emulsion remains stable and is capable of infinite dilution with water without breaking.

#### No 2

Batavia Dammar	25	lb.
Paraffin Wax	25	lb.
Oleic Acid	5	lb.
Morpholine	2.5	lb.
Water	250	lb.

Melt the wax and sift in the Dammar. When all is melted, add the oleic acid and stir until the mixture is homogeneous. Do the same with the morpholine. Keeping the mixture hot and continuing the stirring, add the water slowly. The water should previously be heated to about 85–95° C.

#### No. 3

Batavia Dammar	37.5	lb.
Beeswax	37.5	lb.
Oleic Acid	8	lb.
Morpholine	4	lb.
Water	375	lb.

Melt the wax. Sift in the Dammar. When all is melted, add the oleic acid and stir until the mixture is homogeneous. Do the same with the morpholine. Keeping the mixture hot and continuing the stirring add the water slowly. The water should be previously heated to 85-95° C.

# Plasticized Rosin Emulsion

Rosin		17
Theop (Plastici	zer)	3
Caustic Potash	(45%)	2
Water		78

Cleaning Emulsion	Bases
Duponol LS Paste or	
Duponol ES Paste	47.6
Hexalin	4.8
Tetralin	476

Prepare by adding the Duponol LS Paste to the previously mixed solvents.

Duponol LS Paste	15.0
Hexalin	2.0
Pine Oil	3.0
Tetralin	70.0
Water	10.0

Prepare by mixing together at room temperature the Duponol, Hexalin and Pine Oil. Stir until a clear mixture is formed. Continue stirring and add the Tetralin slowly. After the Tetralin has been added and the mixture thoroughly agitated, add the water.

Die Lubricating Emulsion	
Mineral Oil	4
Aerosol OT (100%)	1
Glycostearin	1

Heat together to 100-120° C., then cool to 80° C. and then add slowly with stirring to 100 water (heated to 80° C.).

# Waterproofing Emulsion British Patent 540,650

Aqueous basic aluminum formate (aluminum oxide 20, formic acid 28%) (20) is diluted with hot water (40), melted wax (acid value 19, 10 kg.) added at 70°, and the mixture stirred to give a stable emulsion.

Emulsifying Base	
Aerosol OT (100%)	40
Oleic Acid	42
Triethanolamine	18

The Aerosol OT is dissolved in the oleic acid by heating to 50° to 60° C. The mixture is cooled to room temperature and the triethanolamine added. 5% of this emulsifier can be mixed with 95% of oil and to it added 30–50% water, whereupon a thick creamy paste will be obtained, which can be further diluted with additional water.

Soluble Oils	
Formula No. 1	
Mineral Oil	82.9
Caustic Potash (45%)	0.1
Diethylene Glycol	2.0
Ultranate, Refined	15.0
No. 2	
U. S. Patent 2,230,556	3
Potash Soap	30
Olein	7
Cyclohexanol	2
Paraffin Oil	32

## Lacquer Emulsions

Combination of a lacquer with an emulsifying mixture gives some degree of emulsification and can be realized by any customary method. Most useful concentration ratio is  $2\frac{1}{2}$  lacquer to 1 of water phase.

Stability generally varies with particle size—all other variables being constant.

Poorest emulsions are made by rapid stirring with a high speed mixer. They are greatly improved by a stator-rotor type sheering action, of a colloid mill. The most stable emulsions are usually produced by high pressure extrusion, i.e. in an homogenizer. For easily dispersed systems, an homogenizer alone is sufficient. More difficultly dispersable systems must be predispersed by other types of equipment (colloid mill) before passing through homogenizer.

An emulsion with many large

Nanhthenic Miscible Oils (II S. Patent 2 289 536)

agglomerate particles can in general be expected to have a short life. The dispersed droplets should be small and uniform.

Almost any good emulsifying agent, and this includes soap will form some type of an emulsion with a lacquer. Useful stabilities and this means three months or better, can only be realized by a careful selection of the emulsifier. One of the best found contains 0.5% Dupanol,

1.0% sulfonated castor oil either alone or mixed with other emulsifiers or lacquer solvents.

Lacquers rich in resins are more easily dispersed than those that are nitrocellulose rich, and as a rule have a longer life. (Table A No. 2 and 5.)

Lacquer emulsions have high flash points and are usually broken by freezing. Lacquers of very high viscosity are difficult to disperse.

	Naphtnenic Misc	apie (	Jus	(U. l	s. Pa	tent	2,289	J,53t	)		
	Formula No		2	` 3	4	5	6	7	8	9	10
1.	Potassium naphthenate									_	_
	from—										
	Heavy gas oil	65	48								
	Light Lube oil			37	37	37	23	20	30		
	Heavy lube oil			-	-		_			13	30
2.	Light lube oil	20	35	50	45	50	58	62	55	69	64
3.	Common solvents		•		20	00	•	-	00	00	01
	Group 1—Water soluble										
	Ethylene glycol										3
	Diethylene Glycol	5	5	5	5	5	5	5	5	5	O.
	Group 2—Oil soluble		•	ŭ	Ŭ	Ŭ		•	•	•	
	Sub-group A										
	Pine Oil		10		10						
	Alpha terpineol	5		5			5	5	10	5	
	Octyl alcohol			·		5	0	0	10	O	
	Sub-group B					Ü					
	Rosin	5					5			5	3
	Cresylic acid							5		U	,
4.	Water		2	3	3	3	4	3		3	
	• *				_		•			0	
	Nitro										
	Table A—Lac	equer	Bas	e Fo	rmul	ae (c	lear)				
	Formula 1	No. 1		2		3		4			5
Nit	tro Cellulose (Dry Weight)	30	)	2	5	3	0	3	0	4	0.0
	stor Oil	30	)	-	-	-	-		_	_	_
	ethyl Citrate	****	-	2	0	_	-				5.0
	cresyl Phosphate		-		_	12	2				-
	outyl Phthalate		-	_	-	-	-	13	3	_	-
	sin (Alkyd)		-	10	)	13	5	18	5		-
	tyl Acetate	25	5	2	5	2	5	22	2	30	0.0
	lene		*		5			-		7	7.5
But	tanol	15	5	18	5,	18	3	20	)	17	7.5

No. 6	
Pigmented Nitrocellulose	20%
(Dry Weight)	
Resin (Alkyd)	8
Castor Oil (Blown)	6
Diamyl Phthalate	6
Carbon Black	2
Xylene	14.4
Octyl Acetate	10
Butyl Acetate	25
Alcohol (Present in	
Nitro Cellulose)	8.6

# Table A

Any of these formulae can be emulsified without much difficulty using any of the emulsifiers of Table B. The difference lies in the properties of the dried films.

They are all formulated electrolyte free—small amounts can be included and dispersed. The presence of gelatin or casein in the water phase will help disperse a certain concentration of electrolytes.

# Lacquer Emulsifiers Table B Formula No. 1

I Official Tio. I	
Duponol	0.5%
Sulfonated Castor Oil	1.0
Water	98.5
No. 2	
Duponol	0.5%
Sulfonated Castor Oil	1.0
Acetone	10.0
Water	88.5
No. 3	
Duponol	0.5%
Sulfonated Castor Oil	1.0
Casein	0.5
Water	98.0

No. 4	
Duponol	0.5%
Sulfonated Castor Oil	1.0
Gelatin	2.0
Water	96.5
No. 5	
Duponol	0.5%
Sulfonated Castor Oil	1.0
Casein	0.5
Acetone	10.0
Water	88.0
No. 6	
Sodium Oleate	6.0%
Water	$94.0^{'}$
No. 7	
Duponol	0.5%
Sulfonated Castor Oil	1.0
Methyl Cellulose	0.3
Water	98.2

Table B illustrates many of the various possible combinations of emulsifiers.

No. 1.—The emulsion stability varies with the composition of the lacquer phase. The presence of resins in lacquer usually aids the dispersion, both as to the ease of forming the emulsion and the uniformity of droplet size.

No. 2.—The presence of acetone gives (1) increased emulsifying power for n/c rich lacquers, (2) depresses freezing temperature of the emulsion, (3) acetone replaced by a water miscible high boiling solvent decreases the tendency of film blush.

Nos. 3, 4, 5, 8 are all of the same general type, i.e., they contain an auxiliary emulsifier or stabilizer. This additional material helps produce emulsions from lacquers of very high viscosity and those that are relatively rich in n/c.

No. 6.—While the stability of the

Water

emulsion using this emulsifying mixture may be satisfactory, too high a concentration of the emulsifiers that are incompatible with the lacquer results in a decrease of gloss upon the surface of the dried films.

No. 7.—Will produce a W/O emulsion. If the concentration is decreased to get an O/W emulsion a poor emulsion results (only par-

tially emulsified).

Lacquer emulsions with casein emulsions are O/W; gelatin emulsions are W/O; 0.03% is the upper limit of methyl cellulose that can be included without producing "flatting" of the film. Methyl cellulose is an exceptionally good emulsifying aid.

Demulsifier for Crude Petroleum
Emulsions
U. S. Patent 2,127,140

Emusions		
U. S. Patent 2,127,140		
Formula No. 1		
Ammonium Ricinoleate	H9.78	
Cyclohexanol	12.05	
Ammonia	1.91	
Furfuraldehyde Potas-		
sium Bisulphite	3.20	
Castor Oil	20.45	
Water	12.09	
No. 2		
Ammonium Ricinoleate	46.00	
Ammonia	0.86	
Furfuraldehyde Potas-		
sium Bisulphite	8.93	
Hydro Furamide	0.29	
Castor Oil	30.00	

13.69

#### CHAPTER SIX

# FARM AND GARDEN SPECIALTIES

# Weed Killers Formula No. 1

Dissolve 20–50 grams of sodium chlorate in 1 liter of water. Apply 1–1.5 liter solution per square meter for all common weeds. For weeds with tubers or bulbs apply the same solution twice or three times in intervals of one to two weeks or use

# No. 2

100-200 grams sodium chlorate per liter of water.

Caution: These concentrated solutions when dried on inflammable material like cloths, paper, etc., cause a fire hazard.

Less dangerous in these cases is:

#### No. 3

100–200 grams sodium chlorate, 200–400 grams calcium chloride dissolved in 1 liter of water. Apply, by spraying or by a watering can, 1–1.5 liter solution per square meter.

## No. 4

Less effective, but without fire hazard and not poisonous to livestock: 25-100 grams ammonium thiocyanate in 1 liter of water. Apply 2 liters per square meter by spraying or by watering can.

For arable land which will not be cultivated for 4–6 months, formulas 1, 2 or 3 may be used at a rate of 100 gallons per acre. When formula 4 is used at a rate of 200 gallons per acre, the field may be cultivated after 1–3 months.

# No. 5

Eradication of weeds in cereal crops: Dissolve 1 volume concentrated sulphuric acid (66° Bé.) in 10–20 volumes of water. Apply 50–200 gallons per acre by spraying.

The effect of these herbicides and all other mixtures depends also on the nature of the weeds, on the weather (very dry and very wet times are unfavorable), on the properties of the soil (sandy soils often need less chemicals than clay), the pH, the organic matter and the nitrates in the soil, etc.

Furfural is very toxic to dandelions and other annual weeds, but is too expensive to be used alone as a weed killer. This has led to the preparation of mixtures usually containing kerosene or light petroleum distillates which themselves have some lethal properties toward vegetative materials.

The advantage of the furfural weed killers is in their ease of handling, effectiveness, and in their non-persistency in the soil which facilitates reseeding.

## No. 6

One recommended formula for a furfural herbicide comprises 45 parts of kerosene, 45 parts xylol, and 10 parts of furfural. The xylol is used as a mutual solvent for the kerosene and furfural. In making this preparation the kerosene and

xylol are first mixed and the 10 parts of furfural are added with stirring.

#### No. 7

An emulsion of the herbicide may also be prepared comprising 89 parts of kerosene or light petroleum distillate and 1 part of crude oil, such as is commonly used in oiling roads, and 10 parts of furfural. The emulsion is not permanent and, consequently, it is necessary to agitate the material thoroughly from time to time during the period of use; otherwise, the constituents will separate and lose their maximum effectiveness. The solution form is generally recommended in preference to the emulsion form.

Two methods of application are used. The first comprises individual treatment of dandelions in lawns, golf courses, and the like. The application is made by means of a socalled "dandelion gun," which comprises a tube with a valve in the bottom so arranged that when the gun is placed on the crown of a weed and pressed lightly a few cubic centimeters of the liquid is discharged on the crown of the dandelion. This causes it to turn brown, dry, and disintegrate. Care must be exercised to see that the weed killer does not contact grass because it has a considerable lethal action on the grass as well as on the weed.

A second method of treatment comprises the so-called broadcast procedure in which the weed killer is sprayed on thickly infested areas resulting in the killing of practically all the vegetation in the area, and this must be followed by reseeding after about a week or ten days. Usually about 500 gallons per acre will suffice for a substantially complete

kill of all annual weeds and weakening of many of the deep-rooted perennials.

Where the individual treatment is used, usually the grass surrounding the treated plant fills in the bare spots. However, if desired the treated areas may be reseeded in order to speed up growth of new grass.

#### No. 8

German Patent 696,671	
Copper Chloride	$\frac{1}{2}$
Potassium Chloride	1/2
Potassium Nitrate	$\frac{1}{2}$
Water	217

# No. 9

	German Patent 683,877	
]	Ferric Sulphate (10% So-	
	lution)	75
(	Copper Sulphate	5
I	Magnesium Sulphate	10
5	Sulphuric Acid (60° Bé)	10

#### No. 10

Canadian Pate	ent <mark>391,4</mark> 5	9
Sodium Chlorate	12.5	lb.
Borax	15 - 25	lb.
Caustic Soda	3.2 - 5.2	lb.
Water	10	gal.

#### No. 11

Ammonium Sulfa-		
mate	0.5 - 1	lb.
Water	1	gal.
Use $1-1\frac{1}{2}$ gal./100	sq. ft.	

#### No. 12

Arsenic Trioxide	4 oz.
Sodium Hydroxide	4 oz.
Water	1 gal.

Boil until clear. Use 1 cupful of this solution per gallon of water and apply the resulting solution to the weeds.

Blood Albumin Water	prevented 100 lb. 25 lb. 12 oz. 300 gal.	Spray for Leaf Rollon Plums Formula No. Quassia Extract Water No. 2 Nicotine (2% Solution	1 2 98
Citrus Thrip Spr Tartar Emetic Sugar Water 10 Use 3–5 gal. per tree. T to thrips and does not inj Combating Thrips o	1½ lb. 2 lb. 00 gal. This is toxic ure foliage.	Crop Dusting Inse British Patent 52 Cuprous Oxide Magnesium Oxide Sulphite-Cellulose Residue Flour	
Dust with Naphthalene, Crude 3	0–40 kg. 0–13 kg.	Talc  Insecticidal Do  4% Derris or Cube	80
repeat as often as necess Fruit Fly Lur Orange juice is used	ary.	(Ground) Talc or Clay Santomerse D. (Wett Agent)	74.5
Banana Leaf Spot Con Copper Sulphate Sulphur Lime, Slaked Kaolin	trol Dust 20 40 30 10	European Corn Bor Formula No. Water Pure Ground Derris Root (4% Rote- none)	
Peach-Borer Spr p-Dichlorbenzene Cottonseed Oil Water	ay 3 lb. 6 qt. 18 qt.	Areskap 100  No. 2  Water Liquid Tannin 50% Free Nicotine	1.5 oz. 25.0 gal. 4.0 oz. 4 oz.
Fish Oil Soap Mix well. Apply ½ pt. per tree.  Alfalfa Snout Beetle	3 oz.	Areskap 100  Gypsy Moth St Lead Arsenate	30.0 lb.
Soyabean Meal Sugar Sodium Silicofluoride Water Mix well; press into p	100 lb. 15 lb. 6 lb. 12 gal.	Fish Oil Motor Oil Aresket 240 Water Dilute to suit.	6.0 lb. 1.2 lb. 1.2 lb. 45.0 lb.

Stinking Smut on Wheat-Spray
(Stock Solution)
Formaldehyde (40%) 2.7 lb.
Santomerse No. 3 1.6 lb.
Water, To make 1.0 gal.
One pint of stock solution added to 40 gallons of water for use.

Insecticide for Gherkins
Water 50 gal.
Copper Sulphate 2 lb.
Quicklime 3 lb.
Lead Arsenate 1 lb.
Nicotine Sulphate 3% pt.
Soap, Liquid ½ pt.
This is effective against downy mildew, mosaic, and aphids.

Grasshopper Poisons
Per 100 lb. of bran, any of the following may be used:
Sodium Arsenite
(30–32% Solution) 1 qt.
or
Paris Green 2 lb.
or
Arsenic Trioxide 2–3 lb.
or
Sodium Arsenate 2 lb.

Colloidal Insecticides Lead Arsenate 10.0 lb. Gum Arabic 3.5 lb. Water 100.0 oz. Mill on colloid mill or paste mill. Red Copper Oxide 730 Cup Grease 200 Butyl Stearate 30 Lubricating Oil (No. 20) SAE) 220

Mill on colloid mill and dilute to spraying consistency with light oil. (Heat and mix before milling.)

Red Copper Oxide 1200 Colloidal Kaolin 200

Gum Arabic	120
Water	1050
Mill on colloid mill and	dilute to
praying consistency with	water.

Colloidal Sulfu	ır
Flowers of Sulfur	30 lb.
Gum Arabic	6 lb.
Water, To make	54 lb.
Mill on a colloid mill;	
at zero setting will produ	ce colloidal
sulfur.	

# HOME-MIXED INSECTICIDE OIL EMULSIONS

The principle involved in the preparation of an oil emulsion is the bringing together of oil and water in the presence of an emulsifying agent and under conditions of violent agitation during which operation the oil is finely dispersed throughout the water medium and remains so for a considerable length of time. There are two types of materials commonly used to emulsify oils for spraying purposes: (1) Dry materials which are dissolved in a small amount of water previous to mixing with the oil; (2) oil soluble emulsifiers which are added directly to the oil.

Methods of preparing summer oil emulsions are explained in the following examples:

Blood Albumin.—Two ounces of actual water soluble blood albumin or eight ounces of the commercial blood albumin-filler mixture are dissolved in about one quart of water in a large pail (16 quart). The oil required for 100 gallons of spray is then added. Emulsification is produced by turning water from the spray gun under high pressure into the mixture of water, blood albumin

and oil. By the time the pail is filled with the creamy emulsion it is sufficiently mixed to pour into the sprav tank where it is diluted to make 100 gallons. Agitation with both the spray gun and tank agitator is continued until the full amount of water is added. The tank agitator is kept in action until the spray is applied. When preparing emulsions using more oil, a larger container is desirable for the original emulsification. Summer oil sprays are not usually prepared directly in the spray tank as is the customarv practice when making dormant oil sprays for the reason that the small amount of oil required for foliage sprays could very easily be lost by adhering to the sides of the tank or by floating on the water.

One part of most oil soluble emulsifiers (glycerylokate) after being thoroughly mixed into 99 parts of oil will produce an emulsion when water is added under high pressure from the spray gun. The important consideration is to have the emulsifier thoroughly mixed into the oil. For illustration, 150 cc. of emulsifier is added to 4 gallons of oil in a 5gallon can. Violent shaking of the container will thoroughly mix the emulsifier in the oil. To prepare the emulsion, measure out the required amount of oil in a 16-quart pail or larger container if more than 200 gallons of spray are to be prepared. (No allowance is made for the small amount of emulsifier when measuring out the oil.) The water is then added under high pressure from the spray gun to produce the emulsion after which the mixture is poured into the spray tank and diluted to the required concentration similar to the method described under blood albumin.

A weak Bordo mixture (¾–3–100) is not only an emulsifier for summer oil sprays but also affords some protection against apple scab and acts as a corrective for arsenical injury. To emulsify with Bordo, after preparing the mixture in a small amount of water, follow the method described for blood albumin. To avoid russeting the fruit, it is advisable to use only the weak Bordo in the summer and not to apply copper sprays before July first.

Locust Poison	
British Patent 535,339	
M-Dinitrobenzene	$\frac{1}{2}$
Sodium Sulphate (Anhy-	
drous)	1/2
Grind together and mix with	
Bran	28
Molasses	1
Finally add	
Water	28

Gladiolus Thrip Spray
Tartar Emetic 4 lb.
Brown Sugar 16 lb.
Water 100 gal.
Apply frequently in a fine mist.

Chinch Bug Control
Mineral Oil Emulsion, Refined 2.500 oz.
Nicotine Sulfate 0.125 oz.
or
Derris Extract 0.125 oz.
Water 1.000 gal.
Apply 70 gal. per acre of corn at 2-4 ff. stage.

Insecticide Spreader and Sti	icker
U. S. Patent 2,109,961	
Fish Oil	500
Caustic Potash	85

Wat	er					83
Alco	hol					85
The	above	is	mixed	and	then	used
	-	-				

with powdered insecticides.

# Chigger Control Formula No. 1

Spray 1% kerosene emulsion on bushes and grass.

No. 2

Dust every 10 days with sulphur (1 lb. to 1000 sq. ft.).

Insect Repellent Spray for Animals Australian Patent 109,014

Carbon Tetrachloride 46
Kerosene 46
Castor Oil 3
Mineral Oil 3
Eucalyptus Oil 2

Nicotine Spray Activator Efficiency is trebled by adding a 1–500 dispersion of agar-agar or gum karaya.

Snail and Slug Bait

Molasses, Black Strap
Calcium Arsenate
1 lb.

Metaldehyde
4/2 lb.

Bran
16 lb.

Water
2 gal.

Walnut Husk Fly Bait
Glycerin, Technical 2%
Caustic Soda 3%
Water 95%

Nematode (Fungi) Destroyer Canadian Patent 391,483 Use 0.01–0.1% solution of sodium chlorite.

 $\begin{array}{ccc} \text{Walnut Caterpillar Spray} \\ \text{Lead Arsenate} & 3 & \text{lb.} \\ \text{Lime} & 6 & \text{lb.} \\ \text{Fish Oil} & 3\frac{1}{2} & \text{lb.} \\ \text{Water} & 100 & \text{gal.} \\ \end{array}$ 

Red Spider Spray
U. S. Patent 2,105,727
Selenium 302
Lime-Sulphur Solution 1 gal.

Codling Moth Spray for Pears
Copper Sulfate 2 lb.
Hydrated Lime 10 lb.
Spreader

Lead Arsenate 3 lb. Water, To make 100 gal.

Japanese Beetle Spray (Patented)

Rosin 10 lb.
Lye 1 lb.
Fish Oil Soap 1 lb.
Corrosive Sublimate 1 lb.
Nicotine Sulfate 1 oz.

The first three ingredients are boiled in 10 gallons of water until the mixture turns black; the corrosive sublimate and nicotine sulfate are then added in 20 gallons of water. For spraying fruit trees, hardy shrubs, grass and weeds, the mixture should be diluted with two parts of water. For beans and other delicate plants, dilute with three or four parts of water.

Japanese Beetle Lure
Geraniol 10
Eugenol 8

Mosquito Repellents
Diethylene Glycol Monobutylether Acetate 33
Diethylene Glycol Monoethylether 32
Alcohol 28
Corn Oil 7

This is far better than citronella oil.

Mosquito Spray
Tobacco Dust 5 lb.
Water 1 gal.
Steep for 1–2 days. Filter and add
Soft Soap 0.65 oz.

Elimination of Silverfish Powdered Arsenious

Oxide 8 g. Cracker Crumbs, Fine 100 g. Mix well, moisten slightly, roll

into small loose pellets and distribute back of books, etc., where infestation occurs.

tation occurs.

Silverfish cannot climb a clean vertical glass wall. A trap may then be devised by covering the outside of a vaseline jar up to the mouth with rough adhesive paper or cloth. Leave inner wall untouched, and place a teaspoonful of flour in the jar. Silverfish climb up and fall in, but cannot get out. Occasionally shake out remains and put in fresh flour.

Roach Destruction
Sprinkle sodium fluoride freely
and constantly where roaches frequent, until they all disappear.
Then as needed.

To Destroy Ant Hills or Nests Pour a sufficient amount of carbon bisulphide over the hill or nest to follow the holes or trails down into the ground. Then set fire to it. The fumes and fire tend to exterminate the ants. Use when nest is occupied.

Ant Repellents and Poisons Homes, gardens, fences and other places infested with ants can usually be freed of the pests by the use of a mixture made of:

Heat the arsenic with the glycerin (to about 150° C.) till clear. When cold add the water in which the

honey has been dissolved.

A recommended procedure is to place a piece of wet cloth or blotting paper on a plate (to be kept wet by additions of water as necessary), sprinkle a few grains of sugar on the surface and add about 10 to 20 drops of the above solution. This solution is effective because it attracts the ants to their death.

Sodium fluosilicate, mixed with glycerin and honey, also makes a good ant poison, but not quite as effective as the arsenic solution. An old fashioned yet useful ant poison can be made from equal parts of tartar emetic and sugar made into a paste with glycerin. This poison paste is spread around the places frequented by the ants.

Fumigating Stored Food with Carbon Disulfide

Where large quantities of beans or cereal products are to be fumigated, it is more convenient to use carbon disulfide to kill the insects in them. Carbon disulfide is a very effective fumigant where infested materials can be confined in a small, relatively air-tight space such as a barrel or box. It is advised for treating both food and clothing to rid them of insects.

Carbon disulfide is a heavy clear liquid with a disagreeable odor. It is highly inflammable, and its fumes

food.

are explosive when mixed with air. For this reason it must never be used around an open flame or by a person who is smoking. It is used at the rate of 1 pound to each 100 cubic feet of space or about 1½ ounces, liquid measure, of carbon disulfide to each 10 cubic feet of

space in the container. Place the chemical in shallow pans or pour it on some rags on the top of the material to be fumigated. The gas is heavier than air; as the material evaporates it will sink through the articles to be fumigated. The container should be kept tightly closed or sealed for 24 to 36 hours at a temperature between 65 and 80 degrees F. Best results are secured when the temperature is at or above 70 degrees F. It is not effective when the temperature is below 60 degrees. When used according to the above directions fumigation will not harm grains or beans for plating, or cereals and dried fruits for

Colchicine Plant Treating Emulsion
Water 20 cc.
Glyceryl Monostearate 2 g.
Lanolin 8 g.
Colchicine ½ g.

Add first two items together. Mix until melted. Stir to creamy soap solution. Add lanolin. Heat till melted and just below boiling point. Add colchicine. Stir till thick creamy emulsion results. Stir intermittently until it has cooled to room temperature.

Seedless-Fruit Forming Hormont
Spray
Dichlorophenoxyacetic
Acid 10-25
Water 1,000,000

# Seed Disinfectant French Patent 847,302 Methyl Mercury Iodide 1.2 Ethyl Mercury Iodide 1.5 Calcium Arsenate 10.0 Quartz Sand 87.3

#### Pea Seed Treatment

Spergon, Semesan, and 2% Ceresan are used for treating seed of all pea varieties except Alaska and Rogers Winner which do not appear to be quite so susceptible to injury from decay organisms. Red copper oxide is an excellent treatment for the early varieties but may injure some of the late-maturing sorts. Treatment is simple. The seed and chemical are placed in a rotary mixer, such as a barrel churn, and tumbled until each seed is thoroughly coated. This usually takes four to five minutes with 25 to 30 revolutions a minute. The gardener can accomplish the same thing by shaking the seed and chemical in a tightly covered fruit jar.

Spergon is applied at the rate of 1½ ounces per bushel of seed, while Semesan and 2% Ceresan are applied at the rate of 2½ ounces per bushel. If the seed is to be sown by a grain drill, graphite should be added to Semesan and 2% Ceresan at the rate of 1¼ ounces per bushel. Spergon is a natural lubricant and does not need any added graphite.

# Treating Oat Seed

In treating seed oats with formaldehyde, a mixture of 1 pint of formaldehyde and 2 pints of water may be carefully and evenly sprayed over each 75 bushels of seed, applying the spray to each scoopful of oats as it is turned over. The seed should then be shoveled from one pile to another several times and then covered tightly with burlap bags or blankets for two to five days. The temperature at all times should be above 50° F. The oats should be planted from two to five days after treatment or else passed through a fanning mill to drive out the formaldehyde gas. The seed can then be safely stored and planted at any time and any excess seed safely fed to livestock.

Tree Canker Salve Swiss Patent 209,590

Rosin 80
Coal Tar 20
Melt together, mix and apply while fluid.

Cannibalism (Poultry) Remedy Cannibalism among hens may be remedied by dissolving permanganate of potash in the drinking water until it is the color of cherry juice and then give them no other drinking water. A little salt should be placed in the water which will make them drink more frequently and will give them more of this medicated water. If one will use motor oil, lamp black, a little kerosene and turpentine and creosote in a mixture and bathe the injured parts to take away the bloody appearance, cannibalism will be stopped. Chickens will not pick feathers where there is an odor of creosote or turpentine.

# Control of Chicken Chiggers or Harvest Mites

If an abscess has not yet formed, the inflamed area may be treated with sulfur ointment, Peruvian balsam, or a mixture of one part of kerosene with three parts of lard. If suppuration has occurred the scab should be removed and the area washed with 4 per cent carbolic acid solution. Frequent light dusting with flowers of sulfur will keep the chickens from becoming infested.

Treatment of Poultry Favus

Favus is a disease of the skin of chickens characterized by the formation of white area on the comb and wattles. Occasionally this infection, caused by a fungus, may extend to the feathered parts of the body. Since this disease is transmitted from fowl to fowl by direct or indirect contact, affected animals should be promptly isolated and treated with an iodine-glycerin mixture. This mixture is composed of:

Tincture of Iodine 1 Glycerin 6

This combination should be applied two or three times per week to the infected areas. Since it will probably not be effective when the feathered skin is involved, animals so infected should be destroyed to prevent their becoming centers of infection for the whole flock.

Control of Chicken Feather Mite

Feather mites may be destroyed by dipping affected fowls in a tub containing a mixture of water, 1 gallon; flowers of sulfur, 2 ounces; and soap, 1 ounce.

The feathers should be thoroughly wet to the skin. The head should be submerged for an instant. During the dipping process the mixture should be stirred so as to keep the sulfur in suspension. Dipping should be done only on warm, sunny days, or in a heated building. If treatment

is found to be necessary during the winter or early spring months, thorough dusting of the fowls with flowers of sulfur should take the place of dipping.

The nesting material should be removed and burned, and nest boxes, roosts, walls, and floor should be sprayed or painted with anthracene oil as recommended for use against the common chicken mite.

A simpler method than the one just mentioned, reported as satisfactory in some cases but not so successful in others, consists in painting the perches with a 40 per cent nicotine sulfate solution shortly before the fowls go to roost, and dusting the nest with sulfur. Nests of English sparrows in the immediate vicinity of the poultry house should be destroyed.

Chicken Lice Powders and Their Application

A very satisfactory way of eliminating lice from poultry is to treat each fowl separately with sodium fluoride. If applied to all fowls as directed, one treatment is sufficient to kill all lice and their eggs. It is applied either by the so-called pinch method, or by means of a duster made by punching small nail holes in the bottom of a can having a tight-fitting cover, or by dipping. If the pinch method is used, the bird is held on a table while sodium fluoride is applied next to the skin under the feathers, as follows: One pinch on the head, one on the neck, two on the back, one on the breast, one below the vent, one on the tail, one on each thigh, and one on the under side of each wing. The feathers should be ruffled to allow the powder to get next to the skin. If the bird is held in a large shallow pan, the small quantity of powder which falls off will be saved. If the powder is dusted on by means of a shaker the quantity of sodium fluoride used may be reduced by using three parts of road dust or flour to one part of the chemical. This method requires the services of a second person to hold and turn the fowl.

When considerable numbers of birds are to be treated the sodium fluoride should be used in the form of a dip, a rounded tablespoonful (1 ounce) of commercial sodium fluoride being used to each gallon of water. The birds should be held by the wings and plunged into a tub filled with the solution, the head being left out, while the feathers are ruffled with the hand to allow the solution to penetrate to the skin. The head is then ducked once or twice and the bird held for a few seconds to drain, and then released. Dipping is just as effective as the other methods and is quicker and more economical of material. Dipping should be done only on warm. sunny days.

To sick fowls or to very young chickens or turkeys, sodium fluoride should be applied only by the pinch method, and especially in the case of young birds it should be used cautiously, in very small pinches.

One pound of sodium fluoride will treat 100 birds by the pinch method.

Another good lice powder is flowers of sulfur, which should be applied with a duster. Although sulfur is considerably cheaper than sodium fluoride, it is less effective against lice and hence must be applied more liberally, so that its use is in reality

more expensive than that of sodium fluoride. Many other powders, some of which contain pyrethrum (insect powder), are commonly used, but they have no advantage over sodium fluoride.

Dust baths containing a mixture of tobacco dust or other insecticide and ordinary road dust are often recommended to destroy lice. While it is a good plan to let the birds dust themselves when they wish, no method which allows the bird to treat itself for lice can be expected to eradicate them all, since fowls cannot get the dusting powder on all parts of the body where lice are, and many lousy birds will not use the dust baths.

A simple procedure, which is effective in controlling lice but will not eradicate them, consists in the application of undiluted 40 per cent solution of nicotine sulfate to the top surface of the roosts by means of a paint brush. This is done a short time (from 15 to 20 minutes) before the fowls go to roost. The fumes of the nicotine kill the lice during the first, second, and third nights after application. The head lice, naturally, are least affected. As some of the lice are not killed and the eggs are not destroyed, it is necessary to repeat the treatment frequently.

Disinfection of Poultry Houses

In case of an actual outbreak of virulent disease it is advisable to use for disinfecting purposes a whitewash made by dissolving 1 pound of commercial lye (containing 94 per cent of sodium hydroxide) and 2½ pounds of water-slaked lime in 5½ gallons of water. If the solution is not used at once, it should be tightly

covered to prevent deterioration. This solution is cheap, odorless, and destructive to almost all kinds of disease germs. On prolonged contact, however, it may be injurious to painted or varnished surfaces, and to some fabrics. It is corrosive to aluminum, but relatively harmless to the metallic fixtures ordinarily found about chicken houses, and to wooden construction or equipment. The poultry yard may be disinfected by wetting it thoroughly; use from  $\frac{1}{2}$  to 1 gallon of the solution per square yard of soil surface, depending upon the absorbent quality of the ground. It is essential, however, that all refuse matter be removed from the surface and burned or buried before poultry runs are disinfected.

The above-mentioned disinfectant solution has been found through experimentation to be ineffective against the germs of tuberculosis. For combating that infection, the chicken houses, enclosed runs, and all eating, drinking, and other utensils should be thoroughly cleaned and disinfected with a strong solution of such germicides as carbolic acid or compound solution of cresol. Carbolic acid may be used in 5 per cent solution and compound solution of cresol in 3 per cent solution.

Kerosene emulsion is frequently used to destroy mites. To make the emulsion, shave half a pound of hard laundry soap into half a gallon of soft water and boil the mixture until all the soap is dissolved; then remove it to a safe distance from the fire and stir into it at once, while still hot, 2 gallons of kerosene. This makes a thick, creamy emulsion or stock mixture. When it is to be used

for killing mites in the houses, 1	Corn-Gluten Meal 4.0
quart of this emulsion is mixed with	Alfalfa-Leaf Meal 10.0
10 quarts of water.	Ground Limestone (or
TO Quality of Wattor.	Oyster-shell) 2.0
CHICKEN FEED	Steamed Bonemeal 1.5
	Salt Mixture 1.0
Starting Mash	Cod Liver Oil 1.0
No. 2 Yellow Corn	No. 2
Meal 28 lb.	
Standard Wheat	Ground Yellow Corn 21.0
Middlings 20 lb.	Wheat Middlings 30.0
No. 2 Heavy Oats,	Wheat Bran 10.0
Finely pulverized 10 lb.	Dried Skim Milk (or
Standard Wheat Bran 16 lb.	Dried Buttermilk) 10.0
Fish Meal (55%	Meat Scrap 15.0
Protein) 8 lb.	Alfalfa-Leaf Meal 10.0
Meat Scraps (55%	Ground Limestone (or
Protein) 8 lb.	Oyster-shell) 2.0
Dried Skim Milk	Salt Mixture 1.0
(or Buttermilk) 5 lb.	Cod Liver Oil 1.0
Ground Limestone	
(39% calcium and	Laying Scratch Grain
	No. 2 Cracked Yellow
not over 2% mag-	Corn 60 lb.
nesium) 3 lb.	Whole Wheat 40 lb.
Salt Mixture (Made	During winter 100 lb. No. 2 yel-
by mixing $12\frac{1}{2}$ lb.	low corn can be used for scratch.
common salt with	
3.4 oz. anhydrous	Laying Mash
manganous sul-	Formula No. 1
fate) 1 lb.	No. 2 Yellow Corn
Cod Liver Oil 1½ lb.	Meal 24 lb.
	Standard Wheat
Starting Scratch Grain	Middlings 20 lb.
Cracked Wheat 40 lb.	No. 2 Heavy Oats,
No. 2 Yellow Cracked	
Corn 60 lb.	Finely pulverized 20 lb.
COIII 00 ID.	Standard Wheat Bran 10 lb.
01 11 10 1 75 1	Fish Meal (55%
Starting and Growing Mash	Protein) $6\frac{1}{2}$ lb.
Formula No. 1	Meat Scrap (55%
Ground Yellow Corn 17.5	Protein) $6\frac{1}{2}$ lb.
Wheat Middlings 30.0	Dried Skim Milk (or
Wheat Bran 10.0	Buttermilk) 7 lb.
Dried Skim Milk (or	Steamed Bone Meal 1 lb.
Dried Buttermilk) 10.0	Ground Limestone
Meat Scrap 5.0	(39% Calcium and
Fish Meal 4.0	not over 2% magne-
Soybean Meal 4.0	sium) or oyster shell 3 lb.
25, 2502 2,2502	sidility of dystel stient 5 10.

~ 11 34° 1 (34° 1	
Salt Mixture (Made	
by mixing $12\frac{1}{2}$ lb.	
common salt with	
3.4 oz. anhydrous	
manganous sul-	
fate)	1 lb. 1½ lb.
Cod Liver Oil	$1\frac{1}{2}$ lb.
No. 2	
Wheat Middlings	31.5
Wheat Bran	20.0
Dried Skim Milk (or	=0.0
Dried Buttermilk)	10.0
Meat Scrap	4.5
Fish Meal	5.0
Soybean Meal	$\frac{0.0}{2.3}$
Corn-Gluten Meal	$\frac{2.3}{2.4}$
Alfalfa Toof Mool	12.0
Alfalfa-Leaf Meal	12.0
Ground Limestone (or	0.0
oyster shell) Steamed Bonemeal	6.8
	1.5
Common Salt (or Salt	1.0
mixture)	1.2
Cod Liver Oil	2.8
No. 3	
Finely Ground Oats	19.0
Wheat Middlings	15.0
Wheat Bran	10.0
Dried Skim Milk (or	
Dried Buttermilk)	10.0
Meat Scrap	10.0
Soybean Meal	5.0
Linseed Meal	4.0
Alfalfa-Leaf Meal	15.0
Ground Limestone (or	
oyster shell)	5.6
Steamed Bonemeal	$\frac{0.0}{2.4}$
Salt Mixture	1.2
Cod Liver Oil	2.8
Cod Liver Oil	4.0
-	

Mixed Protein-Vitamin Con	cen-
trate for Chickens	
Alfalfa-Leaf Meal	25
Dried Skim Milk or	
Dried Buttermilk	20
Fish Meal or Meat Scrap	20

Soybean Meal	10
Corn Gluten	5
Linseed Meal (Old process)	5
Steamed Bonemeal	10
Ground Limestone	1
Salt Mixture	2
Cod Liver Oil	2

A mixture of 100 pounds of common salt and 1.7 pounds of anhydrous manganous sulfate (or 2.5 pounds of manganous sulfate tetrahydrate).

Or 0.4 part, by weight, of fortified cod liver oil that contains at least 400 A. O. A. C. chick units of Vitamin D and 3,000 International Units of Vitamin A per gram.

# Fowl Reviver Pills

As most poultry men know, medication for fowls is best given in pill or tablet form. In making these items glycerin or glycerin-containing preparations known as glycerites are usually employed as the excipient of massing material. An instance of such usage is given in the following recipe, modified from an English formula, for making fowl tonic pills:

Ferrous Sulfate	2	dr.
Extract of Gentian	$\frac{1}{2}$	dr.
Calcium Phosphate	1	$\mathrm{dr}.$
Glycerite of		
Tragacanth	suff	icient
-	to 1	nake
	9. m	าลรร

Divide into 5 grain pills.

Tonic pills for pigeons are made from a similar formula. They consist of:

Ferrous Sulfate Powdered Capsicum	1 20	dr. gr.
Extract of Nux		0
Vomica	6	gr.

Powdered Gentian ½ dr. Glycerite of

Tragacanth sufficient
Mix the ingredients and divide

Mix the ingredients and divide into sixty pills. Coat with sugar. Allow each pigeon six of these pills per day.

Glycerite of tragacanth is made from:

Powdered Tragacanth 125 g. Glycerin 775 cc. Water 185 cc.

Heat together in a double boiler, mixing until a smooth paste is formed.

Pigeon Malaria Control

A thorough cleaning of the pigeon nests at intervals not to exceed 25 days, using a light spray of kerosene extract of pyrethrum in the interior of buildings, and one of the following procedures: Dusting the squabs and pigeons with fresh pyrethrum powder, derris powder, or tobacco powder containing about 6 per cent of nicotine; dipping them with either an aqueous extract of pyrethrum with soap or derris extract with soap and water; or using the kerosene extract of pyrethrum spray on the birds.

Removing Oil Gloss from Eggs U. S. Patent 2,109,575

Dip in following solution for 2–3 minutes:

Sodium Dihydrogen

Phosphate 5– 10% Sodium Lauryl

Sulphate 0.1–0.25%

Bedbug Extermination
German Patent 701,761
The walls and especially the habi-

tat of the insects is first sprayed with an irritant. After 15-30 minutes the disinfectant proper is atomized within the room. The irritant is made as follows: 1 liter of a 15% pyrethrum extract is mixed with 150 liters of highly refined mineral oil; to this mixture is added wintergreen oil 2 kgms., citronella oil 1 kgm., and paradichlorobenzene 3 kgms. The disinfecting mixture is made up of: 15% pyrethrum extract 40%, highly refined mineral oil 35%, petroleum ether or carbon tetrachloride 20%, and Turkey red oil (50%) 5%. Neither of these preparations is injurious to men or animals.

# House-Fly Preparations

(1) Pyrethrum ½ lb., kerosene 1 gal. and methyl salicylate 3 fl. oz., (2) soap ¼ lb., water ½ gal. and kerosene 1 gal. A safe and effective poison bait consists of 3 teaspoonfuls of formalin to 1 pint of milk or water with a little sugar added. Flypapers or wires can be prepared by use of rosin 2 lb. and castor oil 1 pint.

# Lures for Rats

The following materials attract rats in the order given, with bread having a standard rating of 100:

0	
Oatmeal	80
Tallow	70
Bread and Milk	60
Banana	60
Flour	50
Barley	50
Bloater Paste	30
Fish (Smoked)	20
Drippings	20
Lard	10

Rat Extermination Compositions Formula No. 1

Red-Squill (Fine Powdered) 1 Oatmeal 4

Mix well and add sufficient oil of aniseed to give a faint smell to the bait.

No. 2

Red-Squill (Fine
Powder)
Oat or Maize Meal
Dripping or Tallow

14

Melt the fat and quickly pour on to the dry ingredients, which have been previously well mixed. Stir well until a stiff paste is produced, then add oil of aniseed to give a faint smell to the bait.

No. 3

Red-Squill (Fine Powder)	4
Grated Cheese	5
Fat	5
Oatmeal or Flour	6
	. 7 .

Mix the ingredients into a thick paste and cut into pieces about the size of a walnut and bake lightly in

a quick oven.

Red-squill powder, when mixed with flour, is very suitable for making up into small biscuits, which can be used as baits in hedgerows, refuse dumps, barns, stables, and even dwelling-houses. One biscuit is sufficient to kill a rat. It is advisable to use the biscuits freely so as to poison as many rodents as possible with the first application. The biscuits should be laid in the evening and pushed well down the rat holes. They keep well and retain their toxicity.

No. 4

Red-Squill	(Fine Powder)	1
Flour		$2\frac{3}{4}$
Fat		$1\frac{1}{4}$

Mix the squill and flour well together and knead in the fat, adding sufficient water to make a fairly stiff dough. Roll out into a sheet ¼ inch thick and cut into about 1,400 biscuits for each pound of squill powder used.

No. 5

Red-Squill (Fine Powder)	6
Breadcrumbs	15
Kipper (Minced)	4
Fat	5

Make a paste. One dessertspoonful is a toxic dose. This preparation should be made up as required for use, as it retains its toxic value only for three or four days.

Red-Squill Liquid Extracts

No. 6

190. 0	
Red-Squill Bulbs	1
Water	2
Salicylic Acid 2 oz. to every	
10 gallons.	

Chop up the bulbs as finely as possible and place in an earthenware vessel. Boil the water and pour it on to the bulbs, stir in the salicylic acid and macerate for several hours. When cold, strain through fine muslin, pressing out as much as possible. Pour into amber-colored glass-stoppered bottles and store in a cool, dark place.

The bait is made as follows: The liquid is mixed with an equal quantity of fresh milk, which has been scalded and allowed to cool. Bread (finely divided) may be used in place of oatmeal, making a thin bread-and-milk mixture. A quantity of the bait is poured into a saucer or similar receptacle, which is placed near the rat holes and runs at night. Another method is to soak small squares of stale bread in the liquid squill. These can then be laid in the rat holes, using a wooden spoon for the purpose. Yessels containing

water should be placed in the vicinity for the rodents to drink.

#### No. 7

Red-Squill (Bulbs, Chopped) 60 lb.
Distilled Water 10 gal.
Hydrochloric Acid 3½ fl. oz.
Salicylic Acid 7 oz.

Macerate bulbs with the acid liquid for twenty-four hours, stirring occasionally. Pour off the liquid, press the bulbs thoroughly, adding this to the decanted liquid. Pour in amber-colored stoppered bottles, preferably covering the surface with a layer of sweet oil or nut oil. To use: Place the extract in saucers with an equal quantity of milk, containing oatmeal, gruel or bread. 20 minims, equivalent to about 10 gr. of bulb, should be fatal. The extract does not keep well and should be used as soon as possible.

#### No. 8

A new rat-bait formula with powdered red-squill is prepared as follows:

The basic food is dried bread-crumbs. Obtain dried but not moldy white bread in whole loaves (not sliced); a non-milk bread is best. Break up the bread with the hands and put through grinder with %-inch holes, then press through a sieve with around 40 holes to the square inch.

(	Ground Dried Bread-	
	crumbs	52
(	Ground Fresh Pork Fat	
	(Back Strips Are Best)	4
(	Ground Fresh Halibut or	
	Haddock or Cod	16
I	Powdered Red-Squill	8
1	Mix the bread, pork fat and	hali

but well, and then add the squill and thoroughly mix.

#### No. 9

Ground Dried Breadcrumbs 68
Glycerin, Nut Oil or
Mazola Oil 4
Powdered Red-Squill 8
Mix the bread and glycerin and then add the squill and thoroughly mix.

#### No. 10

Ground Dried Breadcrumbs 30
Glycerin, Nut Oil or
Mazola Oil 2½
Fresh Bait—Hamburger
or fish or ground sweetpotatoes or ground apples or ground bananas 40
Powdered Red-Squill 8
Mix the bread, glycerin and squill.
Then add the fresh bait. Mix thor-

No. 11

oughly.

Ground Hamburger 5 lb. Powdered Red-Squill 8 oz.

Thoroughly mix the hamburger and squill, adding water to make quite moist.

Bait Exposure

Place bait in half-teaspoonful quantities at intervals along runways and walls and in all places where rats may feed. Use plenty of baits and cover the entire premises at one time. If using formula No. 11 or 10, place the baits in the late afternoon or evening, before dark. Uneaten baits should be collected and destroyed after three days. If using formula No. 8 or 9, the baits can be placed at any time of day. These baits will not deteriorate, so they can be collected at a later date if uneaten and exposed again after

four weeks. Do not use the fresh or moist baits during freezing temperatures. It is best to keep the bait out of reach of animals, children and

irresponsible persons.

Most of the baits can be prepared by the manufacturers of the poison. The liquid extract of squill should be placed in dark-colored bottles and well sealed. The baked squill biscuits will keep quite well and retain their toxicity. The squill powder must necessarily be sold in sealed containers which will keep the contents perfectly dry. Complete instructions for use, for the information of purchasers, should be enclosed with all packages.

Experiment Rat Food
Whole Wheat (Finely
ground) 1600 g.
Whole Milk (Powdered) 800 g.
Salt 32 g.

Sheep Dips Formula No. 1 5 lb. Soft Soap Liquid Phenol (Minimum 97% Tar Acid) 3 qt. Water g. s. to 100 gal. No. 2 18 lb. Sulphur Quicklime 9 lb. Water 21 gal. No. 3 Tobacco Waste 35 lb. Water 21 gal.

The first of these is quite simply made up by dissolving the soap, with gentle warming, in the liquefied phenol, the solution being subsequently admixed with the water.

Sulphur

10 lb.

In the second formula, the sulphur

and lime are made into a thick paste with water. The whole is then placed in a strong cloth, the ends tied, and placed in a boiler containing 10 gallons of water, so that the contents are completely covered, avoiding burning. After boiling for two hours the solids are thrown away and the liquor again made up to 10 gallons and stored in tightly-closed drums. The quantity is sufficient for 100 gallons.

The third product is made by steeping the tobacco "offal" in the water for a period of four days, after which the sulphur is added to the strained liquor, the resulting mixture being sufficient to make 100

gallons of dip.

, carp.	
No. 4	
White Arsenic	$2\frac{1}{2}$ lb.
Sodium Carbonate	$1\frac{1}{4}$ lb.
or	·
Caustic Soda	½ lb.

These proportions are finally made up to 100 gallons; 4 to 8 lb. of sulphur may be added to this formula, thus giving a sulphurarsenic-washing soda type of dip

	N	0.5				
Tar Acids					29.0	)
Paraffin Oil					36.0	)
Lanolin					8.0	)
Soft Soap					17.5	-
Water					9.5	,
One gallon	of	this	to	be	used	in
100 gallons of	wa	ater.				

No. 6			
Soap	1	lb.	
Crude Carbolic Acid	1	pt.	
Water	50	gal.	
No. 7			
Copper Sulphate	8	lb.	
White Arsenic	2	lb.	
Hydrochloric Acid		pt.	
Water To make 10	0	gal.	

Sheep Blow-Fly Wound Formula No.		ssings
Zinc Sulphate		lb.
Water	95	lb.
No. 2		•
Phenol	4	lb.
Whale Oil	96	lb.
No. 3		
Boric Acid	3	lb.
Glycerin	1	gal.
Blow-Fly Destro Formula No. Carbon Disulfide Sulphonated Castor	-	oz.
Oil	2 fl.	07
Water	2 gal	
Mix vigorously before	use. A	Apply
2 gal. per sq. yard of soi	l surfa	ice.

Australian Patent 110	,141
Anthracene Oil	100
Rosin	20
Phenol	5
Zinc chloride	5
Petroleum Ether	130
No. 3	
Boric Acid	30
Tar Oil (B.p. 170–210° C.	.) 2
Bentonite	2
Sulfatate (Wetting	
Agent)	$\frac{1}{2}$
Water	$65\frac{1}{2}$

No. 2

Tapeworms in Sheep

Nicotine sulphate, commonly known under the trade name of Black Leaf 40, is effective against tapeworms and hookworms in sheep. The dose should be one-half ounce or two teaspoons mixed with one quart of water. Lambs weighing 40 to 60 pounds should be given one ounce as a dose. Sheep 100 pounds or over should have from two to four ounces. Sheep should be kept

off feed for 24 hours before drenching. Use a long-necked bottle and be careful not to hold the head too high. Repeat in three weeks and change pasture for sheep every year.

-	
Cow Milk Stimulation Power	der
Potassium Nitrate	1
Alum	1
Sublimed Sulphur	1
Prepared Chalk	1
White Bole	2
Red Clover	5
Anise	10
Fennel	10
Salt	10
O: 1 01 101 11	

Give 1 or 2 handfuls in the morning feed, making sure that the powdered composition is thoroughly mixed.

Molasses Cattle Feed
British Patent 521,332
Hay, Finely Ground 47
Molasses 53
Mix together and dry to 12%
moisture content.

# Calf Scour Treatment

A very good treatment for calf scours is to reduce the feed approximately one half. A 6 gram dose of bismuth sub-nitrate will help to check the profuse diarrhea. One level teaspoonful of bismuth sub-nitrate will weigh about 6 grams. Care should be taken to get the calves back on full feed. A second dose may be given if needed.

Livestock Screwworm	Remedy
Diphenylamine	3.5
Benzol	3.5
Turkey-Red Oil	1.0
Lampblack	2.0
Apply thoroughly to w	ounds.

Treatment of Cattle Ringworm

The ringworm is treated by scraping off the scab with a knife blade and applying tincture of iodine or a mixture of equal parts of iodine and glycerin. This should also be put around the margin of the infected area. Immediate treatment of the first spot seen in order to prevent spread to other animals through indirect contact is necessary.

### Cattle Salt Sickness Cure

Prevention: Add one pound of either the sulfate or chloride of Cobalt to each ton of the regular salt sick mixture. This material must be thoroughly mixed, to secure results.

For smaller amounts, use this

formula:

Salt 100 lb.
Red Oxide of Iron 25 lb.
Powdered Copper Sulphate 1 lb.
Cobalt Salt 22 g.

This, too, must be mixed thoroughly to secure proper results.

Perhaps the best manner in which to make the mixture, is to mix the salt, copper and iron, and then dissolve the cobalt, 22 grams, in a small amount of water, and then spray this water over the mineral mixture, using a fly sprayer for this purpose.

For Advanced Cases: Dissolve 10 grams of cobalt chloride or cobalt sulfate in one gallon of water. Give each animal six ounces, as a drench one weekly for three or four weeks. Calves should have 3 fluid ounces, and other animals in like proportion.

# For Animal Ear Aches

What to do when one of the farm animals suffers from ear pains is often a problem. This can usually be solved, however, by the use of the following preparation which is very similar to that employed in human cases of ear ache:

Phenol 3
Glycerin 97
Add horic acid until the glyceri

Add boric acid until the glycerin will not dissolve any more. Let stand overnight and strain.

To use—put half an eyedropperful into the animal's ear and remove the excess.

# Animal Dandruff Treatment

When the skin is dry, treatment consists of washing the affected areas with soap and water or gasoline and applying antiseptics. A recommended solution is the following:

Salicylic Acid 1
Glycerin 3
Alcohol 60

When the skin is moist, the treatment is slightly different. Cleanse with gasoline, clip the hair and then apply the antiseptic.

# Glycerin Treatment for Ear Wax in Dogs

Treatment consists essentially of removing the wax and cleaning the ear. Applying drugs which tend to lessen the secretion are helpful. The following preparation is useful in controlling this condition:

Salicylic Acid 1.5 Glycerin 5.0 Alcohol, To make 100.0

A great deal of itching is associated with the excess wax production, and in some cases the lining of the dog's ear will become thickened and red. Recovery is slow in many cases and the condition may last for years, with intermittent periods of relief. Hence the need for prompt care and treatment.

Animal Eczema Treatment

In cases of chronic and seborrhic eczema of animals iodized glycerin is one of the most useful remedies. As the first step in the treatment, all crusts must be removed. In most cases the skin may be washed with soap and water. Iodized glycerin to be used after these preliminary procedures is readily prepared from:

Tincture of Iodine 1
Glycerin 4

Treating Ear Mange in Animals
Ear mange is not difficult to control in farm and household animals, if the suggestions given below are followed carefully. Use a mixture of 1 per cent cresol, 1 per cent carbolic acid or creosote, added to glycerin. Some animals require slightly different mixtures, however. For foxes, equal parts of tincture of iodine and glycerin is advocated and for ear mites in goats, an ointment of flowers of sulfur in sweet oil has proven both economical and effective.

Whichever preparation is used, however, the inside of the ear is swabbed with a cotton pledget held with forceps and moistened with the prescribed solution, taking particular care not to injure the eardrum. The accumulations and detritus in the ear should then be carefully cleaned out with a swab and the solution applied again. This treatment should be repeated after a week to kill any mites that may have hatched in the interval since the first treatment. To prevent reinfection the pens and premises should be thoroughly cleaned and washed with a suitable insecticide

~~	~ .	~	
1)00	Chat	i br	essing
ンしょ	-cav	2021	

Mineral Oil	3
Pine Oil	1

Mix and add trace of oil soluble blue dye (0.1 g. per gal.).

Spray on dog's coat or moisten cloth with dressing and rub lightly to achieve desired gloss. This will improve appearance and assist in controlling fleas.

# Hair Restorer for Dogs

Tincture of Cantharidin	1/4	oz.
Almond Oil	1	oz.
Glycerin	1	oz.

Lime Water, To make 4 oz.

Dress the skin where the hair is thin with daily applications of the above lotion.

# Dog Wash

For washing dogs, to maintain the healthy condition of their skin and fur, the following solution has been recommended:

Soft Soap	8	oz.
Glycerin	$2\frac{1}{2}$	oz.
Alcohol	2	oz.
Phenol	3/8	oz.
Eucalyptus Oil	$\frac{1}{4}$	oz.
Water, To make	35	oz.

# Mouth Wash for Dogs

When a mildly astringent, soothing mouth wash is needed for dogs, a suitable preparation can be made from the following:

Tincture of Ferric

Chloride	1	oz.
Potassium Chlorate	2	OZ.
Glycerin	4	oz.
Water, To make	1	gal.

# For Animal Ringworm

In the treatment of animal ringworm, a mixture of equal parts of glycerin, tincture of iodine, and chloral hydrate appears to be more efficient than the tincture of iodine alone, which is generally used. Others have found that a mixture of equal parts of tincture of iodine and glycerin is also very efficient in clearing up cattle ringworm.

Treatment generally consists of clipping whatever hair may be left on the diseased area. The scabs and crusts should then be softened with soap and warm, soft water. In some cases, it may be necessary to scrape the diseased area with a knife blade or even to sandpaper down the surface of the affected part. The diseased parts are then painted with the glycerin, tincture of iodine, chloral hydrate mixture.

# Dog Mange Treatment

A glycerin wash is an important feature of a recommended treatment for sarcoptic mange in dogs. The treatment calls first for the application of the following preparation:

Oil of Tar	1
Olive Oil	1
Turpentine	1

Two good dressings with this preparation, with an interval of three days, will destroy sarcoptic mange mites. After this treatment the dog is washed with a neutral soap and rinsed with a quart or two of warm water containing 5 per cent of glycerin.

This glycerin wash apparently serves to soothe the irritated skin, promotes healing and helps to restore the natural sheen of the animal's fur or hair.

(N.B. There are two forms of mange: sarcoptic mange and follicular mange. A preparation that will cure one form is practically useless in the other type. Follicular mange is very hard to cure and sometimes it is necessary to destroy the affected animal.)

# Breeding Kennel Dog Foods

		For	nula										
	Auburn*	No.	No.	No.	No.					No.			
Ingredient	Ration	1	2	3	4	5	6†	7	8	9†	10	11	12
Yellow Corn	35	86	66	44	56.5	56	58	58	60	46	55	43	47
Wheat Shorts	20		20	20	20	20	20	20	20	20	20	20	20
Wheat Bran	10												_2
Meat Scrap	10					18	20				10		5
Fish Meal	10				17			20	10				ð
Tankage									18	29	12		
Peanut Meal										29	12	27	15
Cottonseed Meal				077								2.	10
Soybean Meal Skimmilk Powder	- 10	10	10	$\frac{27}{5}$	5	5						5	5
Bone Meal	- 10 2	10	3	2.5	J	J				2.5	;	ĭ	Ŭ
Alfalfa Meal	$\frac{2}{2}$	9	J	2.0									
Salt	1	1	1.	1	1	1	1	1	1	1	1	1	1
Limestone	•	-		0.5	0.5		- 77			0.5	5 1	$^{2}$	1
Sardine Oil							1	1	1	1	1	1	1

<sup>\*</sup> Found to be complete for growth, maintenance and reproduction.

<sup>†</sup> Found to be complete for growth and maintenance.

Intestinal	Parisite	Remedy	for	
	Horses	1		

Phenothiazine 40 g. Carbon Disulphide 24 cc. Administer after a 36 hour fast.

# Glycerin-Phenol Treatment for Horse Galls

Of practical value in the treatment of horse galls is the simple glycerin-phenol mixture given below:

Phenol 1 Glycerin 15

This preparation has properties intermediate between those of ointments and lotions, both of which are used in the treatment of horse galls.

The animal should be permitted to rest for several days to allow healing to progress.

# Horse Liniment

Camphor 5 Tincture of Cantharides 5

Tincture of Capsicum	5
Tincture of Arnica	50
Alcohol	35
Diglycol Oleate	5

# Treating Horse Cracked Heels and Leg Irritations

Tincture of Iodine	1
Carbolic Acid	3
Glycerin, To make	32

A piece of cotton large enough to cover the injured area is saturated with the mixture, covered with a sheet of cotton and bandaged on. This should be repeated every day or two.

This is an excellent preparation for chronic scratches. It was used when horses' legs became blistered or irritated from the salt thrown on the street in cold weather. It is helpful in almost any leg condition.

# Garden Fertilizers

$\mathbf{Formula}$	No. 1	2	3	4	5
Sulphate of Ammonia	$3\frac{3}{4}$		1	5	2
Hoof-and-Horn Meal		$5\frac{1}{4}$	$1\frac{1}{2}$	-	5
Superphosphate (16% P <sub>2</sub> O <sub>5</sub> )	10		10	10	$8\frac{1}{2}$
Steamed Bone Flour	$2\frac{1}{2}$	$5\frac{1}{2}$	$4\frac{1}{2}$	$2\frac{1}{2}$	$2\frac{1}{2}$
Bone Meal		$5\frac{1}{2}$	Total Control of the		
Sulphate of Potash	$3\frac{3}{4}$	$3\frac{3}{4}$	3	$2\frac{1}{2}$	2

# Reinforced Manures

A ton of average mixed farm manure, in the moist condition, will contain about ten pounds of nitrogen, six pounds of phosphoric acid and ten pounds of potash. It is thus apparent that it is important to increase the phosphoric acid content of manure. It is well also to increase to some extent the amount of available nitrogen and potash, especially

if it is to be used in place of commercial fertilizer. A suitable mixture could be made as follows:

Formula No. 1

T OI III OI A	TAO.	T	
	Cc	ontaini	ng
	N	$P_2O_5$	$\mathbf{K}_{2}$ O
	lb.	lb.	lb.
1400 lb. Farm			
Manure	7.0	4.2	7.0
400 lb. (16%)			
Superphosphate		<b>G4.0</b>	

	Co	ntaini	ng
	$\mathbf{N}$	$P_2O_5$	K,O
		lb.	
100 lb. Sulfate of			
Ammonia	20.5		
100 lb. (50%)			
Muriate of			
Potash			50.0
In plant food c	ontent	this	would

approximate 800 pounds of a 4-8-7 fertilizer, which would be suitable for a variety of crops.

No. 2

Containing N  $P_2O_5$   $K_2O$ lb. lb. lb. 1500 lb. Hen 12.0 Manure 15.06.0 300 lb .(20%) 60.0Superphosphate 100 lb. Sulfate of 20.5 Ammonia 100 lb. (50%)

Muriate of

50.0 Potash

One ton of this mixture would be approximately equivalent, in plant food content, to 800 pounds of a 4-9-7 fertilizer.

> No. 3 Containing N P<sub>2</sub>O<sub>5</sub> K<sub>2</sub>O lb. lb. lb.

1600 lb. Dried 32.0 Poultry Manure 51.2 51.2 300 lb. (16%)

48.0 Superphosphate

50 lb. Sulfate of Ammonia

10.3

50 lb. (50%) Muriate of

Potash 25.0

One ton of this mixture would approximate in plant food content 1000 pounds of a 5-10-5 fertilizer, which would be suitable for a variety of vegetable and other crops.

It is frequently advisable to use superphosphate on the dropping boards in poultry houses. This reinforces the manure at its weakest point-phosphoric acid-and likewise aids in retaining ammonia which might otherwise be lost. The ammonia in the manure, which is more or less volatile, and thus easily lost, unites with the gypsum of the superphosphate to form a stable compound, ammonium sulfate.

It is not advisable to use lime with manure. This reacts, with compounds in the manure, in a way that causes the loss of ammonia.

Manure in piles should not be exposed to leaching rains, which would naturally cause a great loss of soluble constituents, but on the other hand should be kept moderately moist to prevent loss of ammonia and destruction of organic matter through undue heating. Unless manure can be kept moist and well packed, without exposure to heavy rains, it is best, where possible, to spread on the fields as produced.

Manure is also reinforced and saved by the proper use of bedding. The liquid portion of the manure is the most valuable, and the greater the absorbing properties of the bedding the greater its value in this respect. There are a number of materials which may be used for bedding, as for example, the different straws, salt marsh hay, peanut shells, wood shavings, sawdust, and peat moss. Of these, peat moss has the greatest absorbing power but contains comparatively little plant food. Straws, salt marsh hay, and peanut shells contain an appreciable amount of plant food constituents.

# Poultry Lime Granules British Patent 539,298

Calcium Carbonate	25,000
Calcium Phosphate	500
Magnesium Carbonate	200
Iron Sulphate	200
Sulphur, Flowers of	10
Potassium Permanganat	e <b>5</b>

The above is mixed and tumbled in a rotary drum while being sprayed with 18-20% water. Dextrin or skimmed milk may be dissolved in the water if a smooth finish is wanted.

# Substitute for Farm Manure

Because manure is not available on many farms now, a fairly good substitute can be made up as follows: To one ton of straw or similar material, including garden refuse and leaves, add a mixture of about 75 pounds ammonium sulfate, 50 pounds superphosphate, and 100 pounds of powdered limestone. This is mixed with the straw. Keep the whole moist by frequent watering, and turn it over occasionally. After about three months, the straw will become well rotted and will be quite similar in appearance, composition,

and effects to the ordinary farm manure.

Inexpensive Fertil	izer	
Wood Ashes	1	lb.
Ammonium Phosphate	2	oz.
Sodium Nitrate	2	OZ.
Ferrous Sulphate	$\frac{1}{4}$	oz.
Mix all together and	1150	1 too

Mix all together and use 1 teaspoonful placed around the plant, not closer than 10 inches, else the mixture may burn the tender roots.

Conservatory Ferti	lizer	
Potassium Nitrate	2	OZ.
Disodium Phosphate	5	OZ.
Ammonium Nitrate	1	oz.
Ferrous Sulphate	1/8	oz.
Calcium Chloride	1/8	oz.
Use $\frac{1}{4}$ oz. to a gallon		
void sprinkling foliage	wit	h the

Plant Growth Stimulant
German Patent 682,023
Fluorescein 600 mg.
Iron Sulphate 500 mg.

Copper Sulphate

mixture.

Peat, Powdered 100 kg.

Mix the above well and make weakly alkaline with sodium bicarbonate solution.

40 mg.

#### CHAPTER SEVEN

# FOOD PRODUCTS

Uncooked Dried Fruit Candies
Whole, Seeded Muscat
Raisins 2.5 lb.
Prunes, Pitted, Finely
Ground 2.5 lb.
Coarsely Chopped, Walnuts or Almonds 2.5 lb.

Warm and mix the fruits in a jacketed kettle until well softened, add the nuts and mix. Press into rectangular metal or wooden forms, or roll out on an oiled slab or on oiled paper. Let harden, cut to size if on a slab. Coat with ground nuts or in other suitable manner. Wrap as 5¢ bars. The prunes and raisins are rather sticky and therefore bind the mass together. Figs may be substituted for the prunes.

The dried fruits should contain about 22% moisture and should neither be too dry and hard, nor too moist and soft. Dried apricots may be substituted in part for the prunes, equal to about 50% of the prunes.

A better bar is obtained if a binder of fondant or fudge is used to give a firmer texture to the candy.

Raisins (Seeded Muscat
or Seedless)
2.5 lb.
Pitted Prunes, Finely
Ground
2.5 lb.
Coarsely Chopped Walnuts or Almonds
Freshly Made Warm
Fondant Preferably
Made with Invert
Mix in a mechanical mixer, or

warm and mix in a jacketed kettle. Spread on oiled slab or paper to harden. Cut to desired size.

The flavor of the bar in the second formula is improved if about 10%, by weight, of orange peel jam is added. It may be made by taking dried whole orange peel not previously used for oil recovery, adding to it 6–7 parts of water, boiling 2–3 minutes, soaking overnight, cooking soft, grinding finely, adding one half its weight of sugar and cooking to a heavy jam.

"Arctic Ice" Dried Fruit Candy High Melting Fat (90° F. or Above) lb. Powdered Sugar lb. 10 Powdered Milk 31/2 lt. Chopped or Ground Dried Fruit 20 lb. (Figs, Apricots, Prunes or Raisins or a Mixture of Any Two or More) Vanilla Flavoring, To suit Chopped Walnuts or 3-5 lb. Almonds

Melt the Fat. Stir in the powdered milk and sugar. Allow to cool until it begins to thicken. Add the fruits and nuts. Mix well. Spread on slab or paper to harden. Cut to desired size.

Fruit Rolls: Another uncooked fruit candy can be made by mixing

ground dried fruits with about 20% their weight of chopped nuts and a little honey (about 20%), or orange concentrate, invert syrup, or other heavy syrup as a binder, and extruding through a sausage casing filling machine, cutting off the "sausage" in short lengths as it is extruded, and coating these pieces with chopped nuts, ground cocoanut, or powdered sugar. All this is done mechanically in making date rolls. These are coated with cocoanut.

A mixture of a sticky dried fruit such as ground raisins with a less sticky one, such as ground prunes or apricots, may be used, and the syrup binder omitted. Figs need little syrup binder and no added raisins if they are previously processed in a packing plant or by the confectioner to about 23% moisture, that is until they are pliable. They keep much better if syrup is added.

Fruit Jelly Candies

If made with fruit pulp or fruit juice, the candy is more flavorful and contains the dietary value of the fruit used. Fresh fruits are cooked with a little water until soft and are then sieved; dried fruits are cooked in sufficient water to cover well and when soft are sieved to give a juice or pulp. Canned pie grade fruits in No. 10 cans may be sieved without additional cooking. As a general rule, the dried fruits will be more suitable since they are inexpensive and give pulps that are "meaty" and not too thin or watery. Canned or bottled fruit juices may be used, such as pineapple, grape, orange or grapefruit.

Fruit Pulp or Juice 40 lb. Cane Sugar 30 lb. Invert Syrup or
Glucose Syrup 30 lb.
Powdered Confectioner's Pectin (High
Jellying Power) 1½ lb.
Citric Acid, 8 Ounces
Dissolved in 2 Pints
of Water

Mix the dry pectin with half the sugar. Heat about 3 gallons of water to boiling and sprinkle the mixture of pectin and sugar with it, stirring rapidly to avoid lumping. Several minutes heating will be necessary to dissolve it.

Mix the fruit pulp (or juice), invert and syrup or glucose syrup, remaining sugar and then the pectin solution. Cook in a jacketed kettle to 223° F., add the citric acid solution, and then boil to 223½°-224° F., that is 11½-12° F. above the boiling point of water. Cast in starch molds, or pour on to an oiled slab or oiled paper to harden. It is advisable to follow the latter procedure as it is sometimes difficult to cast the hot jelly. Coat with coarse sugar or in finely cut cocoanut.

Other Suggestions

Dried fruits can be used in various standard candies by adding them after the batch has been cooked to the finishing point. For example it can be whipped into marshmallow, or added to fondant after creaming, or to fudge before pouring. The writer does not pretend to be, or does not pose as, an expert confectioner; he is primarily a fruit products chemist and technologist. Therefore, you as experienced candy makers, will see other possible uses of fruits in candy that do not occur to me, and will be able to improve

greatly upon the formulae I have offered in this article.

The principal fact to remember concerning dried fruits is that they contain from 50 to 65% of sugar and hence are excellent substitutes for sugar in certain kinds of candy to which they are adapted. Also they produce candies of exceptional dietary value.

Maple Bonbon Coating
Water 3½ gal.
Condensed Maple
Syrup (2½ Fold) 10 lb.
Sugar (Sucrose) 75 lb.
Salt 3½ oz.

Salt 34 oz. Egg White (Beaten) 1/2 pint Sheet Gelatin

(Melted in 2 oz.

Hot Water) 1 oz.

Cook sugar, condensed maple flavor, salt and water together to 240-242° F. in steam-jacketed kettle. Turn off steam and add melted gelatin.

Pour batch on Ball beater and allow to cool to blood heat (97° F.) before heating. When half beaten, add egg whites which have been previously whipped to a light fluff.

Let set overnight before using. Produces a fine bonbon coating for highest-class goods.

# Praline Crunch Granulated Sugar 1 lb.

Butter 1 lb.
Nut Meats, Roasted 8 oz.

Nut meats should be chopped, not too fine. Melt the sugar to a golden brown, 340 to 350° F. Remove from the fire and thoroughly mix in the nut meats and butter. Pour onto a buttered bun pan. When cool, crush.

This can be used in icings or to dress the top and sides of a cake.

# Retention of Flavor in Hard Candies

Flavor retention in hard candies can be obtained by the use of glyceryl oleate (edible). It acts as a solvent fixative for extract flavors used in hard candies such as peppermint, cherry, lemon, etc., and prevents the flavor from volatilizing on addition to the hot melt (300° F.).

low	
	lb.
8	lb.
15	lb.
65	lb.
10	lb.
	8 15 65

Flavor and Color, As desired

Soak the gelatin in the cold water. Heat the soaked gelatin carefully until fluid (about 140° F.). Add the fluid gelatin to the egg whites, 35 lb. of sugar and the standardized invert sugar. Whip this mixture until it is fairly stiff. Just before finishing the whipping, add the remaining 30 lb. of sugar along with the flavor and color. Beat until of the consistency of marshmallow.

For banana flavor use, for each 10-lb. batch, about 4 oz. of ripe banana powder containing dry milk solids. Incorporate it in any way convenient, preferably first blended with about an equal weight of sugar.

Marshmallow Fil	ler	
Sugar XXXX	4	lb.
Glucose	1	lb.
Egg Whites	$\frac{1}{2}$	pt.
Invert Syrup	4	lb.
Vanilla Gelatin (220		
Bloom), High Test	$2\frac{3}{4}$	oz.
Water	1	pt.

1/8 OZ.

Salt

Soak gelatin in the water for one hour and then heat to 180° F. Place in the mixing bowl with the other ingredients and beat for 5 minutes at medium speed. Change to high speed and beat until stiff. Add flavor to taste.

> Marshmallow for Chocolate Dipping

40 lb. Granulated Sugar Standardized Invert 10 lb. Sugar 50 lb. Corn Syrup

3 lb. Gelatin Water 14 lb.

Dissolve the gelatin in the water until tender, then heat until fully dissolved. Add the granulated and standardized invert sugar and heat until they are dissolved. Place the batch into the beater, add the corn syrup and beat until the marshmallow is sufficiently light. Flavor and color can be added as desired. The proportion of water must be increased or defreased according to the conditions under which the goods are manufactured.

# Caramel Base

Water 1 lb. 8 oz. Brown Sugar 5 lb. Butter 1 lb.

Sugar (Granulated 3 lb. Sucrose) Powdered Skim

Milk 1 lb. 11 oz. Water 2 lb. 8 oz.

Place ingredients A (water, brown sugar and butter) in a copper kettle and stir until the sugar is dissolved. Place on fire and boil to 320° F. If no thermometer is available, boil to

a hard crack. Wash sides of ketic with a wet brush while boiling, but do not stir.

When temperature reaches 300° F., turn flame down low and boil slowly until the temperature reaches 320° F.

Of the ingredients marked B, mix together the sugar and dry milk. Pour this mixture into the water. and stir with a wire whip until all ingredients are dissolved.

Remove kettle containing A from fire when temperature has reached 320° F. and add gradually the mixture B (sugar, milk, water) while stirring A briskly with a wire whip. Continue this stirring until base is smooth.

If a darker color is desired, add 2 oz. of burnt sugar color. Cool base before using. Store in a covered container in a cool, dry place.

This caramel base has excellent keeping properties, and may be used as required.

Caramel Sauce

White Sugar	5
Water	5
Cream	1
Butter	0.3
Flour	0.1

Brown the white sugar, add water and boil until it forms a soft ball in cold water. Stir quickly. Let come just to a boil, turn off heat and add butter.

"Homemade" Fudge Icing Granulated Sugar 4 lb. 8 oz. Corn Syrup 12 oz. Milk 1½ pt. Concentrated Maple Syrup (2½ Fold) 8 oz. Butter

6 oz.

Boil the granulated sugar, corn syrup and milk together to 234° F., and at the finish of the cook, add the concentrated maple syrup. Cook to 130° F. Finally, add, and mix until smooth, 6 oz. of butter and sufficient icing sugar to give the consistency desired. Apply warm or at about 110° F.

Chewing Gum Base	9
U. S. Patent 2,137,74	46
Formula No. 1	
Jelutong (Dry)	92%
Paraffin Wax (M. P.	•
168° F.)	8
No. 2	
Ester Gum	30%
Coumarone Resin	45
Latex (Dry)	15
Paraffin Wax (M. P.	
180° F.)	10
No. 3	
Jelutong (Dry)	80%
Gutta Siak	15
Paraffin Wax (M. P.	
176° F.)	5

A chewing gum mix is made employing about 20% of the chewing gum base, about 60% of pulverized sugar (sucrose), about 19% commercial corn syrup, and about 1% of a desired flavor.

Chewing Gum

Activated Charcoal	Chewing	Gum
British Patent	523,122	
Gum Base	20	lb.
Glucose	20	lb.
Sugar	60	lb.
Activated Charcoal	$3\frac{1}{4}$	lb.
Flavoring	1	lb.

Pumpernickel	Bread	
Rye Meal	4 lb.	
Rye Flour	4 lb.	
Strong Clear Flour	5–6 lb.	

Water	1	gal.
Yeast		oz.
Salt		oz.
Malt Extract	2	oz.

Temperature of stove should be approximately 82° F. to obtain the best results. Approximate time for first rising, 1 hour, 30 minutes; second rising, 30 minutes; and take-in 30 minutes.

Scale and round out the dough. Make up and place close together on boards or boxes dusted with cornmeal. Grease loaves when placing them together.

Soy Noodles		
Flour, Spring Wheat	117	lb.
Soy Flour, Full Fat	13	lb.
Whole Eggs	24	lb.
Water	24	lb.

Mix soy flour with wheat flour, then proceed as with regular noodles.

Silver Dou	ghnut	Gla	ze	
Glucose		lb.		oz.
Salt			1	oz.
Water	1	lh	Q	07

Add glucose and salt to water. Heat to boiling and remove from fire.

Gelatin	1	oz.
Water, Cold	8	oz.

Stir gelatin into the cold water. Let stand about 5 minutes, or while glucose-water syrup is heating to a boil.

Add gelatin solution to the hot syrup immediately after removing from the fire. Stir until gelatin is thoroughly dissolved in the hot syrup.

Sugar, XXXX 20 lb.
Vanilla Extract 1 oz.
Sift sugar to remove all lumps.

Stir while slowly pouring the hot gelatin-glucose solution on the sugar. Mix thoroughly. Cool to about 120° F. to use.

Doughnuts give off considerable moisture while cooling. A good glaze can be ruined by dipping doughnuts while too warm. For best results, cool doughnuts to about 110° F. and have the glaze at about 120° F. Dip the doughnuts and lift them out immediately to drain on wire screens or racks.

If the glazed doughnuts are packaged, they must not be placed in airtight packages. For this will promote sweating and soaking the glaze.

Prepared Doughnut Glace Sugar, Confectioner's 100 lb. Pure or Imitation Vanilla

(16 Concentrate) 1 oz. Algin 1 oz. Powdered Gum Karaya 1 oz. Gelatin (Fine Powdered) 8 oz. Tapioca Flour 3 lb.

Mix ingredients together (add vanilla mixed with part of the sugar). Add boiling water to produce consistency and stiffness required to coat doughnuts. Keep over hot water bath while using.

Macaroon Cup Cakes

Macaroon Cup C	Jakes
Egg Whites	5 lb.
Granulated Sugar	9 lb.
Salt	$\frac{3}{4}$ oz.
Cream of Tartar	1 oz.
Vanilla Extract	1 oz.
Macaroon Cocoanut	

White Flour 5 oz.

Whip egg whites to a wet peak, but not quite as stiff as for angel

food. Mix 4 lb. granulated sugar with the salt, cream of tartar, and vanilla. Add mixture to the beaten whites. Do not overbeat. Mix remaining 5 lb. of granulated sugar with the macaroon cocoanut and white flour. Fold in gently, either by hand or by machine.

Use crinkled parchment cup cake liners in standard cup cake pans. Measure 15 to 16 oz. per doz. cups. Bake approximately 20 to 25 minutes at 350° F. For variety place pieces of candied fruit or nuts on top of the batter before baking.

For commercial production the egg whites should be 75° F. Hand finishing of mixing is recommended.

Homemade Pie Dough for Fruit Pies

Flour (Ordinary Pastry

Flour)		10	lb.
Shortening		7	lb.
Ice Water	2 lb.	12	oz.
Salt		6	oz.
Corn Sugar		5	oz.

Rub the shortening and flour together until the flour is partly coated with fat. Do not mix to a paste but, on the other hand, do not leave the shortening lumps too large.

Dissolve the salt and corn sugar in the water, add to the flour and shortening mixture until the mass

is of uniform consistency.

Washing of pies made with this dough is not necessary. If correctly mixed, crusts will color uniformly on both top and bottom. If the flour is too soft, the crust will not remain crisp. If bread flour is used, the crust will likely shrink. Therefore, a medium-quality pastry flour is recommended for this formula.

Salt

 $5\frac{1}{4}$  oz.

Pointers for preparation:

1. The best results are obtained by using cold ingredients.

2. Store the flour to be used for pies in a cool place.

3. Water should be below 45° F.

4. Shortening should be kept in a cool place.

5. Hot flour or shortening will ruin the crust.

The shortening used in pie dough should be a product having a mild lard flavor; a better body than is normally obtained in lard; and a wide plastic range.

## Waffle Mix

77 001110 171112		
Sugar	36	lb.
Salt	15	lb.
Totally Hydrogenate	d	
Shortening	120	lb.
Soy Flour	18	lb.
Milk Powder	36	lb.
Soda	12	lb.
Cream of Tartar	12	lb.
Egg Yolk	40	lb.
Malted Milk	9	lb.
Cake Flour	360	lb.
Bread Flour	240	lb.
Powdered Turmeric	2.5	oz.

Mix ingredients together. Add a sufficient amount of liquid milk or water to produce a batter of medium consistency. Usually approximately 1 lb. 4 oz. of liquid milk to 1 lb. of flour. Batter should not, however, be excessively soft.

# Cinnamon Meringue

Egg Whites	1	lb.	8	oz.	
Sugar	2	lb.	10	oz.	
Vanilla Extract			$\frac{1}{2}$	oz.	
Cinnamon			1/4	oz.	

Beat egg whites until firm. Add sugar and vanilla slowly. Add cinnamon and stir in until smooth.

Marshmallow Cake Icing

Albumen 1½ lb. Gelatin (220 Bloom),

 $\begin{array}{cccc} \text{High Test} & 9 & \text{oz.} \\ \text{Granulated Sugar} & 10\frac{1}{2} & \text{oz.} \\ \text{Water (140° F.)} & 11\frac{1}{2} & \text{lb.} \\ \text{Vanilla} & 2\frac{1}{2} & \text{oz.} \\ \text{Granulated Sugar} & 21 & \text{lb.} \end{array}$ 

Sift the albumen, gelatin and sugar three times. Place water in a mixing bowl and add the sifted albumen, gelatin and sugar and whip by hand until dissolved. Place bowl in machine and whip at high speed over a period of 6 minutes. Then whip at low speed for a few minutes. Add vanilla and mix 30 seconds. Add sugar and salt gradually over a period of 30 seconds. Remove whip and fold a few times by hand.

# Cream-Type Icing Stock (Non-Sticky)

(Non-Sticky)				
Butter	2	lb.	8	οz.
Hydrogenated				
Shortening	5	lb.	4	oz.
Water	10	lb.	6	oz.
Sugar (Powdered				
4X)	50	lb.	0	oz.
Salt			8	oz.
Dry Milk Solids *	10	lb.	6	oz.

Blend butter and shortening thoroughly at 75° F. Add water carefully with slow-speed beating to make an emulsion. Blend sugar, salt and dry milk solids thoroughly and add gradually to emulsion. Cream well

Desired variations may be had by adding various flavorings, colorings, fruits or nuts to this icing stock.

<sup>\*</sup> Not over 11/2% fat content.

Butter Cream Icing
Butter 12 oz.
Hydrogenated
Shortening 2 lb. 6 oz.
Water 2 lb. 4 oz.
Sugar (Powdered
4X) 12 lb. 8 oz.
Dry Milk Solids \* 3 lb. 12 oz.
Vanilla Extract,

To suit

Egg Whites 12 oz. Blend fats well at 75° F. Add water carefully with slow-speed beating to make an emulsion. Sift sugar and milk solids several times and add gradually to mix. Beat smooth. Add vanilla flavor. Beat egg whites stiff and fold in. Mix until smooth.

If chocolate flavor and color are desired, add 1 oz. natural or "domestic" cocoa powder for each 15 oz. of butter cream icing stock used. Mix on low speed to get uniformity in mix

Caramel Custard Pie Whole Milk lb. Brown Sugar lb. Salt 1/4 oz. Vanilla  $1\frac{1}{2}$  oz. 2 lb. 12 oz. Frozen Eggs Maple Flavor 1/8 oz. Caramel Color ½ oz. Heat the milk to 140° F. Add the

sugar, salt, flavors and color.

Stir until the sugar is melted. Add the eggs and stir. Do not whip.

Strain through a small sieve to remove any insoluble matter. Skim off the foam from the surface.

Pour into unbaked shells. Bake at 450° F.

Improved Yeast
U. S. Patent 2,223,465
After yeast has been "filter-

\* Not over 1½% fat content.

pressed" 0.12-1% of any of the following is incorporated:

Propylene Glycol Laurate Glyceryl Mono Laurate Sorbitol Laurate

A whiter color; improved cutting and increase in water binding capacity results.

Fruit Purées for Ice Cream

The preparation of raspberry, boysenberry, loganberry, young-berry, blackberry and blueberry pectinized purées is a relatively simple matter, e.g.

Pulpy Fruit Juice or

Purée 100 lb. Granulated Sugar 50 lb. Enzyme-Converted

Corn Syrup (43° Bé) 60 lb. Pectin \* (110 Grade) 2 lb. Citric Acid † 1½ lb. Water 20 lb.

The pectin is stirred into 15 lb. of the enzyme-converted corn syrup, which has previously been warmed to about 160° F. This suspension of pectin in corn syrup is then slowly stirred into the water which has been brought just to the boiling point. The solution is agitated rapidly and kept hot for 5 to 10 minutes, or until a smooth syrupy solution is obtained. Heating is then discontinued, and while the agitation is continued the remainder of the enzyme-converted corn syrup is added. The fruit purée, to which has been previously added the granulated sugar and finely powdered cit-

\*Less pectin is required for black raspberry purée. One pound per 100 lb. of fruit will be sufficient.

† The more tart the fruit, the less citric acid should be added. Thus little, if any, citric acid needs to be used in making loganberry purée.

ric acid, is then stirred with rapid agitation into the solution of the pectin in the corn syrup.

The product may be heated to 170° F. and then canned without cooling, or it may be cooled for immediate use or for freezing preservation. If the purée is canned, it should be filled into cans lined with special fruit enamel, taking care to fill each can completely. The cans are closed immediately, then they are inverted or turned on the side in order to sterilize the covers. After standing for five minutes, they are cooled in running water.

If the purée is to be used immediately or frozen for future use it should be cooled, under slow agitation, by running water in the jacket of the kettle in which it was made. If the purée is to be preserved by freezing, it should be cooled as cold as possible in the kettle and then run into 30- or 50-lb. enamel-lined slip-cover cans and frozen at 0° F. or lower.

#### Peach Purée

Ground Peaches	100	lb.
Granulated Sugar	50	lb.
Enzyme-Converted		
Corn Syrup (43° Bé)	60	lb.
Pectin	$2\frac{1}{2}$	lb.
Citric Acid	$1\frac{1}{4}$	lb.
Water	20	lb.

The solution of the pectin in the enzyme-converted corn syrup is obtained in exactly the same manner as described above under pectinized berry purée. In this case the solution is raised to and maintained at 175° F. The peaches are peeled either by scalding in boiling water or steam for about 90 seconds or by immersion in hot lye solution.

After the peels have been rubbed off, the peaches are halved and the pits removed. The halved peaches are placed in the hopper of a food chopper, especially arranged to grind soft fruits, or in a similar grinding device, sprinkled with some of the sugar and some citric acid solution prepared by dissolving the citric acid in a small amount of water. As fast as the peaches are ground, they are stirred directly into the pectin-corn syrup solution, which is maintained steadily at 175° F. When the proper weight of ground peaches has been added, any remaining sugar and citric acid is stirred into the batch. Then the pectinized purée is cooled by circulating cold water in the jacket of the kettle.

Currant Purée		
Pulpy Currant Juice	100	lb.
Granulated Sugar	50	lb.
Enzyme-Converted		
Corn Syrup	60	lb.
Pectin (100 Grade)	1	lb.
Water	20	lb.
~		

Currant juice is so tart that no citric acid need be used.

Pineapple Purée					
	Canned Crushed Pine	e-			
	apple	100	lb.		
	Granulated Sugar	45	lb.		
	Enzyme-Converted				
	Corn Syrup	60	lb.		
	Pectin (100 Grade)	$2\frac{1}{2}$	lb.		
	Citric Acid	$1\frac{1}{2}$	lb.		
		_			

First the crushed pineapple should be disintegrated. The pulpy product is combined with the sugar, syrup and pectin by the procedure described under berry purées. A suitable color should be added, as

otherwise the product is scarcely noticeable in the ice cream.

Grape Purée Concord Grape Juice 100 lb. Granulated Sugar lb. Enzyme-Converted Corn Syrup 60 lh. Pectin (100 Grade)  $^{2}$ lb. Citric Acid 11/2 lb. Water 20 lb.

The method of making this product is the same as that described for berry purées, the Concord grape juice being substituted for the pulpy fruit juice.

Damson Plum Purée
Damson Plums Frozen
with Sugar (3+1) 100 lb.
Granulated Sugar 12½ lb.
Enzyme-Converted
Corn Syrup 45 lb.
Pectin (100 Grade) 1 lb.
Water 15 lb.

The thawed plums should be converted into a purée in a tomato juice extractor of the tapered screw type. The resultant purée is combined with the sugar, corn syrup, and pectin according to the manner described under berry purées. Damson plums are so tart that no acid need be added.

English Morello Cherry Purée English Morello Cherry Purée 100 lb. Granulated Sugar 50 lb. Enyzme-Converted Corn Syrup 60 lb. Pectin (100 Grade)  $2\frac{1}{2}$  lb. Water 25lh

English Morello cherries usually are so acid that no citric acid need be used. Either fresh or frozen cherries can be used.

Maraschino Cherry Purée

The Maraschino cherries should be pulped in a suitable machine which will comminute even the skins. The pulp should then be mixed with the syrup and the cherry juice. From then on the procedure is the same as that described for berry purées.

Maraschino Cherries		
in Syrup (Pulped)	35	lb.
Hot Pressed Montmo-		
rency Cherry Juice	65	lb.
Granulated Sugar	40	lb.
Enzyme-Converted		
Corn Syrup	60	lb.
Pectin (100 Grade)	$2\frac{1}{2}$	lb.
Citric Acid	8	oz.
Water	20	lb.

Orange Marmalade Purée
An orange marmalade is prepared
by cooking the following ingredients
for about 15 minutes.

Orange Juice	= -1
	5  qt.
Lemon Juice	1 qt.
Finely Sliced and	
Chopped Cooked	
Orange Peel	2 lb.
Granulated Sugar	7 lb.
Enzyme-Converted	
Corn Syrup	8 lb.
Pectin	5 oz.
Water	2 lb.

The pectin is dissolved in corn syrup and water according to the procedure described under berry purées. The finely sliced and chopped cooked orange peel is heated to boiling in the mixture of juices. Then the pectin solution is stirred in. Next the granulated sugar is added and finally the remainder of the corn syrup. The whole is

boiled for about 15 minutes but the total solids content should not be permitted to rise above about 55%. The product may be used in making either a variegated ice cream or sherbet.

Milk Chocolate Ice Cr	eam
Heavy Sweet Cream *	30
Condensed Skim Milk	30
Sugar, Granulated	10
Corn Syrup Solids	5
Malt Syrup	2.5
Cocoa Powder	2.6
Gelatin	0.3
Soybean Lecithin	0.1
Water	19.5

Combine cocoa powder with equal parts of granulated cane sugar and mix dry, then add the water. Pre-

pare the chocolate syrup by adding the lecithin and malt syrup with the aid of an agitator until smooth.

Place cream and condensed skim milk in the pasteurizing tank and apply heat. When the temperature on the recording chart of the pasteurizer reaches 120° F., add the remainder of the granulated sugar, the gelatin, and corn syrup solids. Finally add the prepared chocolate syrup and proceed with the pasteurization process by heating the complete chocolate ice cream mix to 155° F. for 30 minutes. Homogenize at 2500 lb. pressure. Cool to about 45° F. Place in storage tank until ready to freeze.

The preparation of the chocolate syrup is best accomplished in a steam-jacketed receptacle or double boiler.

## Ice Cream Mixes

(Using all butter in place of cream.)

10 caranta	2		12%	f _ +	971/0/ 7	70±0.	1 0.1:3	~
40 quarts			1270	120	371/2%			
					Usi	ng	Whole	MIIK
Sweet Butter		13 I	b	Sweet:	Butter.		11	lb.
Sugar	13 lb.	8 o	z.	Skim I	Milk Powd	er	4	lb.
Skim Milk Powder	9 lb.	8 o	z.	Whole	Milk		$30\frac{1}{2}$	qt.
Gelatin		6 o	z.	Sugar		13	lb. 8	oz.
Egg Yolk Powder		6 o	z.	Gelatir			6	oz.
Water	8	54 1	b.	Egg Yo	olk Powder		6	oz.
			4401	C _ 1	201/M T	7-1-1	1 0 1: 1	~

		14%	iat	38½% Total Soil	as
				Using Whole	e Milk
Butter	15	lb.	Butter	13	lb.
Skim Milk Powder 2	lb. 5	oz.	Skim N	Iilk Powder	3 lb.
Sugar 13	lb. 8	oz.	Sugar	13 lb. 8	oz.
Gelatin	6	OZ.	Gelatin		oz.
Egg Yolk Powder	6	OZ.	$\operatorname{Egg} \operatorname{Yo}$	lk Powder	oz.
Milk	$29\frac{1}{2}$	at.	$\mathbf{Milk}$	30	) qt.

<sup>\*</sup> Use sweet cream with 40% butterfat content.

		16%	fat	39½% Tota	l Solid	ls
		·		Using	Whole	Milk
Butter	17	lb.	Butter		15	lb.
Skim Milk Powder 7	lb. 3	oz.	Skim M	ilk Powder 8	lb. 6	oz.
Sugar 13	lb. 8	oz.	Sugar	13	lb. 8	oz.
Gelatin	6	oz.	Gelatin		6	oz.
Egg Yolk Powder	6	OZ.	$\operatorname{Egg} \operatorname{Yol}$	k Powder	6	oz.
Water	52	lb.	$_{ m Water}$		$26\frac{1}{2}$	qt.

#### Procedure

- 1. Dissolve milk powder in water. Add butter. Heat to 110° F.
- 2. Mix thoroughly sugar, dry egg yolk and gelatin powder.

3. Add to milk while stirring continually.

4. Heat to 145-150° F. Hold for 10 to 20 minutes.

5. Stir vigorously and pour into bowl.

6. Homogenize with nozzle nuts slightly loosened.

7. Cool immediately and put into ice box for 24 to 48 hours aging.

# Artificial Whipping Cream (Quantity 1 Gallon)

Heavy Cream	
Sweet Cream Butter	32 oz.
Shortening	20 oz.
Whole Milk Powder	12 oz.
Cold Water	72 oz.
Coffee Flavored Cr	eam
Butter	32 oz.
Shortening	20 oz.
Cold Water	72 oz.
Whole Milk Powder	12 oz.
Liquid Coffee Concen-	
trate	4 oz.
(Do not use coffee extr	act.)
Banana Cream	
Banana Cream Butter	24 oz.
	24 oz. 24 oz.
Butter Shortening Whole Milk Powder	
Butter Shortening	24 oz.
Butter Shortening Whole Milk Powder	24 oz.
Butter Shortening Whole Milk Powder Prepared Banana	24 oz. 6 oz.
Butter Shortening Whole Milk Powder Prepared Banana Powder	24 oz. 6 oz. 8 oz. 72 oz.
Butter Shortening Whole Milk Powder Prepared Banana Powder Cold Water	24 oz. 6 oz. 8 oz. 72 oz.
Butter Shortening Whole Milk Powder Prepared Banana Powder Cold Water Chocolate Crean	24 oz. 6 oz. 8 oz. 72 oz.
Butter Shortening Whole Milk Powder Prepared Banana Powder Cold Water Chocolate Cream Butter	24 oz. 6 oz. 8 oz. 72 oz. 1 24 oz. 20 oz.
Butter Shortening Whole Milk Powder Prepared Banana Powder Cold Water Chocolate Crean Butter Shortening	24 oz. 6 oz. 8 oz. 72 oz. 1 24 oz. 20 oz.

Whole Milk Powder 10 oz. Cold Water 72 oz.

Mocha Cream

Whip together chocolate and coffee cream—50:50.

#### Extra Heavy Cream

Butter	28 oz.
Shortening	24 oz.
Whole Milk Powder	16 oz.
Cold Water	72 oz.

(Use in hot weather and with fresh fruits.)

Dissolve milk powder in cold water using wire whip. Add the fats and heat to 145° F. Don't heat over 150°! Stir thoroughly before pouring mix into the machine bowl. Homogenize with nozzle nuts slightly loosened. Cool finished cream immediately with stirring. Store in cold ice box not higher than 40° for at least 48 hours before using. Whip the same as dairy cream. Sugar and flavor to taste.

The butter used in these mixes must be a pure sweet cream butter

which has not been neutralized. The flavor depends upon the butter used. Treat the finished product the way you treat a regular dairy cream.

Heavy Coffee Cream (Cut this with milk as usual) Formula No. 1

Milk
Butter
3 lb. 12 oz.
No. 2

Butter
3 lb. 10 oz.

Whole Milk

Powder 7 oz.

Water 5 lb.

Break butter into small pieces. Put into milk. Heat in double boiler to 140–145° F. Adjust valves to lowmedium pressure and homogenize.

To dissolve milk powder in water, use wire whip agitating briskly. Then follow procedure above. Always use cold water to dissolve milk powder.

Fudge Milk (10 Gallons) (3% Milk)

Cane Sugar 3 lb. 12 oz. Corn Sugar 3 lb. Chocolate Liquor

(Bitter Choco-

Powder

If desired, 1½ lb. of malted milk powder can be added to the mix and then only 5 lb. of skim milk powder should be used.

6 lb.

The mix may be made up with one pound of butter in place of 3½ lb. The mix then cannot be called a milk, it must be called a drink, e.g.

Chocolate Fudge Drink Fudge Malted Drink, etc.

Whip milk powder into cold water until dissolved. Break up butter into pieces and put into milk. Add sugar, gelatin, broken chocolate and heat to 140–150° F. Stir for ten minutes until everything has dissolved. Strain while pouring into machine. Homogenize at high pressure with valves one turn from the top.

Cream Neutralizers (For Butter Manufacture)

Formula No. 1	
Sodium Sesquicarbonate	100
No. 2	
Sodium Carbonate	65
Sodium Bicarbonate	35
No. 3	
Sodium Carbonate	80
Sodium Bicarbonate	20
No. 4	
Sodium Carbonate	55
Sodium Bicarbonate	45

Increasing Melting Point of Butter Butter, for use in hot climates, is mixed with melted glyceryl tristearate (an edible product), in various amounts, to increase its melting point.

Smoked Cheese in Sausage Casing
Use only processed cheese. Heat
cheese until an emulsion forms as in
processing for loaf cheese and then,
while hot, force through standard
sausage stuffer into the Visking No.
2x20-in. red fibrous casing. Chill until solid. Place in smokehouse and
subject to a hickory smoke for 48
hours at as low temperature as possible to obtain in smokehouse.

Remove from smokehouse and cool for 12 hours at room temperature.

If desired, the finished product may be wrapped in a decorative or trade-marked transparent sheet.

Also, a sharp, snappy natural cheese may be used instead of the processed cheese. In that case the cheese is cut up, ground through a ½-in. plate, and worked in the same machine as meat packers use for sausage or in a large vertical bowl type mixer and at the speed as used in creaming butter.

The natural cheeses are not heated as in the case of processed cheese but transferred from the sausage machine or mixer bowl into the stuffer. Stuffing, smoking and cooling procedure is same as when proc-

essed cheese is used.

The mechanically worked natural cheese may be made into 2- or 5-lb. loaves, held for 48 hours, cut into four pieces, smoked and wrapped. This product has good demand in eastern markets at present.

PROCESS CHEESE SPREADS Pimento Cream Spread Cream Curd from 6% Fat Milk lh. 252Pimento Through 5/16-in. Grinder Plate  $62\frac{1}{2}$  lb. Vinegar-Sugar Solution 40 lb. Gum Paste 31 lb Salt 5 lb. Cheese Color 6 OZ. Cayenne Pepper 1½ oz. Sugar (Granulated) lb.

Mix thoroughly before putting into cooking kettle. Heat to 170° F. Run through filling machine into sterilized glass containers of desired capacity. Use of emulsifier optional. If used, emulsifiers are: Sodium ci-

trate, 1%, or di-sodium phosphate, 2%, calculated on weight of batch mix.

Relish Spread		
Cream Curd from 6%		
Fat Milk	250	lb.
Sweet Pickle Relish	60	lb.
Vinegar-Sugar Solu-		
tion	40	lb.
Pimento (Through an		
½-in. Grinder Plate)	27	lb.
Condensed Whey or		
Whey Powder Plus		
Water	30	lb.
Gum Paste	40	lb.
An amulaifion may be u	ood.	2022

An emulsifier may be used; some operators prefer its use, some do not.

Mix constituents thoroughly, heat to 165° F. or slightly higher, depending upon flavor desired, and run through filling machine into sterilized glass containers of desired capacity.

Limburger Cheese 180 lb.
Cream Curd from 6%
Fat Milk 60 lb.
Water 10 lb.
Disodium Phosphate 10 lb.
Salt 2 lb.

Limburger Cheese in Glass

Mix thoroughly and heat to 174° F. Run through filling machine into sterilized glass containers of desired capacity.

Preferred way to cook limburger cheese to assure good spreading consistency is to use 80 lb. of soft smooth limburger, 40 lb. of a firm cheese but with a sharp limburger flavor and 60 lb. of limburger with a "clean" but slightly "off" flavor.

Put 70 lb. of this limburger mixture in cooking kettle with steam turned on and heat with stirring until fat begins to separate sufficiently to give a slight glistening appearance to the cheese which pulls together to form a mass.

Add 5 lb. of the phosphate and 1 lb. of the salt, with continued heating and stirring. Add another 40 lb. of the limburger mixture and stir until mass is smoothed out. Add 30 lb. of the cream curd and stir until smoothed out. Add remainder of limburger mixture. Heat and stir until smooth before adding the remaining 5 lb. of phosphate, 1 lb. of

salt and 30 lb. of cream curd.

Caution: After the first charge of cheese is put into kettle, additions of more than 60 lb. should not be made. Also, subsequent additions should not be made until the charge in the kettle has been thoroughly smoothed out by gradual heating and constant stirring by the mechanical agitator in the cooking kettle. The procedure followed in building up the batch in the kettle may be varied according to the operator's experience and the particular properties desired in the finished limburger cheese mixture.

Special "Sharp" Spread American Cheddar

Cheese (Smooth)	340	lb.
Salt	$2\frac{1}{2}$	lb.
Disodium Phosphate	6	lb.
Condensed Whey	84	lb.
Water	40	lb.

If needed to firm up the batch, 1 to 2 lb. of sodium citrate or of sodium metaphosphate may be added.

Cheese Color, To suit

The American cheddar cheese should be partly broken down. One-half should be of clean flavor and aged.

Add cheese to heated kettle slowly

as in making the limburger product. Add 15 lb. of the water at start. Do not add the condensed whey until after the batch has been heated to about 135° F.

Finish by heating to 160° F. and packaging in containers other than glass. Make into packages similar to those of processed cheeses.

"Supply" Type Cheese

Aged cheese is used. It should have a pleasing nutty flavor, be not too firm nor too soft in texture. Color is of no consequence unless finished product is to be designated as a "white" cheese.

Cheese	491	lb.
Salt	5	lb.
Sugar	4	lb.

If a high-acid cheese is used, molds will grow more rapidly than if a low-acid or neutral cheese is used, particularly in the case of the 4-oz. ground-cheese package. Also, the low-acid cheese permits whipping in of as much as 3% water. Development of mold growth can be checked largely through the use of propionic acid or its salts.

The cheese used is first cleaned and ground, as in the making of processed cheese, through a 3/32- or ½-in. plate. It is then placed in a sausage machine or an upright bowl and beater-type mixer, and salt, sugar, color, other seasoning and water are added, if used. Mix thoroughly preparatory to second passage through grinder in which the perforated plate has been replaced with a funnel of predetermined shape and size to give desired extrusion cross section.

As the helical screw in the grinder forces the ground mixture through

the funnel, it is caught on a strip of paper of required width which reels off a roll as the extruded mixture forces the paper strip over a roller conveyor about 6 ft. long.

The paper supports the extruded cheese until it is cut into desired length and put on trays for transfer

to cooler or chilling room.

#### Caciocavallo Cheese

The manufacture of this cheese is peculiar to southern and central Italy; but today it is manufactured in the northern part and on the island as well.

The quality of the taste and its convenient shape make this cheese popular with both Italians and foreign consumers. It is made by a mixture of skimmed evening milk and skimmed morning milk. Sometimes cow's milk mixed with sheep milk is used.

Coagulation: The milk is allowed to coagulate at 35° C. (95° F.) in a tub or pail using as much rennet as may be necessary to complete the coagulation in about half an hour.

Breaking: When the mass has reached the proper consistency, it is broken with a sort of ladle and then with a buckler (harp) into particles, about the size of a hazel nut, which are allowed to settle at the bottom of the container.

In the meantime, the whey is gradually separated until the mass, having been exposed to the air, collects itself and is compressed somewhat with a stirrer. It is then covered with hot whey and left until matured.

Maturation is complete when a piece of the mass, having been immersed in boiling water, stretches out into a smooth elastic thread, and the milky whey from which the mass came has a value of 6.5 to 8 (Soxhlet), .14 to .18 acidity.

At this point the milky mass is sliced and placed into a tub over which boiling water is poured. In this way, the slices merge into an elastic mass which is made uniform by continued pressing and stretching by hand through the use of wooden spatula. Finally it is pulled into one long cord which, in turn, is subdivided, into pieces about 3 kg. (6½ pounds).

A very convenient kneader has been devised to prepare the curd for this cheese. Every piece is reduced to a sort of clew \* which is left in hot water and is then worked into a

solid sphere without folds.

Shaping the form: This operation, which can be carried out only by one who has had a long experience in this type of work, is called "closing of the curd." This closing gives the cheese its characteristic long fusiform appearance with a sort of "neck" at one end. Then, placing it in a tin form † or on a short piece of linen, so that it does not lose its shape, it is cooled in cold water.

Salting: As soon as the cheese becomes cold, it is transferred to the brine basin where it stays for three days. After this, the cheese is taken from the brine and each piece of cheese is tied individually by a vegetable string at the head. They are later hung up in pairs on loomed poles ‡ near each other in a dry

\*This has reference to a ball, as of

† Refers to a piece of iron which has been tinned over.

‡ Poles with linen forms hanging from them.

chamber at 15 to 18° C. (59 to 64° F.). During this seasoning, this cheese receives no care other than oiling it and cleansing it of greenish molds which cover it. Then the cheese will become yellowed by a smoking process.

Ripening: It matures in from 10 to 12 months and weighs from 1.5 to 2 kg. (3.3 to 4.4 pounds).

Yield: One hundred liters (about 200 pounds) of whole milk yield 8 kg. (17.6 pounds) of fresh cheese and 7 kg. (15.4 pounds) of ripened cheese.

From this work a very rich whey is left which furnishes a good quality to the skim milk. Caciocavallo is a product which is indicated particularly for grating purposes having the quality of resisting the heat of Summer which is so destructive to most cheeses.

This type of cheese rarely swells but when it does, it is so violent it goes so far as to crack the entire form.\*

Such extraordinary action is attributed to butyric fermentation which occurs when the fermenting whey of the curd is substituted for the whey heated to 80° C. (176° F.), which is intended to soften the curd especially when it is made with milk that has been skimmed too much.

Under these latter conditions, the vegetative bacterial cells are killed, leaving the spore-forming bacteria which cause butyric fermentation.

It is easy to discover the existence of this fermentation when having pierced the form of cheese with a needle and bringing a lighted match close to the hole, the escaping hydrogen gas lights.

To avoid this, the temperature of the whey, which is used to hold the curd in a hot bath, must never exceed 50° C. (122° F.).

#### Provolone

Provolone, like the Caciocavallo, originated in southern Italy and Sicily and its manufacture is identical with that which has been described for Caciocavallo. The only difference lies in the fact that the forms are spherical or oval and that whole milk is used. It is a table product (used for eating and not grating purposes) being highly esteemed for its tenderness and butyric quality.

Yield: 10 kg. (22 pounds) of this cheese are obtained from a corresponding 100 kg. (220 pounds) of fresh milk. This 10 kg. (22 pounds), when it is ripened, is then reduced to around 8.7 kg. (19.1 pounds). Each form weighs from 2 to 4 kg. (4.4 to 8.8 pounds).

#### Provole

Originated in Calabria and Sicily, these cheeses are manufactured from wild ox or buffalo milk by means of a process similar to Mozzarella.

As soon as the milk is drawn, it is coagulated with lamb or goat rennet. The coagulated mass is broken coarsely and let set till the particles become settled to the bottom of the container, then the container is covered or sealed. Afterwards the cheese mass is raised, sliced, and thrown into a bucket containing nearly boiling water or whey. In short time, the curd becomes tender and soft and at this point it is manipulated, re-

<sup>\*</sup>A complete piece of cheese is referred to as a "form."

ducing it into small spherical pieces of 1 kg. (2.2 pounds) weight which are then transferred to brine where they are kept for about a day, after which they are ready for consumption.

#### Pecorino Romano

This is the only unique type of sheep milk cheese which belongs distinctly to Italy. It gets its name from the Roman fields where it is produced on a large scale and from where it is exported. Today, its manufacture is extended through southern Italy and into Sardinia.

It is manufactured in a sort of cottage or barn built with poles and straw, using the following utensils:

1. A copper kettle or boiler.

2. "La chiova"—a long ruler-like piece of wood used for stirring.

3. "Cascine"—woven forms for soft cheese—made by weaving willows or twigs.

4. Cheese table or platform for

working cheese.

The milk, as soon as it is drawn, is taken into the barn or hut and strained through a linen cloth stretched across the kettle. Then it is heated to about 38° C. (100° F.) and a paste of rennet is added, which is made from dried baby lamb stomachs cut up and kneaded in brine.

Coagulation: The coagulation should take place in 15 to 20 min-

utes.

It is left to harden further for 10 to 15 minutes, after which it is broken with the "chiova."

It is cooked for 15 or 20 minutes, constantly stirring the particles (using the same device) and raising the temperature to 50° C. (122° F.). The kettle is removed from the fire

and is left to allow the curd to settle for 10 to 15 minutes until it is gathered at the bottom in a mass.

In the meantime, some pails of fresh water are poured into the kettle to lower the temperature of the whey.

Then the cheesemaker very carefully compresses the cheese at the bottom of the kettle, turns it over, and continues the pressing on all sides. In doing this, always working under the whey, with a string he cuts the mass in one or more pieces and turns them over to his assistants, to be kneaded in the forms on the table.

Molding the cheese: The cheese is pressed in the forms, to overflowing, in such a fashion as to make a great part of it rise over the rim of woven mold. This becomes manipulated, by hand, into a sort of cone shape. This is worked until the vertex of the cone is flush with the rim of the form. The whev, meanwhile. is being squeezed out of the cheese and trickles out through the openings on the side of the form. From these same holes, punctures are made in various directions into the mass to let out as much whey as possible. In the meantime, the cheese is still under hand pressure. This operation is called "friction" and lasts around one-quarter hour. The pressing is continued for 20 minutes with much care and skill in order to eliminate all perforations and make the mass entirely solid.

Salting: After two days, the salting is begun, in the salting rooms or chambers, by applying dry salt abundantly. During the salting operation, the cheese is removed from the form and deposited on a

sort of stone trough and then, after a few days, they are transported to a wooden table, situated near the same place. Every other day, they are turned over and rubbed with fresh salt and placed in piles of twos or threes. The salting period lasts around two months.

From the salting chambers, the cheeses pass into the ripening rooms where they are immediately scraped and cleaned.

The only cure which they then receive is turning over and a rubbing by hand (comparable to massaging).

The cheeses are properly ripened in one year.

Yield: 100 l. (200 pounds) of milk yield 20 kg. (44 pounds) of fresh cheese which, during ripening, become reduced by 18 to 30% or to about 16 to 17 kg. (35.2 to 37.4 pounds). Each form is from 12 to 14 cm. (4.8 to 5.6 inches) high with a diameter of 24 to 26 cm. (9.6 to 10.4 inches), and weighs on the average 7 kg. (15.2 pounds).

The whey, remaining after the process, is of milky appearance and is highly esteemed in the Roman country for its high residual of albumin and fat content which makes possible a 10 to 12 kg. (22 to 26.4 pounds) yield of ricotta of a fine and delicate quality.

American Formulae for Provolone Type

A liquid smoke can be used to produce a fine smoked cheese of the American or Provolone type. It is essential to add the liquid smoke directly to the milk. It cannot be added to the curds; and there is no special advantage in adding it to

the whey directly after cutting the curd. There is no way of determining the traces of liquid smoke which remain in the curd. The practice in no way affects the healthfulness of the cheese. However, any one contemplating using it should determine its legal status as used in cheese that is to be consumed in the state, or that enters the interstate trade channel.

0.07% of liquid smoke, three-fourths of a pound per 1000 pounds of milk, added to the milk is sufficient.

The milk for the Provolone type is prepared by mixing three parts of whole milk with two parts of skim milk by weight. 1% of culture, and 1½ ounces of color, and six ounces of rennet are used per 1000 pounds of milk. The setting temperature is 86° F.

After cutting, the curd is cooked to 94° F. in 40 minutes, and to 108° F. in 10 more minutes. The curd is then cooled from 108 to 94° F. in about 45 minutes and allowed to mat over night. The following morning the curd is soaked in 120° F. water for 30 minutes. The salting rate is 2.5 on the curd weight basis. The cheese is rubbed freely after making. The cheese is made in regular Young American hoops to give a cheese weighing eight pounds.

American Romano Type

Romano type can be made from whole milk with  $2\frac{1}{2}\%$  of starter. When the acidity reaches .20 to .22 and the temperature 86° F.,  $2\frac{1}{2}$  ounces of rennet per 1000 pounds of milk are added. After 25 minutes the curd is cut as in American cheesemaking.

The curd is cooked from 86 to 110° F. for 40 minutes, and held until properly firmed. This can be guided by a whey acidity of .3.

The drained curd is salted at the rate of 1½ pounds per 1000 pounds of milk. The cheese is hooped and pressed with cloths in the hoops for 24 hours. After three days, and again after seven, the cheeses are rubbed with salt. As the cheeses tend to dry they are also rubbed with a neutral oil.

American Style Process Cheese Green (Young) 5½ Cheddars Cheddars Sharp (Aged) Cheddar Cheddars 1 Skim Milk 1/4 Cheddar Cheddars Salt 3 lb. 2 lb. Sugar Disodium Phosphate 13 lb. (Anhy.) Water4 gal.

Dissolve the salt, sugar, and disodium phosphate in the water. Slowly add the cheese, ground medium fine, to the above solution at 170° F. with constant stirring until uniform and smooth. Pour into box molds.

Romano Type Pro	cess (	Cheese
Green (Young)		
Cheddars	$1\frac{1}{2}$	lb.
Sharp (Aged)		
Cheddars	2	lb.
Sbrinza Cheese	2	lb.
Monterey Cheese	1/2	lb.
Salt	1	07.

Disodium Phos-		
phate		
(Anhy.)	2	oz.
Water	20	fl. oz.

Prepare in the same manner as American Style Process Cheese.

Quick Curing Cheddar Cheese By following the method described, a good marketable cheese can be made from milk which contains a low, medium or high percentage of acidity. Low acidity ranges from 0.17 to 0.21%; medium, from 0.22 to 0.23%; overripe, 0.23 to 0.24%, and high, from 0.24 to 0.30%.

The procedure in the case of milk whether low acidity or high, is the same up to a certain point in all cases. After the milk has been put into the cheese vat, 5% of a good active starter is added, followed immediately by the addition of the usual amount of rennet.

The coagulation of the milk occurs within a short or long period, depending on the acidity of the milk at the time of adding the rennet. The curd is cut into cubes, about  $\frac{3}{8}$  of an inch, immediately after the milk has coagulated firmly.

The acid test of the first whey that separates out, in the case of the low acid milk .2, would be approximately .12, and in the case of milk with an acidity of .23, the first whey would be .15, and, in every case, the whey would test approximately 8 points less than the milk.

The first whey from milk containing 0.3% acid would test 0.22.

Whey must be removed when its acidity is approximately 0.175%. Slightly higher acidity (for instance, .18) would make little difference.

but .18 would be about the limit of the whey acidity that could be allowed.

The addition of water at the time of cutting the curd should be in such quantity as to lower the acid content of the whey in all cases to near .12. The addition of water later on should be with the idea of having the whey acidity approximately 0.175 when drawn. After drawing the whey the curd is piled and milled, etc., not different from the procedure in the case of cheese made by the process now in common use.

In making cheese for the market by the procedure outlined above, all steps in processing the milk are shortened. The average time taken for the milk to coagulate is little if any longer than half the time usually required. The curd is cut as soon as it is firm enough, and this is left to the judgment of the cheese maker.

> Improved Cream Cheese Cream Cheese 35% Fat

Standardize cream to contain 12% fat.

Pasteurize at 150° F.; homogenize at 1500 single stage.

Cool to 70° F.; add 1% starter. Let set overnight to develop .7% acidity.

Cut with cheese knives and cook to 110-115° F.

Drain on cloth racks for about an hour.

Test cheese curd for fat and moisture.

Calculate amount of cream and water to add to give 35% fat and 55% water.

Put water and cream in vat.

Calculate amount of salt using .75%.

Calculate amount of gum using .25%. The gum should consist of mixture of equal parts of locust bear gum, Irish moss, and gum Karaya.

Mix salt and gum together and sieve onto the cream while agitated (gum and salt may be mixed in part of the cheese).

Start heating and add cheese curd. Pasteurize to 160° F.; homogenize at 2500 single stage.

Package while hot.

Precautions: It is best to have the cheese curd tested for fat percentage desired in the finished cheese so that excessive quantities of cream or water need not be added. The cheese curd is made most fluid by added water. Too high a water content makes a sticky, soft cheese. Also low fat and high gum content makes a sticky cheese.

It is best to add no extra skimmilk solids to the original milk, skimmilk, and cream from which the cheese curd is made.

The lower the cooking temperature of the milk the easier the cheese curd melts down. Low homogenization pressures of the milk promote fat drainage but too low a pressure increases losses of fat in the whey. The whey should test below .2%.

Any tendency toward moisture drainage in the cheese can be prevented by increased amounts of gum.

The boxes should be inverted when the cheese is cooling. If the cheese has shrunk too far from boxes, the hot cheese mixture may be cooled to 140° F. before homogenization to reduce shrinkage in volume due to cooling.

Formula for 250 Gallon Batch
Milk test 3.5%; cream test 55%.
Cream 354 lb.
Milk 210 gal.

Cheese curd yield Water and cream 700–720 lb. 175

875 lb. cheese

Salt  $6\frac{1}{2}$  lb. Gums 2.2 lb. or 35.2 oz. made up of

Irish Moss12 oz.Karaya Gum12 oz.Locust Bean Gum12 oz.

Cream Cheese 25% Fat

Standardize milk to contain 6% fat.

Then proceed as given for 35% fat cheese except that cheese is to test 25% fat and 60% water and .5% gum is to be used. The milk should be cooked about 5° lower.

Formula for 250 Gallon Batch Milk test 3.5%; cream test 55%. Cream 104 lb. Milk 238 gal.

Cheese curd yield 630–650 lb. Water and cream 155

785 lb. cheese

Salt 6.0 lb.

Gums 3.9 lb. or 62.4 oz. made up of

Irish Moss21 oz.Karaya Gum21 oz.Locust Bean Gum21 oz.

Mold Control in Cheese Making Simple means of mold control are now in use in the cheese industry. Washing of walls, ceilings and shelves with a 10% copper sulphate solution, or a 5% borax solution, has been of great aid. Likewise, cheddar cheeses can be dipped in a 5% borax solution before being paraffined. Or, if the paraffin is agitated during dipping, the borax can be added directly to the paraffin. This not only controls molds, but also prevents fungus or rind rot from developing.

It has also proved possible, in mixing water paints or cement coatings for cheese rooms, to substitute 10% copper sulphate solution for the water. Whether such a paint is used or not, walls and ceilings should be well made and kept well painted. Every possible effort should be made to keep foreign matter and mold from walls and ceilings.

If condensation on the ceiling is hard to control, then the ceiling should be washed more frequently, with the 5% borax solution. In any case, walls and ceilings should be washed at regular, frequent intervals with borax solution, after being first scrubbed with soap and water.

Borax should be spread on floors that are washed and kept dry.

### SMOKED POULTRY

Birds for production of smoked poultry should be killed by piercing the brain and bleeding, followed by any method of picking which will cause a minimum of injury to the skin surface of the bird. In drawing, great care should be taken to avoid rupturing the intestines and subsequent contamination of the body cavity with the intestinal contents. The deposition of large numbers of microorganisms in the body cavity, which may later cause off-flavors and difficulty in the pickling process, is thus prevented.

Following evisceration, it is well to wipe out the body cavity with a paper towel. This tends to absorb any leakage or excess moisture which may remain. A better cure in the pickle as well as a more thorough smoke is obtained if the bird is split down the back before immersing it in the pickle. From a sales standpoint the halved bird is an added advantage, since if it seems desirable to sell either a whole or a half bird, the quantity in each part can be controlled.

Poultry Pickling	Solution
Water	5 gal.
Salt	4 lb.
Sugar	30 oz.
Celery Oil	8 cc.
Black Pepper Oil	8 cc.
Parsley Leaves Oil	8 cc.
Sage Oil	5 cc.
Thyme Oil	5 cc.
Marjoram Oil	5 cc.
Bay Leaves Oil	6 cc.
Sweet Basil Oil	6 cc.
Coriander Oil	5 cc.
Cardamon Oil	5 cc.

These oils are dissolved together in 200 cc. of ethyl alcohol. To prepare 5 gal. of pickle, 4 lb. of salt and 30 oz. of sugar are used. Twentytwo cubic centimeters of the alcoholic solution of essential oils is added to a small amount of the sugar, together with about one gram of gum tragacanth, and the whole thoroughly mixed with a mortar and pestle. The remainder of the sugar and salt is dissolved in 5 gal. of water to which the essential oilsugar-tragacanth material is added slowly with constant stirring. Properly prepared, the pickle should have a cloudy appearance.

Meat Curing Br	ine	
Sodium Chloride	3	lb.
Granulated Sugar	4	oz.
Sodium Nitrate	2	oz.
Sodium Nitrite	1/4	oz.
Enough for 100 pound	ds of	meat.

Meat and Vegetable Stew				
Army Ration C				
Beef	50	lb.		
Potatoes	15	lb.		
Or Dehydrated				
Potato Cubes	3	lb.		
Carrots	15	lb.		
Dry Beans	8	lb.		
Tomato Juice or				
Pulp	12	lb.		
Salt	14.5	oz.		
Pepper, Black	0.5	oz.		
Celery Salt	5	oz.		

The beef component shall be based on the weight of the raw beef before braising. If fresh (unfrozen) beef is used, it is to be ground in a meat grinder fitted with a plate having holes approximately 34 in. in diameter. If beef is frozen the holes will be approximately 1 in. in diameter. In lieu of grinding, the beef may be diced in cubes approximately 1/2 in. in diameter. Beef shall be braised until medium well done, with only enough added moisture to prevent scorching. All juices from the meat shall be included in the product.

The potato component shall be based on the weight of the peeled, trimmed and diced potatoes. These shall be cut into cubes of approximately 3% in. The dehydrated potato cubes, when used, shall be based on the weight of the dehydrated potato cubes. Dehydrated potato cubes shall be reconstituted in water before use.

The carrot component shall be based on the weight of the cleaned and diced carrots. These shall be diced into cubes of approximately  $\frac{3}{8}$  in.

The bean component shall be based on the dried beans before

soaking.

Beans in the finished product shall be whole, separate and tender, shall not be mashed or pasty, but the

skins may be split.

The braised beef, diced carrots and potatoes, soaked beans, tomato juice or pulp, and spices shall be thoroughly mixed. Water may be added, if necessary, to bring the moisture of the finished product within the prescribed range. After thorough mixing, the product shall be filled into tin cans, size 300 x 308. If solids and juices are separated for convenience in canning, they shall be placed in cans in proper proportion. The filled cans shall be exhausted, sealed and processed. Moisture content of the finished product shall be not less than 72% and not more than 76%. Net contents of the cans shall not be less than 12 oz.

Genuine Dill Pickles

Remove head from a thoroughly cleaned and washed barrel.

Throw in handful of dill weed, put in from 5 to 5½ bu. of cucumbers, and spread about 1 lb. of dry spices on top of cucumbers.

Replace head of barrel.

Lay barrel on its side, remove the bung and fill with 32 to 35 salometer brine. The brine will likely vary in salt content in different parts of the country.

Permit fermentation to proceed

and replace lost brine daily. Fermentation will usually be complete in about 10 days in regions having warm weather.

After fermentation ceases, the bungs are replaced and the barrel of pickles stored in refrigerated warehouses if they are to be kept in stock. Sometimes they are held for a year.

During the elapsed time the brine slowly dissolves some of the oil from the dill weed and brings it in contact with the outside of the pickles from where it may eventually penetrate into the pickle.

> Use of Spice Oil to Replace Dill Weed

By using an emulsion of dill weed oil, the flavoring of the pickles will take place in a considerably shorter length of time.

From the beginning, the emulsion will impart a dill flavor to the brine. As the brine penetrates into the cucumber during fermentation, the dill flavor will also be carried in and with probably deeper penetration than is the case when the dill weed itself is used.

At one time genuine dills did not contain any flavor other than that of dill weed. Today many packers use spices to get variations in flavor. In such instances spice oil emulsions can quite readily be used instead of the dry spices that may be added. Care must be taken not to overflavor. After the amount of spice oil needed has been calculated on the basis of dry spices used, the quantity used should be half of the calculated amount. The spice oils are more quickly available to the pickles than when dry spices are used.

Mixed Dill Pickle Spices

Mix well the following materials: cinnamon saigon broken and sifted 30 lb., whole clove 27 lb., whole allspice 27 lb., small red chili peppers 8 lb., and unbroken bay leaves 8 lb.

#### Dill Pickle Flavor

A satisfactory emulsion or colloidal suspension is made by grinding  $3\frac{1}{2}$  oz. of dill weed oil with 1 oz. of a gum emulsifier in a mortar with a pestle and by making up to 1 pt. with water and vigorous stirring. Beating for a few minutes with an egg beater helps. Two ounces of the emulsion flavors one barrel of pickles carrying 15 to 18 gal. of brine.

Other methods used to get dill weed oil into brine include: (a) using ethyl alcohol as a solvent, (b) using salt or sugar as a carrier. One pound of dill weed oil made up to 1 gal. with the alcohol may be used on the basis of 2 to 4 oz. of the solution to 15 to 18 gal. of brine; enough for 1 bbl. of dill pickles. Or ½ oz. of the dill weed oil mixed thoroughly with 1 lb. of salt or sugar will flavor a barrel of dills.

Keeping Pickles Green

Several factors seem to govern the retention of a fresh green color in pickles. One is to allow plenty of time for the preliminary soaking in salt water, as it seems that "short-cut" methods have a tendency to spoil the color. Soft water should be used in making pickles when possible, as the substance in hard water seems to darken the color.

Some recipes call for alum, and this is to make them crisp and green—but while this is not absolutely injurious, it is not recommended as a general practice.

Hydrated or powdered lime may be added to the solution used in pickling to increase the green color.

Free Flowing Salt	
U. S. Patent 2,288,409	
Magnesium Carbonate	40
Calcium Stearate	1
Salt	359

Vinegar-Sugar Solution
Cider Vinegar 3 lb.
Sugar, Granulated 2 lb.
Warm and stir till dissolved.

Warm and stir till dissolved. Artificial Cinnamon Cinnamaldehyde (96%) 3-4% 4% Eugenol Powdered Almond 100% Shells. To make Curry Powder, Indian Type 4 oz. Coriander 4 oz. Tumeric 2 lb. Cinnamon 8 oz. Cayenne 1 lb. Mustard 1 lb. Ginger 8 oz. Allspice 2 lb. Fenugreek

All ingredients should be dry. Grind to fine powder and sift through a fine-mesh sieve. Mix thoroughly. Package in airtight, moisture-tight container to avoid loss of flavor.

Spice Essential Oil Equivalents \* Equivalent quantity Quantity of spice of essential oil Dry Spice Spice 100 lb. Allspice ..... 100 lb. Almond, bitter .... 100 lb. Bay leaves ..... 2 1 1/2 lb. 100 lb. Black pepper ..... Oleoresin 100 lb. Black pepper .....

\*When compared with best grade of dry spice.

				1
		Em	iivai	lent.
0 4		-	anti	
Quanti	ıy			
of			spic	
Dry Spr	ice Spice	esse		
100 lb.	Angelica root		$\frac{3}{4}$	lb.
100 lb.	Angelica seed	1		lb.
100 lb.	Anise star (Chinese)	3		lb.
100 lb.	Basil, sweet		2/5	OZ
		2		lb.
100 lb.	Calamus root		/2	lb.
100 lb.	Caraway seed	5		- 1
100 lb.	Cardamom seed	5		lb.
100 lb.	Carrot seed	$^{2}$		lb.
100 lb.	Cassia cinnamon	1		Ib.
100 lb.	d	Ole	oresi	n
.di 001	Capsicum	8		lb.
100 lb.	Celery seed	3		lb.
100 lb.	Cinnamon, Ceylon.	1		lb.
	Chinamon, Ceylon	17		lb.
100 lb.	Cloves	17	1/	
100 lb.	Coriander seed		$\frac{1}{2}$	lb.
100 lb.	Cumin seed	3		lb.
100 lb.	Dill seed	3	$\frac{1}{2}$	lb.
100 lb.	Dill weed		1/2	lb.
100 lb.	Estragon		1/2	lb.
100 lb.	Fennel seed	5	12	lb.
100 10.		_	i a.	
100 lb.	Garlic	Imi	ь. па	- 1
		4		oz.
100 lb.	Ginger	Ole	oresi	n
100 10.	-	10		!b.
100 11	77 11.1	Imi	t. fla	vor
100 lb.	Horse radish	. 1		oz.
100 lb.	Laurel leaves (dis-	( -		٠
100 10.		2		lb.
100 11	tilled) (bay leaves)	4	1/	
100 lb.	Lavage root		$\frac{1}{2}$	lb.
100 lb.	Mace	12	$\frac{1}{2}$	lb.
100 lb.	Marjoram, sweet		$\frac{1}{2}$	lb.
100 lb.	Marjoram, wild	2		lb.
100 lb.	Mustard seed		3/4	lb.
100 lb.	Nutmeg	19	1/2	lb.
	~	(Imi		
100 lb.	Onion	, .	t. Ha	1
		4		oz.
100 lb.	Paprika	Ole	ores	ın
_00 10.				
100 lb.	Parsley seed	` 3		lb.
100 lb.	Pimento berries	3	1.2	lb.
100 lb.	Sage	2	-	lb.
100 lb.	Thyme	$\bar{2}$		lb.
	Valerian root	1		lb.
100 lb.	valerian root	1		ID.
	Marronnoise			
	Mayonnaise			. 1
	Formula No. 1			- 1
Foo	Yolk (Fresh			7
		=	11-	
01	Frozen) 1.	-	lb.	
Sug	ar	3	lb.	
		$1\frac{1}{4}$	lb.	
				4
Salt		1	lb.	

Paprika	3/2	lb.
Pepper (White)	1	OZ.
Oil (Salad)	12	gal.
Vinegar (100 Grain,		
White)	4	qt.
Water	2	qt.

Beat the yolks at high speed until they are thoroughly broken, which may require about one minute.

Now add the sugar, salt and spices and beat for another 2 to 5 minutes until the mixture is well creamed.

Now start adding the oil slowly, at the rate of a gallon per minute, until 8 gallons have been added. Change the speed of the beater to first speed while adding one quart of vinegar and one quart of water; the mixture should be thoroughly agitated. Turn the beater on high speed and add the remainder of the oil at the rate of one gallon every two minutes. Then shift the beater to slow speed and add the remainder of the vinegar and water.

The beater should now be shut off to scrape down the sides of the bowl. Then mix the entire batch at slow speed for at least another two minutes taking care not to overbeat which tends to make the mayonnaise thin.

No. 2		
Egg Yolk	5	lb.
Oil	$2\frac{1}{4}$	gal.
Vinegar (45 Grain)	$1\frac{1}{4}$	qt.
Sugar	10	OZ.
Mustard Flour	4	OZ.
Salt	6	oz.
White Pepper	$\frac{1}{2}$	OZ.
Paprika	$\frac{1}{2}$	OZ.
No. 3		

U. S. Patent 2,264,593 Egg Yolk 120 Cottonseed Oil 330 Spice and Salt Mixture 24

Cider Vinegar (45 Grain) Monochloracetic Acid	160
Salad Dressing Formula No. 1	s
-	340 g.
Whole Egg	320 cc.
Vinegar	80 cc.
Water	44 g.
Salt	40 g.
Sugar	16 g.
Mustard	3160 cc.
Oil No. 2	3100 00.
Oil	1420 cc.
Egg Yolk	200 g.
Vinegar (6% Solu-	
tion)	174 cc.
Mustard	20 g.
Salt	15 g.
Sugar	50 g.
Water	121 cc.
No. 3	
Corn Starch	90.0 g.
Tapioca Flour	20.0 g.
Sugar	152.0 g.
Vinegar	152.0 g.
Salt	31.0 g.
Mustard	12.5 g.
	3.0 g.
Pepper Egg Yolk	100.0 g.
Water	455.0 cc.
Cottonseed Oil	830.0 cc.
Add cold water to	
to 184° F., mix until	it cools to
120° F.; add spices,	vinegar and
sugar; cool to 90°; th	en add egg.
Pour oil in slowly and	homogenize
the mixture.	
No. 4	
Corn Starch	110.0 g.
Tapioca Flour	25.0 g.
Sugar	152.0 g.
Tri a man	152 0 g

152.0 g.

31.0 g.

12.5 g.

Vinegar

Mustard

Salt

Pepper	3.0 g.
Egg Yolk	125.0 g.
Water *	540.0 cc.
Cottonseed Oil	700.0 cc.

	<del></del>
Salad Dressing (Nor	n-Fattening)
Water (1080 cc. fo	r
Agar, 1800 cc. fo	r
Starch)	2880.0 cc.
Agar	48.5 g.
Starch	142.5 g.
Pepper	.5 g.
Saccharine (10% So	
lution)	7.2 cc.
	28.5 g.
Mustard	
Vinegar (5% Solu	
tion)	513.0 cc.
Paprika	5.0 g.
Gum Tragacanth	28.0 g.
Mineral Oil (Visco	s-
ity 175–185)	1995.0 cc.
Turmeric	2.0 g.
Combine the ingre	
Compile one mgr	oonigo
order given and home	gemze.

Dried Fruit Bars	
Formula No. 1	
Fig Paste	3
Prunes, Pitted	3
Apricots, Dried	3
Honey or Heavy Invert	
Syrup	1
No. 2	
Fig Paste	3
Apricots, Dried	6
Honey or Invert Syrup	1
No. 3	
	3
Fig Paste	3
Apricots, Dried	$\tilde{2}$
Raisins, Ground †	~

\*200 more cc. of water are added during homogenizing; aside from this, procedure is as above.

† Preferably seeded Muscat, these may be replaced by dates of high invert sugar content. The average moisture content must be below 20% in the finished

product.

Grind the fruit, mix, then regrind. Extrude in a sausage machine fitted with a rectangular opening. Cut to desired size. Wrap in moistureproof cellophane, then again in heavy cellophane. Heat in air until the centers of the bars are at 140° F. Cool in air. For Army use pack in insectproof containers such as 5-gal. cans.

## Dried-Fruit Cereal

Ground Dried Fruit	100 lb.
Corn Sugar	100 lb.
Wheat Bran	50 lb.
Whole-Wheat Flour	100 lb.
Salt	3 lb.
Baking Powder	3 lb.

Mix all ingredients except baking powder with water to give the desired consistency. Then mix the baking powder in quickly and make the dough into loaves. Dust with whole-wheat flour and place in pans greased with nonrancidifying fat and bake to about 410° F. The loaves are then sliced and the slices are dried bone dry on trays in a dehydrator. These are then coarsely crushed, screened to uniform size, toasted a short time at 300° F. and packed in attachment line, paraffin wrapped cartons.

## Fruit Preserve Thickener

Corn Sugar	35
Cane Sugar	25
Vegetable Gum (Galagum)	40

Fining or Clarifying Powder for Fruit Juices

Tannic Acid  $1\frac{1}{4}-1\frac{1}{2}$  oz. Gelatin  $1\frac{1}{2}-6$  oz.

Use the above amount for 120 gal. fruit juice.

## Sulphured Fruits

To produce the solution of sulphur dioxide used in preserving the fruit, the following method may be followed: Place on a scale a barrel containing 378 lb. of water. Run sulphur dioxide gas, which must be free from arsenic, into the water through a laboratory tube. This is continued until enough gas has been dissolved to bring the weight of the contents of the barrel to 400 lb. Specific gravity of the solution should be 1.025 or upwards. The water should be as cold as possible, and the gas must be fed in gradually. Six to 10 hours are usually required to obtain a solution of the required strength.

Generally speaking, the fruit is prepared for preservation by this process by the same methods as for

canning or cold packing.

Weighed quantities of this prepared fruit are placed in the pulping tank. (If a jacketed kettle or cooker with closed coils is used, 15% of water based on the weight of the fruit should be run in first and brought to a boil.) Steam is turned on gently as soon as the open steam discharge (or jacket or coil) is covered and the balance of the fruit is added as quickly as possible. The steam is then turned on full and the batch is boiled vigorously for from 3 to 5 minutes in order to sterilize it.

With certain soft fruits, such as raspberries, no further cooking is necessary. But, generally speaking, additional boiling is required to make the fruit sufficiently soft and fluid. No hard portions should remain and the heat should penetrate thoroughly to all portions of the fruit. With plums and similar fruits, stones and pits should be reasonably

free from adhering fruit structure. The fruit should not be cooked to a mush, but should be kept as whole as possible. In the case of large fruit, some breaking up is necessary, but as distinct pieces as possible are desirable. The general texture of the product should be that of "stewed" fruit.

Of course, if the fruit is too firm. the user can render it softer. But, if it is too soft, there are no means of rendering it more firm. However, it is essential that the fruit be softened sufficiently to permit penetration by the sulphur dioxide solution, and also to permit easy passage through discharge valve and through the bung of the barrel. The additional cooking required to reach this condition usually takes from 5 to 20 minutes, depending on the degree of firmness of the raw fruit and the efficiency of the equipment. With soft fruit, it may be necessary to stir with a paddle to obtain uniform cooking.

When cooking is completed, the batch should be discharged to a mixing tank or receiver, where it is standardized with water to the calculated volume, if a definite "fruit strength" is specified. About 10% dilution usually occurs owing to condensation where "live" steam is injected into the fruit. Or, if a jacket or closed heating coil is used, the loss by evaporation from the 15% added water usually results in about the same final dilution. With some fruits, additional dilution may be necessary if the pulp proves too thick to flow and to allow thorough mixing of the sulphur dioxide solution.

Adding the Solution

The pulp is then run into barrels, with as little delay as possible so as to avoid cooling. The barrels are filled to within 2 or 3 in. of the bung hole, by means of a funnel. The consistency should be such that the pulp will not run out of the receiver entirely by gravity, but must be assisted by a flat paddle, "squeegee" or equivalent.

The cooperage used for this product should be new oak or fir barrels of 50 U.S. gallons capacity. Waxed barrels must not be used for this product.

Before filling, 5 lb. of the sulphur dioxide solution is placed in each barrel. After filling, 5 lb. more of the solution is placed in each barrel. The batch should be stirred constantly while filling, to avoid floating of the fruit and to assure uniformity between barrels. After the final sulphur dioxide solution addition is made, the barrels are closed. They are then rocked and next rolled over a number of times, to mix the sulphur dioxide solution thoroughly through the pulp. Poor mixing may result in spoilage.

Samples of each batch should be taken in sealed glass jars, stored in a warm place and examined frequently. These samples should be taken from the barrels the day following their filling and will serve as a check on the efficiency of the preservation process. If the pulp has been properly prepared, the color will bleach and there will be no fermentation.

In carrying out this method of fruit preservation, it should be remembered that sulphur dioxide is volatile and has an irritating effect on the membranes of the nose and throat, although it should be harmless in any concentrations normally met with. The solution had best be made up in a separate room or out of doors. Also, the barreling is best carried out in a separate department.

## Removing Skins from Nuts U. S. Patent 2,273,183

Immerse meats, with skins, in a solution of approximately 3% of one of the alkalies of the group which consists of sodium hydroxide, sodium carbonate, sodium bicarbonate and borax for 1-4 minutes. Remove meats; rinse in water. Immerse meats in a 2-4% acid bath of the group which consists of hydrochloric, acetic and citric acids for 1-4 minutes. Remove meats; subject to a forcible action of water to remove the skins.

# Cracking Walnuts (American Black)

Hold the walnut on end, and continue cracking after the first breaks until the quarters, which usually separate at first, are each cracked further. Any quarter in which the meat is not well exposed can be cracked again. When this procedure is successful, the meat can be removed in whole quarters.

## Improving Firmness of Canned Tomatoes

Peeled tomatoes are dipped in 2% calcium chloride solution for 2-3 minutes.

### Improved French Fried Potatoes U. S. Patent 2,212,461

Sliced potatoes are soaked in vinegar, diluted (0.4-0.7% acetic),

for 5 minutes to 5 hours prior to frying.

Removing Egg Shells

Shells will come off hard-boiled eggs easily if the shells are slightly cracked and then dropped quickly into cold water.

#### Sauerkraut

Kraut is prepared in the home from large, firm, well-ripened heads of cabbage. These should be allowed to stand at room temperature for a day to wilt, the wilting causing the leaves to become less brittle and thus not so likely to break in cutting. The outer leaves are trimmed down to the white leaves and the heads are then washed. With ordinary home equipment, the heads must be cut in halves or quarters with a large knife and the core removed or cut fine. The kraut is cut with an ordinary kraut cutting board with blades set to cut shreds about the thickness of a dime. The setting of the blades varies, some preferring to cut the cabbage very fine. while others use a coarse cut.

The cabbage is packed in clean, paraffined barrels or jars with a light sprinkling of salt. If it is necessary to paraffin the barrels, a high-grade paraffin wax should be melted and applied to the dry container with a brush.

Salt is used in the proportion of 1 pound to 40 to 45 pounds of cut cabbage. If the salt is allowed to remain on the shredded cabbage a short time before packing, less breaking of the shreds is obtained.

Packing is quite often the cause of much unnecessary bruising and tearing of shreds and results in a softening of the kraut. A large wooden tamper should be used and with it the kraut should be firmly pressed or pushed down to force out the air rather than pounded until juice is produced. Ordinarily, pounding is not necessary to draw out the juice for if the salt is added as noted above, it will draw out more than enough juice to cover the cabbage by the time the container is filled. When the container is filled the juice should come to the surface.

The kraut should be covered with a clean white muslin cloth and then with a round paraffined cover of such size that it just fits within the container. A weight is placed upon the cover of such size that the juice comes to the bottom of the cover. but not over it. This will keep the cloth moist but juice will not cover the cloth. The weight necessary for this purpose varies, especially during the first few days of fermentation and with changes in temperature, and therefore should be watched carefully. For smaller containers a weight consisting of a jar to which water can be added or taken from serves very well. The placing of weights on the kraut is very important in producing good quality sauerkraut. Commercial packers are very particular about this

Fermentation starts within a day after packing as is usually evidenced by the formation of gas bubbles on the surface. Although fermentation is more rapid at higher temperatures, more spoilage is also likely to occur. The best quality kraut is produced at 70° F. or lower. It requires a month to six weeks for

the kraut to cure properly at these temperatures.

If it is used quite frequently and intended to be entirely consumed in fall and winter, kraut may be left in the container in a cold room; otherwise, it should be canned. Canning is simple and insures a good supply of kraut throughout the year. The cold pack method is more commonly used, although kraut may be successfully packed by hot pack methods. In the cold pack method the kraut is warmed to between 110° and 130° F. in its own juice, packed into sterilized jars, covered, and cooked in a kettle of boiling water for 20 to 25 minutes. The jar is sealed when removed and placed in a cold place so that it may cool as rapidly as possible. If allowed to remain hot for a long period, the kraut softens and darkens in color. When canned and cooled properly the kraut is very much like the raw product in texture and flavor.

Although many people have made kraut for years, few realize what happens in the typical curing process. When cabbage is cut there are a great many bacteria, both good and bad, yeast and molds upon the cut shreds. The salt sprinkled upon the cabbage draws out the sugar which is used by certain of the bacteria. They change the sugar to acids and other by-products. A typical mellowing of the cabbage takes place with these changes, resulting in the product we term sauerkraut (acid cabbage).

When kraut is properly packed, with the correct amount of salt, and at a reasonable temperature, only certain good types of bacteria are able to grow. The various spoilage

types of bacteria, yeast, and molds are stopped from growing by the absence of air and the acid which is rapidly formed by these desirable bacteria. At times insufficient amounts of salt are used, or the kraut is not thoroughly packed, or the juice has drained off, or the kraut may not be covered properly. Under such conditions spoilage may occur.

Tagging Foods and Beverages

The source of beverages may be traced by their appearance under ultraviolet light. Many soft drinks and some foods contain natural fluorescent dyestuffs.

A small amount of neutral acriflavine, one part in several million, or one part in 50 million of fluorescein or uranine causes a distinct fluorescence in liquids.

#### CHAPTER EIGHT

## HIDES, LEATHER AND FUR

Rapid Vegetable Tanning
Vegetable tanning can be done in
a very short period of time when
the hide is first treated with sodium
hexametaphosphate. The tannage
may be performed in a drum, paddle or vat. The strength of the vegetable tanning solution may vary
from 30° Barkometer to 80°. The
time, depending upon the equipment, will vary from a few hours

to seven days for heavy leather.

The unhaired hide should be thoroughly cleansed, i.e., it should be washed as free as possible from lime salts after bating or it may be neutralized with ammonium chloride or sulphate and then washed with cold water to free it of soluble salts. The extent of bating apparently will not effect subsequent plumpness. After having washed the stock, it is drained and placed into the tan drum with the following amounts of materials, based on the white weight:

Water	125	%
Sodium Hexameta-		
phosphate	5	%
Sulphuric Acid	1.	5%

After milling 15 minutes, the pH is determined; this should be adjusted to 2.2 to 2.4 with sulphuric acid. The stock is milled for a period of three to four hours, then permitted to rest in the drum overnight. The next morning the stock

is washed with cold water for about one hour. It is then ready for vegetable tanning.

The vegetable tanning material may consist of a mixture of hemlock, chestnut and quebracho or any other suitable mixture. Very good results are obtained with quebracho alone. It is, however, very important that the pH of the vegetable tanning material be adjusted to a pH of 3.0 to 3.2. This may be done with an organic acid such as formic, acetic or lactic, or with a synthetic tanning agent such as mentioned previously. Inorganic acids are not satisfactory excepting phosphoric. We have found that phosphoric acid is the most economical to use. The 85% syrupy type is recommended.

The strength of the vegetable tanning solution may vary from 30° to 80° Barkometer. The acid or syntan is added directly to it, stirred well.

Tanning may be done in one of two ways:

1. In the drum: The drum may be the ordinary tanning drum, but one of the following dimensions is preferable: 8 feet in diameter, 8 to 10 feet face. The speed should not exceed 14 r.p.m., the total load to be no more than 100 sides of light cows or the equivalent in smaller stock. The total amount of tanning material need not exceed 18% on a pure tannin basis. Time of milling will vary from four to six hours, depend-

151

ing upon the plumpness of the stock. After the stock is tanned, it is horsed up for 24 hours, then pressed or put through the wringer and split. It may then be retanned and shaved, fatliquored or stuffed. The spent tan liquor is refreshed and used for a

subsequent pack.

2. In the rocker vat: For this purpose it is not necessary to have a rocker section in which the liquor is varied in strength from a weak tail to a strong head, but each vat may be of the same strength. The liquor may vary from 30° to 60° Barkometer. The stock is hung into the rocker vat in the conventional manner and rocking proceeded with until the stock is tanned through. Steer hides for belt or sole will be tanned through in from three to five days' time. Sole leather stock may then be placed into the layaways and the balance of the process continued as usual. The spent or sapped liquor in the rocker vats is refreshed and the next lot entered.

In drum tanning some drawn grain is obtained, which is, however, easily set out. Drawn grain is directly blamed to the speed of the drum. In the rocker vat no drawn grain is obtained, nor is it necessary always to retan after rocker tanning, especially for bag, case, and strap leather.

Two outstanding properties result from metaphosphate treatment before vegetable tanning, namely, plumper leather and stronger leather.

## . Chrome Tanning Soakina

After the hides are trimmed and split into sides, lots are made con-

sisting of 3000 lb., one side more or less. This is called a "pack" and will be so distinguished throughout. The pack is placed in a paddle vat with 1450 U.S. gallons of water at a temperature of no higher than 65° F.. preferably between 60 and 65° F. The pack is milled for a half hour, then allowed to rest. The total time for soaking should not exceed 18 hours, and during this period the pack should be milled for a 15 minute period each three hours.

After the 18 hour period and while the pack is being milled, it is washed with water at a temperature of 60 to 65° F. for a period of one hour. The amount of water consumed for washing should total 3000 gal., flowing into the paddle vat at the surface and in a far corner and discharging from an opening in the bottom of the paddle in a position opposite to the point where the stream enters the paddle vat.

After the washing, the pack is pulled from the paddle, placed flat on trucks, drawn to the fleshing machine, where the sides are "green" fleshed as clean as possible, i.e., no fleshy tissue should remain on the sides after passing through the machine.

## Limina

Liming is preferably done in a paddle vat which is prepared as follows:

The paddle vat should contain approximately 400 gal. of an old or mellow lime.

To this is added 1000 gal. of water (65 to 70° F.) and

Hydrated Lime 100 lb. Sodium Sulphide 30 lb.

The pack is thrown into the paddle vat while the wheel is in motion. When all of the pack has been entered, milling should continue for 15 minutes. It is assumed that at this stage it is about mid-day. During the afternoon the stock is milled for 15 minutes each two hours. It is then permitted to rest. The next morning the stock is again milled for a period of 15 minutes, then after three hours the following is added to the paddle vat:

Hydrated Lime 100 lb. Sodium Sulphide 20 lb.

During the next 24 hours the pack is milled 15 minutes every three hours, excepting at night time, when it is permitted to rest.

On the third day nothing is added to the paddle vat, but every three hours the pack is milled for a period of 15 minutes. During the last milling period of the third day the contents of the vat is warmed to 75° F., then allowed to rest overnight.

On the morning of the fourth day the pack is milled for 15 minutes. The sides are then removed from the vat, placed on trucks and taken to the unhairing machine. The sides are then unhaired, head split, refleshed, scudded, and examined for fine hair.

#### Acid Wash

From the fine hair stage the pack is placed in a paddle vat which is filled with water. The pack is then washed for a period of a half hour, the water being at a temperature of 65 to 70° F., the amount being approximately 1500 gal. The operation is carried on in a similar manner as the wash after soaking. After the sides are washed and the paddle vat

filled with water, the acid wash is applied as follows:

Have available approximately 20 lb. of muriatic acid in a small tub to which is affixed a hard rubber pet cock or syphon. The acid is run into the paddle vat in a small stream at one side of the paddle; the operator constantly takes a small portion of the liquor and tests it for acidity with methyl orange indicator. At this stage the operator must use judgment, gained by experience, and retard the flow of the acid at intervals so that the fluid contents of the vat remains acid to methyl orange indicator for a period of two minutes. After this period, hydrated lime is added to a degree to obtain a constant pH = 8.5. The sides are now ready for the bating operation.

## Bating

The temperature of the contents of the paddle vat is now raised to 85° F. After the temperature remains constant for five minutes the bating material is added. The amount used is 34% on the white weight of the pack.

It is quite impossible to describe the bating operation excepting to state that during the time of bating the temperature should be held at 85° F. and the pH at a point not to exceed 9.5. The time required for bating may vary from 15 minutes to 45 minutes, depending upon the extent to which the whole process is kept in balance.

The extent of bating is a predetermined stage which only the operator can judge by feel and appearance, and then only after a prolonged period of experience.

When the operator has decided the end point of the bate, the pack is washed with a stream of cold water, 65° F. or below, for a half hour, requiring approximately 1500 gal. of water. The sides are then removed from the paddle and transferred to the pickle paddle.

Pickle

The pickle is prepared in the fol-

lowing manner:

To 1450 gal. of water add sufficient common salt to make a 10% by volume solution. Sufficient sulphuric acid is added to make a 0.15% by volume solution. To this solution the sides are added.

On the white weight of the stock the following is added to the paddle wheel while the stock is being milled:

Sodium Chloride 10 % Concentrated Sulphuric Acid (66° Bé.) 1.4%

The stock is milled for a period of four hours, then allowed to rest overnight. Next morning the stock is milled for one hour. The sides are then removed from the paddle wheel and "horsed" up to drain for a period of 24 hours.

The spent pickle is readjusted with water, salt and acid, if need be, to its original strength of 10% salt and 0.15% acid. It is now in order for the second pack. After every tenth pack the contents of the paddle is discarded.

The liquor may be used for a longer period if provision is made to permit it to settle for several days, syphon off the clear supernatant and discard the calcium sulphate.

Tanning

Tanning is done in drums.

A one bath chrome liquor is used.

After the pickled stock has

drained for 24 hours it is made into lots of 2000 lb. each, that amount being chosen as a charge for a tan drum.

The drum is prepared as follows: Water 75%, on the drained pickle weight of stock.

Salt 4%, on the drained pickle weight of stock.

Place the stock in the drum containing the above and mill for five minutes, then add the following amounts of chrome liquor:

10 gal. Chrome Liquor, mill 20 minutes, then

10 gal. Chrome Liquor, mill 20 minutes, then

10 gal. Chrome Liquor, mill 30 minutes, then

10 gal. Chrome Liquor, mill 3 hours

Then add 0.5% or 10 lb. of sodium bicarbonate, which is first dissolved in 25 gal. of water and divided into three equal portions, each of which is added at intervals of 15 minutes.

After the last portion of bicarbonate is added, milling is continued for 3½ hours. The drum is then stopped, the door removed; note that all stock is submerged, and let stand overnight. The next morning the drum is closed and the stock milled for a period of one hour. A boil test is then made. If the boil test is satisfactory, a pH determination is also made on the stock. If this is satisfactory, the stock is removed from the drum and piled flat on trucks to drain overnight.

Mechanical Operations

The following morning the stock is put through a wringer, then set out by machine. The sides are then sorted for splitting. Three weights are generally sorted, namely, heavy, medium and light. Sorting is regulated so that after splitting, the thickness of the whole side will correspond to the thickness of the belly, which should not be split. It is often found that cow sides vary considerably in thickness between belly and back. For this reason, judgment must be exercised by the sorter not to permit too heavy a split to be removed.

After the stock is split (the belt knife machine is generally used), it is sorted for thickness, by gauging, and the type of leather it is best suited for.

#### Kinds of Side Leather

Side leather tanners usually limit the weights of raw material (green salted weight) to from 25 to 60 lb. hides. Within these weights will be found hides which when split into sides will produce leathers known to the American trade as:

Buck sides, 25 to 35 lb. hides; for misses' shoes.

Veal sides, 25 to 35 lb. hides; for children's and misses' shoes.

Sport Elk, 25 to 43 lb. hides; for misses', girls' and boys' shoes.

Gunmetal sides, 35 to 55 lb. hides. The heavier hides are usually "spready," being thin cow sides, usually called "extremes," used largely for men's semi-dress shoes.

Elk sides, "43 lb. and up" hides, used largely for work shoes.

Waterproof sides, "43 lb. and up" hides. A choice leather for "high cuts," waterproof boots and shoes.

Retan sides, "43 lb. and up" hides. A side on which are found barbed wire scratches and other grain defects, and which are buffed before they are finished. "Retan" denotes a

chrome tanned leather which is later retanned with vegetable tanning material, then heavily stuffed with greases. It is used principally for work shoes and "high-cut" boots.

There are, of course, specialties made by many side leather tanners. These special leathers are usually designated by some trade name and used for children's, misses' and girls' shoes. In addition, large quantities of sides are used for the purpose of making white leather for women's, girls' and children's shoes. Practically all white leathers are chrome tanned, excepting for a small percentage, which are tanned with alum, formaldehyde, and synthetic tanning materials.

#### Coloring

After the sides have been split, shaved and sorted, lots of 500 lb. are formed for each weight. This is the standard amount per color drum.

The stock is placed in the drum with water at a temperature of 70° F. and rinsed for five minutes. The drum is then well drained, after which 150 gal. of water at a temperature of 70° F. is added. While the drum is in motion, 25 lb. (5%) of synthetic tanning material, first diluted to 20 gal. with water, is added. The stock is milled for 30 minutes, then is added 7.5 lb. sodium bicarbonate in 20 gal. of water in three equal portions at intervals of 10 minutes. After the last portion is added, the stock is then milled for 30 minutes longer. It is then washed with running water at 70° F. for 30 minutes. The temperature of the water is then gradually raised, at such a rate as to reach a temperature of 120° F. in the next 20 minutes. Washing is continued at this temperature for a 10 minute period. Total washing time is one hour, and 2500 gal. of water should be consumed for this washing operation. The stock at this stage should show a pH = 4.8 to 5.2.

The stock is now in proper condition for coloring and fatliquoring.

Preparing Sheepskins for Tanning

After cleansing the wool and removing all burrs, etc., pickle with acid and salt and then tan straight away. This method tends, however, to produce a somewhat hard leather and it is better to go to a little expense and trouble to soften the skins.

The following bath:
Water at 65° F.
Ammonia (0.910)
Hydrogen Peroxide
(100 Vol.)
300 gal.
14 pt.
6 pt.

should be used and goods paddled in it for 30 minutes and then left overnight. Next morning the skins should be drained, lightly hydroextracted and neutralized by use of a weak organic acid bath using 1% of lactic acid on fleshed weight. The pH of the cut surface should be 4.5–5.0.

The most suitable pickle is an alum one and a useful formula is: Water at 65° F. 100 gal.

Potash Alum 50 lb. Salt 50 lb.

Paddle the skins for  $2\frac{1}{2}$  hours, then drain overnight and tan next morning in the usual way. The potash alum pickle is particularly recommended in the case of chrome tanning.

Hide Dehairing Powder
U. S. Patent 2,226,883
Sodium Hyposulphite 50%
Sodium Sulphite

Sodium Sulphite
Anhydrous 40–45%
Lime 5–10%

Fat Liquor for Hides British Patent 534,244

Egg Yolk	1.42
Sulphonated Neats-Foot	
Oil	6.40
Fig Soap	0.54
Oxidized Cod-Liver Oil	1.34
Sulphonated Cod-Liver	
Ōil	0.75
Pine Oil	0.62

Deglazing Leather

Trisodium Phosphate 4 oz. Borax 2 oz. Diglycol Stearate  $\frac{1}{2}$  oz. Sulfatate (Wetting

Agent) 1/4 oz. Water, To make 1 gal.

Warm and mix until dissolved. Apply, warm, with sponge or soft brush.

Leather Degreaser
French Patent 846 569

Figure 1 atent 040,000	
Trisodium Phosphate	70
Soda Ash	20
Castile Soap	10
Water 3	333

Waterproofing Leather British Patent 532,306

Leather is immersed at  $50-55^{\circ}$  C. for  $\frac{1}{2}-1$  min. and brushed or sprayed with

Paraffin Wax 1
Stearin 1
Benzine 8

Sole Leather Waterp	
Japanese Patent 12	8,561
Asphalt	8%
Rosin	7%
Boiled Oil	13%
Heat together until un	iform; add
Copal Varnish	47%
Cool and add	
Turpentine	10%
Benzol	15%

### Dyeing Glove Leather

An important item in the glove leather industry is the production of wash fast shades on the various combination tannages—chrome and formaldehyde—formaldehyde and alum and variations of these basic treatments on sheep and kid skins.

The dveing procedure consists of giving the skins a preparatory drumming for 30-40 minutes with 4% ammonia at 130° F. The dyestuff may be then added to the same bath or applied from a fresh bath if desired and drumming continued at 130° F. for 30 minutes. The color is then exhausted and fixed with from 3-8% formic acid, depending on depth of shade, the acid being fed on in three portions at intervals to insure leveling and penetration. Fat-liquor is then added and drummed 10 minutes longer. Percentages are based on dry weight of the leather.

Out of some 250 distinct dyestuffs checked for maximum wash fastness, only 14 were selected as giving most satisfaction. These are listed: Chrome Leather Yellow 2G Conc Chrome Leather Yellow C Conc Amanil Fast Orange PRZ Amanil Leather Orange DB Benzo Fast Orange S Amanil Leather Orange PR

Amacid Leather Orange PGS
Leather Brown SR
Leather Brown RN
Amanil Leather Brown SG
Amanil Leather Brown BR
Amanil Leather Green LT
Amanil Leather Brown RLH or BR

Ten minutes agitation at 100° F. with 2 grams neutral soap chips per quart of water is the wash test used.

## Belt Edge Coloring Formula No. 1

T OTHER TAO. T		
Nelgin	6.15	g.
Titanox A (Water		
Dispersible)	17.00	g.
Water	29.50	g.
Moldex (Preservative)	0.09	g.
Dissolve Moldex in boi	ling w	ater
	1 0	٠.

then add Nelgin and let soak for ½ hour. Stir vigorously while adding Titanox.

	No. 2				
1.	Diglycol Stearate	4	12	g.	
2.	Water		388	g.	
3.	Titanox A (Water				

Dispersible) 100 g. Boil 1 and 2 together, cool and

while mixing vigorously add 3 and mix until uniform.

To get different colored materials

To get different colored materials replace the Titanox by any other inert pigment or color.

Black Leather Dye (Stain)
Alcohol-Soluble Black
Dye 50 g.
Benzyl Alcohol 100 cc.
Alcohol 550 cc.
Water 300 cc.
Glycerin 50 cc.

Antique Leather Finish Antique leather is employed for furniture purposes. Usually sheepskin is employed, or, for better qualities, vachette leather. The so-called antique grain is produced either by embossing or by tanning with concentrated liquor. Such leather shows dark and light parts. If the raised parts are to be light and the deeper parts dark proceed as follows:

The skin is dyed in the usual manner in the shade desired for the raised parts. After drying lightly rub a protective wax mixture on the raised parts, leaving the deeper parts free. Then apply the solution of a black or other darker colored dye by means of a sponge.

The following mixture may be used as a wax reserve: Melt together: 75 parts stearine, 5 parts

Japan wax, 5 parts Carnauba wax, 75 parts petrolatum.

Sometimes the deeper parts are required to be lighter than the raised parts. In this case dye the leather in the shade desired for the deeper parts, and then cover the raised parts with pyroxylin lacquer previously colored in the required darker shade and mixed with a little castor oil.

## Fluorescent Leather

Chrome tanned leather is dyed with a solution of one of the following fluorescent dyes:

Fluorescent Blue G Rhodamine 3B Eosine G Brilliant Flavine S Fluorescent Violet G Diazo Scarlet PRD

Mordanted leather can be made fluorescent by dyeing with yellow OX, Red BX, and Red 6G. Shellac or casein may be used as binders and barium sulphate added to obtain good coverage and an increase in brilliancy.

## Artificial Leather U. S. Patent 2,273,973

A flexible webbing is coated with Nitrocellulose 40
Butylacetylricinoleate 30
Castor Oil 15

Polymerized Rapeseed Oil 15 The above can be colored by suitable pigments.

Numida Effect on Feathers Gum Arabic Solution

 (25-50% Solution)
 1 qt.

 Cold Water
 2 qt.

 Glycerin
 1 qt.

Strain thoroughly to remove all particles of dirt, etc.

Take the dry feathers and work in this solution until thoroughly saturated; wring through the ordinary wash wringer, and squeeze out as much of the solution as possible, after which rub through the hands thoroughly for about five minutes in order to evenly distribute the remaining portion of the liquid that is in the feathers. Then string the feathers and beat them out on a wooden board for several minutes until the fine stems separate, after which hang up and dry over night.

Self Sterilizing Bristles and Sponges British Patent 543,948

Bristles, hair or sponges (100 g.) are immersed, at room temperature, for several hours in silver nitrate (3-5% solution), then drained and washed.

Bleaching and Dyeing of Horsehair and Pigs' Bristles

The most valuable horsehair for commercial purposes is that from the mane and tail. Tail hair fetches the highest prices when it is over 571/2 centimeters long. And sometimes it is from 75 to 85 centimeters in length. Mane hair, on the other hand, is seldom longer than 45 cm. True white hair is in best demand. and next comes the coal black. The market value of sorrel, brown or grav horsehair is not anywhere near so great. Skin hair is also used for various purposes, as for instance. unholstery and cushions, and is also spun into coarse varn to be used for weaving haircloths, such as that used for lining the lapels of men's overcoats to make them keep their shape. Skin horsehair, together with cow hair, frequently is mixed in the mortar used for ceilings to make it hold better. The shorter mane hair is very much in demand for high grade upholstering. Such horsehair seldom is dyed before use, but simply is freed from impurities by means of soap and alkali.

Now the chief consumers of all horsehair fabrics are the manufacturers of sieves and filters to be used in making flour, gun powder, oils, and so forth. Also this hair used for filters and filter goods once it is cleaned is seldom dved. Horsehair of the better quality often is taken instead of cow or donkey hair, for making high grade driving belts. Hair goods often are used for military cravats, a kind of pliable collar or stock worn by military men in some countries. This fabric, used in cravats, has a cotton or linen warp and a horsehair filling. Tufts of white or colored horsehair frequently are used in the accoutrement of military uniforms in some countries. The principal use for high grade white horsehair, however, is for violin and cello bows. Only the best material when used in this way can withstand the friction from the constant action of the bow across the strings of the musical instrument.

A short description of the use of horsehair for violin bows may be of interest. The animals are especially chosen as suitable for the supply of raw material. The mane hair is cut off from the horse close to the root. the shortest length of the hair sorted out being about 75 centimeters. When it has been cut out the hair is tied in convenient bunches and sent to the finisher. The work of the finisher is usually not on a very large scale and therefore his outfit is simple consisting of little more than a few large vats to contain the cleaning fluid, an iron boiler of about 450 liters content, heated with wood or coal, for warming up the water, and a few other simple articles of equip-

In the preparation of the hair for cleaning, the ends are cut evenly and each end is dipped into a flat tub, containing a melted mass that consists of paraffin, shellac and colophony in their proper proportion. When cooled the mixture becomes firm like ordinary sealing wax and the hair ends are fastened in a bunch. Sometimes instead of the shellac preparation melted pitch is used, some finishers even prefering pitch since it neither saponifies nor becomes sticky in a strong cleaning bath as the other agents do.

For cleaning bow hair, soap and ammonia, or—if the hair is very dirty—soap and pearl ash are used. In the cleaning the hair bunches are stretched crosswise over a portable wooden frame and the ends attached

lightly to the side of it. The whole is then dipped a few minutes into the cleaning bath, whereupon the frame is taken out and laid on a wooden bench on which a row of parallel grooves or rills of about 21/2 centimeters' width are carved out for the reception of each strand of hair. The worker then takes a flat brush of white pigs' bristles and brushes carefully with soap lye each of the strands lying in its groove. After this process the frame with the strands again is entered into the wash tub and treated in it for a short time. It then is rinsed in another tub several times in clear warm water in order to remove any remaining soap. The frame is then laid aside for the strands of hair to dry somewhat.

The goods are now ready for bleaching with sulphur fumes. The equipment used for this purpose consists of a gas-tight wooden box that holds about six of the abovementioned strand filled frames. A number of wooden holders are adjusted at the sides of the bleaching box, forming spaces between the frames. In the double bottom of the bleaching box there are a number of holes to permit the passage of the sulphur fumes produced by burning lump sulphur in an iron pan in the space formed by the double bottom. The goods are allowed to remain in the bleaching box over night, and on the following day the frames with their contents are removed from the apparatus and rinsed repeatedly with water, in which process a little washing blue is added to the last bath to remove any yellow tinge from the hair. The frames then are placed on a wooden stand for dripping. This usually takes place in some well-aired room apart from the cleaning plant, both to dry the hair and at the same time to remove any odor of the sulphur fumes. Finally the strands are cut from the frame and sorted for shipment.

Horsehair from the mane and tail, when it is to be used for weaving haircloth is always cleaned until it is perfectly free from all impurities. Before beginning the cleaning process, the hair is sorted out into bunches of suitable lengths, the fastening of which is left loose enough for the cleaning fluid to pass through it easily. The equipment used for cleaning the hair consists of a wooden tub of about 1.2 square meters surface, fitted with a double bottom with perforations, to provide for circulation of the fluid. A steam pipe to heat the bath is fitted into the space formed by the double bottom. The liquid is circulated by means of a centrifugal pump. The bunches of hair are put into the dry tub, and care should be taken that a firm package is formed that does not leave openings for the liquid to rush through. When the packing is completed, a wooden lattice is laid over the bunches of hair. This device consists of a number of hardwood staves, fixed crosswise as in a garden lattice. The railing is attached by metal clamps to prevent its rising up when the tub is filled with the cleaning fluid.

The cleaning is carried out at a temperature of about 36° C. using soap and soda or soap and ammonia. Generally, after a fifteen minute treatment of a lot, the liquid is let off into a reserve container, and the bunches taken out of the apparatus

and then laid in again but in a different position, the purpose of the change being to effect a thorough cleansing. After a treatment of an hour all in all in the cleansing bath, the exhausted liquid is let off and the tub again filled with fresh warm water to rinse off the residual soap. After several such rinsings the bunches are removed from the apparatus and centrifuged.

If the cleaned goods are to be dyed, about the same kind of apparatus is used as is usually used for cleaning purposes. But almost any kind of package dyeing machine can be used for dyeing the bunches, it being unnecessary that the circulation of the water be effected by centrifugal pumps, since direct steam also can be applied for this purpose. Black and brown afterchroming dyestuffs usually are used for the purpose of fast dyeing of the horsehair for upholstering fabrics and for brush bristles. Also acid black is used for dyeing the hair, a black of excellent fastness to light and washing being selected. Acid blue black is used only when special fastness to light and rubbing is desired, but when fastness to washing is not so important.

In order to insure a thorough penetration of the color, the process is carried out at a boiling point for from one and a half to two hours. Experience shows that dyed horse-hair turns out very much lighter if it is taken out of the bath sooner. By using a more strongly acidified bath, it is possible to apply any well known acid dyestuff, that goes on the fiber evenly, for the dyeing of horsehair. In cases where it is necessary to bleach out the natural color

of the hair strands to some extent, a short treatment in a boiling, weakly acidified bath with an approximate 3% content of sodium sulphoxylate formaldehyde will serve the purpose.

### Pigs' Bristles

High grade white bristles are used by the makers of tooth brushes and other toilet brushes. The natural colored goods are usually converted into cheap curled hair for filling mattresses and other similar goods. The bristles are clipped off from the slaughtered pig when it is taken out of the scalding-vat. The best material is from along the spine towards the end, and from the flanks. The various kinds are sorted out one from the other and arranged according to length and color-black, white and brown being the ordinary shades.

After the bristles are scraped off from the pig, they are dried in flat boxes in the open air, the containers being covered over with some light fabric when wind is blowing, to prevent loss. When the bristles are dried they are either sprinkled with salt or dipped in salt water, to prevent decay of the bits of skin and flesh still clinging to the roots. The material is then packed in barrels or bags for shipment to the consumer.

After the goods have been received at the plant of the manufacturer of brushes or of other articles, the bristles are sorted out by hand and the bits of skin or dirt on the goods removed by rubbing them across the ridges of the metal bottom of a flat trough. Thereupon the bristles are transported to another part of the equipment which is fitted with a bottom similar to a fine mesh

sieve. The entire lot of bristles is then worked for a while on this sieve, when most of the dust falls through the mesh, while the worker removes by hand any particles of dirt which are too large to fall through. After the bristles have been treated in the above described manner they are packed for wet cleaning in sacks of five pound lots.

In small plants the cleaning apparatus consists of a number of large barrels, the upper part of which has been removed. The goods are treated in these. The sacks in the cleaning fluid are kneaded and pressed by a workman, a pounder being used, like that sometimes used by women in the hand laundering wearing apparel. In better of equipped plants there is a machine which is similar to the fulling apparatus for the manufacture of felt hats. This machine is fitted with a number of wooden pistons, to which are attached rubber suction caps, and the movement to and fro of these pistons, operated by the propelling force of the driving mechanism connected with them, removes all impurities from the bristles by suction and pressure. For the sake of convenience in handling, the goods are packed in 5 lb. lots in sacks.

When the bristles have been soaped, the bags are pressed into a contrivance which consists of two boards of heavy wood slung parallel, the lower of which is fastened to a portable stand, while the upper board is movable and is fitted with a long handle to obtain the necessary leverage for the desired pressure. Since the whole is portable, it can be used at the side of any tub in the

plant wherever it is needed. The soap water which is squeezed out of the sacks that are thus manipulated is collected in a trough fastened underneath the apparatus. After the soap water is pressed out, the sacks containing the bristles are rinsed in warm water until they are quite free from soap and then pressed out again, when they are ready for bleaching.

Before peroxide bleaching came to be generally adopted, pigs' bristles were cleaned with sodium bisulphite. but the latter is now being used less and less since results are much better with the newer process. However, where a cheap process is neccessary, bisulphite is still applied. The bath for bisulphite bleaching contains one liter of sodium bisulphite of 75° Tw. to 100 liters of water. The bags containing the bristles are soaked for one hour in the cold liquid, being turned from time to time, and are then entered in a tub of fresh cold water for careful rinsing.

For peroxide bleaching, wooden tubs are used, fitted with lead steam pipes for heating the liquid. For a bath of 135 liters, 9 liters of bleaching agent are used, consisting of hydrogen peroxide (12% by volume), in conjunction with a sufficient quantity of ammonia to make the bath slightly alkaline. The sacks containing the bristles are entered into the cold bath, and when they have been moved about by hand for a time, the temperature of the bath is slowly increased to 50° C. The bath is then permitted to cool from six to eight hours, when the bags are removed from the liquid. squeezed off and rinsed. The goods

are then taken out of the sacks and laid in flat cloth-covered containers

nor drying.

The pigs' bristles are dyed in suitable sacks in a package dyeing machine, where the circulation of the liquid is effected either by a pump or by direct steam pressure. In smaller establishments the sacks are treated in open tubs, in which case they are hung on wooden poles placed across the top of the tubeach sack containing about two pounds of bristles. Afterchroming black and logwood black are the main dyes for bristles which are intended for brushmaking. During this process care should be taken that the bristles are thoroughly soaked through, as the ends of insufficiently soaked bristles, when made into brushes and trimmed, will have a gray or purple appearance.

Generally the black goods are given a light soap bath after the dyeing, in order to free the bristles from any loose dyestuff particles. For this treatment olive oil soap is used, a small quantity of pure olive oil being generally added to the bath also to give the goods a better hand and luster.

Fur Bleach U. S. Patent 2,086,123 Formula No. 1 Hydrogen Peroxide

(30%) 25 cc. Iron Sulphate 5 g. Ammonium Bifluoride 2 g.

Water, To make 1 l.

No. 2 U. S. Patent 2,092,746

Hydrogen Peroxide (100 Vol.)

3-5 gal.

Sodium Silicate 12 lb.
Sodium Oxalate 2 lb.
Water 100 gal.

Fur Softener and Lubricant
U. S. Patent 2,262,611
Lanolin 20-35%
Cedar Wood Oil 3-10%
Benzine, To make 100%

Softening and Flexibilizing Dyed Furs

Diglycol Stearate 10 lb. Water 12 gal.

Boil together and mix until uniform. Cool to room temperature and add to it 107 gal. of dye-bath solution. Dye in the usual way. If salts are present in the dye-bath, the addition of a wetting agent, such as Wetanol is necessary.

Fur and Leather Conditioner
Diglycol Laurate 14.0
Neatsfoot Oil 36.0
Mineral Oil 49.5
Santomerse OS
(Oil Soluble) 0.5

This gives a considerable improvement in the behavior and appearance over formulae made with sulphonated oils which frequently react unfavorably with fur pelts.

Lustering Furs

Immerse the degreased and dried fur in the following solution for about three hours:

 Water
 19 l.

 Salt
 800 g.

 Potassium Iodide
 150 g.

 Iodine
 90 g.

The iodine-impregnated fur is then subjected to a lustering operation with a suitable oil. The process is particularly effective on lamb furs, which have a tendency to curl and readily spot with water.

Glazing Solution for Furs
Mineral Oil 10
Chloroform 90
Spray the fur using an atomizer.

#### Fur Gloss

Dissolve 3 to 6 ounces of paraffin wax in 1 gallon petroleum cleaning solvent.

Approved cleaning solvent is preferable because of its safety during ordinary handling.

Precaution: Paraffin separates from the petroleum solvent at temperatures below 70° F. At —15° F. it is completely chilled out of the solvent.

This finish is used for the saturation of dry cleaned furs to replace any oils removed and to make them water repellent. It is also sponged or sprayed on materials that are lifeless or lusterless after cleaning and drying to produce high gloss.

> Non-Curling Fur U. S. Patent 2,234,138

The fur is treated for three hours with

Aniline or Phenylene
Diamine 60
Acetic Acid 50
and then for three hours with an aqueous solution containing

Formaldehyde 50
Then wash and dry.

Fur Carroting Solution
British Patent 532,370
Formula No. 1 No. 2
Nitric Acid (63%) 15 12
Hydrogen Peroxide
(100 Vol.) 20 17
Urea — 0.05
Citric Acid — 0.05

#### CHAPTER NINE

#### INKS AND MARKING MATERIALS

CARBON PAPER INKS	3 1	Blue Pencil (Soluble Type	oe)
Black Carbon		Victoria Blue	10
(Certified Public Accountar	nt)	Oleic Acid	30
Carnauba Wax	40	Ceresine Wax	5
Mineral Oil	40	Carnauba Wax	25
Carbon Black	10	Mineral Oil	<b>3</b> 0
Iron Blue	10		
Hon Blac		Hectograph Carbon	
DI 1 C 1		Crystal Violet	60
Black Carbon		Carnauba Wax	9
Carnauba Wax	30	Opal Wax or Acrawax B	10
Methyl Violet Base	$^2$	Mineral Oil	20
Oleic Acid	8	Lecithin	1
Beeswax	3		_
Carbon Black	15	One-Time Ink	
Lard Oil	42	Montan Wax	30
		Paraffin Wax	5
Black Universal Carbon		Methyl Violet	1
Extra Heavy Mineral Oil	40	Lampblack	15
Oleic Acid	5	Mineral Oil	49
Carnauba Wax	37		20
Crystal Violet	3	Manifolding Paper Coati	nø
Carbon Black	15	Emulsion	
Carbon Diack	10	U. S. Patent 2,299,694	
		Toluene	150
Black Pencil Carbon		Gum Dammar	150
Mineral Oil	18	Dissolve the above by mixing	
Oleic Acid	23	then add to the following	
Rosin	7	emulsified:	arrorr
Montan Wax	30	Glycerin	80
Lampblack	12	Diethylene Glycol	14
Milori Blue	10	Carbon Black	6
-		Carbon Black	U
Blue Pencil Carbon		TYPEWRITER RIBBON	INKS
Carnauba Wax	30	Black	11/110
Paraffin Wax	10	Formula No. 1	
Milori Blue	$\frac{10}{25}$	Nigrosine Base	5
	25 35	Oleic Acid	25
Petrolatum	30	Oleic Acid	40

Carbon Black	15	STAMP-PAD INKS
Mineral Oil	55	Green
Grind thoroughly before	apply-	Light Green SFA 0.40 g.
ing to ribbon fabric.		Diethylene Glycol 50.00 cc
No. 2		Heat till completely dissolved.
Victoria Blue Base	1	
Nigrosine Base	4	
Oleic Acid	25	Blue
Black Toner 1	5-25	Formula No. 1
Mineral Oil	55	Methylene Blue A
		(ex conc.) 0.40 g.
Black Two-Color		Crystal Violet A 0.04 g.
Formula No. 1		Diethylene Glycol 50.00 cc.
Carbon Black	20	No. 2
Lard Oil	40	Victoria Pure Blue BO 0.50 g.
Castor Oil	40	Diethylene Glycol 50.00 cc.
No. 2	10	Heat till dissolved. Filter.
Milori Blue	5	No. 3
Peerless Black	15	Soluble Blue 16
Sperm Oil	80	Glycerin 64
Sperm On	30	Rub fine in mortar.
		Glucose 32
Red Record	20	Water 16
Red Lithol Toner	30	* Syrup de Gomme 16
Mineral Oil	70	Mix thoroughly and combine.
*		
Blue Record		
Blue Toner	20	Red Stamp Ink
Lard Oil	40	Formula No. 1
Castor Oil	40	Crocein Scarlet MOO 37 g.
		Diethylene Glycol 50 cc.
Hectograph Ribbon Inl	2	Heat till dissolved.
Crystal Violet	50	No. 2
Mineral Oil	45	AE Fuchsine $1\frac{1}{2}$
Petrolatum	5	Alcohol 12
		Glycerin 64
Purple Checkwriter		Mix thoroughly.
Methyl Violet Base	10	Glucose 32
Violet Toner	5	Water 6
Oleic Acid	85	* Syrup de Gomme 16
0101011010	00	Gradually add to glycerin solu
Multimonh		tion. Stir well.
Multigraph	10	*Syrup de Gomme
Nigrosine Base Oleic Acid	10	Gum Arabic Nubs 1
Milori Blue	75	Water 5
	5	Stir until substantially dissolved an
Drop Black	10	then strain out dirt and lumps.

Black		Thermo-Setting Print	ting In	k
Carbon Black	5	British Patent 543		
Glycerin	88	Cumar Resin	•	56
Rub down in mortar.		Blown Soyabean Oil		20
Glucose	16	Carnauba Wax		10
Water	4	Carbon Black		10
* Syrup de Gomme	20	Violet Toner		2
		Blue Toner		2
Stamp Ink for Egg	gs	20101		
Gum Arabic	0.10	Duintin a Inla		
Water	4.00	Printing Ink		
Glycerin	4.37	German Patent 70	4,951	00
Formaldehyde (40%)	0.03	Varnish		28
Ultramarine-Blue	1.50	Glycerin		36
		Dye		18
Meat Stamping Ink-	-Blue	Ammonium Nitrate		4
Blue Dye (pure food)	30	Ester Gum		14
Dextrin	20	×	-	
Glycerin	82	Rotary Heliogravu	re Ink	
Water	70	French Patent 84		
yy a ter	10	Formula No.		
A sure area Deienties a T	1-	Alcohol	300	cc.
Aqueous Printing I		Butanol	100	-
Canadian Patent 405		Zein		g.
Rosin Powdered 25		Water	80	_
Water	0		16	
	6½ pt.	Nigrosine NB	10	8.
Dissolve the above and	d add the	No. 2	220	00
following solution:		Alcohol	320	
Zein	50 lb.	Zein		g.
Water	50 qt.	Water		cc.
Ammonia	2 qt.	Nigrosine NB	8	g.
Color	To suit	No. 3		
		Alcohol	400	
Colloidal Carbon B	lack	Zein		g.
Carbon Black	31	Water	100	
Water	59	Titanium Oxide	300	g.
Glycerin	5			
Soda Ash	1	Rotogravure Ink for Ce	llulose	Foils
Quebracho	4	French Patent 84	11 GO7	, 1 0111
Mill on colloid mill; th	is formula			00
makes a supercolloidal bl		Acetone	500	
•	_	Benzene	500	
* Syrup de Gomm	e 1	Alcohol	2000	_
Gum Arabic Nubs Water	5	Shellac	1500	
Stir until substantially dis	-	Victoria Blue		%
then strain out dirt and lum		Cellulose Acetate	1–3	%

Intaglio Printing Ink
British Patent 513,247
Gilsonite 15–33½%
Naphtha, Petroleum 85–95%
Methyl Ethyl
Ketone 5–15%

Raised Printing Resin (Thermoplastic) "Ink" Base
U. S. Patent 2,272,706

Lewisol 2L
or
Amberol 801
or
Rauzene X-135

Ethyl Cellulose 17½ Hercolyn 17½

Raised Printing "Ink" U. S. Patent 2,272,706 Formula No. 1 (Satin Gloss Finish) Raised Printing Resin  $173\frac{3}{4}$ Zinc Stearate  $21\frac{3}{4}$ Surfex (Calcium Carbonate)  $14\frac{1}{2}$ No. 2 (Luster White Finish) Satin Gloss Finish Compound (Above)  $21\frac{3}{4}$ Titanium Dioxide 131/2 Zinc Oxide  $4\frac{1}{2}$ 

Ink for Printing on Rayon Ribbon Ethyl Cellulose (High Viscosity) ½ oz. Denatured Alcohol ½ pt.

Ultramarine Blue

 $\frac{1}{2}$ 

Allow to stand for about 20 to 30 minutes until a jell forms. Add:

Tributyl Phosphate 1/5 oz.
Surfex 3/4 oz.
Titanox 11/2 oz.
Magnesium Carbonate 1 oz.

For other colors substitute other pigments for the Titanox.

Use alcohol for thinning.

Textile Printing Ink U. S. Patent 2,213,006

Nitrocellulose (viscosity 80 sec.) 10, a pigment 15, a mixture of monoalkyl ethers of ethylene glycol and diethylene glycol (32), and (petroleum naphtha) 27–29 parts is mixed to form a non-stringy, gel-like ink capable of plastic flow under pressure.

White Ink for Photostats

Black photostats can be written on with white figures by using a 50% solution of syrupy phosphoric acid. Write on the black photostats with a clean gold or glass pen, leave to react for 3-4 minutes, then wash the character with plain water and dry with a blotter.

Blue Indelible Ink

For an ink that will resist not only water and oil, but alcohol, oxalic acid, alkalies, the chlorides, etc., mix the following: Dissolve 4 parts of shellac in 36 parts of boiling water, carrying 2 parts of borax. Filter and set aside. Now dissolve 2 parts of gum arabic in 4 parts of water and add the solution to the filtrate. Finally, after the solution is quite cold, add 2 parts of powdered indigo and dissolve by agitation. Let stand for several hours, then decant and put in small bottles.

Removable Marking Ink for Leather and Textiles

Ammonia (0.5%) 2 kg.

Dimethylglyoxime (0.5%) 2 kg.

Ferrous Ammonium

Sulphate (1%) 700 g.

This ink is readily removed by

This ink is readily removed by bleaching with oxalic acid (1-3% solution).

Invisible Laundry Inks

(1) An invisible laundry ink which fluoresces a bright blue in ultraviolet light and which cannot be seen in daylight, is made by dissolving beta-naphthol in water and alkalinizing with sodium hydroxide. The ink is good for rayon, cotton, and other fibers.

(2) Another ink is made by dissolving oxynaphthionic acid in dilute sodium hydroxide solution. Under ultraviolet light this ink fluoresces a yellowish-green color. Inks with sodium hydroxide should not be used on animal fibers such as wool and silk.

Invisible Ink Formula No. 1

Water 50 cc. Uranyl Nitrate 1–2 g.

When applied to paper and similar objects and allowed to dry, this ink fluoresces a bright yellowish-green under ultraviolet light. It should not be used on foods or other products intended for human consumption.

No. 2

Water 50 cc.
Cinchonine 0.2 g.
Sulphuric Acid To make acid

This ink may be used on wood and durable cellulose products and fluoresces a bright blue under ultraviolet light.

Sympathetic (Invisible) Inks Formula No. 1

The writing fluid is the juice of the onion, and it may be obtained by plunging the pen into a peeled onion. On drying the writing is absolutely colorless, but on applying heat, such as from a lighted candle or match, the writing develops to a deep red brown.

No. 2

British Patent 235,968

A mixture of phenolphthalein, glycerin, alcohol, and carbon tetrachloride is the writing fluid. On drying it is colorless, but on the application of ammonia it turns reddish.

> Invisible Printing Ink (Pyrographic Ink)

Potassium Nitrate 90 Rosin 5 Sulphur 5

Mix the above and then add sodium silicate to bring to any consistency desired.

When the above ink is used on paper and the latter is ignited, it burns along impression.

Invisible Writing Carbon Paper

A fluorescent substance, which may be either organic such as anthracene, or inorganic such as zinc sulphide phosphor, is coated on paper in a base of several per cent drying wax and an organic solvent which also acts as a vehicle. This paper may be used in the typewriter instead of carbon copying paper for typing invisible messages which may only be read under the proper wavelength of ultra-violet light. Dark paper which has been padded to prevent impressions is preferred for the final message.

Hectographing (Copying) Invisible Writing

(1) One of the inks described in this section may be made up as hectograph ink with the proper colorless vehicle, such as glycerin, and used in the usual manner. (2) A fluorescent dye can be added to ordinary hectograph ink for conveying an additional meaning to a message. For example, a red fluorescing dye, which would be invisible in white light, would mean that the reader should ignore that part of the message containing the red fluorescent dye whereas that containing the green fluorescent dye should be read.

#### Invisible Pass-Out Ink

(1) A saturated aqueous-alcohol solution of beta-methyl umbelliferone may be used as an invisible fluorescent stamping ink. A little glycerin or other suspending or thickening agent may be added. When used with a clean rubber stamp marks may be applied to the skin which are not visible in ordinary light but, under ultra-violet light, they glow a brilliant blue color.

An alcoholic solution of tumeric may be used to harmlessly stain skin for tagging and marking purposes. Under ultraviolet light a yellowish fluorescence is noted.

Parachute Marking Ink

Mix 837 parts by weight of boiled linseed oil with 17 parts by weight of aluminum stearate. Heat to 115.6° C. until stearate is in solution. Cool the solution. Place it in a ball mill and add 525 parts by weight of ultramarine blue. Grind for at least eight hours. Add 450 parts by weight of spar varnish and continue to grind for at least eight hours more.

#### Silk Screen Inks

There are two types of inks used in the silk screen processes: Those that undergo chemical change on drying such as linseed oil inks, and those that dry by evaporation only. The following formulae are for those that dry by evaporation and undergo no chemical change.

For mixing the inks a ½ or ¼ H.P. motor having fastened to its shaft a metal or wooden propeller is installed in a vertical position so that it can be used to mix the contents of a one gallon can or larger.

It is only necessary to add as much color as is found to be necessary to achieve the desired shade. With a half dozen different flushed colors on hand it is possible to obtain many colored inks of a variety of shades.

The process consists in the preparation of a gum solution, mixing in the fillers and dryers, and addition of the flushed color.

#### Gum Solution

Solvesso No. 1 or 2	35
Varnoline	35
Gum Batu, Finely	
Powdered	50

The solvents are first mixed and then the gum is added slowly and then stirred for about 15 minutes. A thick oily solution and gum suspension results.

The following is added slowly under constant stirring:

or compound builting.	
Magnesium Carbonate	10
Surfex	10
Petrolatum	. 3
Titanox	5

It is only necessary to add to this any desired flushed color. To make a blue ink for example, add to the above

Flushed Ultramarine Blue

When agitation has resulted in a uniform mixture, add

Water slowly and stir constantly. This will cause the ink to swell up and become very thick, and will impart to the ink its fine drying properties. All of the above proportions can be altered to suit the occasion and any flushed color can be employed. This ink cannot be used with any silk screen using a glue background. If it is desired to use a glue screen it is then only necessary to omit the water. For thinning the following solvent is prepared:

#### Ink Thinner

Kerosene	5
Varnoline	95

The thinner is added slowly and the ink mixed very thoroughly each time before any more thinner is added.

For diluting the ink color a good base is needed. This is made exactly the same way as the ink. Use the following proportions:

#### Base Formula

Varnoline	35
Solvesso No. 1 or No. 2	35
Batu Gum	50
Magnesium Carbonate	10
When thoroughly mixed add	slowly
Water	35

For use dilute the ink with the base in any proportion desired. If too thick, add thinner and stir slowly to an even consistency.

#### Silk Screen Black

Solvesso No. 1 o	or <b>2</b>	35
Varnoline		35
Gum Batu		50
Petrolatum		2
Kerosene		2

Carbon Black	20
Magnesium Carbonate	10

#### Marking Paper Money

Paper money, such as ransom money, may be invisibly tagged by dusting with anthracene. Under ultra-violet light a bright greenish fluorescence is observed.

By wiping a paper note with a cloth moistened with lubricating oil or petrolatum an invisible mark will be made which shows, under ultraviolet light, as a bright bluish region.

#### Cattle Marker

Caone marker	
Paraffin Wax	40
Tallow	20
Woolfat	20
Ceresin (58/60° C.)	15
Oil Soluble Color	1-2
Pigment (To Match	•
Color) As	desired

#### Lantern Slide Ink

An ink consisting of a 3% solution of celluloid in "Cellosolve" or other similar solvent, and colored sufficiently with crystal violet, or other dye, will write on clean glass, using an ordinary steel pen. Slides can be very easily prepared. It is necessary that the glass be unusually clean and free from any oil film. The dry glass, after washing with soap and water, should be sponged with acetone, and the surface must not be touched with the hand during the writing. The handle of a toothbrush is a satisfactory source of celluloid. The ink dries rapidly and corrections can be easily made, after erasing by scraping with a razor blade.

#### Ink for Glassware

Inks for printing on glass are useful for identifying or otherwise marking laboratory apparatus. The following may be applied by means of an ordinary rubber stamp and fixed by heating up slowly in a torch almost to the softening point of the glass.

#### Formula No. 1 British Patent 212,938

A mixture of 1 part of cupric oxide and 1.5 parts of boric acid is fused. A mixture of 1 part of litharge, 1.5 parts of zinc oxide, 0.4 parts of boric acid, and 0.1 parts of cryolite is also fused. The two are ground together in the proportion of two parts of the former to one part of the latter and this is ground in well with one-fifth its weight of castor oil.

#### No. 2

#### U. S. Patent 1,538,890

A mixture of seven parts of silver oxide and three parts of lead borate is well ground in with glycerin or linseed oil and gum dammar until a somewhat tacky suspension is obtained.

#### No. 3

Grind together well one part cobalt oxide, one part manganese oxide, one part chromic oxide, and one part lead borate and grind this mixture well with glycerin until a tacky paste is obtained.

Glass Marking Ink	
Formula No. 1	
Barium Sulphate	15
Ammonium Bifluoride	15
Ammonium Sulphate	10
Oxalic Acid	8
Glycerin	40
Water	12

Package in wax or hard rubber bottles. Apply in ventilated hood. If too thick, dilute with water. The addition of 1–5% sodium fluoride speeds up the action of the above mixture.

If a black marking is wanted, replace the barium sulphate by

8-10

Lampblack No. 2

U. S. Patent 2,254,865

Lampblack	20.9
Titanium Dioxide	4.2
Silver Oxide	1.2
Glycerin	73.7

Ink for Ruling on Glass Use India ink to which has been added 1% Lepage's Mucilage.

#### Glass Crayon

In the laboratory a worker often has need to write on glass vessels, flasks, and the like. If no glass pencil is available a good substitute can be made as follows:

Mix while it is melted,

Paraffin Wax 98 g. Stearin 2 g.

Then add 10-15 g. of an oil soluble dye in either red, blue, black, or yellow. Let the liquid cool slightly and before it sets to a hard mass, pour it into large paper soda straws, the ends of which have been plugged with a small cork. Next, set these filled tubes in ice water or better still in a refrigerator. When they have gotten hard, tear off one end and use them to mark on glass.

## Etching of Designs and Lettering on Metals

For uniformity the formulae of solutions prepared by dissolving a dry salt in a liquid have been expressed in terms of grams per liter (g./l.) and of avoirdupois ounces per gallon (oz./gal.) of the resultant solution, while the formulae of solutions prepared from a mixture of liquids have been expressed in terms of milliliters (often called cubic centimeters) per liter (ml./l.) and of fluid ounces (1/16 pint) per gal. (fl. oz./gal.). Unless otherwise stated aqueous solutions are referred to, that is, the substances are dissolved in sufficient water to produce the specified final volume.

The etching of designs on metals is usually accomplished in three steps, namely, (a) application of a protective coating. (b) cutting the design through the coating, (c) etching the design. In the first step, the metal is coated with a thin layer of a substance known as a "resist," so called because it is resistant to the action of the etching solution. It should also have the property of adhering firmly to the metal so as to confine the etching action to the desired areas or lines, and should respond to the cutting tool readily without being disturbed adjacent to the cut.

The second step in the process is the cutting of the design. This may be done either mechanically or chemically, provided the resist is completely removed from the areas which it is desired to etch.

The final step is the etching with a solution that will dissolve the metal. Usually acids are used, although acid salts, neutral salts of a more noble metal than that being etched, or even alkaline solutions, may be used for certain metals or alloys.

The particular process to be used for a specific purpose depends on a number of factors, such as the nature of the metal to be etched, the number of pieces to be etched with the same design, the complexity of the design, and the desired sharpness of the etched lines.

The surface to be etched should be smooth and free from scratches. It should also be clean so as not to interfere with the uniform etching of the materials. Alkali cleaners or organic solvents are generally used to remove grease from the metal pieces.

Since the application of the resist and the cutting of the design are to a large extent interdependent, they will be discussed together.

Waxes such as paraffin, ceresin, beeswax and ozokerite, are often used as resists. They may be used either singly or blended together in mixtures. For example, a mixture of 3 parts of paraffin and 1 part of beeswax has been found very suitable. The melted wax is applied to the surface to be etched, by dipping. brushing or flowing. When the wax is solidified, the design may be cut through it with a sharp tool by hand or by means of a pantograph. Some pantograph devices are constructed so that a number of tools can be operated simultaneously, with considerable saving in time.

In another method, the metal surface is coated with a solution of gum guaiacum in alcohol. After the coating has dried, the pattern to be etched is stamped on the surface by means of a rubber stamp wet with a concentrated solution of sodium hydroxide (for example, 300

g./l. or 40 oz./gal.). The alkali causes the gum to become soluble in water so that when the surface is washed the bare metal is exposed. This washing should be done quickly with a large quantity of water, so that the alkali will not spread over the surface and dissolve the resist from areas it is desired to protect.

A third pretreatment consists in rolling a thin film of ink on the surface to be etched. The type of ink is designated in German publications as "Umdruckfarbe" ("transfer ink"). The following mixture gives satisfactory results.

Printer's Ink	100
India Ink	10
Castile Soap	4
Beeswax	4
Animal Fat	2
Rosin	1

The components of this mixture are blended by heating and rubbing to

produce a smooth paste.

The ink film, after being applied to the surface, is dusted with finely powdered asphalt, and the two are blended together by gentle heating. If powdered asphalt is not available, powdered rosin, although less satisfactory, may be substituted for it. If distortion of the metal article by heating is feared, the blending may be done by suspending the treated article for a few seconds in the vapor of alcohol or trichloroethylene.

The cutting of the design is readily carried out in the following manner: The assembled letters or characters in the form of steel stencils are clamped in a suitable holder. A sheet of tissue paper or fine sandpaper (No. 00) is placed on top of

the resist coating and the design is impressed therein with light pressure, such as can be obtained with a small press. On releasing the pressure, the resist adheres to the paper and the desired design is exposed as bare metal.

Another procedure for applying the resist is as follows: The desired design is first printed on the surface with an ink which contains a considerable amount of fats. The inked surface is then coated with a rapidly drying spirit varnish, which dries readily over the bare metal but not over the greasy ink. The resist is then removed from the inked areas by a solvent that does not affect the dried varnish film. Petroleum oil has been recommended for this purpose. Before etching, the surface must finally be degreased by light rubbing with some material such as tripoli powder or by a suitable solvent. This method, though time-consuming, is specially useful on a curved surface or in locations where it is difficult to use the steel stencils described in the previous method.

Still another process in the preparation of the surface for etching consists in first printing the background, or that part of the surface to be protected from the etching, with heavy printing ink, which is then dusted with powdered "dragon's blood" or with a mixture of powdered asphalt and rosin. After the powder has been brushed or blown off from the dry, bare metal, the ink and acid-resisting powder are fused together by baking, if heating does not affect the metal, or by the cold fusion process with alcohol vapor described previously. The

contrivance for printing the design on the surface may be a simple rubber or linoleum stamp prepared with the design depressed instead of being in relief as in the ordinary rubber stamp. By another rather rough method, the design may be printed in reverse on tissue paper with heavy printer's ink. While the ink is still tacky, the tissue is applied to the metal surface and allowed to dry. The tissue is then removed after moistening it with water, leaving the ink film as the resist on the metal.

For quantity production, the printing of the design on the surface is most easily accomplished by first making a master plate in the manner used in photoengraving. A large drawing in black and white is made of the desired design, which then is photographed and reduced to the desired size. The design is transferred to a sensitized zinc plate by clamping the photographic negative over the zinc plate and exposing to the rays from an arc light. Light renders the exposed areas insoluble in the etching reagent, whereas unexposed areas (portions covered by the opaque film) are dissolved when the zinc plate is etched with dilute nitric acid. The resulting master plate with the exposed areas or background of the design raised in relief is used for transferring the design onto the article to be etched, which is often done in a flat-bed printing press. The master plate, after being inked with an asphalt-base ink, is rolled with a clean printer's roller which picks up the ink and transfers it to the article to be etched. This is followed

by dusting with asphalt powder, as has already been described. Sometimes the etching of the master plate is omitted, since the areas of the sensitized zinc plate exposed to the light acquire the property of being wetted by and holding the ink, whereas ink will not stick to the unexposed areas.

#### Etching

It should be remembered that the solutions used in etching are corrosive to the skin and clothing and should be handled with care. If any of the acids should get on the skin, wash immediately with a large amount of water and neutralize any remaining acid with baking soda.

After a satisfactory resist has been applied to the metal surface and the design cut into it, the surface is ready for the etching. It is important that the etching action should take place uniformly over the entire exposed area and not be localized at certain points. It should also progress down into the metal and not undercut the areas covered by the resist and thereby spread over the surface.

The choice of the etching reagent is dependent on the nature of the metal being etched. It is often advisable to perform a few preliminary tests to determine the type and concentration of etching solution which gives the most satisfactory results. The formulae suggested here will serve as a starting point for experiments to enable one to decide upon the best reagent.

#### Reagents for Iron and Steel

The usual etching solution for iron and plain carbon steel is dilute nitric acid. One part of concentrated

nitric acid diluted with three parts of water has been found to give satisfactory results in most cases. The following variation of the nitric acid solution has certain advantages, although it cannot be used where alcohol would dissolve the resist, as is the case with gum guaiacum, or with resists produced on the metal by photographic processes.

	ml./l.	fl. oz./gal
Nitric Acid		
(sp. g. 1.42)	220	28
Hydrochloric		
Acid (sp. g.		
1.18)	20.5	3
Ethyl Alcohol		
(95%)	110	14
Water, To make	1 l.	1 gal.
A concentrated	0.033003	a golistica

A concentrated aqueous solution of ferric chloride is often used to etch steel.

Resists such as the spirit-varnish film in the fourth resist described above will not withstand the action of strong acids. For such purposes a less corrosive reagent, for instance, a copper chloride solution slightly acidified with nitric acid, or one prepared according to the following formula will be useful.

Ferric Chloride

		avoir.
	g./l.	oz./gal.
Copper Sulphate	200	27
Zinc Sulphate	8	1
Sodium Chloride	165	22

Stainless steel is etched with much more difficulty than ordinary lowcarbon steel. Ferric chloride (sometimes called iron perchloride), usually with the addition of hydrochloric acid, is the most widely used reagent for this type of steel. The time required for the etching to be completed is much longer (about 30 minutes) than that for the plain carbon steel. After the etching has been completed and the resist removed, it is advisable to repassivate the surface by immersion in concentrated nitric acid, if practicable. This treatment restores the original property of corrosion resistance to the stainless steel.

## Reagents for Nonferrous Metals and Alloys

Copper and its alloys may be conveniently etched with ferric chloride solutions. A formula which has been recommended for etching brass is

avoir. oz./gal.

	Hydrochloric Acid, (sp. g. 1.18)	55	(47 ml.)	7.3	(6	fl. oz.)	
S	ome other formulas for etching	copp	per and brass	are:			
		g./l		avo	oir. o	z./gal.	
(a)	Potassium Chlorate	27		3.6			
	Ferric Chloride	60		8			
	Nitric Acid, (sp. g. 1.42)	46	(32 ml.)	6.1	(4.1)	fl. oz.)	
(b)	Ferric Chloride	390		52			
	Hydrochloric Acid, (sp. g. 1.18)	83	(70 ml.)	11	(9	fl. oz.)	
	Alcohol (95%), To make	1 l	•	1 g	al.		
(c)	Potassium Chlorate	20		2.7			
	Hydrochloric Acid, (sp. g. 1.18)	80	(68 ml.)	10.7	(8.7)	fl. oz.)	

g./l.

45

Zinc may be etched with dilute nitric acid. A solution containing sulphuric acid and sodium dichromate has also been used for this purpose, as well as a solution of the following composition.

ml./l. fl. oz./gal.

Glacial acetic acid,  $HC_2H_3O_2$  (sp. g. 1.05) 400 51.2 Nitric acid,  $HNO_3$  (sp. g. 1.42) 100 12.8 Alcohol (95%),

To make 1 l. 1 gal.

Aluminum may be etched with dilute hydrochloric or hydrofluoric acid. (If the latter acid is used, more than usual precautions must be taken to keep from breathing the fumes or getting any in contact with the skin.) A 5% solution of sodium hydroxide may also be used for etching aluminum, provided the resist is unaffected by this solution.

Nitric acid is the common etching reagent for silver, and may be used as a 20 percent solution in water.

After the design has been cut in the resist on the article and a suitable etching reagent has been selected, the next step is the actual etching. In working with small articles, the back and sides are first usually given an acid-resisting coating, such as asphalt varnish, which is allowed to dry. They are then completely immersed in the etching solution. Best results are obtained if the bubbles formed in the action are removed from the surface which is being etched. This can be accomplished by gently swabbing the surface. After a sufficient depth

of cut has been obtained, the articles are removed from the etching bath, washed with water, and any acid remaining on the pieces is neutralized with a weak sodium carbonate solution. They are again washed, dried, freed from the resist coating with a suitable solvent and finally coated with a thin film of oil, varnish, or lacquer to prevent corrosion. In the etching of small designs on large surfaces, immersion of the whole article in the bath is not feasible. Here, the etching solution may be swabbed on the design with a rag held on the end of a stick, or a dam may be built around the design and the solution poured into the enclosed area. A rubber ring with a cross-section of about 1/2 inch square has been found suitable for a dam. A coating of petrolatum on the lower side of the ring prevents leakage of the solution between the ring and the resist. Dams may also be built up out of such materials as clay, plaster, molding wax or asphalt.

After the etching has been completed, the solution may be poured off if convenient, or most of it may be pipetted off by suction into a suitable container and the last traces removed with a damp sponge.

The etch produced with acids is often not readily visible under all lighting conditions. Coloring of the design or of the unetched areas is often resorted to in order to produce a pleasing appearance and to attract attention to the design, trade mark or lettering. An almost unlimited field is available to the etcher for producing various effects in color. A coloring process may be substituted for the etching process

by using a solution which colors as well as etches, or the etching may be completed first and followed by the coloring. Sometimes the colors are produced by spraying colored enamels on the etched design. After the enamel has dried, a solvent is used which dissolves the resist but does not affect the enamel, which therefore remains in the etched lines and areas. Two-color effects may be produced by the use of masks or stencils to block off parts of the design.

Coloring of the metal by chemical solutions is very often done. If the highlights are to be colored or plated, the appropriate treatment is applied to the whole article before the resist is applied. The design is later etched through the colored or plated coating in the usual manner. If it is desired to color the design, this is done before the resist is removed. A large number of solutions have been developed for obtaining various colors on metals. The following are typical:

Black Coloring of Iron

The objects are first copperplated by immersing for about 10 seconds in a solution made by mixing solutions A and B diluting to 1 liter (or 1 gallon) with water.

Solution A—10 g. (1.3 avoir. oz.) Copper Sulphate, in 250 ml. (32 fl. oz.) water.

Solution B—15 g. (2 avoir. oz.)
Stannous Chloride, in 17 ml.
(2.2 fl. oz.) Hydrochloric A c i d
(sp. g. 1.18) and
100 ml. (13 fl. oz.)
water.

After the plating is completed, the objects are rinsed and blackened by immersion for two or three minutes in a solution prepared as follows:

Dissolve by heating 1.5 kg. (12.5 lb.) of sodium thiosulphate in 1 liter (or 1 gallon) of water. Allow to cool and add 65 ml. (8.3 fl.oz.) of concentrated hydrochloric acid. Small amounts of hydrochloric acid are necessary from time to time to reactivate this solution.

Black Coloring of Brass
Immerse for about 20 minutes in the following solution:

g./l. avoir. oz./gal.

Basic Copper Carbonate 35 4.6

Aqua Ammonia (sp. g. 0.90) 103 (115 ml.) 13.8 (14.7 fl. oz.)

Black nickel plating is often used to color zinc, aluminum and other metals.

If it is desired simply to mark a steel specimen with some sort of an identification symbol or to write on the surface in large bold letters in which blurring of the edges is of no consequence, it is possible to apply the etching solution directly to the steel surface without the aid of a resist. The solution is best applied by a pen which is resistant to the acid, such as a wooden stylus or quill pen. A stainless steel pen is also satisfactory for this purpose. A rubber stamp with a pad of blotting paper or asbestos is sometimes used. The following "ink" has been used for work of this kind:

Nitric Acid (sp. g. 1.42) Silver Nitrate

Electrical etching devices and tools are available with which lines can be drawn on metal by a rapidly vibrating point connected to a source of low voltage current. A small arc is formed by the make and break circuit between the vibrating point and the piece being etched, thereby leaving a permanent cut in the metal. This machine may be constructed as a multiple pantograph so that a large number of pieces may be marked at one time from a single master plate.

#### Electrolytic Etching

Etching of nearly all metals may be accomplished by making them anodic in a suitable solution. (This is just the opposite of electroplating). In general a solution of a salt of the same metal as that which is being etched may be used, or a neutral salt of sodium or potassium. For example, copper may be etched anodically in a solution containing 200 g./l. or 27 oz./gal. of copper sulphate. Steel may be etched by making it the anode in a solution containing 60 g./l. or 8 oz./gal. of sodium chloride. The cathode should be of carbon or of any metal that is not attacked by the solution. A direct current is used with a low voltage, usually from 2 to 4 volts. The voltage should be regulated so as to produce a current that dissolves the metal, but does not evolve much oxygen, which may lift off the resist. One advantage of electrolytic etching is that the metal is not attacked except when the current is passing,

and hence the depth of the lines can be readily controlled.

A design may also be produced on metal sheet by mechanical means. The areas which are to remain bright and shiny are covered with masking tape or a stencil. The article may then be sandblasted to dull the surface and produce a pleasing contrast.

#### Ink for Brass

Rub 2 oz. of copper carbonate with a little water and add sufficient solution of ammonia (10%) to dissolve, then add 10% of glycerin.

#### Fluorescent Chalk

Chalk suitable for making blackboard writing, which is luminous, may be made by soaking ordinary calcium carbonate blocks, used to cut chalk sticks from, in a concentrated solution of calcium salicylate.

Many pastels are ordinarily fluorescent and these may be employed where a fluorescent chalk is required.

Invisible writing with chalk may be made by impregnating charcoal sticks or black chalk with theobromine or sodium salicylate. When this chalk is used, on a slate blackboard, the marks will not be visible at a distance but when illuminated with ultra-violet light they will show up with a bright blue color.

#### Fluorescent Inks

Fluorescent inks are very useful for marking documents, papers, books, etc. Various substances may be used.

#### Formula No. 1

Dissolve quinine sulphate in a small quantity of water to which a few drops of sulphuric acid have been added. This solution is applied to cloth or paper and when dry is invisible in daylight and shows a blue fluorescence under ultra-violet light.

No. 2

Dissolve anthracene (purified by recrystallizing from pyridine) in benzene. Apply to paper or cloth and dry. It is invisible in daylight and shows a brilliant blue fluorescence under ultra-violet light. Crude anthracene when applied in the same way is almost colorless in daylight and green under ultra-violet light.

No. 3

Luminous zinc sulphide is mixed with dammar varnish and applied to cloth or paper. When dry, the material fluoresces under ultra-violet light and then phosphoresces when removed.

#### Fluorescent Crayon

Fluorescent crayon is made by impregnating ordinary wax base used in crayon manufacture with a fluorescent dyestuff.

For phosphorescent crayons, calcium sulphide phosphor may be added to the crayon base and markings made with the crayon will glow for some time after excitation with white light or, preferably ultra-violet light.

Zinc orthosilicate or theobromine may be added to the crayon base to make its writing fluorescent.

Magic Writing Pad

Cardboard is coated with the following composition and covered

with a sheet of waxed or oiled paper or cellophane. When the latter is written on with a stylus or pencil the writing appears. When this sheet is lifted away from the coated cardboard the writing disappears.

Beeswax	4
Venice Turpentine	9
Lard	4
China Clay	$3\frac{1}{2}$
Carbon Black	1
Mineral Oil	<b>2</b>

The consistency may be varied by varying the proportions of liquid in the formula.

### Tailor's Chalk White

French Chalk	20
Pipe Clay	20
White Curd Soap	6
Water, To suit	

Make into a stiff paste with sufficient water. From this form slabs of desired size and press into the oiled wooden or metal moulds. After moulding dry the pieces in a moderately heated place.

Yellow

1 000000	
Chalk Powder	28
Soapstone	18
Pipe Clay	10
Yellow Ochre	7
Lemon Chrome Yellow	$1^{1}/$
Water, To suit	
Proceed as above.	
Blue	
Chalk	20
Pipe Clay	20
Soapstone	15
Ultramarine Blue	10
Water, To suit	
Proceed as above.	
Black	
Soapstone	56
Doaharone	50

Bone Black

Yellow Soap	6
Gum Arabic	<b>2</b>
Glycerin	1

Dissolve the gum in a small quantity of water, add glycerin, mix in pigments. Then grind to a smooth paste with water and proceed as above.

# Erasable Crayon U. S. Patent 2,215,902 Charcoal, Powdered 130 Kaolin 50 Calcium Carbonate 20 Black, Greaseless 20 Soap 2 Gum Tragacanth 5

## Soluble Crayon for Marking Textiles Paraffin Wax 649 Stearic Acid 125 Ultramarine Blue HM 24 Emulsifier S-489 91

Melt paraffin and stearic acid to about 158° stir in the ultramarine blue. Turn off heat and add S-489, while stirring thoroughly. Continue stirring until it begins to solidify. Add to molds and chill as soon as possible.

#### Heat Resisting Stencil Sheet U. S. Patent 2,242,313

Flexible "Cellophane" is coated with the following mixture:

Mineral Black	5
Castor or Cottonseed Oil	12
Carnauba Wax	49
Aluminum Powder	34

#### Ink Eradicator

Solution A—Dilute 4 cc. of concentrated hydrochloric acid to 100 cc. with water. Label—Solution A.

Solution B—Dilute 50 cc. of commercial "Chlorox" or "Javelle Water" with 50 cc. of water. Label—Solution B.

Application: Moisten the ink blot or mark with a drop or two of Solution A. Blot. Then moisten with a drop or so of Solution B. Blot and then let dry before writing over the bleached area.

#### CHAPTER TEN

#### LUBRICANTS AND OILS

Wood and Fiber Lubricant Wood and nonmetallic surfaces of the type of synthetic fibers are difficultly lubricated, since the lubricant usually causes swelling or remains entirely on the surface. This is true even when the friction is against metal. A suitable lubricant for this purpose can be prepared from 1 oz. camphor, sufficient castor oil to make a thin paste, and 2.5 lb. of finely shaved paraffin wax. The camphor is first dissolved in the castor oil, with slight heating if necessary; the paraffin wax is then added and the whole well mixed until solution is complete (eventually with further heating). The mixture is cooled and stored in air-tight containers.

Driving Journal Lubrican U. S. Patent 2,229,030	t
Sodium Laurate	25
Sodium Arachidate	20
Refined Petroleum	45
Heavy Black Petroleum	10

Diesel Engine Lubricant
U. S. Patent 2,234,005
Lubricating Oil 95
Aluminum Petroleum
Sulphonate ½-5

Chassis Lubricant
U. S. Patent 2,264,353
Aluminum Stearate 3–8 %
Aluminum Naphthenate 0.5%

Tolyisobuty telle	U.	1 70
Viscous Lubricating Oil, To make	100	%
Gyroscope Bearing Lu	ıbrica	$_{ m int}$
Sperm Oil		50
Mineral Oil, Refined		50

0 10%

Polyricobutyrlana

Dental Lubric	ant
(For removing inlay	pattern)
Castor Oil	1
Diglycol Dilaurate	1

#### Lubricant for Glass Molds Formula No. 1 Varnish 1 l.

Linseed Oil ½ l.
(Boiled with a little rosin)
Minium (Finely
Sifted) 5 kg.

Turpentine 40 cc.
After applying above to mold, dust lightly with powdered charcoal and dry.

No. 2		
Varnish	1	1.
Linseed Oil	1	1.
Rosin	300	g.
Chestnut Flour	250	g.
Boil together.		_

Die Member Lubric	ant
U. S. Patent 2,276,	453
Stearic Acid	20-30
Spermaceti	4-6
Lanolin	4-6
Borax	1-3
Water. To make a good	emulsion

Drawing Die Lubricant		
U. S. Patent 2,121	,606	
Kaolin or Bentonite	17.00	
Water	100.00	
Boric Acid	5.75	
Magnesium Oxide	0.45	

Nickel Working Lubricant

Nickel alloys can now be drawn, stamped or formed and then annealed without cleaning, by using a dispersion of Diglycol stearate in water.

Diglycol stearate S is a white, wax-like solid, dispersible in water, and has a melting point of 51–54° C. It will fire off completely at any annealing temperature (400° F. min.) in an atmosphere of Oxygen or Hydrogen.

As an example, an alloy composed of 78% nickel, 4% manganese, copper and iron is drawn with a 2% dispersion of Diglycol stearate, as follows:

Flat plate approximately 5 inches square—

1st draw—2" deep, 1½" diameter (anneal).

2nd draw—3" deep, 1" diameter (anneal).

For drawing and stamping, usually a 1% concentration is sprayed on, and is sufficient as a lubricant. Even lesser concentrations can generally be used to replace sulphonated oils which are used as coolants in stamping. In all cases, there was no residue on firing.

Lubricant for Metal Working
U. S. Patent 2,238,738
A. For forming metals.
Soap 56
Iron Oxide 4

40

Lime Water

B. For drilling or cutting	steel.
Soap	28
Iron Oxide	2
Lime Water	70

Metal Drawing Lubricant
British Patent 543,253
Mineral Oil 100
Bentonite 25–33
Curd Soap (1% Solution) 9900

Wire-Drawing Lubricant
U. S. Patent 2,126,128
Stearic Acid 65
Mineral Oil 35

Melt together, mix well and allow to cool. Apply melted and wash off with hot dilute caustic soda solution.

Non-Gumming Lubricating Oil U. S. Patent 2,229,858 Lubricating Oil 99.5 Cyclohexylamine 0.5

Coolant and Lubricant for Rolling Strip Steel

U. S. Patent 2,246,549
Palm Oil 1 -50 %
Water 50 -99 %
Lactic Acid 0.3-33.3%

Pipe Thread Lubricant U. S. Patent 2,205,990

 $\begin{array}{ccc} \text{Cup Grease} & 40 & -45\% \\ \text{Zinc Dust} & 60 & -55\% \\ \text{Nitrobenzol} & 0.1-1\% \end{array}$ 

Anti-Seize Compound for Threaded Fittings Formula No. 1

T OIIII aid I i O. I	
Asphalt	9
Gilsonite	1
Lubricating Oil	10
Graphite (200 Mesh)	10

Petrolatum	10
White Lead	60
No. 2	
Petroleum Oil, Refin	.ed <b>60</b>
Mica (100 Mesh), F	
Rustproofing Lul	bricant
U. S. Patent 2,2	22,487
Lubricating Oil,	
Light	97.5–87%
Lard Oil	2 -10%
Lecithin	0.5- 3%
Corrosion Preventive	Compound
(For motors and	-
Lard Oil	engmes)
Methylaminophenol	
Peanut Oil	30
Oil-Insoluble Stopcoc	k Lubricant
Soluble starch	10 g.
Glycerin	25 g.
*	

Stir the starch thoroughly into the glycerin, heat to 140° C., and allow to stand for a short time until any sediment has settled. Decant the clear liquid and allow to remain overnight. The resulting product is a thick, greasy preparation, soluble in water but not in oil.

## Stop-cock Lubricant (Ether Insoluble)

A gel is prepared by suspending 9 grams of soluble starch in 22 grams of glycerol and heating to 140° C. After standing for a short time, the clear solution is decanted from the sediment and allowed to cool. The mixture is then allowed to stand overnight, when it takes on the consistency of a thick grease and can be employed as a lubricant.

	Hydraulio	e Fluids			
Form	nula No. 1	No. 2	No. 3	No.	4
Castor Oil	45	25	40	20	cc.
Propylene Glycol	15	15	25	25	cc
Hydroxyethyl Butyl Ether	10-20	10-20			
Alcohol	$17\frac{1}{2}$	38	$32\frac{1}{2}$	53	cc.
Phosphoric Acid	$\frac{1}{4}$	$\frac{1}{4}$	$\frac{1}{4}$	$\frac{1}{4}$	cc,
Cresylic Acid	$\frac{1}{4}$	$\frac{1}{4}$	$\frac{1}{4}$	, 1	cc.
Diethanolamine, Enough t	to give a ne	utralization	number of	4–8.	

Anti-Static Belt Dressing
Fish Glue 9 oz.
Glycerin 7 oz.
Sulphonated Castor Oil 7 oz.
Water 12 oz.
Lampblack 6 oz.
Ammonia (2%) 2 oz.

The glue and glycerin are first heated together, with frequent stirring, for two hours, at a temperature at which the mixture barely boils. The other ingredients are then stirred into this warm mixture in the order named. The two ounces of approximately 2% ammonia can be made by adding  $\frac{1}{4}$  oz. of ordinary household ammonia to  $1-\frac{3}{4}$  oz. of water.

These quantities are sufficient to make about a quart of dressing, which should be kept in a closed container. This dressing should be used regularly and may be applied to the side that bears against the pulleys while the belt is running.

For use on fan belts of automo-

biles and tractors, and for similar equipment, a simpler, very easily made preparation can be obtained by mixing graphite and glycerin in the desired proportions. Applied to the areas of friction this simple product is said to be very helpful in reducing static electricity.

Cutting	Oil	Вε	ses
Formu	la I	No.	1

Cottonseed Oil	71.2
Rosin	28.8
Oleic Acid	2.0
Triethanolamine	1.2
No. 2	
Talloil	32
Caustic Potash (45%)	8
Tertiary Butyl Alcohol	8
Mineral Oil	192

Rust Inhibitor for Cutting Oils German Patent 680,884

Use 1/40-1/2 parts of sodium nitrate to each part of soluble oil in finished emulsion.

"Soluble" Oils Formula No. 1		
Sulphonated Fish Oil	7	5
Pale Oil No. 100	2	5
No. 2		
Sulphonated Neat's Foot		
Õil	6	0
Pale Oil No. 100	4	0
No. 3		
U. S. Patent 2,231,21	14	
Rosin Soap	9%	0
Naphthenic Soap	9%	ó
Rosin	2%	ó
Naphthenic Acid	2%	6
Sulphonated Castor Oil	3%	ó
Butyl Carbitol	1%	0
Water	4%	ó
Mineral Oil, To make	100%	ó

Non-Foaming Soluble Oil			
U. S. Patent 2,2	65,799		
Mineral Oil	85.10 %		
Mahogany Sulphon-	,		
ates	9.50 %		
Naphthenic Acid	2.50 %		
Sodium Hydroxide	0.40 %		
Water	1.60 %		
Isopropyl Alcohol	0.90 %		
Sodium Aluminate	0.2 - 1%		

Engine Crankcase Flushing Oil
U. S. Patent 2,259,872

Mineral Oil (28° or
Higher A.P.I.
Gravity: Saybolt
Viscosity 80–140
at 100° F.) 60–80%

Dichlorbenzene 5–20%

5-20%

Slushing Oil for Protecting Steel
U. S. Patent 2,124,446

Magnesium Naphthenate 5–10%

Light Lubricating Oil,
To make 100%

Isopropyl Alcohol

#### Sticky Viscous Oil

Where an extremely sticky oil is needed, use Standard Viscous Oil (Standard Oil Co. of Calif., Richmond, Calif.) which is a mixture of isobutene polymers. Commercial grades run from No. 8 (color and viscosity like honey in the summer) through grades of increasing viscosity, but same color, numbered as 16, 32, to No. 64, which is so stiff that it will scarcely run out of a bottle at room temperature. Stickiness can be increased by dissolving resins therein.

Drying Oil from Corn Oil A kettle is filled ¾ full with corn oil and zinc shavings (6% of the

oil). The oil is slowly heated to 200-290° C. and kept at that temperature until its viscosity at 20° is 300-400 seconds. The oil is then allowed to cool to 170-180° C. It is then poured into another kettle and mixed with 3% zinc resinate. When the latter dissolves, drier is added followed by 92% of mineral spirits. After standing 5 days, the drying oil has a viscosity of 6-9 seconds. The zinc shavings can be used over again 5 or 6 times.

## Black Harness Oil

Ceresin 2 2 Ozokerite 32 Cod Oil 26 Herring Oil Whale Oil 14 Pale Oil No. 100 22 Black Stain \*

Mix all components, except dye, until melted and dissolved. Add dye; mix thoroughly and let it cool. This oil is good if it leaves a black spot on paper. If spot is not black, some more dye should be used.

\* Preparation of Black Stain

Oil soluble (black) nigrosine base should be heated in red oil or stearic acid for 4-6 hours at a temperature above 100° C. but not exceeding 105° C. Proportion of dye to fatty acid is 1:3.

Transparent Lubricant Grease French Patent 849,105 Spindle (Mineral Oil) 100 kg. Aluminum Stearate 6 kg. Vegetable Fat 4 kg.

Penetrating Liquid Lubricant Grease U. S. Patent 2,247,577

Aluminum Stearate 1 -10%

Morpholine 0.5 - 3%Lubricating Oil. To make 100% Gasket Grease Potash Soap 22Glycerin Castor Oil, Heavy Bodied Heat together, with stirring to 121° C. Turn off heat and stir till temperature falls to 38° C. Pour into containers. Wool Grease Substitute Petrolatum 50-100 Ester Gum 50 Heat to 100° C, and mix until uniform. Drilling Fluids, Well Formula No. 1 U. S. Patent 2,258,202 Graphite 2 Bentonite 98 Water, To suit No. 2 Dutch Patent 50,258 Crude Petroleum (Boiling Above 200° C.) 62.5Hematite, Finely Ground 126.0 Mexican Asphalt 41.0 No. 3 U. S. Patent 2,109,337 Clay 1 Silica, Amorphous (325) Mesh) 99 No. 4 U. S. Patent 2,122,236 Iron Blast Furnace Flue Dust (Finer Portions) 30 Beidellite 10 Water 60 Dubbing, Leather Ceresin 9 Aluminum Stearate 1

Neatsfoot Oil

Tallow

40

50

Petroleum Jelly	
Formula No. 1	
Petrolatum (White)	20
Ceresin	3
Paraffin Wax	4
White Light Mineral Oil	73
No. 2	
Petrolatum (White)	10
Paraffin Wax	6
Ceresin	3
Ozokerite	<b>2</b>
Cetyl Alcohol	6
White Heavy Mineral Oil	73

Mix all solid components. Heat until melted and dissolved. Heat oil in separate container 5–10° above temperature needed to melt the solid components. Mix all components and stir well. Pour in containers and allow to solidify without stirring.

Bleaching Oils and Fats

Melt the fat at 60-65° C. and stir with 2% of its weight of hydrogen peroxide 30% strength. After two hours, during which a foam is produced, the whole is covered with a cloth and left overnight. The oil may be heated for a further hour, the temperature being raised to 80° C. An unmistakable improvement in color and odor results from the above treatment, but rebleaching with a further 2% peroxide results in very considerable lightening in color and diminution in odor.

Bleaching with hydrogen peroxide is largely dependent on the efficiency of the agitation. The most efficient method appears to be the use of compressed air which gives an excellent emulsion. The stronger the strength of peroxide, added to the fat, the higher the temperature required for adequate bleaching. It is preferable to use a 30% rather than a 60% strength.

Bleaching soap fats with organic peroxides, such as benzoyl peroxide, has certain advantages as these chemicals are fairly readily soluble in oils and can be easily and quickly processed. Benzoyl peroxide is a white, almost odorless powder, insoluble in water, but completely soluble in oils and fats at 80° C. When warmed it decomposes readily into benzoic anhydride and free oxygen, finally forming benzoic acid, which is quite harmless to the oil but may, if desired, be volatilized away by blowing with steam. Only 0.1 to 0.2% by weight of oil is necessary to effect bleaching action. The usual method is to stir the requisite quantity of benzoyl peroxide into the oil at 70 to 80° C. until it is completely dissolved, when the whole is heated to 95 to 100° C. Bleaching is usually complete in 15 to 30 minutes or even less, leaving the fat quite clear from sediment.

#### CHAPTER ELEVEN

#### MATERIALS OF CONSTRUCTION

#### Fireproofing Solution for Wood Formula No. 1

The solution is made by dissolving separately 1½ oz. of sodium bichromate and 7 oz. zinc chloride and then combining in a total of 1 gal. of water.

Color may be added for decorative, identification or other purposes. However, the solution exerts a powerfully destructive action on most coal-tar colors. Of many so checked only the following three are unattacked:

Amacid Blue V Kiton Red S Amacid Yellow T Ex.

These may be combined to produce a number of shades.

The wood is brushed generously or allowed to soak in the solution and then dried.

No. 2	
Ammonium Chloride	12
Zinc Chloride	8
Water	80

Wood Fence Post Preservation

Air dry for 24 hours after cutting and scrape off exuded pitch. Impregnate for 3 days in

Copper Sulphate or Zinc

Chloride 2 lb. Water 1 gal.

Then air dry for at least a month before setting.

#### Fluorescent Wood

Ordinary locust wood fluoresces a bright yellow under ultra-violet light and this material may be fabricated into a wide variety of objects. Locust wood can be turned on the lathe and still retain its fluorescence.

An alcoholic solution of turmeric, dyes wood a yellow color and under ultra-violet light a bright yellowish fluorescence is noted. When turmeric dyed wood is treated with acids or alkalies the fluorescence is brightened and changed in hue.

Uranine, eosine, acriflavine, and other fluorescent dyes in 0.5% alcoholic or aqueous solution can be used to make wood fluorescent.

When wood is rubbed briskly with lubricating oil or petrolatum a fluorescent coating is imparted which remains for a considerable time. The fluorescence with these substances is bluish.

An alcoholic solution of anthracene colors wood greenish and under ultra-violet light a brilliant greenish fluorescence is seen.

## Acid Resisting Glass Flux U. S. Patent 2,225,159

Lead Oxide	50-75%
Silica	12-25%
Boric Oxide	1-10%
Titanium Dioxide	1- 8%

Infra Red Absorbing	Glass
U. S. Patent 2,226,	
Phosphoric Acid	81
Alumina	$7\frac{1}{2}$
Barium Carbonate	$4\frac{1}{2}$
Ferric Phosphate, Hy-	
drated	1-10
Fuse together.	

Decorative Glasswan	re Glaz <b>e</b>
U. S. Patent 2,22	25,161
Lead Oxide	55-80%
Silica	15-35%
Titanium Dioxide	2- 7%

Transparent Red Glaze
U. S. Patent 2,130,215

Lead Oxide 686
Boric Acid 249
Flint 120
Cadmium Carbonate 94
Cadmium Sulphide, Red 30
Melt below 1000° under nitrogen.

#### Improving Adhesion of Vitreous Enamel

U. S. Patent 2,271,706

Dissolve 0.6 lb. antimony tetraoxide in a gallon of cold 18° Bé. muriatic acid. Then add 0.0006 lb. of arsenic trioxide. Then add enough solution of stannous chloride in strong muriatic acid to turn the solution colorless or pale green.

After the usual acid pickle, the article is dipped in the above bonding solution, then rinsed in cold water for 1–5 minutes and neutralized in a solution containing ½ to 1 oz./gal. of a mixture of 10%–90% borax plus 90%–10% soda ash at 140°–180° F. for 2 to 8 minutes.

Cement Floor Tile British Patent 524,227 Portland Cement 610 g.

Aluminous Cement	200	
Lime Cement	90	g.
	000	
Casein (10% Solution)	200	cc.
Silver Sand 2	2500	g.
Washed, Sharp Sand	250	g.
Color (Chrome Green)	100	g.

Wall Tile Composition	
British Patent 541,695	
Ball Clay	25
Flint	30
Tale	40
Felspar	5
Barium Carbonate	1/2

Glazed Finish for Bricks

The first thing to do is to build up a good surface on which to apply the glaze. Go over the brick with a stiff bristle brush or wire brush to remove all loose mortar, dust, etc. Then put on a priming coat mixed on this basis:

White Lead	100	lb.
Raw Linseed Oil	5	gal.
Turpentine	$\frac{3}{4}$	gal.
Liquid Drier	1	pt.

This mix makes about 9½ gal. of paint that should cover about 200 sq. ft. of surface per gallon.

After the priming coat dries, apply a second coat mixed on this basis:

CONTROL		
White Lead	100	lb.
Raw Linseed Oil	3	gal.
Turpentine	. 1	gal.
Liquid Drier	1	pt.

This mix makes about 7% gal. of paint that will cover at the rate of 400 sq. ft. per gallon.

A final paint coat that dries fairly flat, on which to apply the glaze, is made on this basis:

White Lead	100	lb.
Lead Mixing Oil	4	gal.

This mix makes 7¼ gal. of paint that will cover about 500 sq. ft. of surface per gallon. The paint should be tinted with colors-in-oil to match the desired color.

When this coat is dry and hard, brush on the glaze coat. The glaze may be mixed as follows:

Lead Mixing Oil 3 gal.
Spar Varnish 1 gal.
or

Flatting Oil 2 gal. Spar Varnish 2 gal.

To tint the glaze, add to it small amounts of the selected colors-in-oil. Colors often used are raw and burnt umber, and raw or burnt sienna.

Heat Insulation
U. S. Patent 2,130,091
Asbestos 7
Magnesium Oxide, Magnesium Sulphate (Addition Compound) 32
Vermiculite 61

Add the above to water, to make a thick slurry. Mix well and pour into molds. Set at 21° C. for 48 hours and dry at 150° C.

Insulating Firebrick
U. S. Patent 2,242,434

Calcium Sulphate ½ H<sub>2</sub>O 37

Sawdust 37

Georgia Kaolin 100

Form to shape and burn before much moisture is lost.

Sound and Heat Insulating Cement
Canadian Patent 402,601
Kaolin 50 g.
Grog 50 g.
Mix the above and to it add 150–
175 cc. of the following which has

been beaten vigorously:

Water	190	g.
Bentonite	6	g.
Soap Bark	<b>2</b>	g.
Karaya, Gum	$^2$	g.

Porous Cast Refractory U. S. Patent 2,224,498	
Magnesium Oxide	40
Alumina	40
Silica	<b>2</b> 0

Silica	20
B-10-7-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-	
Refractory Cement	
British Patent 532,463	
Fired Clay	7
Aluminous Cement	10
Mineral Wool	2
Kieselguhr	2
This is applied on top of f	ibrous
heat insulation materials.	

Artificial Marble	
Swiss Patent 213,857	
Formula No. 1	
Colored Cement	12
Granulated Marble	12

They are mixed dry and then made into a thick paste with water.

No. 2	
White Cement	12
Granulated Marble	12
They are mixed similarly to	For-
mula No. 1.	
No. 3	

210.0	
Cement	50
Stone (washed and pow-	
dered the size of sand)	75
Ingredients are dry mixed.	
No. 4	
Cement	50

0011101	10				00
Stone	(crushed	as	in	For-	
mul	a No. 3)				75
Comd					75

To make the slabs, Formula No. 1 is poured into a mold and No. 2 is poured on top of it. The two are caused to mix so as to produce an

effect of "veins." This is followed by Nos. 3 and 4. The whole is compressed at 200–250 atmospheres. The pressed blocks or slabs are kept for 20 days and then polished with powdered (No. 100) silicon carbide. After another 10 days they are polished again with No. 300 silicon carbide.

Chemically Resistant Machinable Sandstone

#### U.S. Patent 2,227,312

Porous sandstone of apparent density of 2.1–2.4 is heated to 220–240° F. and immersed in the following:

Asphalt 20–40% Gilsonite 80–60% at 220–240° F. under 20–100 lb. per sq. in. pressure. After impregnation, remove adhering bitumen.

Rapid Drying Plaster
U. S. Patent 2,245,458

Calcium Oxide 65
Antigorite 35
Sulphur 2

Building Plaster British Patent 530,001

Asbestos Fibers 8 lb.
Pipe Clay 32 lb.
River Sand 160 lb.
Cement 160 lb.
Water 28–33 gal.

For fine plaster, replace the river sand by marble dust.

#### Fluorescent Plaster

By impregnation of plaster of Paris, while still in the plastic state, with zinc beryllium silicate phosphor or calcium sulphide phosphor a highly fluorescent solid may be obtained. This can be put to a variety of spectacular uses. Slow Setting Portland Cement U. S. Patent 2,290,956 Add 0.2-0.4% casein on weight of dry cement.

Light Weight Cement Mix Canadian Patent 402,600 Grog 30 g.

 Grog
 30 g.

 Kaolin
 30 g.

 Water
 40 g.

To the above mixture add 148 cc. of a beaten mixture of

Soap Bark 2 g. Starch 4 g. Water 194 g.

Cement or Plaster
U. S. Patent 2,227,790
Portland Cement 40
Silica, Ground 35
Calcium Hydroxide, Hydraulic 20

Magnesium Silicate (Colloidal) 5
Cement Setting Retarder

U. S. Patent 2,211,368

Boric Acid 52.5

Borax 26.2

Gum Arabic 5.2

Calcium Tartrate 12.6

Tartaric Acid 3.5

About 0.5% of above mixture is added to the cement.

Quick Setting Magnesia Concrete
U. S. Patent 2,242,785

Magnesium Chloride
1
Magnesic, Caustic Nonsintered
8
Water
15

Porous Light Concrete U. S. Patent 2,240,191

About 4.5 bags of cement, each bag corresponding to about 1 cu. ft. or 94 lb. are mixed with about 17.5 cu. ft. of sand. About 13 lb. of about

35% bleaching powder with about 1/7 lb. of ground licorice root are added to the cement and sand mixture. These materials are now mixed with the necessary amount of water in a conventional cement mixer, about 2.5 lb. of granular urea carrying approximately 42% nitrogen is added and, after mixing, the mixture is poured into the mold or formed in the conventional manner. About 1 cu. yd. of porous concrete is obtained, having a density of about 0.6 of normal.

Concrete Coating
Swiss Patent 204,185
Portland Cement, White
Gravel, Fine
Water
Color, To suit

45
46
9

#### Fluorescent Concrete

By adding several per cent of zinc orthosilicate phosphor to ordinary cement before adding the water and sand, a brilliant green fluorescing concrete is obtained. The phosphor may be varied to get other colors and effects. Many small articles, such as signs and models, may be built with this concrete.

Crystalline Floor Hardener Formula No. 1

Magnesium Fluosilicate  $(6H_2O)$  56.75

Zinc Fluosilicate 25.75

Calcium Fluosilicate 17.50

No. 2

Magnesium Fluosilicate 67

Zinc Fluosilicate 33

Make at least two applications on floors, allowing 24 hours for drying of the first coat. In the first dissolve ½ lb. magnesium fluosilicate crystals in 1 gal. of water and in the

second 2 lb. of magnesium fluosilicate crystals in 1 gal. of water. Apply with a broom or whitewash brush. On new concrete, make the application 48 hours or more after the concrete has hardened. On old concrete, apply when the cement is thoroughly clean, dry and free from paint or oil. In general, the 2½ lb. of crystals in the two above applications should treat 100 sq. ft. of surface.

Roofing Composition U. S. Patent 2,243,494

Roofing and Building Material U. S. Patent 2,210,348

A woven cotton base is imbedded in the following heated composition:

J11 •	
Rock Asphalt	200
Asbestos Fiber	50
Rubber	5
Rosin	5
Cottonseed Oil	30

Patching Interiors of Furnaces U. S. Patent 2,124,865

Furnace interiors, while in operation, are sprayed with a water slurry of

Sandstone (200 Mesh) 97 Fireclay 3

Repairing Rough and Textured Walls

If a test of the surface reveals the fact that the plaster surrounding the crack is sound—not loose—it is a pretty good plan to ignore the advice so freely given in trade papers in the past—to cut out the cracks

back to the plaster, for unless you can be certain that you can imitate perfectly the surface on which you are working so that no trace of the repair remains it is better to proceed as follows, bearing in mind that what is said should not be construed to refer to smooth plaster walls. Cracks in them should be handled in the usual way.

#### Repairing Texture (Plastic) Paint Surfaces

With a sharp-pointed jack knife, clean out any loose plaster that may be adhering to the edge of the crack. Take out a little of the plaster in the rear of the surface to a depth of about one-eighth of an inch in a wedge shape so that the crack is widened beneath the surface. Use every precaution not to widen the surface of the crack any more than is absolutely necessary.

When the crack is cleaned thoroughly, work a thin mixture of flat paint into the crack and allow it to dry. This produces a foundation for the filling of the crack which will follow and will prevent the oil from the filler from being sucked into the plaster. This step is vital and upon its proper performance depend the success of and the life of the repair.

Mix together 12½ lb. of heavy paste white lead and ¼ pt. of flatting oil. Stir until a smooth, creamy mixture results. The consistency will be very heavy.

Mix together 5 to 6 lb. of dry whiting and ½ pt. of flatting oil. Add the whiting to the oil a little at a time and stir until a smooth, even batter results.

Mix together the lead mixture and the whiting mixture and stir until one is thoroughly incorporated with the other, then add a small amount of pale drier and work this in thoroughly.

There should now be a thick, almost putty-like mass of material, which, if kept in a covered can with a thin coating of water on top, should keep indefinitely.

Before using pour off the water, take what is required from the can, level up that which remains in the can, and recover it with water.

Place some dry whiting in a shallow pan or in the cover of a lead keg and place the mixture removed from the can on the powdered whiting. Knead the whiting into the mixture, adding whiting if necessary until a stiff putty is formed. This is the material to be used for filling cracks in rough, sand finished or textured walls.

Take a gob of the special putty in the left hand and with a reasonably flexible putty knife or spatula in the right hand work this putty down into the crack which has previously been prepared to receive it. Fill the crack just a trifle more than full and then go over the surface of the crack with a small sash tool and a very little flat paint or flatting oil. This softens the surface of the filler and will allow you to manipulate it to look like the surrounding surface.

To manipulate the surface of the putty to match a sand finished surface have on hand a little fine sand, a whisk broom and the before mentioned sash tool.

Throw a little of the sand onto the wet surface of the crack, then drag the whisk broom over the surface until a sufficient amount of sand has been worked into the surface of the crack to match the surrounding surface.

When certain that it matches, run a thin coat of flat paint over the sand to bind it. Be sure it is a thin coat for if it is thick enough to fill up the sand finish in the immediate vicinity of the crack, it will show through the final coats.

It is a good idea to confine the putty mixture to within an eighth of an inch of the sides of the crack and to brush the thin mixture of flat paint out to a feather edge to a point a foot or so away from the crack on either side.

This permits painting the surface after the thin, feather edged, touch-up coat is dry without a trace of the repair appearing.

#### Textured Walls

The procedure is similar but instead of the whisk broom use the same tool for manipulating the wet surface of the crack as was used to produce the original texture. Manipulating must be done in such a manner as to blend into the surrounding surface without leaving any trace of the repair.

It may or may not be necessary to put on the final thin touch-up coat and feather edge it out from the crack. Here again use judgment based on the appearance of the repair.

#### Rough Plaster Walls

Follow the same procedure as for textured walls. A spatula, putty or wide knife can frequently be used to imitate rough plaster surfaces on small areas such as the surface of cracks.

#### Repairing Holes in Rough or Textured Walls

Naturally, large holes in rough, sand finished or textured walls must be repaired in the usual way by cutting away the plaster clear back to the lath in accepted wedge shape fashion.

The holes must then be wet down and filled with patching plaster not quite level with the surface, leaving it just enough below the surface so that the sand finish, rough coat or texture will be level with the surrounding surface when it is later applied on top.

When the patching plaster is thoroughly dry the decorator must texture the surface of the hole to match the surrounding surface. This will require rare care and good judgment, to decide what tools and what type of material were used to produce the original texture.

When the texturing is finished, the new texturing should be touched up with flat paint and allowed to dry, after which the entire wall should be given a coat of white, ivory or pale cream flat paint.

When that is dry, the surface may be reglazed in the usual way.

Holes in Sand Finished Walls

The patching is done in the same way up to the point where the patching plaster has been put in and allowed to dry.

Next a coat of varnish is applied to the patch and when it is dry a reasonably heavy coat of paint is applied and sand is thrown on it and manipulated until it matches the surrounding surface.

#### CHAPTER TWELVE

#### METALS, ALLOYS AND THEIR TREATMENT

Magnesium Die Casting Surface Treatments

A chrome-pickle treatment is normally given all magnesium die castings to protect the metal during shipment, storage and machining. The treatment will remove 0.006–0.002 in. of metal from the surface and is not recommended on machined surfaces where close dimensions must be held. The following solutions may be used:

(a) Sodium Dichromate  $(2H_2O)$  1.5 lb. Conc. Nitric Acid (sp. gr. 1.42) 1.5 pt. Water, To make one gallon.

(b) Chromium Trioxide 1.0 lb.
Conc. Nitric Acid
(sp. gr. 1.42) 0.9 pt.
Water, To make one gal.

Temperature of the solution should be 125–135 deg. F. and time of treatment 10 sec. After removal from the treating solution, die castings should be exposed to the air for about 5 sec. before rinsing thoroughly in cold water and then in hot water to facilitate drying.

#### Sealed Chrome-Pickle

A modification of the chromepickle which will give increased corrosion resistance, consists in boiling in a bichromate solution. The die casting, which has been previously chrome-pickled, is immersed for 30 min. in a bath containing 1–2 lb. of sodium, potassium or ammonium bichromate per gal. The bath is maintained at boiling temperature and the solution is controlled to a pH of 4.0–4.4.

Hydrofluoric Acid-Dichromate

This treatment gives practically no change in dimensions. Parts are immersed for 5 min. in a solution containing 15–20% by weight of hydrofluoric acid, and then are rinsed thoroughly in cold water, boiled for 45 min. in a solution containing 1–1.5 lb. of sodium dichromate per gal. and then rinsed thoroughly in cold water followed by a dip in hot water. The concentration of hydrofluoric acid should not be allowed to fall below 10%.

Hydrofluoric Alkaline-Dichromate

Parts are immersed for 5 min. in a 15-20% hydrofluoric acid solution, washed thoroughly in cold running water, and boiled for 45 min. in the following solution:

Ammonium Sulphate 4 oz. Sodium Dichromate  $(2H_2O)$  4 oz. Ammonia (sp. gr. 0.880)  $\frac{1}{3}$  fl. oz. Water, To make one gal.

Depletion of the bath is indicated by non-uniform or pale coatings, slowness of coating formation, and by an increase in the pH to about 6.2. To replenish add equal parts of chromic acid and concentrated sulphuric acid (sp. gr. 1.84) until the pH is decreased to 5.6. The best operating range of the bath is a pH of 5.6–6.0. Wash thoroughly in cold water and boil for at least 5 min. in a solution containing one oz. of arsenious acid per gal. Because of the low cost of this bath no control is advocated.

#### Chrome-Alum Treatment

Parts are immersed in a boiling solution of the following composition:

Potassium Chrome Alum  $(24 \text{ H}_2\text{O})$  4 oz. Sodium Bichromate  $(2\text{H}_2\text{O})$  13.3 oz. Water, To make one gal.

Time of treatment may range from 2–15 min. Upon removal from the bath, the parts should be rinsed thoroughly in cold water followed by a hot water rinse to facilitate drying. The solution may be revivified by the addition of sulphuric acid not exceeding 0.33 fluid oz. per gal. or sufficient to just redissolve a brown precipitate which settles out. The solution should then be boiled. It is best controlled by additions of sulphuric acid to maintain the pH between 2.5–3.5. The pH of a depleted solution is 5.5.

#### Pickling Sterling Silver

Fire scale on sterling silver can be removed in a solution of 3 parts nitric acid, 1 part of water, by volume. The work will turn gray in color. A few seconds is all the time required. For best results, operate solution hot, by having the crock surrounded by a hot water bath. Silver can be recovered from a spent dip by adding a chloride.

An alternative procedure to the use of the nitric acid dip is to heat the sterling article, after fabrication is complete, to a dull red. Then clean, and follow with a pickle in 8% sulphuric acid. The fire scale will then be uniform all over the article and it can be satin finished and burnished, or color buffed. The silver will not have as white a color or take as high a luster, but will have a good color.

Work made the anode in a solution of 8 oz. sodium cyanide, 4 oz. sodium ferro-cyanide to a gallon of water, will be given a fair luster. The work must be cleaned first. Also keep it in agitation during the anodic treatment. Do not agitate solution by air or stirring.

#### Pickling of Stainless Steel

Hot-rolled sheet is pickled for 10–20 minutes in 8% ferrisul, 2% hydrofluoric acid; cold-rolled sheet for 5–15 minutes in 6% ferrisul, 1.5% hydrofluoric acid; bars and wire for 10–40 minutes in 6% ferrisul, 2% hydrofluoric acid; and cold-rolled strip for 1–4 minutes in 12% ferrisul, 2% hydrofluoric acid—all at 160–180° Farenheit. These treatments produce an unetched, white, mat, chemically passivated surface, smoother than could formerly be obtained.

#### NICKEL ALLOYS

#### Pickling

The types of oxide produced on Monel, nickel and Inconel vary with the heating conditions, and the proper pickling solution for each case must be chosen accordingly.

#### Cleaning

Before any attempts at pickling are made, all grease, drawing compounds, lubricants, and other adhering foreign matter acquired during mechanical operations must be removed completely. Soluble oils can be removed with soap and hot water, followed by thorough rinsing in hot or warm water. Tallow, fats and fatty acids can be removed by exposing the work to a hot solution containing 10 to 20% of soda ash (sodium carbonate) or caustic soda (sodium hydroxide). Mineral oils and greases are removed best by organic solvents such as gasoline, kerosene, carbon tetrachloride or other chlorinated solvents, followed by a final dip in a 10 to 20% solution of either caustic soda, trisodium phosphate, or a mixture of both.

#### Removal of Tarnish by Flash Pickling (Bright Dips)

This treatment is applied to drawn and spun shapes, cold-headed rivets, cold-drawn wire and other cold-worked products that have been bright annealed in a strongly reducing, sulphur-free atmosphere, and cooled either out of contact with air or by quenching in a 1 or 2% (by volume) alcohol solution.

#### Monel and "K" Monel

Best results on Monel and "K" Monel are obtained by the use of two solutions, as follows:

#### First Dip—Formula M-1

Water	1 gal. or	1000 cc.
Nitric Acid (38° Bé)	1 gal.	1000 cc,
Common Salt	$\frac{1}{2}$ to $\frac{3}{4}$ lb.	60 to 90 g.
Temperature	70° to 100° F.	21° to 38° C.

Time, Not over 5 sec.

Container—earthenware crocks, glass, or ceramic vessels.

The parts should be cleaned thoroughly in the first dip, using only a short time for each exposure, then rinsed in hot water (180° F.), followed by a rapid dip in the second solution consisting of:

#### Second Dip—Formula M-2

Water	1 gal.	or	1000 cc.
Nitric Acid (38° Bé)	1 gal.		1000 cc.
Temperature	70° to 100° F.		21° to 38° C.

Time, Not over 5 sec.

Container—18-8 stainless steel, glass, or ceramic vessels.

The second dip should be followed by rapid rinsing and neutralizing in 1 to 2% (by volume) ammonia solution (4 to 8 fl. 2z. commercial aqua

ammonia in 1 gal. of water). The parts should then be dried by dipping in boiling water, followed by rubbing in dry sawdust, or with a dry cloth.

Nickel and "Z" Nickel

Only one dip for nickel is required. Use Formula M--3.

Formula	M-3

Water	1 gal.	or	1000 cc.
Sulphuric Acid (66° Bé)	$1\frac{1}{2}$ gal.		1500 cc.
Nitric Acid (38° Bé)	$2\frac{1}{4}$ gal.		<b>2250</b> cc.

#### Allow to cool and add:

Common Salt	$\frac{1}{4}$ lb.	30 g.
Temperature	70° to 100° F.	21° to 38° C.

Time, 5 to 20 sec.

Container—earthenware crocks, glass, or ceramic vessels.

The parts are warmed first by dipping in hot water, after which they are immersed in the acid bath.

The fumes from these flash pickles for Monel and nickel are discomforting and a hood or ventilating system should be provided.

#### Inconel

It is impractical for the average shop to bright anneal Inconel and therefore no consideration need be given to bright or flash pickling such as can be accomplished with Monel and nickel. Flash pickling is used on Inconel only after the oxide or scale has been removed.

Removal of Reduced Oxide

This treatment is applied to forgings, hot-rolled shapes, hot-rolled wire rod in coil, and other hot-worked products that have been oxidized but where the oxide has been reduced by heating in a strongly reducing, sulphur-free atmosphere, followed by cooling out of contact with air or by quenching in 2% (by volume) alcohol-water solution.

Monel, "K" Monel, Nickel and "Z" Nickel

The solution of Formula M-4, following, works equally well for all four materials.

#### Formula M-4

Water	1 gal.	or 1000 cc.
Sulphuric Acid (66° Bé)	3/4 pt.	95 cc.
Sodium Nitrate (crude)	$\frac{1}{2}$ lb.	65 g.
Common Salt	1 lb.	110 g.
Temperature	180° to 190° F	82° to 88° C.
Time 20 to 00 min		

Time, 30 to 90 min.

Containers—earthenware crocks, glass or ceramic vessels, or, for short time usage, wooden barrels.

After pickling, the parts should be rinsed in hot water and neutralized in a 1 to 2% (by volume) ammonia solution. This pickling operation is often facilitated by occasional intermediate scrubbing with pumice on a fibre brush.

It is advisable to maintain separate solutions for Monel and nickel. They work better after having been used a while; therefore, in making up new solutions, about 2% (by volume) of spent solution should be added to the fresh solution.

#### Inconel

Since it is not practical to bright anneal Inconel under average shop conditions, no procedure is offered for the pickling of that alloy to remove reduced oxide.

## Removal of Oxide Film or Scale

This treatment is applied to forgings, hot-headed bolts, all hot-rolled and hot-formed products, and pieces that have been annealed in oxidizing atmospheres, or allowed to cool in air. Two solutions are required for Monel and "K" Monel.

## Monel and "K" Monel First Dip—Formula M-5

Water	1 gal.	r	1000 cc.
Hydrochloric Acid (20° Bé)	$\frac{1}{2}$ gal.		500 cc.
Cupric Chloride	$\frac{1}{4}$ lb.		30 g.
Temperature	180° F.		82° C.
Time	20 to 40 min		

Containers—earthenware crocks, glass, ceramic or acid-proof, brick-lined vessels.

The cupric chloride may be omitted if not readily available, although it is recommended that it be used since the pickling process is slow in its absence.

Rinse in hot water and immerse in the second dip for brightening.

# Second Dip-Formula M-6

Water	1 gal. or 1000 cc.
Sulphuric Acid (66° Bé)	1/10 gal. 100 cc.
Sodium Dichromate	1 1/10 lb. 132 g.
Temperature	70° to 100° F. 21° to 38° C.
Time	5 to 10 min.

Containers—earthenware crocks, glass or ceramic vessels, or rubberlined tanks.

Follow with a rinse in cold water, and then neutralize in 1 to 2% (by volume) ammonia solution.

# Nickel and "Z" Nickel

The hydrochloric acid-cupric chloride first dip solution (Formula M-5) recommended for Monel can be used for nickel also, but a longer time, 1 to 2 hours, is required.

Rinse with hot water and if brightening is required, dip for a few seconds in Formula M-3 and follow by rinsing in cold water and neutralizing in a 1 to 2% (by volume) ammonia solution.

#### Inconel

During hot-working or annealing in oxidizing atmospheres Inconel acquires a tenacious oxide film that is more difficult to remove than those formed on Monel and nickel. The following solutions have been found adequate for the removal of this oxide.

For all types of oxide, both thick and thin, the following solution is used:

#### Acid Formula—Formula M-7

Water	1	gal.	or	1000 cc.
Nitric Acid (38° Bé)	1	gal.		1000 cc.
Hydrofluoric Acid (40%)	1	½ pt.		150 ec.
Temperature	<b>7</b> 0° 1	to 100° F		21° to 38° C.
Time	15 t	o 90 min.		

Container—carbon brick is best.

If the oxide is thin (greenish chromic oxide), the following procedure should be followed, particularly because of the greater ease of handling the solutions. Two solutions are required.

## First Dip-Formula M-8

Water	1 gal.	or	1000 cc.
Sodium Hydroxide	18 oz.		134 g.
Sodium Carbonate	18 oz.		134 g.
Potassium Permanganate	7 to 11 oz.		52 to 82 g.
Temperature	180° to 190° F.		82° to 88° C.
Time	2 hr.		
Container—steel tank.			

The work should not be rinsed; it should be carried directly to the acid solution (second dip).

# Second Dip-Formula M-9

Water	1 gal. or	1000 cc.
Sulphuric Acid (66° Bé)	$\frac{1}{2}$ pt.	63 cc.
Copper Sulfate or Copper Nitrate	$1\frac{1}{2}$ oz.	12 g.
Temperature	180° to 190° F.	82° to 88° C.
Time	1 hr.	

Containers—wood, earthenware, glass, ceramic, or acid-proof, brick-lined vessels.

Follow by rinsing in cold water and neutralizing in 1 to 2% (by volume) ammonia solution.

It is difficult to say which method of pickling Inconel is better. The nitric-hydrofluoric acid pickle works well for shop practice and may be preferred to the alkaline-acid procedure.

# Paste-Pickling

It is desirable sometimes to use paste pickles for large pieces that are difficult to immerse in pickling solutions.

## Monel and "K" Monel

The treatment is applied to hot-rolled plate, forgings, tanks, drawn shells and other large pieces. Use Formula M-10.

Formula M–10				
Lampblack	1	lb.	or	100 g.
Fuller's Earth	10	lb.		1000 g.
Hydrochloric Acid (20° Bé)	3	gal.		2500 cc.
Nitric Acid (38° Bé)	1/2	pt.		52 cc.
Cupric Chloride	1 to	2 lb.		100 to 200 g.
Temperature	70° to	100° F	•	21° to 38° C.
Time	<b>20</b> to	60 min.		

Mix in a crock, butter tub, or similar container and apply with a long-handled brush for large surfaces, or an ordinary paint brush for smaller work. Wash off with a hose and follow with a scrub with sand or pumice. In cold weather, cold wash-water will cause Monel to tarnish. This is prevented by spreading a creamy lime paste directly on the pickle and thoroughly mixing to neutralize the acid. A cold-water wash may then be used. The lime treatment is unnecessary if hot water is used for washing.

#### Nickel and "Z" Nickel

This treatment is applied to hot-rolled plate, forgings, tanks, drawn shells, nickel-clad steel plate, tanks and other large pieces.

Use Formula M-10 and follow the same procedure as for Monel. A longer time is required to descale nickel—2 to 4 hours or longer—depending upon the thickness and the nature of the scale. Nickel does not tarnish with cold-water washing; hence, the lime treatment may be omitted.

#### Inconel

The treatment is applied to hot-worked and annealed parts carrying oxide, Inconel-clad plate, tanks and other large pieces.

Most oxidized Inconel work requires two treatments.

First	Treatment—Formula	a M-11	
Lampblack	1	lb. or	100 g.
Fuller's Earth	10	lb.	1000 g.
Hydrochloric Acid (20°	Bé) 3	gal.	2500 cc.
Cupric Chloride	2	lb.	200 g.
Temperature	70° to 1	100° F.	21° to 38° C.
Time	1 to	3 hr.	

Second Treatmen	nt—Formula M-12	
Lampblack	1 lb. or	100 g.
Fuller's Earth	10 lb.	1000 g.
Nitric Acid (38° Bé)	$2\frac{3}{4}$ gal.	2330 cc.
Hydrochloric Acid (20° Bé)	$\frac{1}{4}$ gal.	175 cc.
Temperature	70° to 100° F.	21° to 38° C.
Time	15 to 60 min.	

Wash thoroughly and scrub with pumice and water, either hot or cold. Removing Discoloration from Automatic Screw-Machine Products

Monel acquires a brown discoloration at high production machining speeds due to the formation of sulphur compounds by reaction with sulphurbase coolants. This discoloration may be removed easily to give a white surface.

Degrease to remove all traces of coolant and immerse in:

#### Formula M-13

Water	1 gal. or	100 cc.
Sodium Cyanide	$\frac{1}{2}$ to 1 lb.	60 to 120 g.
Temperature	70° to 100° F.	21° to 38° C.
Time	5 to 30 min.	

Containers—earthenware crocks, steel, glass, or ceramic vessels.

Handle the parts in a perforated Monel or woven wire dipping basket. Rinse thoroughly in hot water, if available, to hasten drying, or in cold

water followed by shaking or tumbling in sawdust to dry.

CAUTION: Sodium cyanide is a deadly poison and shops not regularly using cyanide solutions should keep the solution and stock of cyanide salt under lock and key. Under no conditions should acid from pickling operations or other sources be carried into the solution. The acid will liberate hydrocycnic acid gas—probably the most lethal industrial substance.

8 1

Removing Copper Flash

Sometimes in the pickling of Monel, nickel and Inconel, especially if the pickling bath should contain copper salts and has been used for some time, a thin copper flash may form on the part. For this reason it is desirable to use separate pickling solutions for nickel and Monel, although the same formula may be called for. If the copper flash should occur, it can be removed readily by immersing the part in an aerated, 4 to 5% ammonia solution (approximately 1 pt. of commercial aqua ammonia to 1 gal. of water) at room temperature. The time required is short, usually only a minute or so. This dip is followed by rinsing in water.

DECORATIVE ETCHING AND COLORING

The etching procedures herein described were developed through practical experience in commercial operations. They differ distinctly from the etching processes used in the preparation of specimens for microscopic or macroscopic examination.

Applying the Resist

The resists used normally in commercial etching operations are applicable to Monel, "K" Monel, nickel and "Z" Nickel. Wax and gelatin resists are applied by swabbing or brushing, and varnish and lacquer resists by brushing or spraying. When coating on both sides is desired, this may be accomplished by dipping.

Rotogravure or carbon tissue transfers should be applied according to the manufacturers' directions. The double transfer method is preferred with Monel. Neither of these resists has been used with nickel or Inconel. Etching Solutions

The etching solutions described for Monel, "K" Monel, nickel and "Z" Nickel are used at room temperature. For most consistent results they should be made up freshly for each use.

A. Monel and "K" Monel

1. For etching through beeswax, varnish, or other chemically inert resists.

a. Iron perchloride (ferric chloride) (38°-42° Bé) or

b. Iron perchloride (38°-42° Bé) containing 10% (by volume) concentrated hydrochloric acid; or

c. Iron perchloride (38°-42° Bé) containing 2% (by volume) concentrated nitric acid.

- 2. For etching through carbon tissue, gelatin, or other light-sensitive resists.
  - a. Iron perchloride (38°-42° Bé) to which 10 per cent (by volume) of concentrated nitric acid has been added.
  - 3. For "deep-etch" lithograph plates:-\*

a. Iron perchloride, lumps—25 g.
 Calcium chloride solution (40°-41° Bé) 1000 cc.
 Hydrochloric acid (c.p.) (1.19 sp. gr.)—20 cc.

B. Nickel and "Z" Nickel

Both solutions 1b and 1c, as described for Monel and "K" Monel, work satisfactorily for nickel and "Z" Nickel. Preference is given generally to solution 1b.

#### C. Inconel

There are no recommended etching solutions for Inconel.

Chemical Coloring

Chemical coloring of Monel and nickel sheets requires a preliminary light etching, graining, or sand blasting. Suitable surfaces for this purpose may be developed readily by brief immersion in a 38°-42° Bé solution of iron perchloride at room temperature.

## A. Monel

Monel may be colored to shades from grey to black by immersion in the following solution.

Potassium sulphide—12 g. per l.

Ammonium chloride—200 g. per l.

The bath should be used at about 160° F. Coloring may be effected either by complete immersion, to assure most uniform results, or by surface swabbing. The solution has poor keeping qualities and must be made up freshly for each set of applications.

After coloring has progressed to the desired shade, the Monel specimens should be dried quickly, preferably in a hot-air blast at about 200° F. If the colored articles are to be subjected to handling and wear, their surfaces should be protected further by an application of clear lacquer or varnish.

<sup>\*</sup>Formula developed by Lithographic Technical Foundation.

#### B. Nickel

Nickel may be coated with an adherent black film by an immersion in the following solution.

Ammonium persulphate—200 g. per l.

Sodium sulphate—100 g. per l. Ferric sulphate—10 g. per l.

Ammonium thiocyanate—5 g. per l.

The solution is used at room temperature, with immersion for 5 minutes being adequate generally to develop a hard black film. In use it is necessary to maintain the red color of the solution by periodic small additions of ammonium thiocyanate, although otherwise the solution retains its useful properties for long periods.

For most requirements the black film developed by this means will need no added surface protection. If such is desired, an application of clear

lacquer or varnish can be made directly over the colored surface.

## Aluminum Dyeing

The aluminum is first thoroughly cleansed and degreased in a hot bath of potassium hydroxide, rinsed hot, then cold.

Next a coating of basic aluminum oxide is formed by electrolysis. The metal is suspended in lead tanks of sulphuric acid and a current of high amperage and low voltage is applied for 20-30 minutes; meanwhile the bath is kept cool with ice.

After a thorough rinse the aluminum is dyed at temperatures between 75° F. and 125° F. for 1-5 minutes depending on depth of shade. This is followed by a sealing treatment produced by dipping the dyed metal in a boiling bath of dilute acetic acid.

A selection of the most suitable colors, mixtures of which will produce practically any desired shade, are known as:

> Metal Canary Yellow Metal Old Gold Metal Green Metal Lilac Metal Delft Blue

Metal Sunflower Metal Fuchsine Metal Copper Red Metal Red B Metal Dark Wine

Many of the ordinary basic and acid colors will dve deep shades but are not fast to the sealing bath.

> Anodizing Aluminum U.S. Patent 2,231,086 Formula No. 1

Tungstic Acid 20 g. Water 30 cc.

Add this mixture to a solution of 300 grams of sodium sulphate and 420 grams of citric acid in 1 liter of water. Operate at 20-30° C., alternating current, 15-25 volts. Time about 30 minutes.

No. 2

Oxalic Acid 69 g./l. Molybdo-Oxalic Acid 40 g./l.

No. 3

Sulphuric Acid 50 g./l. Crystal Cobalt Sulphate 20 g./l.

Room temperature. 21 volts alter-

nating current.

No. 4	
U. S. Patent 2,231,373	
Titanyl Potassium Oxalate	50
Citric Acid	15
Glucose	20
Phosphoric Acid	6
Water	1000
110 volts alternating curre	nt. 75°

Time until 2.5 ampere hours per square decimeter have passed.

C. 5-6 amp./sq. dm.

#### No. 5

#### British Patent 522.571

The aluminum is treated anodically at 110 volts in a hot (95° C.) solution of

Sodium Aluminate	30 g.
Sodium Silicate	10 g.
Sodium Hydroxide	8 g.
Water	1 l.

Then washed with dilute ammonia and dried.

# Coloring Metals

Violet to vellow colors (depending on film thickness) are produced on metals from a bath of

Copper Sulphate	60	g.
Sugar, Refined	90	g.
Sodium Hydroxide	45	g.
Water	1	ĺ.

The metal to be colored is made the cathode and anodes of pure copper are used at temperature of 25- $40^{\circ}$  C. with 0.01 amp./cm<sup>2</sup>.

#### Coloring Aluminum Powder British Patent 489.574 Aluminum Powder 100 g. Alcohol, Denatured 10 g. Sodium Phosphotungstomolybdate 5 g. Water 1500 cc. Boil for 45 min., filter and wash

with water. Add washed paste to

Acridine Orange R

Water

500

Stir and heat at 60° C. for 5-10 min. Filter wash and dry to get a golden vellow powder. Rhodamme B. or other dyes may be used to get other colors

Coloring Aluminum

Commercial aluminum usually contains small proportions of silicon and iron; these impurities, plus the character of the metal itself, introduce certain difficulties in coloring aluminum, particularly by chemical means.

The most popular color is black, which can be obtained on aluminum by the simple expedient of first freeing the metal from all grease by rubbing with a rag saturated with a strong washing soda (sodium carbonate) solution, rinsing well, then flowing the metal surface with well beaten fresh egg albumen, previously strained through several layers of clean muslin. The albumen coating is allowed to dry, after which the plate is gently heated and the temperature gradually raised until a deep black color is attained.

The color (deposit) so produced will withstand the action of acids and can only be removed by repolishing, features of some interest in the case of etched aluminum name plates bearing black backgrounds, since the resist (image) can be removed (after blackening) without damage to the black deposit.

Olive or linseed oil can be applied instead of albumen, as can also strong solutions of tannin or gallic acid: the applications are permitted to dry and the plate then heated.

Rather expensive substitutes for the above agents are solutions of platinum chloride, either aqueous (5%) or alcoholic (1%). The plate is immersed in these solutions and the coating left to dry in a temperature of about 305° F.

A mixture of aniline and bichromate solution imparts an adhering black color to aluminum, and the following procedure promotes a matt black surface to the metal. The first step is to mordant the plate by very briefly immersing it in:

## Formula No. 1

Sulphuric Acid	3
Water	1
water	hong area
after which the plate is	immerseu
in the following bath, mair	ntained at
a temperature between 86	3-95° F.:
a temperature between	

Alcohol (95%)	1000
Antimony Chloride	150
Manganese Nitrate	100
Washed Graphite	20
Hydrochloric Acid	250

The alcoholic solution present on the plate is burned off and the gray metal surface immediately varnished with:

A 1 . . 1. . 1

Alconoi	1000
Sandarac	50
Shellac	100
Nigrosine	100
The varnished plate is	heated
(baked) in an oven and	finally
rubbed with linseed oil	varnish,
which brings forth the desire	d effect.
,,	

1000

#### No. 2

Water 1	28
Potassium Permanganate	$1\frac{1}{2}$
Nitric Acid (20° Bé)	$\frac{1}{3}$
Copper Nitrate	4

The temperature of the bath should be 175° F. and the plate immersed therein from 20 to 30 minutes, after which the blackened surface is protected with a clear lacquer.

No. 3	
Water	128
Caustic Soda	16
Common Salt	4

The solution is kept at 200° F. and the plate immersed for about 15 minutes. It is then rinsed thoroughly and dipped in:

Water	128
Ferrous Sulphate	16
White Arsenic	16
Hydrochloric Acid	128

The plate is dipped for only a few seconds in the cold bath, then rinsed well in hot water and dried by applying fine sawdust, after which the surface is lacquered.

Those possessing electroplating installations may find the following procedure of interest, particularly for etched aluminum name plates. It is based on the deposition of "black" nickel on the etched areas of aluminum, the coating being sufficiently durable for interior service. A typical solution for black nickel plating is:

## No. 4

11	28
Water	
Nickel Ammonium Sulphate	8
Zinc Sulphate	1
Sodium Sulphocyanate	2

Nickel anodes are used, with a voltage of 1 volt and a current density of 1 to 2 amperes per square foot. The bath (electrolyte) is kept nearly neutral by the addition of zinc carbonate.

If anodized aluminum is placed in a solution of an organic dye, the dye unites with the anodic coating on the aluminum and forms a colored lake. These oplors will not wash out. Thus, by dipping anodized aluminum in a green dye solution, a green coating is obtained; in this way, any desired color may be possible.

# Silvering Aluminum Formula No. 1

A white or silvery finish can be imparted to aluminum by immersing the metal from 15 to 20 seconds in a hot 10% solution of caustic soda saturated with common salt. The plate is rinsed, scrubbed briskly, then reimmersed in the solution for about one-half minute, during which an energetic liberation of gas takes place. The plate is again washed and then dried with sawdust.

#### No. 2

Water	1000
Silver Nitrate	10
Potassium Chromate	$2\frac{1}{2}$
Potassium Carbonate	100
Sodium Bicarbonate	80
F707 7 4 5 1 7	, ,

The solution must be used in a boiling state, the time of immersal not to exceed 10 to 15 minutes.

# Coppering Aluminum

Copper-colored finishes can be produced on aluminum by cooking the metal in a weakly acid solution of cupric tartrate, which should possess a specific gravity of 36° Bé. Another solution for the purpose is one containing 1 part of cupric chloride in 8–12 parts of water, with the addition of 2 parts of potassium chloride, the plate is immersed in the solution (122° F.) until the required deposit of copper is obtained.

# Coloring Brass

Black is the most popular color with brass (particularly for name plates). This color is obtainable by four different methods: (1) Those employing electrolysis; (2) those requiring the use of hot solutions; (3) those requiring heating of the metal after application of the coloring bath; and (4) those employing solutions or baths at ordinary (room) temperatures.

When blackening etched brass name plates, one might bear in mind that because of changes in the surface structure of the etched metal. the color may be different from that obtained on unetched brass. Different etching solutions cause the etched surfaces to react differently during blackening, which condition often is attributed to the character of efficiency of the blackening bath, whereas it really is due to the nature or state of the etched metal surface itself. Should any real difficulty be experienced in this direction, it may be necessary to preliminarily copperplate the etched areas before they are subjected to blackening.

The color produced on the metal, not infrequently, is influenced by the metallic constituency of the brass (ratio of zinc and presence of other metals) and its method of manufacture; no one bath is equally efficient for every grade of brass, and different results (as to color) can be expected with different alloys.

# Formula No. 1

Copper Carbonate	$3\frac{1}{2}$
Ammonia (0.960)	$26\frac{1}{2}$
Distilled Water	$5\frac{1}{2}$

The copper carbonate is added to the ammonia and dissolved therein by frequent shaking; at the end of 24 hours standing, there must still be some undissolved carbonate present, assuring a saturated solutionif not, more carbonate must be added. At this stage, the water is added (some craftsmen also prefer the addition of from 25 to 40 grains of graphite), the solution assuming a blue color, which deepens to a darker blue within a few days. The mixture should be contained in a well-stoppered bottle and stored in a cool place.

In use, the clean and grease-free brass is immersed in the bath until the desired depth of color is obtained, the black deposit (color) consisting essentially of cupric oxid. The plate is then withdrawn, rinsed in cold water, briefly immersed in hot water, then dried and the resist removed (in the case of name plates) after which the plate is varnished with clear lacquer. If the color is not sufficiently deep, the immersal may be repeated, obviously before varnishing.

The efficiency of the above bath is enhanced somewhat by using the solution hot (140–170° F.), but here is faced the difficulty of the ammonia volatilizing and escaping into the work chambers in the form of fumes. The solution soon weakens even when cold; heating accelerates this with the ensuing separation (elimination) of cupric oxid from the bath.

A blue-black color can be deposited on brass plates by boiling them in a solution of potassium sulphide (liver of sulphur). This operation must not be carried out in the vicinity of photographic galleries: the fumes from the sulphide bath would irretrievably fog any photographic plate, film or paper with which they came into contact.

A blackish-green color is obtained

on brass plates by immersing them in a boiling solution of:

TAT	0
IN O	~
410.	de la

210.2	
Water	1000
Copper Sulphate	100
Ferrous Sulphate	80
Ammonia	10
Glacial Acetic Acid	5

This bath is particularly efficient with brass alloys of a high copper content.

#### No. 3

Water	1000
Copper Chloride	35
Copper Nitrate	120

After treatment, the plates are rinsed in cold water, then dried either in an oven or by the application of sawdust.

#### No. 4

Brass can be blackened in:

## A

Copper Nitrate	81/4
Water	20
В	
Silver Nitrate	$8\frac{1}{4}$
Water	20

The solutions are prepared separately with the aid of heat, then mixed together. After immersal in the bath, the plate must be heated until a black color is obtained.

## No. 5

Hydrochloric Acid	16
White Arsenic	4
Ferric Chloride	16
or	
Hydrochloric Acid	100
Ferrous Sulphate	10
Arsenic Acid	10
or	
Water	128

Yellow Antimony Sulphide 1/4
The above baths should be used

White Arsenic

hot; the blackened plates, after drying, should be lacquered to prevent tarnishing.

No. 6

Water	128
Lead Acetate	8
Sodium Thiosulphate	8

On immersal, the surface of the brass progressively turns yellow, blue and finally black, the latter color due to a deposit of lead sulphide. With a hot bath, the action is quite rapid. After blackening, the plate is rinsed in cold water, then in hot water, and finally dried. If scratch-brushed dry, the black deposit will have a high luster, but it is well to lacquer the surface to prevent oxidation and fading.

# Oxidizing Brass

Immerse the piece in a solution at 180° F., made up in the following proportions:

Sodium Thiosulphate 136 g. Lead Nitrate 24 g. Ferric Nitrate 17 g. Water 2.4 qt.

Treat until the surface is completely oxidized, remove from solution, rinse in water and dry thoroughly.

# Coloring Bronze

Bronze can be blackened by immersing in:

Formula No. 1
Hydrochloric Acid 1000
Arsenic Acid, Powdered 60
Antimony Chloride 30
Iron Scale 150

All the ingredients are added to the hydrochloric acid, which is then heated to 158-176° F. for one

hour and the mixture frequently stirred to promote solution of the arsenic acid. Avoid inhaling fumes. If the bath is not required immediately, solution of the ingredients in the hydrochloric acid can take place in the cold. The mixture is then allowed to stand from 24 to 36 hours, but intermittently shaken during this time.

The bath is used cold and two immersions (not exceeding 15 seconds each) are, in most instances, sufficient. Before immersing the second time, the bronze must be rinsed with water and dried with soft linen, taking care to remove all drops of water, which otherwise would cause spots. After coloring, the metal is dipped in fairly strong soda solution (to neutralize acid traces), then liberally rinsed in water, and dried with sawdust.

## No. 2

For blackening phosphor bronze: Cupric Nitrate 500 Alcohol (90%) 150

To assist solution of the nitrate, the salt is first melted over a low heat; then, away from flame, the alcohol is added to the warm mass. The bath is used cold and the plate immersed until a good black is obtained. Lacquering of the blackened bronze is suggested.

## No. 3

Blackening of an occasional piece of bronze can be performed by brushing on the metal a 5% aqueous solution of platinum chloride, a much cheaper medium is a potassium sulphide (1:20) solution. With the latter agent, it is necessary to heat the plate bearing the sulphide solution.

Coloring Chromium Blackening Chromium U. S. Patent 1,937,629 Formula No. 1

Sodium Cyanide 45
Soda Ash 35
Salt 20

The period of immersion is from 20 to 30 minutes in a bath maintained at a temperature of 1292–1652° F.

#### No. 2

Black chromium plating can be performed with an electrolyte containing between 250 and 400 grams per liter of chromic acid and 5 cc. per liter of glacial acetic acid. The bath temperature should be kept below 75° F. and a current density between 750 and 1000 amperes per sq. ft. is necessary.

Coloring Copper

A wide array of formulae exist for coloring this metal, but success depends on the character (purity) of the copper, the reaction of the coloring baths, and last but definitely not least—on the skill and patience of the worker. There is no royal (easy) road to success in coloring metals: it is not always possible to exactly duplicate a given color, regardless of the experience of the operator and the care used in preparing baths and treating the metal.

A black finish on copper can be obtained by applying an even coating of

Formula No. 1
Copper Nitrate 2
Water 8
to the surface to be blackened. The

to the surface to be blackened. The plate is then heated over a gas flame to produce the black color; the

operation can be repeated if the deposit is not uniform or the color not sufficiently black.

No. 2	
Water	20
Copper Carbonate	8
Ammonia (.880)	80
Sodium Carbonate	4

The water is heated to about 120° F., after which the carbonates are added, stirring well for five minutes to aid solution; this is followed by the gradual addition of the ammonia, the mixture being continuously stirred and the bath brought to a final temperature of 120° F., when it is ready for use.

The well-cleaned plate is immersed in the bath for about three minutes, next washed in water, and then placed in a solution of sodium sulphide (3 ounces; water, 60 ounces) until the desired color is obtained. To further harden and deepen the color, the well rinsed plate can finally be immersed in a 10% solution of potassium bichromate.

The copper-silver nitrate bath given under *brass* can also be used for blackening copper, as can a liver of sulphur bath:

No. 3	
Water	1000
Potassium Sulphide	20
Salt	20
No. 4	
Water	800
Arsenic Acid	20
Hydrochloric Acid	40
Use at a temperature	of 122-
140° F.	
	201000 01

With the following bath colors on copper ranging from yellow and rose to violet and blue, the color depending on the length of immersion, can be obtained.

1000
7
13
<b>2</b>

The bath should react slightly acid, otherwise the color may be spotty and less permanent.

# Coloring Lead

Lead can be blackened in a warm solution of ammonium sulphide, or in the hydrochloric acid-arsenic bath used for blackening bronze.

# Coloring Nickel

Because of its inherent nice color and durability, nickel is seldom colored. The operation can easily be performed by electrolysis, particularly the so-called "black nickel" coatings. Black or gray tints can be chemically produced on nickel by treatment with platinum chloride (1%) or ammonium sulphide solutions, the latter containing a small proportion of ammonium chloride.

Other baths for the purpose are the arsenic solution for blackening bronze, and the alcoholic cupric nitrate solution (q.v.) for the same metal

# Bronze Powder Effects

Many bronze-powder finish effects can be produced directly on the metal itself, without the use of bronze powder. Light bronze finish effects can be produced on brass, either sheet metal or castings. Darker bronze finishes can be applied to bronze metal or copper plated brass or steel. Copper plated metal gives a darker finish than bronze metal.

Castings are polished with No. 70 emery. One reason for using this grade of emery is that it will take the skin off the casting at a low labor cost, but the most important reason is that the sandblast will remove all of the emery marks.

For light finishes, use brass. For darker browns, use bronze. For brown to black, use copper-plated metal.

The following solution is for light finishes. Add 4 oz. of liver of sulphur to 30 gallons of water heated to 120° F.

After the articles to be finished are sandblasted they are ready to be stained. To stain, immerse the articles in hot water, then in the solution just described. From there transfer them directly into a toning solution made up by adding a gallon of sulphuric acid to 30 gallons of water. (Note: Make sure acid is added to water.) Then give them a cold-water rinse followed by a hotwater rinse. Dry them in hardwood sawdust. Scratch-brush the surfaces with a brass-wire brush.

The coloring will depend upon the number of times you repeat the operations just specified. The more you dip the articles, the darker the finish will be.

After brushing the treated surfaces, give them a coat of matt lacquer for a dull finish or gloss lacquer for a shiny finish.

If a silver color is desired, it can be obtained by: Sandblast first, then bright dip, silver plate, dry out and scratch brush.

If you silver plate a bronze article for about one minute and brush the surface with a steel wire brush, so as to cut it through (that is remove some of the silver so the base metal shows through) you will then have a silver bronze finish.

For a light brown to dark brown color on bronze metal, use the following solution: Mix into one quart of warm water:

Barium Sulphide 2 oz. Liver of Sulphur 4 oz. Aqua Ammonia (26°) 8 oz.

When dissolved, add to 30 gallons of water heated to 120° F. Use this the same as the other solution. It is advisable to make a new solution

every day for best results.

These finishes can be brushed wet, which gives a soft finish. If the wet method is used, it must be remembered that after completing the brushing—that is, until the color you wanted is gotten the article is still wet—that is the way it will look when it is lacquered.

In order to keep the same color on the whole job, keep the first article brushed as a sample. Keep it wet and match each piece to this

one sample.

Articles finished in this manner will keep their color much longer than those coated with regular bronze powder finishes. Bright Dip for Brass

Sulphuric Acid 2 gal.
Nitric Acid 1 gal.
Water 1 qt.

Hydrochloric Acid

(Muriatic) ½ oz. (Use this solution cold.)

If, for any reason, too much muriatic acid has been added to the solution at any time, the work will come out "sooty." In this event, add a small amount of sodium chloride (salt) slowly. Add enough salt to return the solution to proper balance. Use only the exact amount of water specified in the formula; do not get any more in the dip.

Matte Dip for Brass
Sulphuric Acid 1 gal.
Nitric Acid 1 gal.
Zinc Oxide 2 lb.
(Use hot and keep free of water.)
If the action is too coarse, add

If the action is too coarse, add sulphuric acid. If too fine, add nitric acid.

Semi-Lustrous Matte Dip for Brass
Sodium Dichromate 3 oz.
Sulphuric Acid ½ pt.
Water 1 gal.

Both solutions are poisonous and corrosive. Handle with extreme care.

# Steel and Iron Burnishing Baths German Patent 704,400

	Formula No. 1	No. 2	No. 3
Sodium Hydroxide	75	60	60
Disodium Phosphate	$16\frac{1}{2}$	-	10
Sodium Nitrite	5	40	3
Sodium Iodate	$\frac{1}{2}$	Comme	$\frac{1}{2}$
Potassium Iodide		$\frac{1}{2}$	
Trisodium Phosphate	*	-	14
Sodium Carbonate	_	-	4
Temperature of Use	128° C.	133° C.	150° C.
40% water and 60% of any	of above formulae is	used.	

## Bluing of Iron and Steel

The uniformity and general appearance of the color depends considerably on the character of surface finish of the steel previous to the bluing operations. Bright shining colors are produced only on wellpolished surfaces. An abraded or mat surface always appears a little darker than a polished surface colored by the same method. Slight variations, however, are less noticeable on an abraded or mat surface. The brightness or luster can, therefore, be controlled to a great extent by a suitable choice of the finishing operation preceding the coloring.

Uniformity of coloring is greatly influenced by the initial cleanliness of the surface. Grease, rust, or any adherent foreign particles usually shield portions of the surface against the chemical action and lead to uneven coloring. Sometimes a very unsatisfactory spotted appearance is produced. Care must be taken to avoid any contact of the hands with the surface during the cleaning or bluing operations. The articles should be supported by wires, or handled in wire baskets or with suitable tongs. Any surface rust should be removed early in the cleaning operations.

For cleaning metals contaminated with grease or polishing compounds employ organic solvents, such as trichloroethylene, ethylene chloride, orthodichlorobenzene or carbon tetrachloride; emulsifiable solvent cleaners, such as sulphonated corn or castor oil, or triethanolamine oleate added to an organic solvent such as high-flash naphtha or kerosene; or aqueous alkaline solutions, applied either by immersion or elec-

trolytically. These methods may be used individually or in conjunction with one another.

The bluing methods may be divided into three general classes: temper-coloring or heat-tinting, coloring in chemical solutions, and coloring by electrolytic methods. Most of these films or coatings provide only slight protective value against corrosion, unless oil, wax or lacquer is applied to the surface subsequent to the coloring.

# Temper-Coloring or Heat-Tinting in Air

A good blue may be obtained on iron and steel by heat-tinting (temper-coloring) the work in air or other oxidizing atmospheres. The color is produced by the interference of light in a thin surface film of iron oxide. As the thickness of the oxide film increases, the following sequence of colors is obtained: light straw, straw, dark straw or a light golden brown, brown or bronze, purple, dark blue, and light blue. Further heating (with oxidation) produces the "second order" of interference colors in the same sequence, but they are usually less intense and consequently less pleasing. Further oxidation beyond the second order gives very indistinct colors.

In general, the thoroughly cleaned article is placed in an oven or furnace or on a hot metal plate, and the heating is continued until the desired color is obtained. It is then removed, cooled in water and dried. The dry surface may then be coated with a suitable light transparent lacquer or with a film of oil by immersion in a heated light oil (such

as boiled linseed oil). Greater protection against corrosion is secured in this manner.

The period of heating required to obtain any specific color desired depends chiefly upon three factors: the temperature of the oven or furnace, the composition of the steel, and the

size and shape of the article.

The rate at which a desired color can be obtained on steel varies somewhat with the composition of the steel. This is not an important factor, however, unless the differences in composition are very pronounced, for example, open-hearth iron vs. stainless steel. The blue may readily be obtained on these steels by heating in the temperature range of 500 to 700° F. (260 to 370° C.), the period of heating varying from about 3 to 4 hours to one minute respectively for the extremes of this temperature range. Cast iron blues at a slightly lower rate than the open-hearth iron or the steels and, consequently, it requires a little longer period of heating, or a slightly higher temperature.

The temper-coloring of steels, as well as the bluing in molten salt baths, influences the physical properties, because tempering of the steel takes place at these temperatures. Hardened steels are softened somewhat by these processes. Consequently bluing in aqueous solutions at lower temperatures, or electrolytic coloring, may be preferable when it is desirable to maintain the

full hardness of the steel.

The size and shape of the articles are important practical factors that influence the heat-coloring. A large object requires a longer period of heating than does a smaller one, be-

cause of its greater heat capacity. and the consequently longer period of heating required to bring the temperature of the object up to that of the oven or furnace. In irregularly shaped articles, the thinner sections reach the temperature of the furnace more rapidly than do the thicker sections and thus color faster. This may result in non-uniform bluing of the article. This effect can be minimized by placing the article in the cool furnace and allowing it to heat up with the furnace.

The selection of the best operating temperature of the furnace should be determined by a few preliminary tests. If the heating period is so short that the bluing occurs in only a minute or less, the color may not be very uniform. In this case heating at a lower temperature with a correspondingly longer heating period generally gives a more uniform blue, especially with irregularly shaped

objects. Steel strip or wires may be blued by passing them through a bath of molten lead or a low-melting alloy. The color develops only after the steel leaves the bath and comes in contact with the air. The amount of the oxidation, and hence the color, are controlled by adjusting the temperature of the bath and by passing the steel strip or wire through a quenching medium, such as a water bath, when it has developed the desired color.

Very good blue can be obtained on iron and steel by immersion in molten salt baths. The surface of the steel is oxidized by the oxygen liberated in the salt bath, and temper colors, the same as those formed by heating in air, are obtained. The

H

molten salt also serves as an excellent means of heating the article uniformly, and hence is an aid in coloring it evenly. The time-temperature relationships for the formation of these colors are very similar to those obtained by heating in air.

For bluing with the molten salts, either sodium or potassium nitrate or nitrite may be used. A mixture of the sodium and potassium salts is preferable to either alone, because of the lower melting point of the mixture. This permits the coloring to be carried on at lower temperatures, and thereby furnishes better control, because the period of heating is increased and the oxidation can be stopped more easily at the desired color. Some of the salt usually solidifies on the surface of the object immediately upon its immersion in the bath, but melts again in a short time as the temperature of the article rises. This causes non-uniform bluing if the solidified salt is not melted from all of the surface at about the same time, because coloring occurs only when the surface of the article is in contact with the molten salt. In a bath having a low melting point, the amount of salt that solidifies on the object is much less, and it melts more readily, facilitating uniform coloring.

A. Potassium Nitrate 100 Sodium Nitrate 100 Use at about 625° F. (330° C.).

B. Potassium Nitrate 100
Sodium Nitrate 100
Manganese Dioxide 5-10
Use at about 625° F. (330° C.).

C. Potassium Nitrite 110 Sodium Nitrite 90 Use at about 660° F. (350° C.). The salt bath may be melted in a cast iron or steel pot that is free from rust and has a shape and size to suit the articles to be blued. For small articles a short section of a steel pipe closed at one end with a pipe cap is suitable.

The same procedure is followed with all of the different salt baths. The articles should be thoroughly clean, free from rust and free from moisture. Moisture on them at the time of immersion may cause severe spattering of the molten salt. The articles are so suspended as to be completely covered by the molten salt until the desired color has been attained. (The article may be temporarily raised out of the bath to facilitate observation of the coloring.) After the desired blue has been obtained, the article is withdrawn and quenched in clean cold water to stop the oxidation, then immersed in boiling water to remove any salt remaining on the work, and finally dried. To obtain greater protection against corrosion or wear, the blued articles may be dipped in hot oil or finished with a light transparent lacquer or varnish. Finishing with a lacquer that has been lightly tinted blue usually improves the appearance.

Salt bath B is the same as A except for the manganese dioxide. This should be added after the temperature of the molten salt bath has been raised to about 900° F. (495° C.), after which the bath is allowed to cool to about 625° F. (330° C.) before using. All suspended matter should be allowed to settle to the bottom of the pot before the articles are immersed, otherwise discolored

spots will appear on the blued surface.

In general, the blue obtained with aqueous solutions differs considerably in appearance from that obtained by heat-tinting, although in both cases it is mainly due to interference colors. The specific color of the surface film itself has a great influence on the "over-all" appearance, this being especially noticeable in the case of the "luster washes." in which the precipitated surface film of lead sulphide has a characteristic "soft" appearance. Moreover, the blue obtained with aqueous solutions is always less brilliant and less intense than that formed by heat-tinting. A good light blue can be easily obtained but it is difficult to obtain a one corresponding to the dark blue or violet temper color. The aqueous solutions are used at a much lower temperature than that of the molten salt baths and consequently the correct operating conditions can be maintained much more easily. Hardened steels can be blued by this method with very little, if any shortening.

As in the previous methods, the articles must be thoroughly clean. The rust-free article is first cleaned with an organic solvent (acetone, carbon tetrachloride or trichloroethylene). This is followed by electrolytic cathode cleaning in an alkaline solution, such as is generally used in electroplating. Electrolytic cleaning is faster and preferable to immersion alkaline cleaning. The following solution, at a temperature of about 195° F. (90° C.), is suitable:

g./l. oz./gal.
Trisodium Phosphate 30 4.0
Sodium Hydroxide 10 1.5

A steel anode is used and a voltage of 4 to 5 volts is applied with the article serving as the cathode. The articles are then rinsed in water, dipped in a weak sulphuric acid solution (approximately 5% solution) for a few seconds, rinsed thoroughly in clean water and immediately immersed in the coloring solution.

Unless otherwise noted, all the following formulae refer to aqueous solutions, in which the required weights of the materials are dissolved in water and sufficient water is added to make a final volume of 1 liter or 1 gallon.

#### Luster Wash

A very pleasing blue may be obtained on iron and steel by using "luster washes." An adherent lead sulphide film is precipitated on the surface of the immersed article and this produces interference colors which are modified somewhat by the specific color of the lead sulphide. Hence the appearance is different from the interference colors of the oxide films formed by heat-tinting.

Good "luster colors" are obtained with the following four solutions, the blue produced by solution D being slightly better than that of the other solutions.

g./l. oz./gal.

D. Sodium Thiosulphate 200 27.0

Lead Acetate 20 2.5

Potassium Acid
Tartrate 25 3.0

Use at approximately 105° F.

(40° C.).

E. Sodium Thiosul-	g./l.	oz./gal.
phate	70	10
Lead Acetate	20	3
Use at 160 to 17 80° C.).	75° F.	. (70 to
	g./l.	oz./gal.
F. Sodium Thiosul-		, 0
phate	10	1.5
Lead Acetate	10	1.5
Use at approximation (90° C.).	ately	195° F.
	g./l.	oz./gal.
G. Sodium Thiosul-		
phate	30	4.0
Lead Nitrate	8	1.0
Ferric Nitrate	3	0.4
Use at 160 to 17	75° F.	(70 to
80° C.).		
era: 1: 1 1 1	1 7	

The salts should be dissolved separately in portions of the water and then mixed just before using. The cleaned article is immersed in the heated solution and moved to and fro until the desired color appears, whereupon it is rinsed, first in cold water, next in boiling water, and then dried and wiped over with a clean soft cloth. The colored surface may be coated with wax, or a transparent lacquer or varnish as a final treatment.

It is advantageous to use the solution at the lowest operating temperature since the bath is then most stable and the lead sulphide film formed at a low temperature adheres more tightly to the basic metal. Although solution D may be used without the addition of the potassium acid tartrate, the coloring rate is decreased and either a longer immersion period or a higher bath temperature is required. Solution F, which has the lowest concentration of sodium thiosulphate, required the highest temperature. The

concentration of these solutions or of their constituents may be varied considerably and still furnish good coloring, although this may require a change in the temperature of operation.

A light blue on iron and steel may be obtained with either of the two solutions given below:

H. Arsenious

Oxide 85 g./l. 11 oz./gal. Hydrochloric

Acid (sp. gr.

1.18) 630 ml./l. 80 fl. oz./gal. Use at approximately 195° F. (90° C.).

g./l. oz./gal.

I. Sodium Nitrate,
Potassium Nitrate
trate 400 55
Sodium Hydroxide 400 55
Use at approximately 255° F.
(125° C.).

The article, cleaned as given above, is immersed in the heated solution until the desired color is attained, whereupon it is rinsed thoroughly in cold water, then in boiling water and dried. If desired, it is given a final finishing treatment as described previously.

A blue-black or gray-black on iron or steel can be obtained by treatment with the following solution:

g./l. oz./gal.

J. Ferric Chloride 90 12

Mercuric Nitrate 90 12

Hydrochloric Acid

(sp. gr. 1.18) 90 (77 ml.) 12

(10 fl. oz.)

Alcohol

360 (460 ml.) 48 (40 fl. oz.) Water, To make 1 l. or 1 gal. The article (preferably cleaned with an alkaline cleaner) is immersed for 20 minutes, removed and allowed to dry for about 12 hours, after which the immersion and drying operations are repeated. The article is then placed in boiling water for 1 hour and dried again. The colored surface is finished by lightly scratch-brushing and oiling or waxing.

A gun-metal blue or gray can be obtained on iron or steel by immersion in the following solution:

g./l. oz./gal.

K. Ferric Chloride 200 25.0

Antimony Chloride 4 0.5

Gallic Acid 4 0.5

This solution is used hot, at a temperature of 160° F. (70° C.) or higher. The cleaned article is immersed in the bath until the desired color is attained, whereupon it is rinsed thoroughly in cold water, then in hot water, and dried. The finishing treatment is similar to those previously described. More precise control is required with electrolytic methods than with heat-tinting or bluing in aqueous solutions. The coloring is influenced greatly by the initial surface condition (cleanliness and type of finish) and also by the chemical composition of the steel. A slight difference in the chemical composition may cause an appreciable variation in the coloring rate and necessitate a change in the voltage and the current density.

The blue obtained on iron and steel with these electrolytic methods is not so brilliant and intense as that obtained by heat-tinting in air or in salt baths. It is obtained, however, at lower temperatures, which is often very advantageous, especially in the case of fully hardened steels.

A light blue can be obtained by

cathodic treatment in the following solution:

L. Sodium Hydroxide 35 5
Arsenious Oxide 35 5
Sodium Cyanide 7 1

The solution is prepared by dissolving the arsenious oxide and sodium hydroxide in hot water and then adding the sodium cyanide to the cool solution. A plating tank or other suitable vessel equipped with carbon anodes is used. The carefully cleaned article (electrolytic alkaline cleaning preferred) is made the cathode and a potential of about 2 volts is applied. A current density of 2 to 7 amperes per square foot is required. The current density should be adjusted to suit the size and the composition of the steel and is best determined experimentally. A treatment of 1 to 3 minutes is usually sufficient to blue the article, whereupon it is removed, washed in hot water, dried, and if desired, finished as previously described.

A blue or blue-black can be obtained on iron or steel with an electrolytic method, the article to be blued being used alternately as anode and cathode, U. S. Patent 1,342,910. The following solution is used.

M. Sodium Nitrate g./l. oz./gal.
Sodium Hydroxide 375 50

The temperature of the bath is held at 250 to 255° F. (120 to 124° C.), that is, just below the boiling point of the solution. The cleaned article is used as anode against a carbon cathode for 5 minutes with a current density of approximately

150

50 amperes per square foot (4.5 amperes per square decimeter), after which the current is reversed for the same period, the article serving as cathode and the carbon as anode. This cycle is preferably repeated three times. After removal from the bath, the article is washed, dried, and finished in accordance with previous directions. A lighter blue with less gray or gray-black may be obtained by decreasing the coloring periods to 2 or 3 minutes. Stirring of the bath is advisable, as it promotes uniformity of coloring.

# Blackening Iron and Steel British Patent 538,210

The surface is blackened by a twostage treatment in boiling aqueous 2:1 sodium hydroxide-sodium nitrate mixture, the first bath boiling at 11–14° below the second. E.g., the first bath contains 7¾ pounds of the mixture per gallon and boils at 140°, and the second 9¼ pounds of the mixture per gallon and boils at 154°.

Coloring Iron, Blue-Black
German Patent 706,313
Sodium Hydroxide 1200 g.
Sodium Nitrate 50 g.
Manganese Acetate 40 g.
Water 1 l.
Treat for 5 min. at 140° C.

# Coloring Iron

Perhaps the simplest way to blacken iron is to apply to the surface a liberal coating of linseed oil, then heat the plate to the burning point of the oil. The coating so produced can finally be rubbed with benzine or dilute soda solution.

### Formula No. 1

Water	20	oz.
Copper Sulphate	240	gr.
Sodium Thiosulphate	360	gr.

The iron surface must be thoroughly cleaned with dilute sulphuric acid, then boiled in the above bath.

#### No. 2

Water	5000
Mercuric Chloride	250
Ammonium Chloride	250
No. 3	
Water	5000
Ferric Chloride (30° Bé)	375
Copper Sulphate	25
Nitric Acid (26° Bé)	100

The baths should be used near the boiling point; immersion can be repeated until the desired depth of black is obtained.

Alcohol

Besides a glossy black, various other colors can be obtained on iron in the following bath; and, as with copper, the exact color depends on the length of immersion:

Water 1000 Selenious Acid 100 Copper Sulphate 100 Nitric Acid 40 to 60

The bath soon exhausts itself because of precipitation, therein, of insoluble yellow iron selenite.

# Coloring Steel

Closely related to iron is the coloration of steel. In its simplest form, steel is an alloy of iron and carbon, but modern metallurgy has introduced a wide variety of steels, some of which are difficult (if not impossible) to color by simple chemical means. The only recourse with such alloys is the electrolytical deposition of other metals on the surface of the steel.

Steel can be blackened by dipping the thoroughly cleaned metal in a physical solution of sulphur in oil of turpentine (produced by heating the sulphur in the oil on a waterbath). Evaporation of the oil leaves, on the steel, a thin film of sulphur, which is converted to a black color by heating the plate, until dry, in a non-oxidizing flame.

#### Formula No. 1

Water	1000
Caustic Soda	400
Potassium Nitrate	10
Sodium Nitrate	10

The bath should be used at a temperature of 120° F.

#### No. 2

Water	50
Hydrochloric Acid	6
Mercuric Chloride	2
Cupric Chloride	1
Alcohol	5

The plate is immersed in the bath for a few minutes, allowed to dry, then placed in boiling water for onehalf hour. If the surface is not black enough, the operation can be repeated.

The following process of blackening steel depends on initial coppering of the steel surface by immersion for 10 seconds in a bath of:

#### No. 3

Water	250
Copper Sulphate	10
to which is added:	
Water	100
Hydrochloric Acid	20
Stannous Chloride	15
with water added to m	ake a final
1000.	

The adhering film of copper is converted (blackened) to copper

sulphide by immersing the plate for 2-3 minutes in:

Water	1000
Sodium Thiosulphate	1500
Hydrochloric Acid	75

The thiosulphate is dissolved in the water by the aid of heat; on cooling, the hydrochloric acid is added to the solution. Should the bath refuse to blacken after use, add a small volume of hydrochloric acid.

## No. 4

Coloring Steel Blue U. S. Patent 2,102,925

Dip steel sheets into solution of:
Mercuric Chloride 2 lb.
Potassium Chlorate 2 lb.
Nitric Acid (6N) 150 cc.
Water 3 gal.

# Color and Temperature in Heating Steel

The average repair shop is not equipped with pyrometers with which to accurately determine the heat temperature of iron or steel. They have to depend upon the human eye, and in vision the idea of color frequently varies, but for all practical purposes color can be used as a fairly accurate gauge in heating and tempering steel.

Solid bodies which are heated to a point so that they glow with the intensity of their own heat will emit certain colors, depending on the temperature and this independently of the nature of the heated material. In other words, a piece of iron or steel heated to 1500 degrees Fahrenheit, will have practically the same brightness and color as a piece of firebrick which has been heated to the same temperature.

Consequently, providing that the eye of the individual and his keen-

ness of vision are true, the following table will enable the mechanic who has not a pyrometer to determine approximately the temperatures of iron or steel from the following colors:

oximate
perature
$F.^{\circ}$
800
900
950
1000
1050
1100
1250
1300
1450
1550
1600
1625
1700
1800
1900
2250
2400
2600
2800

When the temperature is too low for the material to glow—as in tempering—it is sometimes possible to estimate it by placing a piece of polished steel at a point where it can come approximately to the temperature of the article to be determined upon. After taking the steel away it will be found to have a "temper" color corresponding to the highest temperature reached by it. These colors for the various temperatures are given below and are only for the range between 430° and 600°.

	Approximate
	Temperature
Color	$F.^{\circ}$
Very pale yellow	430
Light yellow	440
Pale straw yellow	450
Straw yellow	460
Deep straw yellow	470
Dark yellow	480
Yellow brown	490
Brown yellow	500
Spotted red yellow	510
Brown purple	520
Light purple	530
Full purple	540
Dark purple	550
Full blue	560
Dark blue	570
Very dark blue	600

From the foregoing table on high heats it is possible to consider the heating and cooling cycles of .20% carbon steel, for example. This is about the average carbon content of the steel most widely encountered in the trade.

Refer to the heat colors in the above chart, and you can then determine the temperatures at which the changes take place in the composition of the steel due to the heat or cooling applied. By this means you can make heat treatment closely accurate in the blacksmith shop.

Stress Relieving, 1150° F.—Around this temperature, there is no change in grain size or composition of the steel. But there is a change in grain structure resulting in plastic flow of the material. In this manner, any internal stresses induced by welding are to all intents and purposes nullified. But if the material has received a permanent

set after welding, stress relieving will not return it to normal.

The material should be held at this temperature for an hour per inch thickness. Cooling in still air is recommended.

Critical Temperature, 1330° F.— No change in grain size of steel but change in composition starts. Iron carbides begin to dissolve and austenitic iron makes its appearance. Below this temperature, quenching has no effect on hardness. Above this temperature, quenching increases the hardness but lowers the ductility of the steel.

Critical Temperature, 1520° F.—At this high-critical temperature, full austenitic iron is obtained. Quick cooling just above this temperature results in a fine grained, hardened steel. As the temperature increases, however, grain growth begins and quenching results in large coarse grains with a corresponding loss in ductility. For welds in this state subsequent annealing is strongly recommended.

Hardened steels may be tempered by reheating to a temperature just below the critical range and followed by a convenient rate of cooling.

Top Annealing Temperature, 1625° F.—For full annealing, the steel should be held around this temperature for one hour per inch of thickness and cooled very slowly in the furnace or in some medium such as lime that will prolong the rate of cooling as compared to that of air.

Top Quenching in Water, 1640° F.
—Above this temperature (a dark orange), the steel should be quenched in oil or lead.

Top Normalizing Temperature,

1770° F.—The steel is heated at this temperature and cooled in still air at ordinary temperatures. The steel is thus given a grain of known structure, size and composition. Normalizing is always followed by some desired heat treatment.

Top Forging Temperature, 2380°F.
—Above this temperature, the steel should not be forged.

At 2710° F., liquid iron appears in the steel, and at 2770° F., iron becomes completely liquid.

## Coloring Silver

In view of the tendency of metallic silver to discolor in the presence of gaseous sulphur compounds, in the atmosphere, it is not surprising that sulphur solutions are used for blackening the metal.

Formula No. 1	
Water	1000
Ammonium Sulphide	4
Ammonium Chloride	8
No. 2	
Water	1000
Potassium Sulphide	5
Ammonium Carbonate	10

The baths are used in a hot state (158-176° F.), and before immersing in the solution, the silver plate should be passed through boiling water.

Silver can be mechanically blackened by rubbing the surface with the following:

No. 3	
Lampblack	30
Graphite	5
Silver Nitrate	15
Lead Acetate	10

The ingredients must be finely powdered and used in the form of a thin paste, achieved by mixing together and grinding the mass to the required state with the addition of sufficient alcohol.

## Coloring Tin

Tin-plated articles or sheets can be blackened by rubbing with carbon black mixed with the least possible volume of French polish. Or the plate can be immersed in:

#### Formula No. 1

Water	10 oz.
Borax	150 gr.
Shellac	300 gr.
Glycerin	150 min.
Nigrosin	600 gr.

With the exception of the nigrosin, the various ingredients are boiled together in the water until dissolved, after which the nigrosin is added. This solution really is a form of varnish, the plate, after dipping, being allowed to dry spontaneously.

## No. 2

A black finish on tin can be had by first ridding the plate of all grease by treatment with a boiling caustic potash solution, rinsing, and immediately immersing in:

Water (Hot)	128	
Antimony Chloride	6	
Copper Chloride	12	

The plate is kept in the bath until the desired color is obtained, then rinsed in hot water.

## No. 3

A dilute (2-5%) palladium chloride solution produces a nice black color on tin, but a less expensive solution is:

#### No 4

Bismuth Subnitrate	5
Nitrie Acid	50
Tartaric Acid	80

The bismuth salt is dissolved in the nitric acid, followed by the addition of the tartaric acid, after which sufficient water is added to make a final 1000 parts of bath.

## Coloring Zinc

Photoengraving zinc etchers have long known that a simple solution of copper sulphate imparts to the surface of zinc a dark gray color, but the following solution gives a more pleasing effect:

#### Formula No 1

romana ro. r	
Water	64
Hydrochloric Acid	8
Copper Chloride	3
Copper Nitrate	2

The solution is slightly blue in color and imparts an intense black to a thoroughly clean zinc surface. After blackening, the metal should be liberally rinsed with water and allowed to dry.

## No. 2

Alcohol	800
Antimony Trichloride	90
Hydrochloric Acid	60

The antimony salt is dissolved in the alcohol, followed by addition of the acid. The solution so obtained can be used for dipping, or it can be locally applied to the zinc with a brush. Drying of the treated areas should be hastened to prevent bleaching of the antimony deposit.

# Cleaning Lead Castings Prior to Plating

Because of the shortage of zinc for domestic use, the zinc base die casting has been replaced by a 12 to 14% antimonial lead casting; and platers have had to change their cleaning cycle to meet the change in casting metal.

There are several methods in use and all of them use different cleaning solutions—by that is meant different proprietary cleaners. However, the cleaners have this in common—they are mild in nature, similar to cleaning solutions used for zinc base die castings.

Cycle No. 1

Degrease.

Clean cathodically in a mild cleaner at 160° F. (change cleaner often).

Rinse.

Soak for 5 minutes in a 10% sodium cyanide solution at room temperature.

Transfer directly to high speed copper for 5 minutes at 35 amp. per sq. ft.

Rinse.

Acid dip.

Nickel plate.

Cycle No. 2

Degrease.

Clean cathodically in a mild cleaner for 1 minute.

Rinse.

Dip in 5% by volume acetic acid. Rinse.

Copper strike in a Rochelle salt copper bath at 2 volts or less for 10 minutes.

Rinse.

Acid dip.

Copper or nickel plate.

Cycle No. 3

Wash in washing machine.

Clean anodically in a mild cleaner for 5 to 20 seconds.

Rinse.

Dip in 3% sulphuric acid for 2 seconds.

Rinse.

Copper strike in a Rochelle salt bath at 10 amp./sq. ft. for 5 minutes.

Rinse.

Copper or nickel plate.

Cycle No. 4

Degrease.

Clean in a mild cleaner cathodically.

Rinse.

Reverse current in a 55° Beaumé sulphuric bath (a nickel strip solution will work) for 15–30 seconds.

Rinse.

Copper strike for 15–30 seconds at 5 volts.

Cycle No. 5

Clean cathodically.

Rinse.

Soak in hot water for 5 minutes. Transfer directly to nickel solution.

Platers' Stripping Solution

This stripping solution is used so that an object may be plated upon the plated portion and then separated from the object forming a mold.

The metallic object, preferably of copper or copper plated is dipped in an aqueous solution of selenious acid of such strength that 1 liter contains .8 g metallic selenium, the object is kept immersed until the copper turns to a deep blue tinge, then washed with water, then plated thereon either with copper, nickel or cobalt, until the desired thickness has been attained, then backed up by pouring on solder. When cool, the original and the plated part can be separated by inserting the point of a knife at the juncture of the original piece and the plating, thereby forming a mold.

Stripping Solution for the Removal of Cadmium Plating Hydrochloric Acid

(37%)

73 cc.

Antimony Trioxide Water

2 g. 27 cc.

Stripping Tin From Brass

For removing a hot-dipped tin coating from 70/30 brass, use a solution of 10 grams "Ferrisul"\* and 10 grams sulphuric acid per 100 cc. This solution removes a 0.0005 inch coating from brass in 5 minutes at a temperature of 75° C. (167° F.) and in 15 minutes at 28° C. (82.4° F.), leaving a matte finish. The relative rates of attack of this solution on tin and brass are:

At 75° C. Tin coating:

8.0 mg. per sq. in. per min. 70/30 brass:

2.7 mg. per sq. in. per min. At 28° C. Tin coating:

> 3.4 mg. per sq. in. per min. 70/30 brass:

1.0 mg. per sq. in. per min. It is known that the rate of attack on the brass is considerably greater for a high brass than for the low brasses or for copper.

# Etching Nickel Plated Printing Plates U. S. Patent 2,233,546

Nickel is removed, where desired, by 40% aqueous copper chloride; the etch is then deepened, without undercutting, by treating with a 40% solution of a 2:1 mixture of iron chloride and nickel chloride.

Stainless Steel Etch British Patent 541,630 Iron Chloride (Saturated Solution) 4 Nitric Acid, Concentrated 1 Hydrofluoric Acid 1 \* Ferric Sulphate.

Color Etching of Stainless Steel U. S. Patent 2,243,787 Gold Tint Formula No. 1 Ammonium Dichromate Sulphuric Acid 7 - 11Water at 85-93° 19 - 23Black No. 2 Ammonium Dichromate 10–14 Sulphuric Acid 36-50 Water at 121-127° 30 - 50

Zinc Etching Fluid U. S. Patent 2,245,219 Copper Sulphate 10-25% Sodium Bisulphate 2%Wetting Agent 0.005% Water, To make 100%

Etching Agent for Zinc Engravings U. S. Patent 2,245,219 Copper Sulphate (20% Solution) 95%Niter Cake (35% Solution) 5% Wetting Agent 0.005%

Aluminum, Protective Coating for U. S. Patent 2,234,206 Formula No. 1

Manganese Dihydrogen Phosphate Manganese Silico Fluoride 50 Potassium Fluoride 4 Water 100

No. 2

Italian Patent 368,331

By dipping aluminum or its alloys for 5-10 min. in a solution of a metal fluoride or silicofluoride or borofluoride in the presence of an organic colloid it acquires a protective coating. A suitable solution may be made by mixing a nearly saturated solution of cadmium silico-fluoride with 4-5 times its weight of water and adding 2-5 parts per thousand of albumen or dextrin.

Brass Plating Bath

Cuprous Cyanide	26.2 g.
Zinc Cyanide	11.3 g.
Sodium Cyanide	45.0 g.
Water, To make	1 l.
TT 1 000 0 d	/ 1

Use at 30° C.; 1 amp./sq. dm.; pH 10.5 with brass anode of about 25% zinc.

# Molybdenum Bronze Plating Solution

Crystal Copper

Orybian Copper		
Sulphate	20	oz.
Molybdenum Trioxi	de 8	oz.
Sulphurie Acid C. P.	7	oz.
Nitric Acid C. P.	$\frac{1}{2}$	oz.
Hydrofluoric Acid		
C. P.	1/4	oz.
Sodium Chloride	$\frac{1}{4}$	oz.
Water	1	gal.

Temperature 75°-80° F. Molybdenum-Iron Anodes (60%-70% Mo.)

The Anodes must be tubular and Hydrogen Gas must be slowly sent through these into the plating bath. Proportion of metals must be reasonably maintained. Anodes should be bagged in Blue African Asbestos Cloth.

# Immersion Plating of Cadmium U. S. Patent 2,272,777

Adherent coatings of cadmium are formed on metals of the group consisting of copper, brass, iron, copper plated iron and brass plated iron without the application of an outside source of electric current by means of immersion in the following:

Example for	Brass:
Cadmium Oxide or	Salt 4
Alkali Cyanide	70-150
Water	1000
Operate at 40°	′–70° C.
Example for	Iron:
Cadmium Oxide or	Salt 5- 8
Caustic Alkali	1200-1400
Water	1000
Operate at 125° C	C. Some alkali

cyanide may be added to this bath.

Copper Plat	ing Bat	th
* *	g./l. o	z./gal.
Copper Cyanide	120	16
Sodium Cyanide	135	18
Free Sodium Cya	a-	
anide corre-		
sponding to	3.75	0.5
Caustic Soda	30	4
or		
Caustic Potash	42	5.6
Brightener	15	<b>2</b>
Anti-pit Agent	1.5	0.2
Operating C	Conditio	ns
Cathode current de	nsity	
10 to 100 amp /	sa ft.	(1 9 to

Cathode current density
10 to 100 amp./sq. ft. (1.2 to
11 amp./dm.<sup>2</sup>)

Anode current density

5 to 30 amp./sq. ft. (0.54 to 3.2 amp./dm.<sup>2</sup>)

E. M. F. on still tanks

1 to 2.5 volts at bus bars

E. M. F. on barrel units 3 to 4 volts

Rate of copper deposition

8.8 amp./sq. ft. (0.95 amp.

/dm.2) deposits

0.001 in./hr. (0.025 mm./hr.)

Cathode efficiency

100% approx.

Anode efficiency 100% approx.

Temperature

75 to 85° C. (168 to 185° F.)

Cathode bar agitation
2 to 15 ft./min. (60 to 450 cm./min.)
Anode to cathode ratio
approx. 2:1

Copper Plating on Iron, Aluminum and Duraluminum

Copper Sulphate 65 g.

Ammonium Sulphate 20 g.

Ammonia 500 cc.

Water, To make 1 l.

Use following current densities:

For Iron 2–3 amp./sq. dm.

For Aluminum 2.7–3 amp./sq. dm.

minum 2.7–3 amp./sq. dm. For Duralu-

minum 4.7-5 amp./sq. dm.

Copper Plating Bath Without Cyanide

Copper Sulphate
Crystals
Ammonium Oxalate
Oxalic Acid
Ammonia (25%)
Sammonia (25%

Ammonia Copper Plating Bath
Copper Sulphate 65 g.
Ammonium Sulphate 20 g.
Ammonia (25%) 500 cc.
Water, To make 1 l.

Before plating clean iron, aluminum or duraluminum with 15% caustic soda; the latter should then be treated with 18% hydrochloric acid.

Use 2.5–3 amp./sq. dm. for iron and aluminum and 4.7–5 amp./sq. dm. for duraluminum.

Black Mirrors

Solution A—Dissolve 10 grams of thiourea in a liter of water.

Solution B—Dissolve 40 grams of lead acetate trihydrate in a liter of water.

Solution C—Dissolve 20.2 grams of sodium hydroxide in a liter of water.

First clean the glass surface upon which the mirror is to be produced with sodium hydroxide, with soap and water and finally water. Protect one surface with Scotch tape or the like. Then immerse the glass plate in a mixture consisting of 100 cc. of Solution A, 25 cc. of Solution B and 50 cc. of Solution C (larger quantities, if desirable). Heat the mixture to 40–41° C. and maintain at this temperature for a period of fifteen minutes, when a black mirror will have been produced.

# Silver Plating Optical Glass

The surface should be cleaned with hot chromate-sulphuric acid solution and thoroughly rinsed with distilled water. It is unnecessary to use the application of caustic soda so often recommended. If a drop of distilled water will spread evenly over the entire surface, it may be considered free from grease or other organic matter.

About a half liter of (1) a 10% silver nitrate solution containing one or two drops of concentrated nitric acid and of (2) a 10% solution of technical triethanolamine are conveniently made up. Both solutions will keep indefinitely.

The surface to be mirrored is placed face upward in a clean Petri dish of sufficient diameter to accommodate it. To 25 cc. of solution 1 in a large test tube are added 10 cc.

of solution 2; then with constant agitation further additions are made of 2 or 3 cc. at a time, just to the point where the precipitate which forms on the first addition clears completely. The mixed solution is poured immediately over the object to be plated so as to cover it by a layer of at least 0.25 inch. The deposition of silver begins within a few seconds.

For the half-reflecting surface required for interferometers, a layer of silver which transmits about as much light as it reflects is ideal. Such a layer has a distinct violet tinge and appears within 10 minutes at room temperature. It is advisable to have several surfaces in preparation at the same time and being plated with the same mixture of reagent but removed from the bath at graduated intervals, and to select the one which has the proper depth of coating rather than attempt to plate a surface additionally which has been found to have been immersed for an insufficient time.

For completely reflecting surfaces, the immersion may last for 24 hours; this particular bath is unique in that the deposition seems to be continuous for that length of time.

When the desired thickness is deposited, the plated object is taken from the bath, only the edges being handled. The silver is removed from the under surface with dilute nitric acid. The mirrored surface is washed with absolute alcohol and then with xylene, and is covered with isobutyl methacrylate which, when allowed to dry, forms an optically inactive film which protects the silvering permanently.

Silvering Mirrors British Patent 537,987

Silvering of e.g., glass is carried out by spraying with a mixture of, e.g., silver nitrate 3, aqueous ammonia 3, and water 128 ounces and a reducing solution comprising a salt (sulphate) of hydroxylamine 2%, aqueous ammonia 1, and water 100 ounces, and 2 ounces of glyoxal in 1 gallon of water.

Plating Silver on Plexiglas (Plastic) Solution A. For pretreatment of Plexiglas

Sodium Hydroxide (C. P.), 350 grams per liter of water

Solution B. Reducing solution Cane Sugar (Granulated), 90 grams

Nitric Acid (C. P.), 4 cc. Ethyl Alcohol, 95%, 175 cc.

Water, Distilled, To make, 1000 cc.

Dissolve the sugar in 500 cc. of water, add the nitric acid slowly with stirring, then add the alcohol and make up to 1000 cc. with the water. Let stand for one week at room temperature before use. Solution C. Silver solution

Part I. Silver Nitrate (CP), 100 grams

Water, Distilled, 1000 cc.

Part II. Sodium Hydroxide (CP) 100 grams

Water, Distilled, 1000 cc.

Part III. Ammonium Hydroxide, (CP, 28%), 400 cc.

Water, Distilled, 600 cc.

Solution D. For removing silver deposits

Nitric Acid, 500 cc. Water, Distilled, 500 cc. Solution E

Dreft (Wetting agent), 50 grams Water, Distilled, 1000 cc.

A Plexiglas, glass, hard rubber, or enamel-lined tray is required for the silvering operation. Leave pieces of Plexiglas to be plated for 24 hours in Solution A. Add 50 parts of Part II (Solution C) and 40 parts of Part III (Solution C) to 1250 parts of distilled water. To this mixture slowly add, with constant stirring about 150 parts of Part I (Solution C), that is, until a clear solution is obtained containing a very small amount of light brown precipitate. Solution C must be mixed fresh from day to day.

For each 20 cc. of Solution C, 1 cc.

of Solution B is required.

Rinse the Plexiglas with distilled water. Always keep an unbroken film of water or silvering solution on the surface of the piece to be silvered.

Immediately mix solutions B and C and pour over the work in the silvering tray. Rock the tray until the solution becomes colorless and the flocculent gray silver precipitate has coagulated. Pour off the solution. Rinse the Plexiglas with distilled water, using also running water. Immediately pour over mirror a second mixture of B and C. Proceed as before. Repeat this a third time. Put mirror on rack to dry. Then paint on a protective coating on back.

Plating Bath Without	t Cyanide
Silver	
Silver Sulphate	3 g.
Potassium Iodide	60 g.
Tetrasodium Pyro-	
phosphate	6 g.

Ammonia (25%)	)		7 cc.
Water			100 cc.
Use at $17-60^{\circ}$	C.	at	0.36 - 2.15
$\mathrm{mp./dm.^2}$			

Silver-Plating Without	Electricity
Silver Nitrate	25
Ammonium Chloride	11
Sodium Thiosulphate	25
Whiting	225
Tartaric Acid	13
Water	480
01 7 77 7 4	70 1

Shake well before using. Rub on articles to be silver plated. This will silverplate copper and brass.

# Plating Solutions Green Gold

Potassium Gold
Cyanide
Sodium Cyanide
Silver Cyanide
Cadmium
Cyanide
Tiny pinch only

Temperature 75–80°
1/10 Sterling Silver
9/10 Fine Gold Anodes

## White Gold

Potassium Gold	
Cyanide	$\frac{1}{4}$ oz.
Sodium Cyanide	$1\frac{1}{4}$ oz.
Nickel Cyanide	$1\frac{1}{4}$ oz.
Cadmium Cyanide	$\frac{1}{4}$ oz.
Nickel Chloride	$\frac{1}{4}$ oz.
Water	1 gal.
Temperature 120°-13	30° F.
ī. 1	

Anodes
1/4 Gold
1/2 Nickel
1/8 Steel

1/24 Cadmium 5/24 Silver

Do not replace Cadmium and Silver Anodes until practically all the Gold Anode is used up. Use Iron Wire to hold Anodes.

# Gold Electroplating Solution Stock Solution

Gold 1 g.
Sodium Cyanide 2 g.
Water, Distilled 100 cc.

Dissolve gold in aqua regia using 150 cc. per ounce of gold, diluting with equal parts distilled water. Heat to speed reaction to completion. Boil down until thermometer reaches 115° C. Dilute 25 cc. water and 25 cc. concentrated hydrochloric acid per ounce of gold. Boil down to 115° C. to remove nitric acid.

Transfer to 3 liter jar to make 250 cc. per ounce of gold. Add ammonium hydroxide with stirring until alkaline and add small excess. Allow precipitate to settle; filter with suction.

Caution: Do not allow to dry or crack. Gold fulminate is explosive!

Wash with about 3 gallons of water until free of chlorine. Dissolve precipitate in solution of 2 g. sodium cyanide per g. of gold. Filter and wash paper, adding washings to filtrate. Analyze for actual gold content and make up with water to 1 g. per 100 cc. solution.

Plating Solution
Stock Solution A 100 cc.
Disodium Phosphate 2 g.
Sodium Cyanide 2 g.
Water, Distilled 1 l.

Plating Instructions
Volts 1–2
Temperature 50–70° C.
Anode Platinum
Color 22 Carat

Add cadmium cyanide to get paler tone. Add nickel cyanide to get lower carat value and color. Add copper cyanide to get redder or pinker color.

Plating Solution
Iron (For Antique Effects)

Ferrous Chloride 41 oz.
Calcium Chloride 19 oz.
Sodium Chloride 1 oz.
Ortho-Phosphoric Acid 5 drp.
Water 1 gal.

Cut up about one ounce of Iron Binding Wire and allow it to dissolve in the above solution (for several days) before putting it into use.

Temperature 190° F.

Rolled Armco Iron Anodes

Anodes should be bagged in Blue African Asbestos Cloth.

Coating Iron with Aluminum or Zinc

British Patent 541,240 A mixture is made of

Zine (or Aluminum)

granular 48.6 Vehicle \* 51.4

The metal is coated with this mixture, dried and heated to 600-700° C.

# Coating Iron with Lead U. S. Patent 2,230,602

Immerse iron or steel in a hot solution of:

Lead Nitrate 6
Sodium Cyanide 100
Water 1000

until a sufficient thickness of lead is gotten.

\*Vehicle consists of Zinc (or Aluminum) Stearate

Toluol

21.4 78.6

## Lead Plating

Like other plating baths the composition of the fluoborate lead bath varies, depending largely on the current density required. For deposits up to about 0.001 in. (0.025 mm.) thick produced at fairly low current densities, a bath of the following composition is recommended:

Formula No. 1
g./l. oz./gal.

Basic Lead Carbonate 150 20

Hydrofluoric Acid
(50%) 240 32

Boric Acid 106 14

0.2

0.025

For barrel plating operation or for still plating at higher current densities in which heavy deposits up to 0.05 in. (1.27 mm.) thick are required, best results can be secured from a bath of the following composition:

Glue

No. 2 g./l. oz./gal. Basic Lead Car-300 40 bonate Hydrofluoric Acid (50%)480 64 Boric Acid 212 28 Glue 0.20.025

The fluoboric acid solution is best prepared by placing the necessary amount of commercial hydrofluoric acid in a lead-lined or rubber-lined, or wooden tank and slowly adding crystalline boric acid. Considerable heat is developed during the ensuing reaction. The solution is allowed to cool, after which the lead is introduced as basic lead carbonate, in the form of a thick paste with water, adding it slowly with stirring. Considerable effervescence results from the dissolving of lead carbonate in

the acid and the resultant evolution of carbon dioxide. The solution is then diluted to the required volume and decanted or filtered into the plating tank. Since the commercial materials used in the preparation of the solution invariably contain sulphate, some precipitate of lead sulphate will be left behind in the original tank. The preparation of the fluoborate lead bath thus entails considerable care and caution, and differs from the preparation of most plating solutions in the respect that the chemicals used must be added in a specific order.

The acidity of the fluoborate bath is high enough so that the pH need not be controlled. However, the concentration of free fluoboric acid in the solution, although not critical, should be maintained within fairly definite limits.

The commercial operating characteristics of the fluoborate bath are given below:

Temperature

25° to 40° C. (77° to 105° F.) Above 40° C. (105° F.) use cooling.

Cathode Current Density
Dilute Type Solution for Thin
Deposits

5 to 50 amp./sq. ft. (0.54 to 5.4 amp./dm.<sup>2</sup>) — extreme limits. Average value — 20 amp./sq. ft. (2.2 amp./dm.<sup>2</sup>) Heavy deposits—10 amp./sq. ft. (1.1 amp./dm.<sup>2</sup>)

Concentrated Type Solution
5 to 70 amp./sq. ft. (0.54 to 7.6 amp./dm.²) — extreme limits.

Average value — 30 amp./sq. ft. (3.2 amp./dm.²) Heavy deposits — 20 amp./sq. ft. (2.2 amp./dm.²)

Cathode Current Efficiency
100%
Throwing Power
Haring cell, 5:1 ratio 8 to 9%.
Anode Current Density
10 to 30 amp./sq. ft. (1.1 to 3.2)
$amp./dm.^2$ )

For Iron or Steel
U. S. Patent 2,230,602
Formula No. 1
Lead Nitrate 6 g./l.
Sodium Cyanide 100 g./l.
Temp. 180°-200° F.

No. 2
Lead Monoxide 5 g./l.
Caustic Soda 100 g./l.
Sodium Cyanide 10 g./l.
Nekal BX (Wetting
Agent) 2.5 g./l.
Temp. 180°-200° F.

No. 3
Lead Monoxide 1.5 g./l.
Caustic Soda 100 g./l.
Sodium Cyanide 50 g./l.
Nekal BX 0.05 g./l.
Room Temperature.

For Copper or Zine
Lead Monoxide 3 g./l.
Caustic Soda 100 g./l.
Sodium Cyanide 25 g./l.
Room Temperature.

No. 4 Lead Carbonate oz. Sodium Hydroxide 6 OZ. Water to 1 gal. Volts 3 - 4175° F. Temperature Anode Lead

Lead Carbona	te	20	oz.
Hydrofluoric A	$\Lambda { m cid}$	32	oz.
Boric Acid		14	oz.
Glue		0.025	oz.
Water	to	10	gal.

Mix hydrofluoric and boric acids together. Add the mixture of lead carbonate and glue. To the whole, add water, at room temperature, 10 to 20 amps. per square foot, lead anode.

Nickel Plating Bath U. S. Patent 2,125,229

Nickel sulphate hexahydrate 32, nickel chloride hexahydrate 4, boric acid 5, selenium dioxide 0.01, and naphthalene disulphonic acid 0.1 gram/liter.

Nickel Plating Salt	
German Patent 699,021	
Nickel Sulphate	90
Sodium Chloride	34
Boric Acid	18
Sodium Naphthalene-	
Sulphonate	2

Nickel Plating Aluminum
U. S. Patent 2,233,410
Degreasing Solution
Formula No. 1

rormula ino.	I.
Manganese Sulphate	3 – 5%
Sodium Cyanide	2 - 6%
Ammonia	2–8%
Gelatin	0.5 – 1%
Cathode at less than 2	volts, pref

Cathode at less than 2 volts, preferably 1–1.5 volts.

No. 2	
Zinc Sulphate	4-6%
Sodium Cyanide	4-8%
Potassium Hydroxide	2-8%
Dextrin	0.5 - 1%
Cathodic at a minimu	m of 0.5-1
volt	

Plating Solution	on
Hexaamino-Nickelo-	
Sulphate	15 - 45%
Ammonium Acetate	1- 5%
Magnesium Sulphate	
C. D. 0.25—6 amps./s	
volts; room temp. or hot	j.

Nickel Dip for Enameling
U. S. Patent 2,265,467
Single Nickel Salts 2–4 oz./gal.
Boric Acid ¼ oz./gal.
Alkali, To pH 5.2–6.4

Immerse the iron for about 5 min. at about 160 or 170° F. Rinse for 1½ min. in a solution of 0.1% by weight of sulphuric acid and then neutralize in the usual neutralizing bath.

Bright Ductile Nickel Plating Bath
British Patent 513,634
Nickel Sulphate 280
Nickel Chloride 60
Boric Acid 30
Nickel Benzene Disulphonate 11
Zinc Sulphate 3
Water, 1 liter.

Nickel Brightener U. S. Patent 2,228,991 Brightener: Cobalt Chloride 14 Cadmium Chloride 1 3 Ammonium Chloride 7 Nickel Chloride Sodium Sulphate, 3 Anhydrous 2 Sulphuric Acid 70  $_{
m Water}$ Plating Solution: Double Nickel Salts 12 oz./gal. Single Nickel

4

oz./gal.

Salts

Boric Acid	3 oz./gal.
${f Ammonium}$	, -
Chloride	4.5 oz./gal.
Sodium Chloride	0.8 oz./gal.
Brightener	, 0
(Above)	0.4 oz./gal.
pH = 5.5	, -
Temperature $= 7$	′0° F.
C. D. = up to 48	amp./sq. ft.
Deposit has a blu	ish cast.
-	

Semi-Bright Nickel Plating
U. S. Patent 2,274,112
Nickel Chloride 300 g./l.
Boric Acid 30 g./l.
pH 1.0
Temp. 110° F.
C. D. 75 amp./sq. ft.

Platinum Plating Solution
Ammonium Nitrate  $3\frac{1}{2}$  oz.
Platinum Diamino
Nitrite  $\frac{1}{3}$  oz.
Sodium Nitrite  $\frac{1}{3}$  oz.
Ammonia  $(26^{\circ})$  2 oz.
Water 1 qt.
Use at  $200^{\circ}$  F. with platinum anodes.

Protective Filming of Tinplate British Patent 282,156

The plain cans are immersed in the filming bath for about five minutes at a temperature of 85–90° C. (185–195° F.). They are then removed and very thoroughly rinsed with water.

The composition of the bath is: Trisodium Phosphate 40 g./l. (Crystalline) Sodium Hexametaphosphate 20 g./l.  $12.5 \, \text{g./l.}$ Sodium Dichromate Sodium Hydroxide 14 g./l. Wetting Agent 5 cc./l.

The solution should preferably be

contained in an enameled tank, but a plain, mild-steel tank may be used provided that the cans do not come into contact with the steel. If possible, softened water should be used in making up the solution. The wetting agent will not dissolve properly in the cold, but dissolves on heating.

The pH of the bath must be maintained at 12.5, and although the process consumes a negligible amount of the chemicals, small adjustments have to be made from time to time. A valuable feature of the process is that the bath is essentially an active degreasing agent and no preliminary degreasing is called for.

The film is quite invisible and the cans have a bright and attractive luster; and as the solution has some passivating action on any iron exposed at pores, the cans are less liable to rust during storage or transport.

 $\begin{array}{cccc} & \text{Tin Plating} \\ & \text{Tin Sulphate} & 54 & \text{g.} \\ & \text{Sulphuric Acid} & 100 & \text{g.} \\ & \text{Cresol or Phenol} & 20-30 & \text{g.} \\ & \text{Gum} & 2\frac{1}{2} & \text{g.} \\ & \text{Water, To make} & 1 & 1. \\ & \text{Use at } 20-30\,^{\circ}\text{ C.}; \text{ at } 2-5 \text{ amp./sq.} \\ & \text{dm.} \end{array}$ 

Tin Coating Aluminum Pistons
The first step in the immersion
method of the tin coating process,
after the piston is machined, is
cleaning. This is accomplished by
dipping the pistons in a 3.0 oz. per
gallon solution of tri-sodium phosphate which is operated at a temperature of between 175° F. and 185°
F. The pistons are immersed in the
cleaning bath only until gas bub-

bles form on the aluminum, since the surface of pistons remaining for too long in the solution would be etched. An etched surface has been one cause of blistered plate.

Following immersion in the cleaning solution, the pistons are rinsed in cold water. The pistons are then dipped in a 3% nitric acid solution for about 30 seconds. This dip is used only to prevent any alkali of the cleaning solution from contaminating the tin bath. A thorough rinse in cold water follows the acid dip.

The pistons are then placed in the sodium stannate bath which is made up by dissolving 6.0 oz. of sodium stannate in each gallon of water used. The tin bath is operated at a temperature between 170° F. and 175° F. The metal content must be kept between 0.9 and 1.5 oz. per gallon of tin. There is a tendency for free alkali to build up in the bath, however, the free alkali content must be kept below 0.3 oz. per gallon, otherwise blistering will develop in the coating. The blisters are semimicroscopic and can only be seen with the aid of a powerful hand lens or a low power microscope.

The tin content of the bath is kept up to standard by the addition of sodium stannate. The stannate is dissolved in hot water and added to the bath as required. The free alkali content is controlled by adding acetic acid, diluted one part of acid to 10 parts of water, to the bath as required.

The length of time the work must remain in the bath depends on how thick a coating is desired. A minimum thickness of .00018 in. of tin is obtained by immersing the work in the bath for four minutes. After the plating operation, the work is rinsed successively in cold and hot water.

After continued operation of the bath, there is a tendency for sludge to form in the bath. This sludge, composed of aluminum, carbonates and stannic tin, must be removed from the solution periodically; otherwise, too great a concentration will cause blistering in the tin coat.

A schedule of sodium stannate and acetic acid additions can be worked out according to production. For example, add 10 lbs. of sodium stannate to the bath after every 1.000 pistons are coated and one gallon of acetic acid after every 2.000 pistons are coated. These additions keep the metal content within the specified range and keep the alkali content below 0.3 oz. per gallon. Therefore, chemical analysis is not necessary each time tin or acid should be added to the bath, but an analysis for tin and free alkali should be performed at least once a day in heavy production.

Immersion Tinning of Copper and Brass U. S. Patent 2,159,510 Sodium Cyanide 50 g. per l. Stannous Chloride 5 g. per l. Caustic Soda 5.6 g. per l.

The solution is easily prepared by adding the caustic soda slowly and with agitation to an aqueous solution of stannous chloride; after adding the sodium cyanide and diluting to the required volume the bath is ready for use.

The article to be tinned must be thoroughly cleaned to remove grease or dirt. Pickling is preferable, though not essential. The better the

surface before immersion the better will be the coating. A brass or copper vessel can be tinned on the inside by filling it with the solution and allowing it to stand until the required coating has been deposited. The insides of pipes and tubes can be coated either by circulating the solution through them or by filling them with the solution for the required time and then draining and washing.

The thickness of the coating depends upon the time of immersion.

For many purposes it is sufficient to judge the coating by its appearance, but it has been found that an immersion of  $2\frac{1}{2}$  minutes in the solution is just sufficient to give a coating of good appearance, but not to protect the copper against attack by moist hydrogen sulphide. Specimens immersed for  $6\frac{1}{2}$  minutes or longer acquire coatings of good appearance which are unattacked by hydrogen sulphide.

Zinc Plating

Zinc Cyanide 8.0 oz./gal. Sodium Cyanide 3.0 oz./gal. Sodium Hydroxide 7.0 oz./gal.

Zinc Oxide 6.0 oz./gal. Sodium Cyanide 10.0 oz./gal. Sodium Hydroxide 2.0 oz./gal.

The temperature of a zinc solution is best kept at between 40 and 50° C. The current density necessary is 10 to 20 amp./sq. ft. The anodes used may be pure zinc or mercury-zinc or aluminum-mercury-zinc. The anodes containing other metals than zinc are far more expensive than the pure zinc. Although they give a better looking deposit than the pure zinc, the pure

zinc anodes used with the addition of mercuric oxide in the plating bath will give as good a result and this

is probably cheaper.

The addition of mercuric oxide to the bath up to 2% of the zinc content increases the cathode efficiency and gives a whiter deposit. While the ordinary zinc solution will not plate cast or malleable iron, the addition of mercury will make possible the plating of these metals. With the addition of mercuric oxide the current density may be raised to 30 or 40 amp./sq. ft.

Incidentally, about zinc anodes. The aluminum-mercury-zinc anodes are sludge-free while the mercury-zinc and the pure zinc anodes produce sludge. The polarization of the aluminum-mercury-zinc anodes is practically constant at 2.9 volts while polarization of the mercury-zinc anodes and the pure zinc anodes at continuous plating will be 3.0 to 3.1 volts.

Another zinc solution used successfully is made up as follows:

Zinc Cyanide 10.0 oz./gal. Sodium Cyanide 4.0 oz./gal. Sodium Hydrox-

ide 10.0 oz./gal.
This solution is analyzed and kept at these concentrations:

Zine 4– 6 oz./gal.
Total Cyanide 10–12 oz./gal.
Sodium Hydroxide 10–12 oz./gal.

Bright Zinc Coating of Steel
and Brass
Zinc Oxide 45
Sodium Cyanide 78
Sodium Hydroxide 75
Glycerin 3–5
Water, To make 1 1.

Plate with 2-4 amp./sq.dm. at 20-25° C. After plating wash for a few seconds with 3-6% nitric acid.

Electropolishing of Copper

Use copper anode in not more than 600 g./ liter of aqueous solution of ortho-phosphoric acid, 20-25° C., current density 75-300 A/square foot.

Polishing Powder for Gold and Platinum Final Finishing Bauxite Ore Con-

centrate 6

Red Rouge Powder (Dixon)

 $\begin{array}{cccc} \text{(Dixon)} & 35 & \text{g.} \\ \text{Putty Powder} & 1 & \text{lb.} \\ \text{Aluminum Chloride} & \frac{1}{2} & \text{lb.} \end{array}$ 

1b.

Mix putty powder and aluminum chloride thoroughly and add bauxite ore concentrate and red rouge powder. Mix again.

To use: Make paste with alcoholwater 50% solution and apply to work. Use high color buff.

Plating Touch-Up Solution

Where nickel or chrome plated surfaces have been scratched or cut through in spots by handling or mechanical operations, they may be temporarily obscured by painting with a 10% solution of mercuric chloride.

Plating Non-Conductors

Four hundred cc. of 9% caustic soda, 200 cc. of reducing solution. (100 g. of sucrose in 250 cc. of water are heated with 0.5 cc. of nitric acid to development of an amber color, and water is added to 1250 cc.), and 80 cc. of formalin are added to 1 l. of solution containing copper sulphate, 30 g., glyc-

erol 80 cc., and concentrated aqueous ammonia 20 cc., and the article (galalith, glass, etc.) is immersed in the solution. After a coating of copper has formed, the desired design is applied with cellulose lacquer, 15% nitric acid is applied to remove uncovered copper, the article washed, the lacquer removed by means of butylacetate, and the required metal coating deposited electrolytically.

Corrosion Resistant Coating
British Patent 476,042
Colloidal Graphite 4.5 %
Gelatin 0.75%
Potassium Dichromate .04%
Water, To make 100 %
This gives a hard, adherent, water resistant coating after subjection to actinic light.

Improving Corrosion Resistance of Metals British Patent 530,006 Prior to painting, iron or steel is coated with:

Phosphoric Acid (75%) 30 g. Zinc Chromate 14 g. Water 8 l.

Metal Degreasing and Rustproofing Solution

U. S. Patent 2,123,856
Trichlorethylene 97.5%
Rosin 2.0%
Linseed Oil, Boiled 0.5%

Rust Inhibitor for Metal to Be Painted

U. S. Patent 2,127,202
Salt 66
Chromium Oxide 33
Cresylic Acid 1
Wash the metal with a solution

of 1-2 oz. of the above per gallon of water.

Rust Preventing Compounds Formula No. 1 Petroleum Asphalt 50 Kerosene or Solvent Naphtha 40 No. 2 Asphalt 52 Benzene 48 Sublimed Red Lead 30 Sodium Chromate  $\frac{1}{2}$ 

Corrosion Prevention U.S. Patent 2,244,526

A process of coating articles of iron, copper and aluminum and their alloys to form a rust and corrosion resistant film, comprises subjection to a molten mixture of an alkali metal nitrate, an alkali metal hydroxide and manganese dioxide followed by neutralization and finishing or fixing in an aqueous solution of a coloring and sealing medium.

First Bath, for Iron and Alloys
Sodium or Potassium Nitrate, Phosphate or Carbonate 66% or more
Sodium or Potassium Hydroxide 34% or less

First Bath, for Copper Alloys and Aluminum

Sodium or Potassium Nitrate 50% Sodium or Potassium Hydroxide 50%

The addition of 1–2% manganese dioxide to either bath improves the fluidity and acts as a flux. Crystal copper sulphate in the same amount also has a stabilizing effect. Temperature is from 500–900° F., preferably 700–900° F.

#### Neutralizer Bath

1–2% hydrochloric acid or up to 5% of either sulphuric acid or oxalic acid at 160° F. A preferable solution is 4 oz./gal. of iron sulphate which not only neutralizes but darkens the color.

#### Finishing Solution

4 oz. to one Imperial gallon of iron sulphate, crystalline haematoxylin, water soluble nigrosine, tannic acid or logwood chips.

#### First Bath

		For	rmu	ıla I	No.	
	1	2	3	4	5	6
Sodium						
Nitrate	5	5				
Potassium						
Nitrate	1	5	1		65	50
Sodium						
Hydrox-						
ide		1	1	2	34	50
Trisodium						
Phos-						
phate			4			
Potassium						
Carbo-						
nate			_	4		
0.5-10% of	ma	nga	ines	se d	ioxi	de o

Rust Preventor and Remov	7er
U. S. Patent 2,235,944	
Linseed Oil, Boiled (Includ-	
ing Drier)	10
Pine Oil	2
Oleic Acid	2
Petroleum Distillate	86

copper sulphate may be added.

Rust Remover	
U. S. Patent 2,209,291	
Formula No. 1	
Phosphoric Acid	36
Zinc Phosphate	3

Gum Arabic	2
Manganese Chloride	1
Water	28
Butyl Propionate	30
Australian Patent 109,096	3
No. 2	
Phosphoric Acid	32
Sulphuric Acid (66° Bé)	15
Potassium Dichromate	4
Zinc Chloride	6
Sodium Potassium Tartrate	2
Water	37
Alcohol	4

#### Rust and Mill Scale Remover

To remove scale and rust from materials which are to be cleaned around a mill, dip the articles in the following, then rinse in plain water and apply a coat of thin oil to prevent further rusting.

one in the contract in the con	
Methyl Alcohol	5
Ortho Phosphoric Acid	40
Denatured Ethyl Alcohol	<b>2</b>
Water	53

#### Cleaning Rusty Tools

The life of tools which will be progressively more difficult to replace may be lengthened by keeping them free from rust. Even heavy deposits of rust can be removed easily and economically by the use of a paste made from the following ingredients:

Glycerin	1
Oxalic Acid	2
Phosphoric Acid	2
Ground Silica	- 5

The tools should be coated with the paste and allowed to stand in a warm place for about 20 minutes, after which the paste and the rust with it can be washed off, and rust preventive applied.

#### Removing Rust from Steel Instruments

Lay the instruments, over night, in a saturated solution of chloride of tin. The rust spots will disappear through reduction. Upon withdrawal from the solution, the instruments are rinsed with water, placed in a hot soda-soap solution, and dried. Cleaning with absolute alcohol and polishing chalk may also follow.

Another method is: Make a solution of 1 part of kerosene in 200 parts of benzene or carbon tetrachloride, and dip the instruments, which have been dried by leaving them in heated air, in this, moving their parts, if movable, as in forceps and scissors, about under the liquid, so that it may enter all the crevices. Next lay the instruments on a plate in a dry room, so that the benzene can evaporate. Needles are similarly thrown in a paraffin solution, and taken out with tongs or tweezers, after which they are allowed to dry on a plate.

Corrosion Inhibitors for Automobile Radiators

With ethylene glycol or glycerol anti-freezes use

Morpholine or Dimethyl Morpholine or Ethanol Morpholine about 0.2%

Preventing Corrosion of Brass U. S. Patent 2,272,216 Rinse in any of the following: Formula No. 1

Zinc Dihydrogen Phosphate 42 lb.

Ammonium Persulphate

8 lb.

Water 100 gal. 5 minutes immersion at 200° F.

No. 2 Manganese Acid Phos-

phate Solution 40 lb.
Zinc Carbonate 1 lb.
Sodium Nitrite 4 lb.
Water 100 gal.

15 min. at 210° F.

No. 3

Zinc Dihydrogen Phos-

phate 40 lb.
Sodium Nitrite 4 lb.
Water 100 gal.

5 min. at 200° F.

Add nitrite continuously for better results as it decomposes rapidly.

Increasing the zinc content in the above solutions such as by adding zinc sulphate or nitrate improves the coating a great deal.

The final rinse may contain 7-21 oz./100 gal. of chromic acid, phosphoric acid, oxalic acid or salt of aluminum, chromium or iron and is operated at 150°-180° F.

Protecting Copper and Brass Against Corrosion U. S. Patent 2,233,442

For brass: To 100 gal. of water add 26 lb. of magnesium dihydrogen phosphate and 4.5 lb. of sodium bromate. Immerse article at 210° F. for approximately 5 minutes or spray the solution on. The final rinse may contain 7–21 oz. of chromic acid, phosphoric acid, oxalic acid in 100 gal., or various metal salts, at a temperature of 150–180° F. for 1 minute.

For copper: To 100 gal. of water add 25.2 lb. of zinc dihydrogen phosphate and 9 lb. of sodium chlorate. Boil. The increase of the zinc content by adding 9 lb. of a soluble

zinc salt improves the coating. The solution should test 2.2 free acid and 15.5 total acid. The operating conditions are the same as for brass.

Corrosion Proofing Iron and Copper U. S. Patent 2,271,374-5

Three baths are used: first, the molten cleaning, stripping and coating bath; second, a neutralizing bath; and, third, a sealing and/or coloring finishing bath. Crystalline copper sulphate or manganese dioxide in amounts of 0.5%-10% can

be added to the formulae below, preferably in amounts of 1%-2% as fluxing and stabilizing agents. Operation is at 600°-900° F.

After coating in the fused bath, the articles are rinsed and neutralized in a weak solution of a suitable acid or aqueous solution of iron sulphate, preferably at a temperature of about 160° F. The preferred bath contains about 4 oz./gal. of iron sulphate. The articles are then rinsed and may be darkened in a third bath containing a dye.

					Form	nula					
	No.										
. 1	2	3	4	5	6	7	8	9	10	11	12
Trisodium Phosphate 3										2	<b>5</b> 0
Potassium Nitrate 2		1				3				1	
Sodium Hydroxide —								1	3	3	50
Sodium Carbonate —	-		-1					_	1		
Potassium Phosphate —			_	2	2						
Sodium Nitrate —					<b>2</b>			3			

Iron Pipe, Corrosion Protected U. S. Patent 2,216,376

Immediately after drawing, quench in:

donon in.	
Linseed Oil	82.5
Oleic Acid	9.4
Trisodium Phosphate	3.0
Lauryl Alcohol	1.0
Triethanolamine	1.8
nd dry.	

Rustproofing Iron and Steel French Patent 850,642

Trisodium Phosphate	1
Sodium Bicarbonate	2
Gelatin	2
Water	100

Immerse metal in above; withdraw and dry. Inhibiting Corrosion of Magnesium Alloys

Electrochemical oxidation in baths containing the following protect magnesium alloys:

Potassium Dichromate	10%
Sodium Hydrogen Phos-	
phate	5%
$\mathbf{or}$	

Sodium Hydroxide 5% Sodium Carbonate 5%

The bath is run at 2 to 3 amp. per sq. dm., at 50° or 45-50°, for 60 or 30 minutes. The chromate bath is rapidly spent. Unless it is renewed, scaly, irregular, poorly adhering layers are formed.

#### Corrosion Prevention of Magnesium U. S. Patent 2,268,331

A method of producing a nonsmudging, adherent coating on a magnesium surface, comprises treating the surface in a hot aqueous solution containing an alkali metal borate and an alkali metal bicarbonate capable of providing available carbon dioxide in the coating solution.

Sodium Bicarbonate 4–12% Borax 1–8%

Time: 5-45 min. Temp.: 200-212° F.

Lubricating, Rust Preventing and Bright Annealing in Manufacture of Nickel Alloy Stampings

Nickel alloys, which are die stamped (the dies being cooled by a soluble oil mix) and then annealed require a protective coating against water, as well as additional lubrication in the forming. Flexo Wax C when applied to the nickel alloy from a solvent solution, either by brushing, spraying or dipping, furnishes lubrication as well as a water resistant finish. It has been found that, when the nickel alloy is annealed, the Flexo Wax C has a reducing action on the oxides and gives a very bright anneal, e.g., a 2% solution of Flexo Wax C in carbon tetrachloride is sprayed on a 78% nickel alloy. The dies do not heat up as much as when only lubricated with a cutting oil and have a longer operating life. After the pieces are formed they are then subjected to a temperature of 1980° F. for the bright anneal,

#### Anti-Rust Solution

The addition of 0.025% sodium chrome glucosate to water, in contact with ferrous metals during mechanical operations, will prevent rusting.

Rust Inhibitor for Water Systems
Sodium Silicate (40° Bé) 30
Caustic Soda 3½
Trisodium Phosphate ½
Aluminum Oxide ¼
(Use ½ pt. to 4 gal.)

Tarnish and Corrosion Prevention
Ozokerite 20
Paraffin Wax 40
Diglycol Stearate 10

The waxes are dispersed in hot water in proportions of 7 parts of wax to 40 parts of water, giving an emulsion which is applied preferably by spraying, leaving a thin, transparent, adhesive and flexible film. Protection is obtained from tarnish or corrosion of ferrous as well as non-ferrous metal surfaces. For instance, the flat ground steel surfaces and the nickeled intaglio portion of candy molds are both protected effectively. The coating tolerates extremes of high room temperature and very low freezing temperature. A recent report indicates that waxy coatings on steel machinery and parts are much better than grease slushing because waxy coatings apparently seek out the spots particularly susceptible to corrosion or which have already begun to corrode. Greases do not always inhibit the electrochemical action resulting in corrosion, whereas waxes do. Where the coating must be removed, boiling water, hot water and soap, or solvents may be used. Silver Tarnish Inhibitor
U. S. Patent 2,117,657
Silver articles are dipped in:
Stannous Chloride 1 g.
Hydrochloric Acid 7 cc.
Water, To make 1 l.

Precious Metal Casting Mold U. S. Patent 2,229,946 Formula No. 1

Silica 40–80% Plaster of Paris 15–60% Ammonium Bromide 1/4–3% U. S. Patent 2,121,969

No. 2

Magnesium Oxide, Fused 75
Calcium Hydroxide 25
Press into shape and heat to 820° C.

#### Core Binders

Emulsified oleoresinous compositions make good core binders. Linseed, cottonseed and castor oils are effective, usually prepared as a melt in rosin before being emulsified in water. For the usual requirements as to mechanical stability a core may be made up with 1.1% of emulsion binder, calculated on weight of sand in the core. For stronger cores, to meet unusually severe requirements, it is necessary to use about 1.4% of binder. Since nearly half of the emulsion is oil, the calculated oil consumption is therefore 0.53% for ordinary binders and 0.68% for stronger binders, calculated on the weight of sand. Linseed oil makes stronger cores than do nondrying oils, but for economy in linseed oil it is quite possible to use cottonseed oil instead. In that case 1.6% of emulsion should be used in cores of ordinary strength, instead of 1.1% as in the case of linseed oil. A suitable recipe for a cottonseed oil core binder is: Blend of cottonseed oil and rosin, 100 parts; oleic acid, 2 parts; triethanolamine, 1.2 part. The oleoresin blend in this recipe is made from 71.2% cottonseed oil and 28.8% rosin. Another binder is made by blending 67.24 parts of castor oil with 32.76 parts of rosin and emulsifying the product in 100 parts of water with the aid of Turkey red oil 1, acidol 1 and sodium hydroxide 0.35 part.

#### Emulsion Core Binder

Castor Oil	67.24
Rosin	32.76
Turkey Red Oil	.50
Acidol	.50
Caustic Soda	.18
Water	100.00

## Foundry Core Binder U. S. Patent 2,215,825

113 pints of ammonium sulphate and 1100 pints of blackstrap molasses are dissolved in 275 pints of water and then 120 pints of a water-soluble glycerol-citric acid resin, an emulsifier comprising 265 pints of tung oil and 15 pints of karaya gum, and 15 pints of beta-naphthol as preservative are added. The core is made by mixing 30 pints of green-sand with 1 pint of binder as made above, molding and baking at 180-300°.

#### Foundry Core Application for Smooth Metal Castings

Non-ferrous metals can now be cast in smooth, fine cores at a considerable saving of time. This is easily accomplished by the addition of a small percentage of "Sulfatate," a new type of wetting agent. The or-

linary core for casting non-ferrous metals is usually a combination of silica, sandclay binder and linseed oil. This type of core is very rough and necessitates a great deal of machining to finish the casting. If, after baking the core, it is dipped into a solution of 1 pt. molasses, 10 lb. graphite, 1 lb. "Sulfatate," and water sufficient to make 5 gal., and then rebaked, the core will present a smooth surface for casting, which will require little, if any, machining on the casting.

The addition of the Sulfatate eliminates the necessity of hanging the core so that the excess graphite-molasses mixture will drip off. The core, when it is withdrawn from the solution, breaks away cleanly. This not only produces a finer and truer core for casting, but also saves a good deal of time in preparation.

#### Refractory Dental Mold for Casting Alloys U. S. Patent 2,243,094 Granular Zircon 100.0

Milled Zircon	50.0
Calcined Magnesia	1.5
Zirconium Oxychloride	
Solution (d. 1.38)	14.0

#### Foundry Sand Binder U. S. Patent 2,206,369

U. S. Patent 2,206,369	)
Silica Flour	75
Milk, Powdered	15
Soya Bean Meal	10
Sodium Oxalate	$1\frac{1}{4}$
Rosin	5
Borax	1
Mineral Oil	1

Quenching and Descaling Bath British Patent 532,807 Orange Pectate Pulp 2 kg.

Water	100 l.
Disodium Phosphate	100 g.
Sodium Hydroxide	50 g.

Quenching for Steel Tempering A mixture of glycerin and water is useful in range between water and oil quenching. The higher the percentage of glycerin the milder the quenching.

# Mild Steel Quenching Bath U. S. Patent 2,216,192 Kerosene 5/6 gal. Tallow, Molten 1/6 gal. Salt 2.0 lb. Disodium Phosphate 0.6 lb. Sodium Bicarbonate 0.6 lb.

Tartaric Acid
Use from 820°.

Tempering Small Tools

0.3 oz.

For twist drills, taps, dies, small punches, or such articles of tool steel that you wish to keep straight, take as follows: Equal parts of prussiate of potash and common salt, put them together in an iron pot over fire. When it gets to proper temperature it will boil and become a cherry red.

Put the tool in this until it becomes a cherry red. You may leave the tool in all day if you wish, for the longer the more it improves the steel. When you take it out, cool in water or linseed oil, always in a vertical position. Do not draw. But for taps or dies draw to dark straw.

Tempering Cold Chisels

At no time when working steel let it sparkle; just get a nice red heat. Better heat it oftener than get it too hot. Make the chisel the width of the stock and don't let it swell out at the bit. If you do, someone will cut on the outside corner and snap off the corner. It has no back sup-

port there.

If in forging, you should get the bit too hot, cut it off as far as it is too hot, and do not fool with it, as it is no good. The higher grade steel you use, the lower you should heat it when tempering. Heat the steel at low red heat and heat at least one-third of the chisel and dip it in cold water.

Try it and if it should not harden very hard, heat it again a little hotter than the first time until it does harden. This way gets the chisel hardened at the lowest heat. The tool should be plunged from 1 to  $1\frac{1}{2}$ inches in the water. This will give plenty of time to rub the chisel and the temper will come down slowly and not hurt you. The temper to be right for general purpose service should be purple at the point. There is only one man out of ten who knows how to grind a chisel after he has bought a good one. They should be ground with a very short bevel. The best chisel that can be made won't stand anything that is ground with a long taper. There is no body or support for cutting edge.

Tempering Bath for Files	
French Patent 847,979	
Barium Chloride	50
Sodium Chloride	20
Potassium Chloride	30
Sodium Cyanide	4–8

Hardening the Thin-Edge Tools First, the warping and springing of steel is mostly due to the heat, and not as many suppose, to the cooling bath. This can readily be demonstrated by laying a long piece of steel on a fire, where the heat will strike it unevenly, and taking note of the changes by sighting over its top. Thus the first important point is to have the heat strike evenly on all sides of the piece.

In hardening such a piece as an axe (and this applies to all thin-edge tools of the same nature), raise it to the proper heat very slowly, and with as little blast as possible, then plunge it into the quenching bath straight down and head first; in other words, the thin or cutting edge should be immersed last. After cooling, immediately hold it over the flame of the fire until the water rolls up and runs around the surface. Tools treated in this way will never crack.

A very good bath for delicate work is hot water. This, in a great many cases, gives the right degree of hardness without having any draw down afterwards.

To temper knives, or any thin tools, two flat pieces of metal should be used. Lay one plate down flat and spread enough oil on it to envelop the piece to be hardened. After that give the piece its proper heat, quickly lay it on the plate and cover immediately with the second flat piece, or plate. If properly done the work will come out straight.

Metal Cleaning and Annealing Bath
U. S. Patent 2,276,101
Borax 90
Fluorspar 10

Steel Tempering Bath Molten lead is covered with a 20-30 mm. layer of

Formula No. 1
Sodium Chloride 50
Potassium Chloride 50

METALS, ALLOY	YS AND
No. 2 Sodium Chloride Calcium Chloride Such protective layers p tempered objects from adhe of lead and oxides.	50 50 rotect erence
Steel Hardening Bath British Patent 527,774 Sodium Cyanide Soda Ash Sodium Chloride Potassium Chloride Barium Chloride Use at 750°-850°.	5 67 7 7 14
	21.4 78.6 solu- um.
Carburizing Compound for Hardening of Steel U. S. Patent 2,260,622 Wood Charcoal, Powdered Barium Carbonate Sodium Silicate (d. 1.4) Clay	Case  45 5 38 12
Metal Treating Fused Salt I German Patent 700,904 Formula No. 1 Potassium Dichromate Potassium Nitrate No. 2	82 18
Potassium Dichromate Potassium Chromate No. 3 Sodium Dichromate Potassium Dichromate These baths are used at	63 37 42 58 500–
700° C.	

Iron Heat Treating Bath German Patent 700,904		
Sodium Dichromate	750	
Potassium Dichromate	250	
Potassium Chromate	100	
Nitrates may be added.		
Use at 500°-700° C.		

Tempering Gold and Silver Alloys U. S. Patent 2,127,676

Alloys of gold 51 to 91%, copper 40 to 8%, and silver 9 to 1% are hardened by cooling to not more than 0°, immersing in molten tallow at 193° for not less than 20 seconds and then in boiling soap solution for not less than 20 seconds, drying, allowing to cool to room temperature and repeating the series of processes.

<del></del>	
Soldering Fluxes Formula No. 1	
Lactic Acid 15	cc.
Sulphate (Wetting	
Agent) 0.2	cc.
Water 85	cc.
No. 2	
British Patent 368,841	
Rosin	20
Aniline Hydrochloride	1
	79
Alcohol, Denatured	19
No. 3	
Rosin	20
Lactic Acid	5
Alcohol, Denatured	75
No. 4	
Rosin	4
Mannitol	1
No. 5	-
Rosin	4
Mannitol	1
	$\frac{1}{2}$
No. 6	
Rosin	48
Mannitol	12

Lactic Acid	10
Alcohol, Denatured	30
No. 7	

British Patent 524,572

Colophony 50, soft petrolatum 45, and silicon dioxide (240 mesh) 5, or of aniline hydrochloride 10, ethylene glycol 75, and carborundum (180 mesh) 15%.

Hard Metal Soldering Flux U. S. Patent 2,267,763 Boric Acid 55-71%

Sodium Fluoride

Non-Acid Flux

45-29%

Petrolatum	65
Ammonium Chloride	$3\frac{1}{2}$
Zinc Chloride	25
Water	$6\frac{1}{2}$

Soldering Fluids

In making up soldering fluids glycerin is a useful ingredient to give the desired body to the solution and assure better wetting properties. Following are two easily prepared soldering fluids which utilize these glycerin properties. The first, which is satisfactory for use on a variety of metals including copper, brass, steel, terne plate, tinned steel, and Monel metal, consists of:

Formula No. 1

T. OI III III II I I I I I	
Zinc Chloride	15
Glycerin	25
Water	60

Zinc chloride can be eliminated by using the following soldering fluid:

	No. 2	
Lactic Acid		1
Glycerin		1
Water		8
	No. 3	
Belro Rosin		50

Methanol

50

#### Aluminum Solder U. S. Patent 2,224,356 Formula No. 1

A fluxed solder for soldering aluminum to aluminum or other metals which will take a coating of tin is made by melting ¼ ounce of zinc, adding ¾ pound of lead, melting (with stirring), and after skimming, adding ¾ pound of tin, which is stirred in; when the mixture is molten, ½ teaspoonful of powdered rosin is added. The rosin ignites and when the flame subsides the metal is skimmed and poured.

No. 2

#### U. S. Patent 2,243,278

$\frac{1}{2}$
$\frac{1}{2}$

Filling Alloy for Aluminum Soft Soldering

#### French Patent 848,862

Tin	10-60%
Lead	15-45%
Zine	20-70%
Silver	1-10%

Solder for Zinc Aluminum Alloys
German Patent 695 626

0011110111 = 0000110 000,0=0	
Tin	74
Lead	20
Zinc	6

Woven Wire Fabric Solder U. S. Patent 2,224,952

Mix together the following metallic powders:

e powders.		
Copper		15
Silver		55
Cadmium		30

Apply to wires to be joined and heat.

36

23

19

1 13

8

METALS, ALLOYS AND	THEIR TREATMENT
Indium Containing Solders Formula No. 1 No. 2	Welding Flux U. S. Patent 2,284,619
Lead 96 95	Borax
Silver 3 3	Sodium Bifluoride
Indium 1 2	Sodium Silicofluoride
	Antimony Fluoride
	Phosphoric Acid
Tin-Free Solder	Trisodium Phosphate
U. S. Patent 2,293,602	- 1150 drain 1 1105 phase
Formula No. 1	
Silver 1.5–3%	Electric Arc Welding Flu
Antimony 0.5–5%	German Patent 681,203
Lead, To make 100%	Sodium Hydroxide
No. 2	Bentonite
Lead 90	Soda Ash
Cadmium 10	Titanium Dioxide
No. 3	Feldspar
Lead 90.5	Water
Cadmium 8.0	*** 4001
Zinc 1.5	
2.0	Aluminum Flux
	British Patent 542,490
Soldering Cast Iron	Formula No. 1
Clean the cast iron perfectly clean	Lithium Chloride
and bright with a coarse file. Use	Zinc Chloride
ordinary acid for a flux and tin the	Stearic Acid
cast with pure block tin. It can then	Potassium Chloride
be soldered with tinner's solder.	Aluminum Acetate
* * * * * * * * * * * * * * * * * * * *	No. 2
	Sodium Chloride
Soldering Metal to Ceramics	Calcium Fluoride
British Patent 542,101	
The roughened ceramic body is	Zinc Chloride
sprayed with an alloy of:	Lithium Chloride
Lead 85	Aluminum Acetate
Antimony 10	Sulphur
Tin 5	Account the first and the firs
Bake at 160° C. and dip in solder	Aluminum Welding Flux
(50-50) for 5 sec. This surface can	U. S. Patent 2,243,424
be soldered to metals in the usual	Formula No. 1
way.	Cadmium Chloride
** **	Cuprous Chloride

Brazing and Welding Flux U. S. Patent 2,229,863

1.5

1.0

20.0

Potassium Carbonate

Ferrous Sulphate

Borax

Electric Arc Welding Flu German Patent 681,203	X
Sodium Hydroxide	4
Bentonite	1
Soda Ash	$\overset{1}{2}$
Titanium Dioxide	18
Toldanor	53
Feldspar Water	$\frac{55}{22}$
water	22
Aluminum Flux	
British Patent 542,490	
Formula No. 1	
Lithium Chloride	18
Zinc Chloride	10
Stearic Acid	4
Potassium Chloride	30
Aluminum Acetate	8
No. 2	
Sodium Chloride	60
Calcium Fluoride	20
Zinc Chloride	10
Lithium Chloride	2
Aluminum Acetate	6
Sulphur	$^{0}_{2}$
Bulphur	4
Cuprous Chloride Cerium Chloride	10.0 29.1 9.0 34.2 6.6 6.6 4.5
2201120112	

246 THE CHEMICAL POLITICIANT			
No. 2 U. S. Patent 2,239,018 Lithium Chloride 10 Sodium Chloride 35	Sodium Chloride 4–8 % Ammonium Chloride 10–18% Stannous Chloride 3–8 % Lithium Chloride 3–8 %		
Potassium Chloride 35 Potassium Fluoride 5 Sodium Fluoride 10	Soldering Flux for Copper U. S. Patent 2,228,352		
Cryolite 5 Cadmium Chloride 20 No. 3	Triethanolamine 35 Glycol 40 Abietic Acid 25		
Aluminum tubing is made from 0.5 m.m. strip and filled with: Potassium Chloride 45	Welding Rods for Red Brass For gas welding: Copper 97.5		
Sodium Chloride 30 Lithium Chloride 15 Lithium Fluoride 3½	Silicon		
Sodium Fluoride 3½ Potassium Pyrosulphate 3 This filled tube is inserted in an-	For carbon arc welding: Copper 97 Silicon 3		
other aluminum tube 8 m.m. outside and 4 m.m. inside diameter.	Welding Rod for Copper Alloys U. S. Patent 2,121,194 Nickel 35.0		
Welding Flux for Cast Iron Iron 14.5	Nickel 35.0   Zinc 15.0   Copper 48.6		
Iron Sulphide12.5Sodium Chloride10.0	Silicon Copper (15%) 1.7 Borax 1.0		
Sodium Nitrate 63.0  Mix together and make into a paste with mineral oil.	Sinter in hydrogen at 700° C.  Bronze Alloy for Welding to Iron		
Flux for Preventing Oxidation of Molten Magnesium Alloys	U. S. Patent 2,129,197 Copper 80.0 Tin 17.3		
British Patent 539,023 Magnesium Chloride 34–40% Calcium Chloride 12–16	Nickel         1.5           Silicon         0.5           Iron         0.5		
Sodium Chloride 15 Potassium Chloride 15	Soldering Iron Tip Alloy Dutch Patent 51,352		
Magnesium Oxide 11–15 Calcium Fluoride 19–23	Zirconium 0.1–1.3% Copper, To make 100%		
Aluminum Soldering and Welding Flux British Potent 513 605	Steel Brazing Flux Powdered borax 1 ounce, boracic		

acid 3 ounces. Melt the borax and

when cool powder it. Mix with acid

and apply as a paste with water. Use regular brazing spelter.

British Patent 513,695

30-40%

2–5 % 20–30%

Potassium Fluoride

Potassium Sulphate Potassium Chloride

#### Brazing Alloy U. S. Patent 2,125,228

An alloy for brazing brass, copper, steel, or cast iron contains copper 68-84, cadmium 3-24, silver not greater than 3.9, and phosphorus 2-4%, with or without tin not greater than 10 and nickel not greater than 2%.

#### Steel Welding Rod Coating U. S. Patent 2,220,954 Potassium Feldspar Wood Fiber 3 Calcium Carbonate 4 4 Clav 6 Ferro-Manganese Sodium Silicate 13 Titanium Dioxide 30 Talc 6 2 Asbestos

Stainless Steel Welding Electrode
Coating

Marble	37
Dolomite	10
Fluorspar	32
Caustic Soda	$4\frac{1}{2}$
Ferro Manganese (75%)	$5\frac{1}{2}$
Ferro Silicon (75%)	2
Ferro Titanium (20%)	$5\frac{1}{2}$
Starch	$3\frac{1}{2}$
Water Glass	24
Apply shout 15% by w	airtht t

Apply about 15% by weight to electrode; dry and heat at 180–200° C. to form a hard layer.

Welding Rod Coatings U. S. Patent 2,240,033

Formula	No. 1	No. 2
- 1	Soft	Hard
	Coating	Coating
Plumbago	3000	3000
Sodium Silicate	2600	1800
Bentonite	90	90
Water	950	1290

#### Dissolving Welding Scale from Stainless Steel

This discoloration is removed by grinding and polishing. However, there are some cases where the scale is dissolved with a mixture of 20% nitric acid with 4% hydrofluoric acid, applying the mixture at a temperature of about 125° F. to the welded seam,

Successive applications at intervals of approximately five minutes, with a small hand brush or equivalent, which would permit some scrubbing action removes the scale satisfactorily for soldering operations.

Non-Tarnishin	g Jewelers Solder
U. S. Pate	ent 2,270,594

	,
Palladium	15-35%
Gold	10-25%
Copper	7-20%
Cadmium	5-15%
Silver, To make	100%

#### Solder for Precious Metals U. S. Patent 2,220,961

Lead	54-48%
Tin	43-39%
* Precious Metal	3-13%

#### Gold Solder

#### U. S. Patent 2,274,863

U. D. I WOOLIV	<b>-</b> ,-,-,-	00
Gold	25	-85%
Palladium	2	-20%
Copper	5	-30%
Cadmium	3	-25%
Silver	1/	2-20%
Zinc	1/1	0-5 %

### Electrical Contact Alloys

U. S. Patent 2,221,285 Formula No. 1

Magnesium	2-4%
0	•

\*Gold, silver or platinum depending on which metal is being soldered.

250 THE CHEMICH	
Lithium 0.05% Silver, To make 100% No. 2	Hot Working Copper Alloy U. S. Patent 2,245,327 Arsenic 0.5-5 %
Boron 0.01–10% Silver, To make 100%	Phosphorus 4.5–8.5% Copper, To make 100%
Electrical Contact and Welding Tip Alloy U. S. Patent	Amethyst Colored Gold Alloy U. S. Patent 2,278,812 Gold 70.6–78.1%
Chromium 3	Aluminum 19.4–22.4%
$ \begin{array}{ccc} \text{Iron} & & & 1\frac{1}{2} \end{array} $	Zine 0.5–10 %
Cadmium 1	21110 0.5–10 %
Copper 94½	Non-Tarnish Dip for Gold Alloy Plates
Electric Fuse Alloy	Solution A
U. S. Patent 2,293,762	Sodium Ortho Phos-
Tin 40–60%	
Cadmium 20–35%	phate 2 oz.
Silver 15–25%	Sodium Carbonate 2 oz.
Copper 2–5 %	Potassium Chromate 1 oz.
	Water to 1 gal.
Sea Water Resistant Aluminum	Solution B
Alloy	Potassium Chromate 8 oz.
U. S. Patent 2,261,210	Potassium Nitrate 8 oz.
	Water to 1 gal.
$\begin{array}{cccc} \text{Magnesium} & & 5.5 - 6 \ \% \\ \text{Zinc} & & 4 \ \% \end{array}$	Dip plated ware in cold solution
	A. Rinse in running water and then
Manganese 0.25–0.5%	soak in solution B for 2-3 minutes
Chromium 0.25–0.3%	Rinse in cold and hot water and dry
Aluminum, To make 100%	in sawdust.
Age Hardening Copper Alloy U. S. Patent 2,261,975	Lead Shot Alloy
Zinc 12 -30 %	Antimony 1 -1.5 %
Nickel 0.25– 3 %	Sodium 0.02–0.04% Lead, To make 100%
Phosphorus 0.02- 0.4%	Lead, To make 100%
Copper, To make 100%	Cast at 400-420° C.
Copper, 10 make 100%	×.
Precipitation Hardened Copper	Porous Metal Bearing Alloy
Alloy	U. S. Patent 2,214,104
U. S. Patent 2,225,339	1
Copper containing beryllium	Lead, Powdered 20
0.1% and chromium 0.4% is	Graphite, Powdered 2
quenched from 900°, reheated at	Stearic Acid 1/100
475-500°, cold swaged and again	Press at 20,000-60,000 lb./sq.in
aged at 100° for 90 minutes.	and sinter at 1095° C.

Improved Tir	Foil Alloy
Tin	100.00
Zinc	8.50
Nickel	0.15
This gives increa	sed strength and
ductility.	

Bell Casting Alloy
German Patent 698,659
Zinc 90–95%
Copper 3%
Aluminum 4%

Bearing Alloy
U. S. Patent 2,245,459
Formula No. 1

Zinc 40%

Lead 0.1 - 3%

Phosphorus 0.01- 3%

Copper, To make 100%

No. 2

U. S. Patent 2,246,067 Lead 1-3 lb. Copper 3 lb. Silver 0.05-10%

Carbonized Bearing Composition
U. S. Patent 2,131,021
Petroleum Coke 19
Sulphur 7-8
Lead Oxide 19
Pitch 47-48

Bake mixture at 1000°, until carbonization is complete and metal is reduced from oxide.

Non-Sticking Coating for
Metal Sheets
U. S. Patent 2,132,557
Mineral Oil, Light 99
Magnesium Stearate 1
Warm and mix until dissolved.

Permanent Magnet
German Patent 701,528
Formula No. 1
Nickel 15–25%, iron 10–25% and

copper 50-75% is formed in the de-

sired shape. The magnet is then heated to over 1000°, quenched, and rolled out over 40%. The magnet is finished by annealing it at 500-700°. By this treatment the coercivity and remanence are increased without impairing any other desirable properties.

No. 2
British Patent 541,474
Aluminum 8–9.25%
Titanium 2 %
Nickel 25 %
Iron, To make 100%
Cast and then forge at 1100-1360°; heat treat for 10 min. at 1320°; quench in hot oil and age harden at 566° for 16 hr.

Permanent Magnet Casting
U. S. Patent 2,121,799
Ferric Oxide 30–50
Aluminum 10–20
Nickel 5–15

Mix the above powders in a graphite crucible and ignite with a small electric arc. Rock crucible and twirl it so that slag freezes on sides. Finally pour into a section carbon mold.

## Tinfoil Substitute in Curing Dental Plates

Two solutions are required. The first is prepared by dissolving 5 or 6 grams of a soluble alginate, such as potassium, sodium, magnesium, or ammonium alginate, in 80 ml. of water. This may require several hours of constant stirring. When solution is complete add 80 ml. of glycerin. This first solution can be applied by dipping, spraying, or painting. After the film has dried, a second solution is applied.

The second solution is a saturated solution of calcium chloride.

The halves of the flask, after the wax has been boiled out, are dipped in the first solution and allowed to drain and dry for a few minutes. A second dipping may be necessary if the solution is too thin or if the plaster does not retain a sufficient amount of the solution to form a continuous film. The halves are next dipped in the chloride solution for 5 or 10 minutes and then dried. The film can be removed from the teeth with a sharp needle-hook instrument similar to an explorer.

The flask is now ready for trial packing and with a moderate amount of care will retain the film until the cure is completed in boil-

ing water.

The substitute has advantages over the foil in that it is easier to apply, takes less time at the bench, gives a smoother surface, and yields easier separations of the halves of the flask.

#### Dental Alloy U. S. Patent 2,246,288

Chromium	10	-49%
Cobalt	20	-48%
Molybdenum	3	-15%
Nickel	10	-40%
Tungsten	3	-12%
Zirconium	1/	4-3%

#### Denture Casting Composition U. S. Patent 2,206,502

A compressed mixture of the following powdered materials is used:

wing powder	ca maccinais	in anota
Chromium		31.00
Cobalt		61.20
Iron		7.00
Tungsten		0.50
Silicon		0.45
Aluminum		0.20
Borax		0.50

Cutting Steel When Cold

Cutting steel cold is a satisfactory method, when bar steel is to be cut or broken into certain lengths, as when making cold chisels or other similar tools, but the advantage of this method will cease when cutting steel over a certain size. For example, octagon, round or square cast steel ranging from the smallest size up to  $1\frac{1}{4}$  inches in diameter, can be broken very quickly and satisfactorily when perfectly cold, by nicking the bar equally from all sides, afterwards placing the nicked part of the bar directly over the square hole of the anvil, then striking it with a sledge when it will break.

Care must be exercised when breaking steel after this method, as the pieces are very apt to fly and strike the blacksmith or his helper. To overcome this danger place the handle of the chisel on the piece which is to be broken off before striking it with the sledge, which will prevent the piece from flying. When nicking the steel, hold the chisel so as to cut in a straight line and so enable the steel to break off square on the ends.

To enable the steel to break with greater ease pour a little cold water directly on the nicked part of the steel. By pouring cold water on the steel all the heat is taken out, as steel will break more readily when perfectly cold than when it is slightly warm.

Breaking a bar of steel cold is a very good way of finding out the hardness or the quality of the steel. For example take a bar of 34 or 78-inch steel (after being nicked). If the steel breaks with one or two blows from the sledge it denotes

hard steel, but soft steel will require five or six blows before it breaks; also hard steel (by looking at the break) will show a fine and close fracture. The fracture of soft steel will be more coarse and rough. If the steel is of good quality, the break or fracture will show a very uniform and silvery white appearance clear through the bar, but if the steel is of poor quality it will show a dull brown appearance.

Hot Cutting: To test steel bars that are too large to break cold, for example a bar two inches in diameter, heat the bar to a deep cherry red, then cut in from all sides, say half an inch deep with a hot chisel, then lay the bar down to cool and when it is perfectly cold it may be broken by striking it with a sledge or dropping the bar over the anvil, and the quality or hardness can be judged as formerly explained. Bear in mind that the steel must not be heated above a deep cherry red (in order to cut in the nick) or the fracture when broken cannot be judged correct, as a high heat in the steel would materially change the appearance and form of the fracture.

 $\begin{array}{ccc} \text{Copper Scale Remover} \\ \text{U. S. Patent 2,211,400} \\ \text{Hydrochloric Acid} & 10 \% \\ \text{Sodium Chlorate} & \frac{1}{2}\% \\ \text{Ferric Chloride} & 10 \% \\ \text{Water, To make} & 100 \% \\ \end{array}$ 

Removing Brittle Surface Austenitic Steel U. S. Patent 2,238,778

20

Pickle at 82° in: Nitric Acid (d 1.42) Stannous Chloride Water

8 72

Passivation of Stainless Steel
U. S. Patent 2,104,667
Dip into following solution:
Nitric Acid 0.1-4%
Sodium Dichromate 0.1-4%

Recovering Gold from Scrap Solution

Precipitate gold with zinc or leadzinc couple. Filter precipitate. Boil in aqua regia. Boil off nitrogen peroxide. Add ferrous sulphate to precipitate gold. Filter and wash precipitate. Dissolve gold in aqua regia. Remove nitrogen peroxide. Add oxalic acid or sodium bisulphite. Precipitate is pure gold. Treat as for preparation of stock solution.

Reclaiming Type Metal from Dross Dutch Patent 50,737

Dross is fused with 1-30% zinc chloride below 600°.

Briquetting Metal Shavings Russian Patent 55,173

Metal shavings are mixed with 5–10% powdered chalk, heated to 200° C. and treated with 80–90% coal tar pitch and 10–20% anthracene oil and pressed.

Porous Metal Swiss Patent 216,467

Iron wire (0.1–0.4 m.m. diameter) fragments are mixed with 5% copper powder and 5% sodium silicate (25–30° Bé). Compress at 200 kg./sq.cm. and gradually heat to 880° C.

#### CHAPTER THIRTEEN

## PAINT, VARNISH, LACQUER AND OTHER COATINGS

TRAFFIC PAIN	TS		$Red\ Oxide$		
Light Green			Iron Oxide Red	200	lb.
Chromium Green Oxide	58	lb.	Dicalite L	100	lb.
Magnesium Silicate	400		Magnesium Silicate		
Vehicle "A" or Vehicle			(325  Mesh)	200	lb.
"B"	521	lb.	50% Solution Rosin in		
Yellow			Petroleum Spirits	45	gal.
C. P. Lemon Yellow			Petroleum Spirits		gal.
Oxide	200	lb.	Paste ground on stor	e or	roller
Magnesium Silicate	406	lb.	mill.		
Vehicle "A" or Vehicle			Thin with:		_
"B"	596	lb.	Petroleum Spirits		gal.
$Red\ Oxide$			Zinol	6	gal.
Red Oxide of Iron C. P.	200	lb.	White	0.50	71
Magnesium Silicate	<b>39</b> 0	lb.	Titanox B	250	
Vehicle "A" or Vehicle			Dicalite L	100	10.
"B"	596	lb.	Magnesium Silicate	150	11.
Burnt Sienna			$(325  { m Mesh}) \ 50\%  { m Solution}  { m Rosin}  { m in}$	150	10.
Burnt Sienna	200		Petroleum Spirits		gal.
Asbestine	368	lb.	Petroleum Spirits		gal.
Vehicle "A" or Vehicle	~~~		Paste ground on ston		
"B"	596	lb.	mill.	C OI	TOTICI
Brown	200	,,	Thin with:		
Burnt Umber	200		Petroleum Spirits	27	gal.
Magnesium Silicate Vehicle "A" or Vehicle	368	10.	Zinol		gal.
"B"	596	lh	Black	_	0
Black	990	10.	Bone Black	125	lb
Carbon Black	40	lb.	Dicalite L	100	
Magnesium Silicate	480		Magnesium Silicate		
Vehicle "A" or Vehicle	100	10.	(325 Mesh)	100	lb.
"B"	581	lb.	50% Solution Rosin in		
The above traffic paints			Petroleum Spirits		gal.
heavy brushing consiste			Petroleum Spirits		gal.
will require reduction for			Paste ground on ston	e or	roller
plications.		-	mill.		
		2	54		

Thin with:

Petroleum Spirits 29 gal. Zinol 5 gal.

The balance of the colors can be made in the same manner.

Another base for traffic paint is casein. The casein paint is not as durable as the cold cut rosin paint and is not good in damp or wet weather, but is inexpensive and can be used for temporary traffic paint.

Black

Casein	10%
Lime	15%
Iron Black	40%
Limestone	20%
Talc	15%

Mix well in Day spiral dry mixer.

White

Casein	10%
Lime	15%
Calcium Carbonate	
(Precipitated)	15%
Limestone Whiting	30%
Talc	30%
Mix well in Day	spiral dry

Color Base

mixer.

Casein	10%
Lime	15%
Talc	15%
Calcium Carbonate	
(Precipitated)	15%
White Clay	15%
Limestone Whiting	30%

Replace 13% precipitated calcium carbonate in the base with ultramarine blue for the blue traffic paint.

Replace 12½% precipitated calcium carbonate in the base with 11½% red iron oxide and 1% lemon yellow ferrite for the red traffic paint.

Replace 5% precipitated cal-

cium carbonate in the base with 2% lemon yellow ferrite and 3% golden cadmium yellow for yellow traffic paint.

Replace 15% precipitated calcium carbonate in the base with chromic oxide green for the green

traffic paint.

To reduce foaming in the above formulae replace 0.5% limestone whiting with 0.5% pine oil.

To prevent mildew replace 1% of limestone whiting with 1% fungicide such as chlorinated phenol.

The above casein powder paints can be mixed with water to spraying or brushing consistency and can be inter-blended either dry or wet to get colors in between the nine basic colors.

Yellow—Burnt Umber—Burnt Sienna—Red Iron Oxide Black

Duccio		
Pigment Comp	osition	
Color	40	%
Asbestine	60	%
Paint Compos	sition	
Pigment	53.50	)%
Vehicle	35.00	)%
Drier and Thinner	11.50	0%
Formula		
Color	261	
Asbestine	392	
Vehicle	425	
V. M. P. Naphtha	142	
Chrome Oxide	Green	
Pigment Comp	osition	
Color	53.84	1%

Color 53.84% Asbestine 46.16%

Paint Composition

Pigment	53.41%
Vehicle	34.99%
Drier and Thinner	11.60%

Formula

Chrome Oxide Green 350 Asbestine 300

DO	THE CHEMICA
Vehicle	495
Thinner	$\begin{array}{c} 425 \\ 142 \end{array}$
White	144
Pigment Com	nogition
Titanated Lithopo	
Asbestine	ne 80 % 20 %
	· ·
Paint Compo	
Pigment	65 %
Vehicle	32.50%
Thinner and Drier	25 %
Formula	500
Titanated Lithopo	
Asbestine	130
Vehicle Thinner	$\begin{array}{c} 325 \\ 25 \end{array}$
Ramapo Green	
Pigment Com	
Color	4.00%
Lithopone	2.80%
Asbestine	93.20%
Paint Comp	
Pigment	49.70%
Vehicle	39.76%
Thinner and Dries	10.63%
Formula	
Color	20
Lithopone	14
Asbestine	466
Vehicle	400
Thinner and Drie	
Vehicle N	lo. 1
F7 Amberol (or	
equal)	100 lb.
Q Linseed Oil	15 gal.
Mineral Spirits	28 gal.
Vehicle N	To. 2
Rosin	100 lb.
Lime Flour	6 lb.
Q Linseed Oil	5 gal.
Mineral Spirits	17 gal.
A. Manila V	
Manila Resin	80 lb.
Plasticizer	20 lb.
Solvent	100 lb.

The best plasticizer is raw or blown castor oil. Fish oil or soya bean oil may be used as alternate plasticizers—they do not yield as good results as obtained with castor oil.

The solvent may consist of denatured alcohol or any other alcohol or Ketone of acceptable volatility.

B. Batu or Pale East India Resin Batu or Pale East India

Resin 75 lb. Plasticizer 25 lb Solvent 100 lb.

The best plasticizers for use with these resins are dehydrated castor oil, fish oil, soya bean oil, and linseed oil.

The solvent may consist of high solvency petroleum naphthas, coal tar naphthas or mixtures of these strong solvents with ordinary low solvency petroleum naphthas.

#### Pigmentation

Best results are obtained with a pigment volume of 40% to 45%. Hiding pigment is incorporated in sufficient quantity to yield the required opacity at a reasonable spreading rate. With this feature taken care of, optimum wearing qualities, appearance, etc., are obtained by the addition of Asbestine to the required pigment volume. Paints made with color pigment only were not equal to color-inert combinations in durability.

White

· (1)	
Titanium-Barium	
Pigment	73
Magnesium Silicate	43
Vehicle "A" or "B"	100

(2)		
Titanated Lithopone	49	9.5
Zinc Oxide	29	9.7
Mica	ć	9.9
Magnesium Silicate	ξ	9.9
Vehicle "B"	100	0.0
Dark Green		
Monastral Green	75	lb.
Magnesium Silicate	318	lb.
Vehicle "A" or		
Vehicle "B"	477	lb.
Blue		
Monastral Blue	45	lb.
Magnesium Silicate	357	lb.
Vehicle "A" or		
Vehicle "B"	519	lb.
m m m		

## Traffic Paints Spirit Type—Manila Type Manila Resin 80 Blown Castor Oil 20 Solvent 100

The solvent may consist of any of the following solvents used either alone or in combination with each other:

Acetone Methyl Alcohol Denatured Ethyl Alcohol Isopropyl Alcohol Butyl Alcohol

#### White

(A) Titanium-Barium

•	Pigment	70
	Asbestine	30
(B)	Titanium-Barium	
	Pigment	80
	Asbestine	20
(C)	Titanium-Barium	
	Pigment	70
	Barytes or Blanc	
	Fixe	30

(D) Titanium Die	oxide 16
Barytes	36
Micaceous T	alc 48
(E) Titanium Di	oxide 16
Barytes	36
Asbestine	48

The above pigment-inert compositions are on a weight basis. The pigment volume content recommended is 40% for all pigment combinations listed above.

#### Yellow

(A) Chrome Yellow	50
Asbestine	50
(B) Chrome Yellow	50
Asbestine	25
Barytes	25
(C) Chrome Yellow	50
Blanc Fixe	50

The above pigment compositions are on a weight basis. The pigment volume content recommended is 35% for the pigment combinations above.

The Manila resin is dissolved by adding it to the solvent which is agitated by means of a high-speed stirrer. Stirring is continued until solution is complete.

The blown castor oil is added to the resin solution and agitation of the solution continued until the mixture is homogeneous.

It is entirely dependent upon the grade of Manila resin used as to whether or not the resin will have to be ground. The resin should be about pea size before it is added to the solvent. Allow to settle or filter solution

Sufficient vehicle is used with the pigment to make a grinding paste of a suitable consistency for ball or pebble mill grinding. After the pigment paste has been ground suffi-

ciently, the remainder of the vehicle is added to the mill and the mill rotated for a short period to incorporate the materials. The finished paint is withdrawn from the mill.

Spirit Type—Batu Type	
Batu Scraped	30
Kettle Bodied Fish Oil	
(Heavy)	10
Solvent	60

The solvent may consist of high solvency petroleum naphtha or mixtures of high solvency petroleum naphtha and low solvency petroleum naphtha.

White

(A)	Titanated Lithopone	50
	Zinc Oxide	30
	Mica	10
	Asbestine	10

(B) Titanium Barium

Pigment

Zinc Oxide

Asbestine

25

The above pigment combinations are on a weight basis. The pigment-volume content is 40% in all cases.

Yellow

(A)	Chrome Yellow	50
	Asbestine	50
(B)	Chrome Yellow	50
	Blanc Fixe	50
(C)	Yellow Lead Chromate	55
	Zinc Oxide	25
	Asbestine	15
	Diatomaceous Earth	5

The above pigmentations are on a weight basis and a pigment-volume content of 35% is recommended.

The Batu resin is ground to pea size and is slowly added to the solvent which is being agitated by means of a high speed stirrer. Stirring is continued until solution is complete and then the fish oil is added, the stirring continued until the solution is homogeneous. Allow the solution to stand until any insoluble matter settles out or filter the solution.

#### Grinding Procedure

Same procedure as for the Manila Spirit Type Traffic Paint. Use a ball mill.

Cooked Type Traffic Paints
Batu Scraped or Pale East
India Resin (Nubs) 100
Kettle Bodied Linseed Oil
or Dehydrated Castor
V. M. & P. Naphtha to
55% non-volatile content Driers equivalent
to 0.5% Pb, and 0.02%
Co as metals on the
weight of oil 80

#### Vehicle Preparation:

Heat the resin and 50 of oil to 620° F. in about 1-11/4 hours. Hold until a cold bead is clear. Add the remainder of the linseed oil.

Reheat to 580° F. only if a cold bead, taken after the oil addition, is not clear. Cool to 250° F. and thin to 55% solids with V. M. & P. Naphtha. Add the driers.

#### White

(A)	Titanium Barium	
	Pigment	56
	Zinc Oxide	24
	Diatomaceous Earth	20
(B)	Titanium Barium	
	Pigment	56
	Zinc Oxide	24
	Asbestine	20
(C)	Titanium Barium	
	Pigment	65
	Zinc Oxide	10
	Asbestine	25

(D)	Titanated Lithopone	50
	Zinc Oxide	30
	Mica	10
	Asbestine	10

The above pigment compositions are on a weight basis. The pigment-volume content recommended is 40%-44%.

#### Yellow

(A)	Chrome Yellow	40
	Zinc Oxide	20
	Asbestine	20
	Lithopone	20
(B)	Chrome Yellow	45
	Zinc Oxide	20
	Asbestine	15
	Diatomaceous Earth	20

The above pigment compositions are on a weight basis. The recommended pigment volume is 40%.

Grind the pigment with sufficient vehicle to give a good grinding paste, in a ball mill. When sufficiently ground, add the remainder of the vehicle and continue grinding to incorporate the paste and vehicle thoroughly. The finished paint is drawn from the mill.

#### White

 Pan

Pigment	62%
Vehicle	48%

#### Pigment Composition:

Lithopone or Titanated	
Lithopone or Titanium-	• )
barium pigment	55%
Zinc Oxide, Lead-free,	
American process	25%
Paint Grade Mica	10%
Siliceous Inerts *	10%

\*To improve night visibility, the required amount of No. 1 or No. 1½ pumice may be substituted. This is added by stirring it into the finish paint.

#### Vehicle Composition:

Zinc resinat	e-linseed oil	
cold-cut v	arnishes *	100%
Nonvolatile	in	
vehicle	40% mi	nimum

#### White

Pigment	(66%)	
Albalith-351	500	lb.
† Pigment-725	400	lb.
Magnesium		

#### Vehicle (34%)

100

1b.

#### † Modified Phenolic

Silicate

arabatata a monora		
Varnish	43.75	gal.
Mineral Spirits	27.75	gal.

Prepare a paste using all the pigment, varnish and one half the mineral spirits. Mill through a roller mill or buhrstone mill set loose. Thin with remaining mineral spirits.

\*The varnish shall be made of the following ingredients in the proportions indicated:

Z-Body Linseed Oil	22.0
Zinc Resinate **	22.0
V. M. & P. Naphtha	53.8
Lead Naphthenate (24% Pb)	1.9
Cobalt Naphthenate (6% Co)	0.3

\*\* No preliminary solution (cutting) of the resin in solvent is necessary. Usual procedure in preparing the paint is to load the crushed resin as received into a pebble mill along with the other ingredients.

† A combination of 75%—XX Zine Oxide (American Process)

A combination of 25%—White, Water Ground Mica (Paint Grade)

‡A 15-gallon modified Phenolic (Amberol F-7 or equal) varnish with 60% Chinawood oil and 40% linseed oil.

Volatile 30% Acid No. 4.0 Specific Gravity 0.91 Weight per Gallon 7.58 lbs.

Viscosity K

			_
White			
Pigment (6	6%)		
Cryptone BT-301	500	lb.	
Pigment-725	400	lb.	
Magnesium	100		
Silicate	100	lb.	
Vehicle (34		10.	
Modified Phenolic	101		
Varnish	127	5 gal.	
	$\frac{43.7}{27.7}$		
Mineral Spirits		_	
Cheap Fire Resist	ant P	aints	
Formula N	o. 1		
Sodium Silicate	1	12 lb.	
Kaolin	1	50 lb.	
Water	1	00 lb.	
No. 2			
Slaked Lime		2 lb.	
Salt		1 oz.	
Water		1 pt.	
-	· D ·	-	
Indoor Fireproo		nt	
Formula N	0. 1		
Pigment:			
White Lead		41.0	
Borax		32.0	
Raw Linseed Oil		22.8	
Turpentine		3.6	
Japan Drier		0.6	
No. 2			
Pigment:			
Titanium-Calcium			
${f Pigment}$		30.0	
Borax		35.0	
Raw Linseed Oil		30.8	
Turpentine		3.6	
Japan Drier		0.6	
No. 3			
Pigment:			
Lithopone		24.0	
Borax		39.5	
Raw Linseed Oil		32.3	
Turpentine		3.6	
Japan Drier		0.6	
No. 4			
Pigment:			
Zinc Oxide		21.0	
×			

Borax		50.0
Raw Linseed Oil		24.8
Turpentine		3.6
Japan Drier		0.6
No. 5		
White Lead, Paste	25	lb.
Borax	17	lb.
Linseed Oil	$1\frac{1}{4}$	gal.
Turpentine	$1\frac{1}{2}$	pt.
Drier, Liquid	1/2	pt.

From the standpoint of hiding power and brushing qualities, an unusually high percentage of borax is undesirable, but fire-retarding effectiveness is lost or decreased if the borax content is dropped too low. It is apparent that a balance must be maintained between paint quality and fire retardance. A minimum of at least 25% by weight of borax appears necessary.

To obtain maximum fire protection, heavy applications of the paint (3 or 4 thick coats or at least 8 gallons per 1000 square feet) were found necessary. This is about twice the amount of paint ordinarily applied to woodwork. Coatings of ordinary thickness undoubtedly would provide protection against comparatively weak fires.

Fine grinding of the borax and subsequent milling in oil are necessary for smoothness, consequently the home preparation of borax paints is practical only when a lumpy, rough coating is not objectionable from the appearance standpoint.

Fireproofing Paint
U. S. Patent 2,247,633
Formula No. 1
Water, Soft 5 gal.
Antimony Chloride 5 oz.
Glue, Powdered 2½ lb.

Mineral Pigment	10	lb.
Diatomaceous Earth No. 2	$2\frac{1}{2}$	lb.
Kaolin	150	lb.
Sodium Silicate (Sp.	Gr.	
1.41–1.43)	112	lb.
Water	100	lb.

#### Waterproof and Chemical Resistant Paint

Mix the following all together and apply with a smooth camel's hair brush to the parts of wood or metal which are to be protected.

Coal Tar Pitch	80 g.
Dissolved in Xylol	80 g.
Add Benzene	40 cc.
Pulverized Silica	30 g.
Chlorinated Rubber	7 g.

Water Proof Casein Coatings

(1) for black glaze: black paste dye 100.0, dry colorless casein 8.0, nigrosine 0.75, latex 5.0 and water 300 parts; (2) for brown glaze: brown dye 100.0, aniline dye 0.5-0.7, dry colorless casein 10.0, latex 6.0 and water 400 parts. The casein is digested with 50% of the water of the formula for 1 hour, allowed to stand an extra hour after which 2-6% ammonia (25%) is added, and the mixture is gently boiled. The dyes are added to the remainder of the water at 50-60° while agitating and then the casein and latex are mixed therewith.

water Resistant Coating F		
British Patent 514,696		
Zein 10	0.00	
Paraffin Wax	4.0	
Methanol (94%) 21	18.2	
Benzene 11	6.0	

Waterproof Woo	d Primer
Celluloid	1
Butyl Acetate	9-10

Butyl Acetate	9-10
Dam Gate Primers	
Formula No. 1	
Zinc Oxide	16
Zine Dust	64
Vehicle No. 2 *	20
No. 2	
Zinc Oxide	13
Iron Oxide	191/2
Zinc Dust	$32\frac{1}{2}$
Vehicle No. 2 *	35
701 1 17 17	

The above are thinned prior to application with one pint to one quart of mineral spirits per gallon of paint.

#### Waterproof Whitewash

Waterproof whitewash for outdoor buildings is made up in the following proportions: slake 62 pounds of quick lime in 12 gallons of hot water, and add two pounds of salt and one pound of sulphate of zinc in two gallons of water. To this add two gallons of skim-milk. An ounce of alum improves this wash but it is not essential. If the whitewash is required for metal surfaces subject to rust, the salt should be omitted.

\*Vehicle No. 2.—The vehicle has the following composition in percentages by weight:

veight:	
Mineral Spirits	28.12
Varnish Oil	17.15
Para Phenyl Phenol-	
Formaldehyde Resin No. 2	16.65
China Wood Oil	25.98
Dipentine ·	4.67
Ethylene Glycol Monoethyl	
Ether	3.84
Toluol	2.38
High Flash Naphtha	1.21

Disinfectant Whitewash

Dissolve 50 pounds of lime in eight gallons of boiling water. To this add six gallons of hot water in which ten pounds of salt and one pound of alum have been dissolved. A can of lve is added to every 25 gallons of the mixture. A pound of cement to every three gallons is gradually added and stirred thoroughly. The alum prevents the lime from rubbing off, the cement makes a creamy mixture easy to apply, and the lye is added as a disinfectant. A quart of creosol disinfectant to every eight gallons would serve the same purpose as the lye, but if a pure whitewash is desired, the lye is preferable. If a real snowy whiteness to whitewash is desired, it can be obtained by adding a very small quantity of washing blue.

Water Resistant Silicate Coating U. S. Patent 2,234,646

Formula No. 1

Sodium Silicate
Water
Tormaldehyde
Sodium Aluminate

1/2 gal.
1/2 gal.
1/2 gal.
1/2 gal.
1/2 gal.

(30% Solution)  $\frac{1}{3}-\frac{1}{2} \text{ oz.}$  Sodium Abietate 1-3 oz.

No. 2

U. S. Patent 2,234,672

Sodium Silicate  $\frac{1}{2}$  gal. Water  $\frac{1}{2}$  gal. Formaldehyde  $\frac{1}{2}$ -3 oz. Latex (40–60%)  $\frac{1}{2}$ -2 oz.

Waterproofing Compound
Petroleum Jelly 33
Rosin 11
Beeswax 56

Chemical Resistant Coatings

Furfuryl alcohol resinifies in the presence of mineral acids to form a black resin. When this reaction occurs in situ on wood or other porous materials, a very satisfactory finish is produced which is resistant to the attack of solvents as well as to most acids and alkalies. Hence this application may be advantageously used for protecting laboratory table tops and other surfaces subjected to chemical action.

The surface to be finished should be scraped and sand-papered until uniformly smooth. It is then painted or sprayed with a liberal application of furfuryl alcohol and after the surface appears to be dry. a 10-15% aqueous solution of hydrochloric acid is applied, usually by brushing. The surface will gradually darken and will become black. As many coats as desired may be applied. After the final application, the surface may be polished and buffed to give a glossy appearance. The finishing operation may consist of rubbing several applications of either linseed or China-wood oil into the surface until a high gloss is secured. One gallon of furfuryl alcohol will cover from 200 to 300 square feet of surface.

#### Note:

1. Do not add concentrated mineral acids to furfuryl alcohol or its solutions since the reaction is quite energetic. However, when dilute acid is used as indicated above, the reaction proceeds smoothly.

2. In place of furfuryl alcohol a mixture consisting of 50-50 furfuryl alcohol and furfural may be

used. The furfural is a good diluent and reduces cost.

- 3. Sulphuric or phosphoric acid works as effectively as hydrochloric.
- 4. Some prefer to use an ethyl alcohol solution of the mineral acid in place of the aqueous solution, since the former is reported to give a more uniform coating.

Wood or Metal Container Coating
U. S. Patent 2,122,543

Ester Gum 65

Japan Wax 11

Petrolatum 24

Mall together and apply bot on

Melt together and apply hot or from a hydrocarbon solvent.

Anti-Corrosive Paint
Linseed Oil (with Drier) 54
Linseed Fatty Acids 6
Ammonia 4
Water 36
Mix until emulsified and grind in a ball mill with
Iron Oxide 60

Acid and Alkali Resistant Protective Coatings for Cement and Concrete

Formula No. 1
Thermally Processed
Congo 50 lb.
Chlorinated Rubber
(125 Cps.) 100 lb.
Solvesso No. 3 350 lb.
Hercolyn 30 lb.

Mix and agitate all ingredients until a homogeneous solution is obtained.

No. 2
Batavia Dammar 50 lb.
Chlorinated Rubber 100 lb.
Solvesso No. 3 350 lb.
Hercolyn 30 lb.

Mix and agitate all ingredients until a homogeneous solution is obtained.

Both of above formulae dry to hard, flexible films which are acid, alkali and alcohol resistant and are recommended for use over concrete.

No. 3
Thermally Processed
Batavia Dammar 12.5 lb.
Chlorinated Rubber 12.5 lb.
Hi-Flash Naphtha 100 lb.
Mix all ingredients together until

a homogeneous lacquer is obtained.

No. 4

Thermally Processed
Brown Kauri
12.5 lb.
Chlorinated Rubber
12.5 lb.
Hi-Flash Naphtha
100 lb.
Mix all ingredients together until
a homogeneous lacquer is obtained.

Acid Resistant Pipe Coating
U. S. Patent 2,214,062
Rosin, Petroleum
Insoluble 70
Linseed Oil 30
Heat at 300° C. for 20 min. and stir in:

Asbestos

Protective Coating for Rods and Tubes

Asphalt 33

Rosin (Vinsol) 35

Rubber 4

Calcium Carbonate 29

"Cut" the above with gasoline

121/2

and mix well during use. Apply with a spray-gun or brush. It dries very quickly to a film without gloss or "tack."

Protective Coating for Porcelain, China and Plated Metal Parts U. S. Patent 2,219,583

This is for the manufacture of an adhesive paste for applying to newspaper, to act as a protective coating for temporary protection of glossy or polished surfaces during such time as such surfaces are likely to be subjected to mechanical abuse or to the attack of corrosive chemicals such as cleaning acids, paints, etc. Surfaces such as enameled iron, porcelain, vitreous china, and electroplated parts are covered by newspaper to which the adhesive paste is applied, so that the paper and paste can readily be removed by means of water so that neither the paste itself, nor the ink of the newspaper will affect the covered parts.

The following formula for this type of paste is chemically stable, and requires no preservative to prevent decomposition, nor the use of a neutralizing agent to overcome the effects of decomposition:

to choose of accomposition,	
Bentonite	50
Water	150
Glycerin	- 10
Borax	15
Abopon Solution	5
(sp. gr. 1.68)	

Primers for Metals
Vehicle No. 1
25 Gallon Length (OiticicaLinseed)
Batu, Black East
India or Pale

100 lb.

East India

Oiticica Oil 20 gal.
Bodied Linseed Oil
(Z Viscosity) 5 gal.

Petroleum thinner to 50% non-volatile content. Driers equivalent to 0.5% Pb, 0.02% Co and 0.01% Mn, as metals on weight of oil.

Heat the resin and 5 gallons of oiticica oil to 600°-610° F. in 60-65 minutes. Hold until a cold "pill" indicates complete compatibility (about 10 minutes). Add remainder of the oiticica oil. Heat to 580°-590° F. Hold for body (viscosity of finished vehicle should be between "B" and "D"). Check with the linseed oil. Allow to cool to about 400°-420° F. Add the petroleum thinner and then the driers.

The above vehicle is especially recommended for preparing primers used for underwater applications.

#### Vehicle No. 2

25 Gallon Length (Linseed or Dehydrated Castor)

Batu, Black East
India or Pale
East India 100 lb.
Bodied Linseed Oil
(OKO 7½ M.) or

(OKO 7½ M.) or Dehydrated Castor Oil 25 gal.

Petroleum thinner to 50% non-volatile content by weight. Driers equivalent to 0.4% Pb, 0.02% Co, and 0.02% Mn, as metals on the weight of oil.

Heat resin and 5 gallons of the linseed oil to 600°-610° F. in about 60-65 minutes. Hold until cold "pill" indicates complete compatibility (about 10 minutes). Add remainder of linseed oil. Heat to 560° F. Allow to cool to about 400°-420°

F. Add the petroleum thinner and then the driers.

The above vehicle is recommended for preparing primers for applications other than underwater purposes.

Vehicle No. 3 25 Gallon Length (Chinawood-Linseed)

Batu, Black East India or Pale

East India

100 lb. Chinawood Oil 20 gal.

Kettle Bodied Linseed Oil (About Z Vis-

cosity) 5 gal.

Petroleum thinner to 50% nonvolatile content. Driers equivalent to 0.5% Lead, 0.02% Manganese, and 0.01% Cobalt as metals on the

weight of oil.

Heat resin and 5 gallons chinawood oil to 600°-610° F., in about 60-70 minutes. Hold until cold "pill" denotes complete compatibility (about 10 minutes). Allow to cool to 540° F. Add remainder of chinawood oil. Heat to 560° F. Hold for desired body (viscosity of finished vehicle should be "C" or lower). Check with the linseed oil. Allow to cool to about 400°-420° F. Add the petroleum thinner and then the driers.

This vehicle is particularly recommended for underwater applications.

Protective Metal Primer Paint Formula No. 1 Pigment (60%)

Zinc Tetroxy

Chromate 855 lb. Vehicle (40%)

Raw Linseed Oil 55½ gal. Kettle Bodied "Q"

Linseed Oil 71/4 gal. Mineral Spirits and

Drier \* 12 gal.

Use all of the kettle bodied oil and as much of the raw linseed oil as required to make paste, grind and reduce with remainder of vehicle.

If the paint happens to be somewhat puffy as first made up, it should be remembered that it will thin slightly on aging. The use of a higher percentage of kettle bodied oil helps to reduce the consistency, but it is preferable not to exceed 15% of bodied oil in the paint.

> No. 2 Pigment (60%)

Zinc Tetroxy

Chromate 560 lb. Iron Oxide 300 lb.

Vehicle (40%)

Raw Linseed Oil 55½ gal.

Kettle Bodied "O"

Linseed Oil  $7\frac{1}{4}$  gal.

Mineral Spirits and Drier 12 gal.

> Metal Priming Paint Formula No. 1 (Baking Primer) Pigment (25%)

XX Zinc Oxide lb. 173 Standard Zinc

Dust-22 81 lb.

Vehicle (75%)

Rezyl No. 420-2

Solution 741/4 gal. Pine Oil 43/4 gal. Solvesso No. 2 16 gal.

\*5% of liquid drier should be sufficient. High percentages of drier may tend to make a puffy paint. If this should occur the consistency may be reduced by using 1/4% soluble litharge (based on the weight of pigment) in making up the paste and reducing the percentage of liquid drier.

Grind the zinc oxide in the Rezyl solution and the pine oil, stir or mix in the zinc dust and thin with the Solvesso.

#### No. 2

Pigment (32%)

Standard Zinc

Dust—22 125 lb.

Vehicle (68%)

 Rezyl No. 408
 61
 lb.

 Rezyl No. 1102
 211
 lb.

 Xylol
 47¾ gal.

 Pine Oil
 2% gal.

 Dipentene
 16 gal.

Add a small portion of the vehicle to a part of the zinc dust, thoroughly stir or mix them, then add zinc dust and vehicle alternately until all the zinc dust is in; thin with the remaining vehicle.

Metal Priming and Finishing Paint (For Priming Galvanized Iron)

Formula No. 1 Pigment (65%)

Zinc Dust 894 lb. XX Zinc Oxide 224 lb.

Vehicle (35%)
Syntex 32 Solution \* 524 lb.
Mineral Spirits 68 lb.

Lead Naphthenate 16%

16% 8½ lb. Cobalt Naphthenate 4% 1¾ lb.

Grind the zinc oxide in a portion of the Syntex solution. The zinc dust should be mixed in the zinc oxide paste with the remainder of the Syntex solution, keeping the paste heavy until all the zinc dust is added, then add the mineral spirits and drier.

This paint, as a primer, has excellent rust inhibitive properties on iron and steel, and exceptional adherence to galvanized metal, zinc and other non-ferrous surfaces. It is free of the tendency to develop an after tack.

No. 2

Pigment (78%)

Standard Zinc

Dust—22 1473 lb. XX Zinc Oxide 368 lb.

Vehicle (22%)

Raw Linseed Oil 60½ gal. Mineral Spirits or

Turpentine 4 gal. Liquid Oil Drier 3<sup>1</sup>/<sub>4</sub> gal.

Grind a zinc oxide-linseed oil paste (18% oil), mix in the zinc dust with part of the remaining oil and not completing the thinning until all the zinc dust has been added. For priming coat applications, the addition of a pint of turpentine or mineral spirits to a gallon of the above paint is recommended. Pure, low acid (below 4), moisture-free linseed oil, turpentine or mineral spirits and a lead-manganese oil drier give uniformly good results.

This paint, as a primer, has excellent rust inhibitive properties on iron and steel, and exceptional adherence to galvanized metal, zinc and other non-ferrous surfaces. It is also suitable for wire screens if reduced with sufficient thinner to prevent webbing.

No. 3

Pigment (70%)

lb.

lb.

lb.

389

Standard Zine
Dust—22 648
XX Zinc Oxide 259

Iron Oxide

<sup>\*</sup>Other comparable alkyd resin solutions may be used, but may require adjustments in drier, thinner, etc.

#### Vehicle (30%)

Raw Linseed Oil 64½ gal.
Mineral Spirits 4½ gal.
Liquid Oil Drier 3⅔ gal.

Grind the zinc oxide and iron oxide into a paste containing 21% of the linseed oil. Mix the zinc dust and part of the added oil into the paste and do not thin to painting consistency until all the zinc dust has been added.

For priming coat applications, the addition of a pint of turpentine substitute to a gallon of the above

paint is recommended.

This paint may be used as a metal primer or finishing coat paint. It has excellent rust inhibitive and durability properties but not as good adherence to galvanized iron as an 80–20:zinc dust-zinc oxide paint. It should also serve as a good general shop coat paint, especially so if a spar varnish is added as part of the vehicle.

#### No. 4

#### Pigment (72%)

Standard Zinc

Dust—22 890 lb.

XX Zinc Oxide 205 lb.

Magnesium Silicate 275 lb.

#### Vehicle (28%)

Raw Linseed Oil 61% gal. Mineral Spirits 4 gal. Liquid Oil Drier 3½ gal.

Start with a zinc oxide-magnesium silicate-linseed oil paste containing 25% oil, mix the zinc dust and part of the added oil into the paste, not completing the thinning until after all the zinc dust has been added.

For priming coat application the addition of a pint of mineral spirits

or turpentine to a gallon of the above paint is recommended.

#### No. 5

#### Pigment (80%)

Standard Zinc

Dust—22 1570 lb. XX Zinc Oxide 392 lb.

#### Vehicle (20%)

Varnish V-172 55 gal. Solvesso No. 2 10 gal.

Start with a zinc oxide-varnish V-172 paste (20% vehicle), mix the zinc dust and part of the added vehicle into the zinc oxide paste, and should not be completely thinned until all the zinc dust has been added.

#### No. 6

#### Pigment (60%)

Standard Zinc

 Dust—22
 453
 lb.

 XX Zinc Oxide
 181
 lb.

 Iron Oxide
 272
 lb.

#### Vehicle (40%)

Varnish V-172  $67\frac{3}{4}$  gal. Solvesso No. 2  $12\frac{1}{2}$  gal.

#### No. 7

#### Pigment (65%)

Standard Zinc

Dust—22 688 lb. XX Zinc Oxide 159 lb. Magnesium Silicate 212 lb.

#### Vehicle (35%)

Varnish V-172 64 gal. Solvesso No. 2  $11\frac{2}{3}$  gal.

Grind the zinc oxide and magnesium silicate to a paste containing 25% of the varnish V-172. Mix the zinc dust and part of the added vehicle into the paste and do not thin to painting consistency until all the zinc dust has been added.

For priming coat application, the addition of a pint of mineral spirits to a gallon of the above paint is recommended.

#### No. 8

#### Pigment (80%)

Standard Zinc Dust-22 1562 lb. lb. XX Zinc Oxide 391

#### Vehicle (20%)

Glyptal Solution No. 2455 33 gal. Raw Linseed Oil 91/4 gal. Mineral Spirits 21gal.

Lead Naphthenate

6 lb. 16%

Cobalt Naphthenate

2 lb. 4%

Manganese Naph-

thenate 4% 1 lb.

Grind the zinc oxide in the linseed oil and Glyptal solution (25% vehicle) to make a paste. Mix the zinc dust and part of the vehicle to be added into the paste, continue until all the zinc dust has been added by alternately adding zinc dust and vehicle. Thin with remaining vehicle. For priming coat applications, the addition of a pint of mineral spirits or turpentine to a gallon of the above paint is recommended.

#### No. 9

#### Pigment (60%)

Standard Zinc

Dust-22 454 lb. XX Zinc Oxide 182 lb. Iron Oxide 272 lb.

#### *Vehicle* (40%)

Glyptal No. 2455

Solution 411/4 gal. Raw Linseed Oil 113/4 gal.

Mineral Spirits	26	gal.
Lead Naphthenate 16%	71/4	lb.
Cobalt Naphthenate 4%	$2\frac{1}{2}$	
Manganese Naph- thenate 4%	11/4	

Metal Priming and Finishing Paste Pigment (85%)

Standard Zinc

Dust-22 1431 lb. XX Zinc Oxide 331 lh. lh. Magnesium Silicate 440

#### Vehicle (15%)

Raw Linseed Oil gal.

Grind the zinc oxide and the magnesium silicate into a paste containing 25% of oil. Then the zinc dust can be mixed into this paste with the remainder of the oil.

#### Metal Finishing Paint Pigment (49%)

Standard Zinc

Dust-22 498 lb. Aluminum Powder 124½ lb.

#### *Vehicle* (51%)

Varnish V-172  $72\frac{1}{2}$  gal. Solvesso No. 2 12½ gal.

No grinding is necessary in preparing this paint; just stir part of the pigment with part of the vehicle, add pigment and vehicle alternately in small portions until all the pigment is thoroughly dispersed, then add the remaining vehicle.

The above paint may be also made by stirring one and two-fifths pounds of aluminum powder and five and three-fifths pounds of zinc dust into a gallon of the vehicle.

This paint may be used as a fin-

ishing paint where the bright metallic sheen of an aluminum paint is desired, and where greater rust resistance than is present in a straight aluminum paint is required.

High Heat Resistant Metal Paint Standard Zinc

 $\begin{array}{cccc} \text{Dust--22} & 880 & \text{lb.} \\ \text{XX Zinc Oxide} & 220 & \text{lb.} \\ \text{Glyptal---2468 Solution} & 67\frac{1}{2} & \text{gal.} \\ \text{Mineral Spirits} & 11\frac{3}{4} & \text{gal.} \end{array}$ 

Grind the zinc oxide in a portion of the Glyptal solution. The zinc dust can then be mixed in the zinc oxide paste with the remainder of the Glyptal solution. Add the mineral spirits.

This paint may be brushed or sprayed, and should give good service on metal which becomes sufficiently hot to burn out the binder, the zinc dust fusing on the metal. If the paint is to be used where the surface is not to be heated, suitable driers should be added to make the paint dry. A suggested combination is 0.6% lead and 0.06% cobalt, as naphthenates, based on the resin non-volatile. The vehicle then becomes 87% Glyptal 2468, 10.8%

(9¾ gal.) mineral spirits, 1.6% (1½ gal.) lead naphthenate (16%), and 0.6% (3¾ pt.) cobalt naphthenate (4%). This paint will air dry with an after tack which it will retain for about a week, even if drier is increased.

This paint has shown excellent performance on super-heated steam inlets to steam turbines, on high temperature electric drying ovens, on breechings from boilers to stacks, on blast furnace stacks and on the metal sides and roof of buildings where pigs are cast. Some of the above exposures are so severe that galvanized iron peels and black iron had to be used. This paint also shows good adherence to galvanized iron.

#### Tinted Metal Paints

Zinc dust paints may be tinted to a wide variety of attractive colors, as well as black, by merely replacing varying percentages of the zinc oxide with tinting pigments.

The following table suggests the percentage composition of a number of tinted zine dust paints in a vehicle composed of 90% raw linseed oil, 5% thinner, 5% liquid drier.

	Gray	Green	Brown	Blue	Red	Black	Metal
Standard Zinc Dust—22	80.0	80.0	80.0	80.0	80.0	80.0	80.0
XX Zinc Oxide	20.0	5.0	14.0	18.0	5.0	5.0	5.0
Prussian Blue		5.0		2.0		5.0	
Chrome Yellow, Medium		10.0					
Burnt Umber			6.0				
Iron Oxide (Persian Gulf)			·		15.0		
Lamp Black						10.0	
Black Iron Oxide							15.0
Pigment %	80.0	78.0	78.0	80.0	80.0	63.0	0.08

Pipe Thread Compound	Protective Coating for Aluminum
Pigment (59.5%) Standard Zinc	Castings and Zinc and Tin Plated Parts
Dust—22 888 lb.	An emulsion is made with the fol-
Vehicle (40.5%)	lowing formula:
Cup Grease * 533 lb.	Diglycol Stearate 1
Varnish V-172 934 gal.	Ozokerite 2
Mix the zinc dust in the cup	Paraffin Wax 4
grease and thin with the varnish.	Water 40
This is a compound for use on	Melt the three waxes together and
threaded pipe joints (oil pipe lines,	keep at a temperature of about 65°
etc.) to seal the joint and resist cor-	to 70° C. Heat the water up to
rosion.	about the same temperature or a
manufacture of the second of t	little above, and add slowly with
Red Lead Base Linseed Oil Primer	high speed agitation to the melted
Pigment~(65%)	waxes.
Red Lead (95%	The emulsion is applied to the
Grade) 416 lb.	castings, etc., by spraying. This en-
Iron Oxide (70%	ables ease of control, saving in la-
$\mathrm{Fe_2O_3min.}$ ) 208 lb.	bor, speeding up of process and elimination of odor over the hot
XX Zinc Oxide 104 lb.	melted wax process because the
Magnesium Silicate 312 lb.	spraying process is a cold one.
Vehicle (35%)	
Raw Linseed Oil 67¾ gal.	Protective Coating for Beer Cans
Mineral Spirits and Drier 5 gal.	British Patent 490,851
Dilei 5 gai.	The metal is made the anode in
	following dispersion:
Coating Screw Threads	Beeswax, White 47 g. Ceresin 453 g.
U. S. Patent 2,181,835	Ceresin 453 g. Sodium Aluminate 5.65 g.
Latex (66%) 13 Colloidal Graphite 87	Sodium Silicate 9.35 g.
Colloidal Graphite 87	Water 2 l.
	Current density 30-50 amp./sq.
Paint for Compass Bowls and Disks	ft. at start, then reduce to 8 amp./
Formula No. 1	sq. ft. After this treatment heat can
White Lead 50 g.	to coalesce wax particles.
Litho Middle Varnish 20 g.	
Mineral Spirits 20 cc.	Hot Melt Metal Pipe
Lead Tungate 5 g. No. 2	Waterproofings
	Formula No. 1 Asphalt 10
Antimony, White 150 g. Pyroxylin 10 g.	Asphalt 10 Rosin 10
Amyl Acetate 180 cc.	No. 2
Amyi Acecate 100 CC.	NO. 2

This is a low viscosity petroleum base lubricant of a suitable consistency

for use through a grease gun.

10

10

Asphalt

Paraffin Wax

Rosin

No. 3	
Asphalt	10
Rosin	10
Neville R-11 Resin	21/5

Painting Farm Implements
Before painting, be sure the wood
is clean and dry and the metal clean
and free from rust. For the first coat
on the wooden parts, use a priming
coat which is:

White Lead	100 lb.
Raw Linseed Oil	4 gal.
Turpentine	2 gal.
Liquid Drier	1 pt.

Tint with Venetian Red if woodwork is to be finished red, or tint with lampblack to a medium gray if wood is to be black.

For the metal tools and parts, use a red lead for the priming coat, regardless of the color these items are to be finished.

For a bright red finishing coat, on both the primed wood and metal surfaces, use Bulletin Red and Venetian Red. Mix it as follows:

Bulletin Red		gal.
Venetian Red	$\frac{1}{2}$	gal.
Raw Linseed Oil	<b>2</b>	qt.
Spar Varnish	1	qt.
Liquid Drier	$1\frac{1}{2}$	pt.

For a black finishing coat, on both the primed wood and metal surfaces, use lampblack. Mix it as follows:

Lampblack	1	gal.
Raw Linseed Oil	2	qt.
Spar Varnish	2	qt.
Liquid Drier	$1\frac{1}{2}$	pt.

If you intend to paint the handles of small tools, in the case of the red finish coat, use just 1 qt. of oil and 2 qt. of varnish with 1 pt. of drier, to each gallon of the Bulletin Red-Venetian Red combina-

tion, in order to get a harder coating. For small tool handles that are to be finished in black, it is advisable to use only 1 qt. of oil, 3 qt. of varnish and 1 pt. of drier to each gallon of lampblack.

Paint for New Galvanized Iron

Many times one wishes to paint new galvanized iron but the paint does not have a good tendency to stick. The following mixture applied to the metal and left to dry and get powdery, will form an excellent base.

Cupric Chloride	1	oz.
	-	
Cupric Nitrate	1	OZ.
Hydrochloric Acid		
(Tech.)	1	07.
Water	1/4	oz.

Mix all together and apply with a swab and allow to dry until the surface turns powdery. Usually several hours are sufficient.

Paint for Hot Metal Surfaces U. S. Patent 2,239,478 Sodium Silicate

(35–37%)	60	gal.
Gum Tragacanth	15	oz.
Starch	30	oz.
Sugar	80	lb.
Water	30	gal.
Alum	30 - 120	oz.
Aluminum Powder	90	lb.

Rust Preventative Black Paint
Melt 300 lb. of pitch very carefully over a fire and remove it from
anywhere near the fire. Now add 10
lb. of pulverized Portland cement
and then 25 gal. of solvent naphtha. Stir well to get a smooth easy
flowing black paint which is well
adapted for heavy outside machinery, bridges, steel work and the like.

Anti-Corrosive Paint					
Formula No	o. 1				
Alcohol	3614	gal.			
Shellac	40	lb.			
	3	gal.			
Turpentine	3				
Pine Tar Oil	3	gal.			
Zinc, Metallic					
Powdered	48	lb.			
Zinc Oxide	142	lb.			
No. 2					
Australian Patent	113.9	46			
Boiled Linseed Oil	11/5				
	22	lb.			
		lb.			
Litharge	1	10.			
Calcium Silicate					
or Cement	$2\frac{1}{2}$	lb.			
-					
Ship Bottom P	aints				
Formula No	1				
Zinc Oxide		200.0			
Zinc Yellow		80.0			
Silica, Dry		45.0			
Magnesium Silicate		48.0			
W. W. Rosin		145.0			
Coal Tar		47.5			
Coal Tar Naphtha	•	380.0			
Manganese Linoleat		75.0			
_	æ	10.0			
No. 2		25.0			
Lamp Black		25.0			
Zinc Oxide		186.0			
Indian Red		93.0			
Silica, Dry		45.0			
Magnesium Silicate		48.0			
zizugitostum zintouto					
W. W. Rosin		145.0			
	-				
Coal Tar		47.5			
Coal Tar Naphtha		380.0			
Manganese Linoleat	e	75.0			
No. 3					
Zinc Oxide	5	238.0			
Indian Red		74.0			
Silica, Dry		38.0			
Magnesium Silicate		38.0			
Cuprous Oxide		145.0			
Mercuric Oxide		45.0			

W. W. Rosin	248.0
Coal Tar Naphtha	338.0
Coal Tar	63.0
Pine Oil	39.0

Finish F r Tints	Pain
61%)	
515	lb.
343	lb.
<b>2</b>	lb.
39%)	
55%	gal
	r Tints -61%) -515 -343 -2 -39%)

Kettle Bodied "Q"
Linseed Oil \* 8¾ gal.
Mineral Spirits and
Liquid Drier † 10 gal.

Liquid Drier † 10 gal.

Pebble or stone mills are recommended since steel rolls may discolor white paints due to abrasion.

#### NAVAL PAINTS Boot-Topping, Black Formula No. 1

Zinc oxide, dry, 164; lampblack, dry, 73; raw linseed oil, 31; spar varnish, 435; paint drier, 222.

#### No. 2

Manganese linoleate, 67; silica, dry, 84; lampblack, dry, 48; zinc oxide, dry, 138; coal tar, 2.5 gal.; formalin resin solution, 79 gal.; cuprous oxide, 109; mercuric oxide, 36.

\*The higher percentage of bodied oil improves leveling.

† In whatever form drier is added, sufficient must be used to make paint dry thoroughly. Naphthenic acid types tend to produce the thinnest paints (without puff). Linoleates tend to produce the heaviest paints (with puff) and resinates are intermediate.

Naval Boot-Topping, Light Gray Formula No. 1

Zinc oxide, dry, 300; lampblack, in oil, 1; ultramarine blue, in oil, 8; spar varnish, 669; petroleum spirits, 33; paint drier, 36.

#### No. 2

Zinc oxide, dry, 289; titanium pigment, dry, 396; lampblack, in oil, 1.5; ultramarine blue, in oil, 13; raw linseed oil, 538; petroleum spirits, 15; paint drier, 87.

Naval Outside White Titanium pigment, dry, 628; zinc oxide, dry, 280; raw linseed oil, 515; petroleum spirits, 29; ultramarine blue, in oil, 0.5; paint drier, 76.

#### Naval Red Lead

Red lead, dry, 185; zinc oxide, dry, 86; venetian red, dry, 355; spar varnish, 315; petroleum spirits, 210; paint drier, 79; aluminum stearate, 93%.

Light Gray, Smokestack Paint White lead, dry, 481; zinc oxide, dry, 188; litharge, dry, 34; lampblack, in oil, 2-6; ultramarine blue, in oil, 2-4; damar varnish, 194; kerosene, 337; paint drier, 55.

#### Naval Green Paint

Zinc oxide, dry, 100; chrome green, dry, 300; chrome yellow, dry, 36; yellow ochre, dry, 75; lampblack, in oil, 60; spar varnish, 418; paint drier, 181.

Anticorrosive Ship Bottom Paint Zinc oxide, dry, 186; venetian red, dry, 93; silica, dry, 93; rosin, grade WW, 145; coal-tar naphtha, 380; coal tar, 47.5; manganese linoleate, 129.

Antifouling Ship Bottom Paint Zinc oxide, dry, 238; silica, dry, 78; magnesium silicate, dry, 72; cuprous oxide, 145; mercuric oxide, 45; rosin, grade WW, 248; coal-tar naphtha, 338; coal tar, 63; pine oil, 39.

Nontoxic Ship Bottom Paint Zinc oxide, dry, 212; silica, dry, 82; magnesium silicate, dry, 83; Indian red, dry, 160; rosin, 200; coaltar naphtha, 296; coal tar, 133; pine oil, 78.

Copper Paint for Bottoms of Wooden Boats

Zinc oxide, dry, 165; Indian red, dry, 165; cuprous oxide, 75; gum shellac, 162; alcohol, 500; pine oil, 90.

White Canvas Preservative Zinc oxide, in oil, 540; litharge, dry, 17; ultramarine blue, in oil, 1; beeswax, 6; crude rubber, 10; gasoline, 430; spar varnish, 32; raw linseed oil, 7; paint drier, 14.

Light Gray Canvas Preservative Zinc oxide, in oil, 540; litharge, dry, 17; ultramarine blue, in oil, 8; lampblack, in oil, 3-4; beeswax, 6; crude rubber, 9; gasoline, 415; spar varnish, 32; raw linseed oil, 7; paint drier, 14.

Gray Deck Paint

Zinc oxide, dry, 325; lampblack, dry, 5; lampblack, in oil, 2; ultramarine blue, in oil, 2; spar varnish, 456; paint drier, 254.

#### Yellow Marking Paint for Boat Decks

Zinc oxide, dry, 257; chrome yellow, dry, 168; magnesium silicate, dry, 168; interior varnish, 304; petroleum spirits, 267; paint drier, 43.

Metallic Brown Paint for Potable Water Tanks

Metallic brown, dry, 397; Indian red, dry, 156; zinc oxide, dry, 79; silica, 78; mixing varnish, 472; paint drier, 109.

Naval Inside White Paint Titanium pigment, dry, 565; zinc oxide, dry, 389; raw linseed oil, 271; damar varnish, 78; petroleum spirits, 194; ultramarine blue, in oil, .5; paint drier, 36.

Naval Flat White (Inside) Zinc oxide, dry, 1,287; raw linseed oil, 281; petroleum spirits, 231; ultramarine blue, in oil, .5; paint drier, 44.

Naval White Enamel (Inside) Titanium pigment, dry, 250; zinc oxide, dry, 250; damar varnish, 683; pine oil, 53; ultramarine blue, in oil, .5.

Naval Semiflat Green (Inside) Titanium pigment, dry, 650; zinc oxide, dry, 300; chrome green oxide, in oil, 4; damar varnish, 386; petroleum spirits, 214.

Naval Light Green, Gloss (Inside)
Titanium pigment, dry, 250; zinc oxide, dry, 250; chrome green oxide, in oil, 3; damar varnish, 585; petroleum spirits, 64; pine oil, 61.

Varnish, Phenolic Type Phenolic resin, 110; tung oil, raw, 279; coal-tar naphtha, water white, 269; xylene, 116; kerosene, 94; lead manganese drier, 11.5; cobalt drier, 11.5.

Inside White for Submarines Titanium pigment, dry, 462; zinc oxide, dry, 146; raw linseed oil, 93; varnish, 451; damar varnish, 25; petroleum spirits, 71; paint drier, 13; ultramarine blue, in oil, 0.5.

Zinc Chromate Primer Zinc chromate, dry, 565; magnesium-silicate, 65; varnish, 653.

Naval White Pain	t .
Titanium Dioxide	251
Zinc Oxide	91
Magnesium Silicate	114
Dipentine	23
Alkyd Resin	420
Petroleum Spirits	189
Lead Naphthenate	11
Cobalt Naphthenate	$1\frac{1}{2}$
Manganese Naphthenat	$e 1\frac{1}{2}$

Asbestos Shingle Paint
Priming Coat
White Lead 100 lb.
Lead Mixing Oil 2½ gal.
Linseed Oil 2½ gal.

Second Coat
White Lead 100 lb.
Lead Mixing Oil 4 gal.

Third Coat—Flat Finish
White Lead 100 lb.
Lead Mixing Oil 4 gal.

Third Coat—Glass Finish
White Lead 100 lb.
Linseed Oil \* 3½ gal
Liquid Drier 1 pt.

\*If boiled oil is used, omit drier.

										I
Finish	Coat	300	8	:	11/8	က	:	:	drier.	Outside House Paint Whites and Tints Pigment (58–61%) Cryptone MS—130 500 lb.
First	Coat	300	41/2	:	$1\frac{1}{2}$	က	$2\frac{1}{4}$	₩	is used, omit	Zinc Oxide (35% Leaded) 250 lb. Magnesium Silicate 83 lb. Soluble Litharge 2 lb. Vehicle (42–39%)
Alternate	Finish Coat	300	:	93%	:	:	:	:	e. If boiled oil	Raw Linseed Oil $58$ gal. Kettle Bodied "Q"  Linseed $5\frac{1}{2}$ gal. Mineral Spirits $6$ gal.
Finish	Coat	300	8%6	:	÷	က	:	:	e formula	Liquid Drier 3¾ gal.  Outside House Paste Paint  Pigment (79–80%)
Finish	Coat	300	9%	:	:	က	:	:	for in thes	Cryptone MS—130 700 lb.  Zinc Oxide (50% Leaded) 300 lb.  Vehicle (21–20%)
First Coat	Repainting	250	<b>1</b>	;	5	$2\frac{1}{2}$	:	:	Boiled linseed oil may be substituted for the raw linseed oil called for in these formulae. If boiled oil is used, omit drier.	Raw Linseed Oil 26¾ gal. Kettle Bodied Linseed "Q" 5¼ gal. Pebble or stone mills are recommended since steel rolls may dis-
Body	Coat	300	41/2	:	41/2	က	:	:	the raw l	color white paint due to abrasion.  Can be used for whites and tints.
Priming	Coat	250	10	:	r r	21/2	:	:	ubstituted for	Thinning Directions for Finish Coat Paint Paste 100 lb. Approx. 5 gal. Raw Linseed Oil
		te Lead lbs.	il gal.	Oil gal.	gal.	pt.	gal.	pt.	d oil may be s	$2\frac{3}{4}$ to $3\frac{1}{2}$ gal.  Turpentine 3 to 5 pt.  P&L Liquid Drier  Approx. 1 qt.
(A		Soft Paste White Lead	Raw Linseed Oil	Boiled Linseed Oil	Turpentine	Liquid Drier	Varnish	Raw Umber	Boiled linsee	Outside House Paint (Fume Proof) Pigment (57–60%) Cryptone MS—130 490 lb. XX Zinc Oxide 250 lb. Magnesium Silicate 83 lb. Soluble Litharge 2 lb.

Vehicle (43-40%)				
Raw Linseed Oil 573/4	gal.			
Kettle Bodied "Q"				
Linseed Oil $5\frac{1}{2}$	gal.			
Mineral Spirits 6	gal.			
Liquid Drier 3¾	gal.			
(For Metropolitan Area	as)			
Whites and Tints				
Pigment (60-62%)				
Cryptone MS—130 540	lb.			
Zinc Oxide	**			
(35% Leaded) 270	lb.			
B. C. W. L. 90	lb.			
Vehicle (40-38%)	1			
Raw Linseed Oil 581/4	gai.			
Kettle Bodied "Q"	1			
	gal.			
Mineral Spirits 6 Liquid Drier 334	gal.			
Liquid Drier 3%	gal.			
(North Atlantic and We	stern			
Seacoast)	505111			
Whites and Tints				
Whites and Tints Pigment (60–62%)				
Whites and Tints Pigment (60-62%) Cryptone MS—130 555	lb.			
Cryptone MS—130 555 Zinc Oxide	lb.			
Cryptone MS—130 555 Zinc Oxide	lb.			
Cryptone MS—130 555 Zinc Oxide (35% Leaded) 300 Soluble Litharge 2				
Cryptone MS—130 555 Zinc Oxide (35% Leaded) 300 Soluble Litharge 2 Vehicle (40–38%)	lb. lb.			
Cryptone MS—130 555 Zinc Oxide (35% Leaded) 300 Soluble Litharge 2 Vehicle (40–38%) Raw Linseed Oil 56%	lb. lb.			
Cryptone MS—130 555 Zinc Oxide (35% Leaded) 300 Soluble Litharge 2 Vehicle (40–38%) Raw Linseed Oil 5634 Kettle Bodied "Q"	lb. lb. gal.			
Cryptone MS—130 555 Zinc Oxide (35% Leaded) 300 Soluble Litharge 2 Vehicle (40–38%) Raw Linseed Oil 5634 Kettle Bodied "Q" Linseed 5½	lb. lb. gal.			
Cryptone MS—130 555 Zinc Oxide (35% Leaded) 300 Soluble Litharge 2 Vehicle (40–38%) Raw Linseed Oil 5634 Kettle Bodied "Q" Linseed 5½ Mineral Spirits 6	lb. lb. gal. gal. gal.			
Cryptone MS—130 555 Zinc Oxide (35% Leaded) 300 Soluble Litharge 2 Vehicle (40–38%) Raw Linseed Oil 5634 Kettle Bodied "Q" Linseed 5½	lb. lb. gal. gal. gal.			
Cryptone MS—130       555         Zinc Oxide       (35% Leaded)       300         Soluble Litharge       2         Vehicle       (40–38%)         Raw Linseed Oil       56¾         Kettle Bodied "Q"       5½         Linseed       5½         Mineral Spirits       6         Liquid Drier       3¾	lb. lb. gal. gal. gal. gal.			
Cryptone MS—130 555 Zinc Oxide (35% Leaded) 300 Soluble Litharge 2 Vehicle (40–38%) Raw Linseed Oil 5634 Kettle Bodied "Q" Linseed 51½ Mineral Spirits 6 Liquid Drier 334  Outside House Paint	lb. lb. gal. gal. gal. gal.			
Cryptone MS—130 555 Zinc Oxide (35% Leaded) 300 Soluble Litharge 2 Vehicle (40–38%) Raw Linseed Oil 5634 Kettle Bodied "Q" Linseed 5½ Mineral Spirits 6 Liquid Drier 334 Outside House Paint Formula No. 1	lb. lb. gal. gal. gal. gal.			
Cryptone MS—130 555 Zinc Oxide (35% Leaded) 300 Soluble Litharge 2 Vehicle (40–38%) Raw Linseed Oil 5634 Kettle Bodied "Q" Linseed 5½ Mineral Spirits 6 Liquid Drier 334  Outside House Paint Formula No. 1 Pigment (63–65%)	lb. lb. gal. gal. gal. gal.			
Cryptone MS—130 555 Zinc Oxide (35% Leaded) 300 Soluble Litharge 2 Vehicle (40–38%) Raw Linseed Oil 5634 Kettle Bodied "Q" Linseed 5½ Mineral Spirits 6 Liquid Drier 334  Outside House Paint Formula No. 1 Pigment (63–65%) Cryptone MS—130 405	lb. lb. gal. gal. gal. gal.			
Cryptone MS—130 555 Zinc Oxide (35% Leaded) 300 Soluble Litharge 2 Vehicle (40–38%) Raw Linseed Oil 56¾ Kettle Bodied "Q" Linseed 5½ Mineral Spirits 6 Liquid Drier 3¾ Outside House Paint Formula No. 1 Pigment (63–65%) Cryptone MS—130 405 XX Zinc Oxide 200	lb. lb. gal. gal. gal. gal. lb. lb. lb.			
Cryptone MS—130 555 Zinc Oxide (35% Leaded) 300 Soluble Litharge 2 Vehicle (40–38%) Raw Linseed Oil 5634 Kettle Bodied "Q" Linseed 5½ Mineral Spirits 6 Liquid Drier 334  Outside House Paint Formula No. 1 Pigment (63–65%) Cryptone MS—130 405 XX Zinc Oxide 200 B. C. W. L. 405	lb. lb. gal. gal. gal. gal.			
Cryptone MS—130 555  Zinc Oxide (35% Leaded) 300  Soluble Litharge 2 Vehicle (40–38%)  Raw Linseed Oil 56¾  Kettle Bodied "Q" Linseed 5½  Mineral Spirits 6 Liquid Drier 3¾  Outside House Paint Formula No. 1 Pigment (63–65%)  Cryptone MS—130 405  XX Zinc Oxide 200  B. C. W. L. 405 Vehicle (37–35%)	lb. lb. gal. gal. gal. gal. lb. lb. lb. lb.			
Cryptone MS—130 555  Zinc Oxide (35% Leaded) 300  Soluble Litharge 2 Vehicle (40–38%)  Raw Linseed Oil 56¾  Kettle Bodied "Q" Linseed 5½  Mineral Spirits 6 Liquid Drier 3¾  Outside House Paint Formula No. 1 Pigment (63–65%)  Cryptone MS—130 405  XX Zinc Oxide 200  B. C. W. L. 405 Vehicle (37–35%)  Raw Linseed Oil 56¼	lb. lb. gal. gal. gal. gal. lb. lb. lb. lb.			
Cryptone MS—130 555  Zinc Oxide	lb. lb. gal. gal. gal. gal. lb. lb. lb. lb.			

Mineral Spirits 6 Liquid Drier 33 No. 2	gal. 4 gal.
Pigment (62–64%)	
Cryptone MS—130 395 Zinc Oxide	lb.
(35% Leaded) 250	lb.
B. C. W. L. 295	lb.
Titanium Dioxide 50	lb.
Vehicle (38–36%)	
Raw Linseed Oil 561/	gal.
Kettle Bodied "Q"	
	gal.
Mineral Spirits 6	gal.
	agal
No. 3	
Pigment (61.5%)	
Pigment—725 400	lb.
Titanium Dioxide 135	lb.
Basic Sulphate,	
White Lead 165	lb.
Magnesium Silicate 200	lb.
Vehicle~(38.5%)	
	gal.
Q-Bodied Linseed	
	gal.
	gal.
Thinner * and Drier,	
To make 100	$\operatorname{gal}$ .

Thinning Directions for New Wood First or Priming Coat—To one gallon of paint add one quart of raw or boiled linseed oil and one pint turpentine or mineral spirits.

Second Coat—To one gallon of paint add one pint turpentine or mineral spirits.

\*The amount required will vary with the efficiency of the drier. In whatever form drier is added, sufficient must be used to make the paint dry thoroughly. Naphthenic acid types tend to produce the thinnest paints. Linoleates tend to produce heavier paints (puffy) and resinates are intermediate.

Third or Finishing Comade. If necessary paint may be redulated half pint of linseemuch turpentine or its as required to desired brushing pramount of linseed of Pigment Fixed Veh 27.3%.	one ga ced wid d oil minera produ opertie il redu	allon of ith one and as al spir- ace the es. This aces the
Thinning Directions Work	for R	epaint
If surface is in go use second and third directions for a two-co job.	coat tl	hinning
Ready Mixed Exterior Pigment (64		e Paint
Titanium Dioxide Non-chalking Type B. C. W. L. 35% Leaded Zinc Oxide Magnesium Silicate	139 149 445	lb. lb.
and Tinting Colors Vehicle (36 Raw Linseed Oil	257 %) 59.5	lb.
Heat Bodied Linsee Oil (Z-2 body) Mineral Spirits	3.4	gal.
and Drier	10.1	gal.
Formula No Pigment (68 Titanium Dioxide 35% Leaded Zinc	(%)	lb.
Oxide B. C. W. L. Magnesium Silicate		lb. lb. lb.
Vehicle (32)	%)	

Raw Linseed Oil

Mineral Spirits

and Drier

gal.

12.8 gal.

```
No. 2
       Pigment (58%)
Titanium Dioxide
                     115
                           lb.
XX Zinc Oxide
                     230
                           lb.
Magnesium Silicate 422
                           lb.
        Vehicle (42%)
Raw Linseed Oil
                      61
                           gal.
Mineral Spirits
  and Drier *
                      12.8 gal.
       Semipaste Paint
        Formula No. 1
       Pigment (79%)
B. C. W. L. or
  B. S. W. L.
                   1081
                          lb.
35% Leaded Zinc
  Oxide
                          1b.
                    542
Magnesium Silicate
   (and Tinting
  Colors)
                          lb.
                    180
        Vehicle (21%)
Raw Linseed Oil
                     61.8 gal.
            No. 2
       Pigment (79%)
B. C. W. L. or
  B. S. W. L.
                    786
                          lb.
35% Leaded
  Zinc Oxide
                    823
                          lb.
Magnesium Silicate
  (and Tinting
  Colors)
                    179
                          lb.
        Vehicle (21%)
Raw Linseed Oil
                     61.2 gal.
Exterior Ready-Mixed Paint
       Formula No. 1
       Pigment (63%)
Titanium Dioxide
  (Semi-Chalking
                       93
                           lb.
  Type)
                     231.5 lb.
XX Zinc Oxide
B. C. W. L. or
  B. S. W. L.
                    231.5 lb.
Whiting
                    139.0 lb.
Magnesium
                    231.5 lb.
  Silicate
* Lead Driers not allowed.
```

Vehicle (37	%)	
Raw Linseed Oil	591/2	gal.
Mineral Spirits		
and Drier	$12\frac{1}{2}$	gal.
No. 2		
Pigment (63	(%)	
Titanium Dioxide		
(Semi-Chalking		
Type)	93	lb.
50% Leaded Zinc		
Oxide	463	lb.
Whiting	139	lb.
Magnesium		
Silicate	231.5	lb.
Vehicle (37		
Raw Linseed Oil	$59\frac{1}{2}$	gal.
Mineral Spirits		
and Drier	$12\frac{1}{2}$	gal.
Semi-Paste P	aint	

 $\begin{array}{ccc} \text{Semi-Paste Paint} & \\ & Pigment & (72\%) \\ \text{Iron Oxide} & 1120 \text{ lb.} \\ \text{XX Zinc Oxide} & 198 \text{ lb.} \\ & Vehicle & (28\%) \\ \text{Raw Linseed Oil} & 66 \text{ gal.} \end{array}$ 

Wood Primer Formula No. 1 Pigment  $(59\frac{1}{2}\%)$ Cryptone MS—130 685 lb. (35% Leaded) Zinc Oxide 120 lb. Vehicle (401/2%) Raw Linseed Oil  $52\frac{1}{2}$  gal. Kettle Bodied "Q" 4¾ gal. Linseed Oil Liquid Drier 21/4 gal. Mineral Spirits 121/2 gal. No. 2

Pigment (57%)

635

110

lb.

lh.

Cryptone MS

(35% Leaded) Zinc Oxide 

 Vehicle (43%)

 Bodied Oil
 43½ gal.

 Raw Linseed Oil
 1½ gal.

 Liquid Drier
 1½ gal.

 Mineral Spirits
 15½ gal.

Mineral Spirits 15½ gal. As much of the bodied oil as necessary is used in the base, which is then reduced with the remainder of the bodied oil, the raw oil, and the liquid drier. Mineral spirits should then be added to produce the body desired.

Vehicle for Wood Primers
Raw Chinawood Oil 25 gal.
Raw or Non-Break
Linseed Oil 75 gal.

Heat raw Chinawood oil and an equal volume of raw or non-break linseed oil to 565° F. in 55 minutes, check with remainder of raw or non-break linseed oil and cool. This is a light bodied oil.

Flat Wall Paint—I		lat
Pigment (59	%)	
Cryptone ZS—800	405	lb.
Magnesium		
Silicate	220	lb.
Diatomaceous		
Silica	110	lb.
Vehicle (419	%)	
Kettle Bodied Lin-	•	
seed Oil (Z-3		
Body)	15.1	gal.
10 lb. Cut Low		
Acid Ester Gum	9.55	gal.
6 oz. Cut Aluminum		
Stearate Gel.	19.94	gal.
Mineral Spirits	11.81	gal.
Kerosene	15.2	gal.
Lead Naphthenate		7
24%	0.56	gal
Cobalt Naphthenate		0
6%	0.15	gal.

Self Priming Flat Paint	N-Glo-5 11.03 gal.
Formula No. 1	Mineral Spirits 13.15 gal.
Pigment (57%)	Kerosene 18.38 gal.
Cryptone ZS—	Combined
800 415 lb.	Naphthenate Drier 1.53 gal.
Magnesium	1% Ivory Soap
Silicate * 285 lb.	Solution 0.76 gal.
Vehicle (43%)	No. 2
37-M OKO Oil 19.2 gal.	
Mineral Spirits 40.3 gal.	Brushing Consistency
Kerosene 15.62 gal.	Pigment (64.5%)
Pb Naphthenate	Albalith 361
24% 0.465 gal.	or 362 780 lb.
Co Naphthenate	Whiting 150 lb.
6% 0.086 gal.	Vehicle (35.5%)
No. 2	T&W 600 Liquid 451/4 gal.
Pigment~(58%)	Refined Linseed Oil 1½ gal.
Cryptone BT—	Mineral Spirits 181/4 gal.
301 600 lb.	Kerosene 53/4 gal.
Magnesium	No. 8 Pale Japan
Silicate 150 lb.	Drier 13/8 gal.
Vehicle (42%)	Soap Solution 3/4 gal.
37-M-OKO Oil 19.6 gal.	If higher consistency is desired
Mineral Spirits 41.0 gal.	either the pigmentation may be in-
Kerosene 15.9 gal.	creased or part of the Albalith-361
Pb Naphthenate	or 362 may be replaced with Al-
24% .47 gal.	balith-424.
Co Naphthenate	No. 3
6% .10 gal.	Reduces One Quart to the Gallon
Flat Wall Paint—High Dry	Pigment (68%)
Hiding Type	Albalith—362 670 lb.
(To reduce 8-2 for brushing)	Albalith—404 155 lb.
Formula No. 1	Asbestine 206 lb.
Pigment (72.4%)	
Albalith—351 1025 lb.	Vehicle (32%)
Whiting 175 lb.	V-169 20½ gal.
	N-Glo-5 6½ gal.
	Mineral Spirits 21½ gal.
Vehicle (27.6%)	V-201 6 gal.
4-3 Kettle Bodied	Kerosene 10 gal.

5.06 gal.

8.02 gal.

Linseed Oil

Refined Linseed Oil

Liquid Drier \*

1

gal.

Blown Linseed Oil 4.97 gal.

\*A portion of the magnesium silicate may be replaced with diatomaceous silicate if a reduction in sheen is desired.

\*The liquid drier is composed of 100 parts lead naphthenate drier (16% Pb).

one part cobalt naphthenate drier (4% Co) and one part manganese naphthenate drier (4% Mn).

1% Ivory Soap		
Solution	$\frac{1}{2}$	gal.
V-214	2	gal.

Prepare a paste using all the pigment, V-169, V-201, N-Glo-5, kerosene and as much of the mineral spirits as needed to produce the desired paste consistency. Grind on roller mill or buhrstone mill. Thin with the remaining mineral spirits and driers.

## No. 4 (Eggshell Flat) Paint Pigment (70%)

Albalith Black Label—11 850 lb. Whiting 180 lb. Calcium Linoleate Pulp (30% solids) 32 lb. Ultramarine Blue  $3\frac{1}{2}$  oz.

#### Vehicle (30%)

Z-3 Bodied Lin-		
seed Oil	20	gal.
Diamond K Lin-		
seed Oil	$\frac{1}{2}$	gal.
N-Glo-5 Gloss Oil		
(Newport		
Industries)	$4\frac{1}{2}$	gal.
Kerosene	$6\frac{3}{4}$	gal.
Mineral Spirits	$31\frac{3}{4}$	gal.
Lead Naphthenate		
Drier (16%)	$\frac{1}{2}$	gal.
Cobalt Naphthenate		
Drier (6%)	$\frac{1}{4}$	gal.

#### No. 5

#### Pigment (67.8%)

Cryptone BA-19,		
BT-367 or		
BT-803	600	lb.
Whiting	335	lb.

Calcium Linoleate
Pulp (30%
solids)
30 lb.
Ultramarine Blue
3 oz.

#### Vehicle (32.2%)

Same ingredients, percentages and gallons as No. 1.

Mix all pigment ingredients with the Z-3 bodied linseed oil, Diamond K linseed oil, gloss oil, and sufficient mineral spirits to give a suitable paste. Mill through a roller or buhrstone mill and thin with the remaining vehicle constituents.

#### No. 6

110. 0		
Red Label Albalith	980	lb.
Asbestine	137	lb.
Aluminum Stearate	5	lb.
Litharge	2	lb.
Zinol	12	lb.
10-lb. Ester Gum		
Cut	124	lb.
A Soybean Oil	142	lb.
Kerosene	$33\frac{1}{2}$	lb.
Mineral Spirits	231	lb.
16% Lead		
Naphthenate	7	lb.
6% Cobalt		
Naphthenate	1	lb.
No. 7		
Titanium Calcium	700	11
Pigment	700	lb.
Asbestine	-150	lb.
Aluminum Stearate	4	lb.
Litharge	2	lb.
Zinol	12	lb.
10-lb. Ester Gum		
Cut	124	lb.
A Soybean Oil	142	lb.
Kerosene	$33\frac{1}{2}$	lb.
Mineral Spirits	231	lb.
16% Lead		
10% 1.000		

#### Reduced Alkalized Polymers for Controlled Penetration Flat Wall Coats

	No. 1	No. 2
Crude Non-break Perilla Oil	1535 lb.	
Heat-Poly. Perilla ("X")	743 lb.	
Linseed Fatty Acid	$7\frac{1}{2}$ lb.	
V.M. Linseed (Punjab)*	• • • •	1675 lb.
Heat-Poly. Linseed ("X") *		303 lb.
Heat-Poly. Linseed ("Q") *	• • • •	151 lb.
Calcium Hydrate	$31\frac{1}{2}$ lb.	13 lb.
Magnesium Oxide		13 lb.
Light Kerosene	67 gal.	97 gal.
Mineral Spirit	607 gal.	575 gal.
Cleaners' Naphtha	57 gal.	53 gal.
	•	

<sup>\*</sup>From minimum 190 iodine number V. M. oil.

Metropolitan Type Gloss Paint Heavy Body—High Gloss— Non-Sagging *Pigment* (53.0%) Cryptone BT-367 700 lb. Vehicle (47.0%) Gloss Oil (N-GLO-5)27¾ gal. 10# Cut Low Acid Ester Gum 14¾ gal.

Heavy Bodied Blown Sova Oil gal. Alkali Refined

Linseed Oil 8 gal. Extra-Heavy Kettle

Bodied Fish Oil 19¾ gal. Mineral Spirits gal.

\* Lead Linoleate Drier 16%  $1\frac{1}{4}$  gal.

\* Cobalt Linoleate Drier 6%

1/4 gal.

Mix the pigment with gloss oil, ester gum solution, blown soya oil, and sufficient mineral spirits to form a good paste. Grind on roller mill and reduce with fish oil, refined linseed, and remaining min-

eral spirits. Finally add driers previously cut in some of the mineral spirits. Final consistency characteristics will be attained after aging 48 hours.

This is a heavy consistency product which can be reduced  $(8-1\frac{1}{2})$ with mineral spirits for application.

Floor Painting and Finishing

If the floor is made of spruce, pine, fir or other soft wood, the paint for the priming coat should be mixed on the following basis:

Soft Paste White

DOLU I abuc 11 mice			
Lead	100	lb.	
Raw Linseed Oil	3	gal.	
Turpentine	2	gal.	
Liquid Drier	1	pt.	
Oil Color for Tinting,			
To suit			

This mix makes 8% gal. of paint that will prime about 600 sq. ft. to 800 sq. ft. of new soft wood flooring per gallon.

The paint in this first coat, as well as in all other coats, should be applied with a well-filled brush and must be spread out carefully and

<sup>\*</sup> Percent metal based on oil—0.7% Pb and 0.046% Co.

rubbed in closely. A prime cause of sticky floors is too much oil in the paint or flowing on the paint in any or all coats so thick that it does not dry properly, then hurrying too much with succeeding coats. Spread the paint out well, rub it in "close" and allow plenty of time for drying—three main points in producing a good floor job.

If the floor is made of birch, maple, beech or some other hard wood, use a priming coat mixed as directed above, but cut the linseed oil down to 2½ gal. Oak and walnut are never painted unless old and much worn,

scarred and bruised.

After the primer is dry and hard, all open joints, cracks, nail holes and other defects should be filled with putty—preferably of the white lead, whiting and linseed oil variety. A little floor varnish in this putty makes it set harder and stick tighter. Fill all the holes and cracks a little more than full, pressing the putty in with a knife. When the putty has dried hard, smooth it off with sandpaper and clean up the dust.

For the next coat, on either soft wood or hard wood floors, use a paint mixed on this basis:

Soft Paste White
Lead 100 lb.
Floor Varnish 1 gal.
Turpentine 2½ gal.

This paint may be tinted to about the color of the finishing coat.

The above mix makes 6½ gal. of paint that will cover at the rate of 700 sq. ft. to 800 sq. ft. per gallon.

When this coat has dried and hardened thoroughly, apply a final coat of paint mixed on this basis: Soft Paste White
Lead 100 lb.
Floor Varnish 2 gal.
Turpentine 1½ gal.
Oil Color for Tinting,
To suit

Painting Old Wood Floors

The first thing to do before painting an old wood floor is to get it in shape to receive paint. If the wood has old paint on it that is blistered, rough and scaly, or is thick and gummy it should be stripped off, using an electric floor sanding machine, a torch and scraper, or a paint remover—paste or liquid. This removal of the old paint may be troublesome and expensive but it is necessary if a good repaint job is to result.

Paint or varnish removed with liquid or paste removers commonly sold for that purpose is most practically handled in less time and with less work this way: Brush the liquid or paste on to three or four boards from wall to wall, or coat in a patch about a yard square. Use a broad scraping knife to roughly skin off the sludge. Then have a half pail of hot water in which about one-half package of Gold Dust, or similar washing powder, has been dissolved. Dip a large wad of No. 3 coarse steel wool in the water and scrub off the stripped surface. That will usually take off everything and leave the wood clean and free from wax from the remover. Sometimes two or more applications of the remover are necessary to cut the old paint or varnish enough.

If the paint is taken off with lye or other caustic remover, the surface

will have to be washed with strong vinegar water after all the leavings have been cleaned up, in order to neutralize all remaining traces of alkali. Regardless of the method used to remove the paint, the floor should then be thoroughly washed with clean, warm water and allowed plenty of time to dry out. When dry, make sure all floor boards are securely nailed and are firm and solid. Fill the cracks, let dry, sand the cracks level and brush off the dust. Paint as outlined before.

In repainting old wood floors on which the old paint is in good shape, the priming coat is not needed. The floor should first be carefully cleaned, however, and all defects puttied up.

Old wood floors that have never been painted or treated in any way should, of course, be repaired and prepared for painting as suggested.

Painted floors, when hard and dry, may be waxed like varnished floors. Such a finish, if renewed regularly, will protect the paint from scratches and assure a very long life.

#### Painting Plywood

For concealing the joints in plywood walls and at the same time providing any desired color decorative scheme, the addition of 5% by weight of wood flour to a flat wall paint has shown interesting possibilities. The resultant mixture has a coarse grained corn meal texture, can be applied with a regulation paint brush at a spreading rate of about 180 to 200 sq. ft. per gallon, and may be textured with various tools.

#### Painting Plaster Statues

If the statues, whether painted or bare, are old and dusty or dirty and have no defective coating of any kind, the only surface preparation needed is a good washing with mild soapy warm water. If the statues do not appear to be very old, and have not been painted, it will be best to insure the neutrality of the plaster by giving the figures a thorough washing with a solution composed of two pounds of zinc sulphate in a gallon of warm water. If there is paint now on the figures and it is cracking and peeling, remove it, using a liquid paint remover. After the paint is removed, rinse the plaster with weak vinegar.

After proper preparation, allow the plaster to dry out thoroughly. For a first coat of paint apply a wall primer. This is a pigmented varnish-type sealer and primer that also has the adherence, spreading capacity and covering power of an actual coat of paint.

Since statuary is usually done in flat finishes, the next coat may be a white lead and mixing oil or white lead and flatting oil paint. If mixing oil is used the paint should consist of equal volumes of white lead and mixing oil. If flatting oil is used, mix the paint on the basis of 25 lb. of white lead to a half-gallon of flatting oil. In either case tint the paint for the proper portions of each statue with colors in oil. These colors have unusually high tinting strength so be sure to add them to your paint, just a small quantity at a time, until the correct tint is reached.

# Cement Paint Australian Patent 113,168 Cement 24 Diatomaceous Earth 1 Linseed Oil, Raw 14 Turpentine 2 Magnesium Carbonate 2

#### Cement Coating U. S. Patent 2,244,449

This new cement type coating is a liquid composition of creamy consistency. It is adapted to form an enamel-like coating on an unpolished non-metallic surface. The composition should be applied while the surface is damp. It is allowed to set and cure while kept damp. The composition consists of the product obtained by mixing together the following ingredients:

Portland Cement 100 pt.
Pigment 10 pt.
Calcium Stearate 1/2-1 pt.
Calcium Chloride 45 pt.

The pigment used is selected from the group consisting of chromium oxide, iron oxide, cobalt oxide, magnesium oxide and aluminum oxide. The aqueous solution of calcium chloride is obtained from dissolving a quantity of calcium chloride in twice the quantity by weight of water.

Plastic Coating for Brick and Cement

Cemeno	
U. S. Patent 2,228	,061
Magnesia	20 – 50
Silica	10-50
Calcium Carbonate	5 - 25
Fluorspar	1-10
Zinc Oxide	1-15
Magnesium Chloride S	solution,
To suit (d. 20-40° Be	é)

### Wall Protective Coating U. S. Patent 2,260,882

Transparent in dry state and water-soluble.

Bentonite	1–12
Gum Arabic or Traga-	
$\operatorname{canth}$	$\frac{1}{2}$ 1
Water, To make	100

## Stipple Paint Pigment (77.5%)

Albalith 387 or Black Label 11 1122 lb.

Magnesium Silicate 2

281 lb. *Vehicle* (22.5%)

White Refined Lin-

Mix the pigments with the oil and thinners. Grind and reduce with the liquid drier.

Possesses good brushing and sets sufficiently slow to allow laps to be picked up after 15 minutes. Kerosene substituted for some of the mineral spirits will further extend this time and has no effect on the final hardness of the film. To lower the consistency the following suggestions are offered:

- 1. Whiting for magnesium silicate.
- 2. Lower consistency pigment as Albalith 386 or Red Label 14.
- 3. Kettle bodied linseed oil for part of the refined oil and reduce the total pigment to maintain the same brushing.
- \*Percent metal based on vehicle non-volatile %Pb 0.5, %Mn 0.005, %Co 0.005.

#### Painting Over Tar, Asphalt or Creosoted Surfaces

First apply a priming coat of shellac or aluminum paint to act as a seal.

#### Painting Linoleum

Scrub the floor thoroughly to remove all traces of dirt and grease. If the linoleum has been waxed, remove the wax with turpentine, because no paint will get a good anchorage on wax. With the floor clean, apply a priming coat mixed on this basis:

#### Soft Paste White

Lead	$12\frac{1}{2}$ lb.
Raw Linseed Oil	$1\frac{1}{2}$ pt.
Turpentine	$1\frac{1}{2}$ pt.
Liquid Drier	2 oz.

Spread this primer out thin and brush it in well. Let it dry and harden for at least a week. Then apply a body coat mixed as follows:

#### Soft Paste White

Lead	$12\frac{1}{2}$	lb.
Raw Linseed Oil	1	pt.
Turpentine	1	qt.
Liquid Drier	2	oz.

This paint should be tinted an ivory shade with raw sienna. Allow the paint at least a week to dry and harden, then apply a coat of good quality prepared floor enamel of the selected shade.

#### Repainting Golf Balls

To remove old paint from golf balls, dip the balls for a few minutes in a warm 10% sodium hydroxide solution. Follow this by scrubbing, washing and drying. Refinish with two or three coats of exterior enamel.

White Lead Finish	Coat P	aints
Formula No. 1-	_White	2
Soft Paste White	1111100	
Lead	100	lb.
Raw Linseed Oil		
	$3\frac{1}{4}$	
Liquid Drier	$\sim$ 1	pt.
No. 2—Silver	Gray	
Soft Paste White		.,
Lead	100	lb.
Paste Lampblack		pt.
Raw Linseed Oil	$3\frac{1}{4}$	
Pure Turpentine	1	pt.
Liquid Drier	1	pt.
No. 3—Mediur	n Gray	
Soft Paste White		
Lead	100	lb.
Paste Lampblack	$\frac{1}{4}$	pt.
Raw Linseed Oil	$3\frac{1}{4}$	gal.
Pure Turpentine	1	pt.
Liquid Drier	1	pt.
No. 4—Foliage	Green	-
Soft Paste White		
Lead	100	lb.
C. P. Chromium		
Oxide Green	1	gal.
Raw Linseed Oil	$2\frac{1}{2}$	
Spar Varnish	1	gal.
Pure Turpentine	1	qt.
Liquid Drier	1	qt.
No. 5—Gray-	Green	- <del>-</del>
Soft Paste White		
Lead	100	lb.
C. P. Chromium	200	-~•
Oxide Green	1/2	gal.
Paste Lampblack		pt.
Raw Linseed Oil	91/2	gal.
Spar Varnish	1/2	gal.
	1	
Pure Turpentine	1	qt.
Liquid Drier	T	pt.
Free Flowing Flat	White P	aint

lb.

800

200

268

Unilith 88

VM-411 Flat Liquid

Suspenso Whiting

gal.

22.3

8.9

34.8

Varnolene 224 34.0 Weight gallon = 14.92 lbs. Vehicle non-volatile (by weight)

= 35%.

100 gallon oil length.

VM-411 is a 4% limed rosinchinawood-linseed oil varnish, 66% non-volatile, with a viscosity of w-x. The weight per gallon is 7.75 lbs.

Paint consistency (Stormer) = 80.

Thixotropic Flat Paint 100 gal. "Ti-Cal" TC 533 lb. Diatomaceous Silica 58 lb. Whiting 132 lb. \* 50-Gallon Ester Gum Varnish 24.3gal. Body Z Perilla 10.0 gal. Kerosene 5.3gal. Mineral Thinner 29.0 gal. Co Naphthenate 6% 1.75 pt. Pb Naphthenate 24% 1.5 pt. Soap Solution 1% 1.45 gal. Gallon weight = 12.2 lbs. Pigment volume = 57% 1/0.75-P/B.

Non-volatile in vehicle = 39% by weight.

Oil length of vehicle = 100 gallons.

Consistency (Stormer) = 132 (choppy).

#### White Enamel

lb. gal.
Tidolith 88 N 700 19.8
D-633 Varnish 625 80.2
Cobalt Nuodex 6% 3 .4
Weight/gallon = 13.28 lbs.
Vehicle non-volatile (by weight)
= 57.0%.

Vehicle oil length = 30 gallons. Vehicle weight/gallon = 7.50 lbs. D-633 is an ester gum-chinawoodlinseed oil varnish of viscosity G. Enamel consistency (Stormer) =

93.

Outside House	Paint	
"Ti-Sil"	310	lb.
35% Leaded Zinc		
Oxide	370	lb.
Magnesium Silicate	147	lb.
Q Body Linseed Oil	4.8	gal.
Alkali Refined Lin-		
seed Oil		gal.
Drier P		gal.
Mineral Thinner		gal.
Gallon weight = 13		
Pigment volume =		
Non-volatile in vehic	eie = 8	19% by
weight.		07
Consistency (Storm (short).	ner)	= 87
(SHOLU).		
Black-Out Pa	aint	
Formula No		
Carbon Black (Low		
Color type—Low		
Oil Absorption)	$7\frac{1}{2}$	lb.
China Clay	145	lb.
Short Oil Rosin		
Varnish	$7\frac{1}{2}$	gal.
Short Oil Gilsonite		
Varnish	9	gal.
Aluminum Stearate	2	lb.
Mineral Spirits		gal.
Obvious adjustment	s sho	uld be
made for other colors.		
made for other colors.  No. 2  Carbon Black (Low		

Color type—Low

5 lb.

75 lb.

80 lb.

55 lb.

5 lb.

Oil Absorption)

Vehicle A or B

Mineral Spirits

Dipentine

Clay

<sup>\*</sup>This varnish weighs 7.4 lb./gal. and contains 60% N. V. by weight.

Vehicle A		
Batu Resin	150	lb.
Refined Soya Bean Oil	25	
No. 8 Litho Linseed Oil	25	lb.
Hi-Flash Naphtha	175	
Mineral Spirits	25	lb.
$Vehicle\ B$		
Batu Resin	150	lb.
Paraffin Oil		lb.
Hi-Flash Naphtha	150	
Mineral Spirits		lb.
No. 3		
Belro Resin-Linseed Oil  Vehicle A	l Var	nish
	00	lb.
23 Viscosity Heat-		
Bodied Linseed Oil 1	50	lb.
Varnish Makers'		
Litharge	3	lb.
Electrolytic Manganese	9	
Dioxide		lb.
Hydrated Lime	3	lb.
Heat the linseed cil a	and 7	5 lb.
Belro Resin to 350° F. in	abo	ut 20
minutes. Add the lime slo	wlv	while
raising temperature to	450	° F.
(about 10 minutes). Ad		
of rosin and reheat to 4		
about 20-25 minutes.		
mixed driers and work in		
to 565° F. and hold at 565		
1¼ hours for a medium		
Cool to 450° F. and redu	ce to	50%
solids with 75 parts mine	ral s	pirits

It is important that the liming operation and additions of driers be carried out slowly. Otherwise severe foaming will result. Belro Resin foams to a greater degree than ordinary rosin.

and then 25 parts of VM&P

Naphtha.

Gilsonite-Linseed Oil Varnish Vehicle B 500 lb. Gilsonite Selects

Y Viscosity Heat-		
Bodied Linseed Oil	320	lb.
Varnish Makers		
Litharge	1	lb.
Electrolytic Manganese		
Dioxide		lb.

Heat Gilsonite and linseed oil to 450° F. in about 40 minutes. Work in mixed driers. Then heat to 565° F. in about 20 minutes and hold at 565° F. for 30 minutes. Cool to 450° F. and reduce with mineral spirits to 45% solids.

### Paint Formulation

Grind		
Excelsior No. 1		
Carbon Black	75	lb.
No. 1290 China Clay	450	lb.
Vehicle A (Belro		
Varnish)	620	lb.
Vehicle B (Gilsonite		
Varnish)	620	lb.
Aluminum Stearate	20	lb.
Reduce		
VM&P Naphtha	420	lb.
3% Cobalt Naph-		
then ate Solution	3.3	lh:

The paste may be ground through either a buhrstone or roller mill. Two passes give a good grind and one pass should be sufficient. If a pebble mill is employed the VM&P Naphtha used for reducing would probably be included in the charge to secure efficient grinding.

Paint made according to this formula is suitable for brushing or spraying to produce complete hid ing with one coat. Coverage on glass as determined by the Gardner Brushout Test is 750 square feet per gallon. For actual coverage under conditions of use expect about 600 square feet per gallon. It dries dust free in less than one hour on glass.

The dried film is a very flat grayblack finish which will pass all the tests that have been suggested for a paint of this kind. Belro yields better results in this type of paint than ordinary rosin and its use is recommended in preference to any other grade of wood or gum rosin. It is available in large quantities and is the lowest cost rosin available at this time.

Camouflage Paint for Glass

A method for treating exterior glass surfaces of buildings so that they are inconspicuous at a distance has been devised. A film of transparent binding liquid is formed on the surface and particles of an aggregate, which have been coated with coloring material, are embedded in it. The particles are of such size that they are dispersed on the surface so that the reflecting property is diminished while light is permitted to be transmitted through the gaps between the particles.

In application, the binding medium is first applied and while this is tacky, the color-coated aggregate is dusted on, so that the particles are dispersed over the surface. An alternative procedure consists in mixing the color-coated aggregate with the binding medium and then applying this mixture to the glass by spraying. A satisfactory binding liquid can be made on the following formulation:

Formula No. 1
Oil-Rosin Mixture (1:3
to 1:1 by Volume of
Melted Rosin to Linseed Oil) 1 gal.

Turpentine (More if Rapid Drying Is Required)

Pure Green (Or Other Color if Desired) 3 lb.

2 pt.

The following mixture has been found to be suitable for the aggregate:

 $\begin{array}{ccccc} \text{Dry Sand} & & 1 & \text{ton} \\ \text{Raw Linseed Oil} & & 1\frac{1}{2} & \text{gal.} \\ \text{Turpentine} & & 10 & \text{pt.} \\ \text{Color} & & 16 & \text{lb.} \end{array}$ 

A volatile solvent, such as a petroleum thinner, may be added as a diluent and in some cases alum is desirable as a fixative for the color. The liquids are first mixed and then fed with the sand in the mixing machine. After being intimately mixed, the powder is spread out to dry.

The proportion of color-coated aggregate used may be varied but it has been found most effective to treat the glass with binding liquid prepared as above, in quantities of about 35 to 55 superficial yards per gallon and with aggregate in quantities of about 40 to 80 superficial yards per hundredweight.

No. 2

Dilute with carbon tetrachloride, Graphite Suspension "Dag," Type 304, to 1/10th its original concentration and paint on with fine brush.

#### Camouflage Paints Light Green No. 1

Pigment	56 %
C.P. Chromium Oxide	12.0 %
Yellow Ochre	17.3 %
Yellow Iron Oxide	2.9 %
Red Iron Oxide	0.35%
Lithopone	16.5 %
Magnesium Silicate	38.45%
Zinc Oxide	12.5 %
Vehicle	44 %

			1		
Z Kettle Bodied Lin-			Zinc Oxide	12.5	%
seed Oil	40	%	Magnesium Silicate	19	%
Mineral Spirits and		•	Vehicle	42	%
Drier	60	%	Z Kettle Bodied Lin-		,
$Dark\ Green\ No.$	2	•	seed Oil	40	%
Pigment	56	%	Mineral Spirits	50	%
C.P. Chromium Oxide	11.8		Earth Yellow No		/-
Yellow Iron Oxide	8.5		Pigment .	65	%
Red Iron Oxide	0.6		Yellow Ochre	19.1	
Mineral Black	1.1	%	Yellow Iron Oxide	17.0	
Lithopone	10.5	•	Burnt Sienna	0.4	
Zinc Oxide	12.5	%	Lithopone	51.0	%
Magnesium Silicate	55.0		Zinc Oxide	12.5	,
Vehicle	44	%	Vehicle	35	%
Z Kettle Bodied Lin-		70	Z Kettle Bodied Lin-	00	/0
seed Oil	40	%	seed Oil	40	%
Mineral Spirits and	10	70	Mineral Spirits	60	%
Drier	60	%	Loam No. 7	00	10
Sand No. 3	00	70	Pigment	55	%
Pigment	63	%	Yellow Iron Oxide	25.4	
Yellow Ochre	$\frac{05}{25}$	%	Mineral Black	4.8	
Mineral Black	0.5	%	Lithopone	6.7	٠.
	62	%	Zinc Oxide	12.5	
Lithopone	12.5		Magnesium Silicate	50.6	,
Zinc Oxide	37	%	Vehicle	45	%
Vehicle Z Kettle Bodied Lin-	01	70	Z Kettle Bodied Lin-	10	10
	40	%	seed Oil	40	%
seed Oil	40	70	Mineral Spirits and	TU	10
Mineral Spirits and	60	01.	Drier	60	%
Drier		%	Earth Red No.		10
Field Drab No.	•	01.	Pigment	56	%
Pigment	60	%	Burnt Sienna	11.5	
Yellow Ochre	28	%		17.6	
Red Iron Oxide	1.3	%	Yellow Ochre Mineral Black	0.3	
Mineral Black	1.5			23.0	
Lithopone	38	%	Lithopone	$\frac{23.0}{12.5}$	
Zinc Oxide	12.5	,	Zinc Oxide	35.0	/
Magnesium Silicate	18.7	,	Magnesium Silicate	33.0 44	٠.
Vehicle	40	%	Vehicle	44	%
Z Kettle Bodied Lin-	40	~	Z Kettle Bodied Lin-	40	01
seed Oil	40	%	seed Oil	40	%
Mineral Spirits	60	%	Mineral Spirits and	co	of
EarthBrownNo			Drier	60	%
Pigment	58	%	Olive Drab No.		04
Yellow Ochre	55	%	Pigment	56	%
Mineral Black	2	%	C.P. Chromium Oxide		, .
Lithopone	11.5	%	Yellow Ochre	31.0	%

Mineral Black	3.3 %	Earth Yellow
Lithopone	11.3 %	White (Lithopone) 40
Zinc Oxide	12.5 %	Yellow Iron Oxide 30
Magnesium Silicate	40.0 %	Chromium Oxide 5
Vehicle	44 %	Iron Oxide Red 3
Z Kettle Bodied Lin-		Loam
seed Oil	40 %	Burnt Umber 11
Mineral Spirits and		Chromium Oxide 15
Drier	60 %	Black Iron Oxide 7
White No. 10		Iron Oxide Red 3
Pigment	62 %	Yellow Iron Oxide 1
Lithopone	40 %	$Earth\ Red$
Zinc Öxide	20 %	White (Lithopone) 45
Magnesium Silicate	40 %	Yellow Iron Oxide 16
Vehicle	38 %	Iron Oxide Red 6
Z Kettle Bodied Lin-		Chromium Oxide 10
seed Oil	40 %	Olive Drab
Mineral Spirits and	,	Chromium Oxide 47
Drier	60 %	Yellow Iron Oxide 13
		Red Iron Oxide 6
	•	Black
Camouflage Paint Pa	igments	Mineral Black
Light Green	8	White
Chromium Oxide	86	Lithopone
Yellow Iron Oxide or		
Yellow Ochre	50	
Red Iron Oxide	1	Military Paint Pigments
$Dark\ Green$		$Metal\ Primer$
Chromium Hydrate	43	(Brown)
Yellow Iron Oxide or		Zinc Yellow 7–20
Yellow Ochre	11	Iron Oxide, Red 35
Red Iron Oxide	2	Zinc Oxide (Not to
Sand		Exceed That of
White (Lithopone)	108	Zinc Yellow) 0-20
Chromium Oxide	7	Tinting Pigments Less than 1
Yellow Iron Oxide	7	Extenders Less than 58
Red Iron Oxide	3	
Field Drab		The second secon
Yellow Iron Oxide	8	Fluorescent Powder
Lithopone	54	British Patent 530,021
Chromium Oxide	13	Formula No. 1
Iron Oxide	3	Calcium Oxide 20
Earth Brown		Molybdenum Oxide 79
Chromium Oxide	60	Lead Acetate 1
Yellow Iron Oxide	24	Samarium Oxide 0.1–3
Iron Oxide Red	12	Fire at 1000° C. for 4 hours.
TIOH ONIGE HOG	14	Late de 1000 O. for 1 mours.

#### British Patent 535,897 No. 2

Magnesium Tungstate 10%
Zinc Beryllium Silicate 62%
Cadmium Borate 28%
This fluoresces with a white light

in electric discharge lamps.

#### British Patent 532,941 No. 3

A mixture of 20–45% magnesium tungstate, 40–70% zinc-beryllium silicate, and 6 to 18% cadmium borate is used.

#### Fluorescent Cadmium Silicate No. 4

450 g. cadmium oxide and 420 g. silica are mixed together with 10 g. manganese chloride. The mixture is dried well above 100° C. for several hours, then heated at 1000° C. for 2 to 3 hours.

#### Fluorescent Magnesium Silicate No. 5

300 g. magnesium oxide, 500 g. silica and 16 g. manganese nitrate are mixed together and heated to 1200° C. for several hours.

#### Fluorescent Zinc Tungstate No. 6

225 g. zinc oxide and 700 g. tungstic oxide with an admixture of 1.5 g. lead nitrate are formed into a paste with pure water. The mixture is dried, then ground, and heated to 1000° C. for several hours.

#### Fluorescent Cadmium Tungstate No. 7

375 g. cadmium oxide and 400 g. tungstic oxide are mixed together, and heated to 1000° C. for one hour. The product shows fluorescence of

moderate intensity. Its brightness can be increased by grinding and refiring at  $1100^{\circ}$  C. for  $1\frac{1}{2}$  hours.

#### Fluorescent Calcium Molybdate No. 8

580 g. purified and dried molybdic acid and 400 g. calcium carbonate are mixed together, and heated to 850° C. for about two hours.

#### Zinc Sulphide, Fluorescing Blue (Laboratory Method) No. 9

Pure hydrogen sulphide is passed into a neutral solution of zinc chloride. The precipitate of zinc sulphide is filtered, washed and dried. For each gram of zinc sulphide add 0.05 g. sodium chloride + 0.05 g. magnesium fluoride + 0.0003 g. silver nitrate, grind well, and heat in a crucible for 10 minutes at 900° C.

#### Fluorescent Zinc Borate No. 10

600 g. purest zinc oxide and 460 g. purest orthoboric acid are mixed together with 3.4 g. manganese nitrate. The dried mixture is fired at 750° C. for one hour. A material showing deep red luminescence is obtained in this way.

#### Fluorescent Cadmium Phosphate No. 11

An aqueous solution of 300 g. very pure ammonium phosphate is added to a similar solution of 630 g. cadmium sulphate. The precipitate thus formed is filtered off, washed, and well mixed with 11 g. manganese chloride. The dry mixture is fired at 1000° C. for about two hours. The

resultant powder shows a light red luminescence.

#### British Patent **521,796** No. **12**

A fluorescent material may be composed of zinc oxide (60), silica (40), beryllium oxide (1.5-2.5), manganese oxide (3-5), and one-half part lithium chloride. The manganese acts as the activator and the mixture is fired at 1000° C.

#### Luminescent Pigment for Ceramics British Patent 487,520

No. 13
Titanium Dioxide 47 %
Magnesium Oxide 48 %
Beryllium Oxide 5 %
Chromium 0.1 %
Wet grind; dry; mold and fire at

#### British Patent 536,305 No. 14

1400-1550° C.

Zinc Oxide 324 g.
Beryllium Oxide 100 g.
Silica 276 g.
Manganese Chloride 19.6 g.
Arsenic Trioxide 30 mg.
Mill wet; dry; roast at 1220° C.

#### Green Pigment No. 15

Dissolve one ounce of analytically pure zinc chloride in 4 ounces of distilled water. Add a trace of manganese sulphate (usually less than 1%). Bring the solution to a boil and add an equal volume of sodium silicate (the flux). The whole is evaporated to dryness.

The above evaporated solid is then placed in a porcelain crucible and heated to a bright red for 2 hours. When cool, this pigment will show a pale green fluorescence and a bright green phosphorescence when exposed to short wave lengths (cold quartz tube) of ultraviolet. Heating the pigment to a bright red for an additional 3 hours will increase both the fluorescence and the phosphorescence. Longer heating will tend to quench the luminescence.

#### Red Pigment No. 16

Substituting cadmium chloride for zinc chloride in the above formula, but giving it exactly the same treatment, it was found necessary to heat the compounds to a bright red for 3 hours before phosphorescence became very intense. Subsequent heating appeared to have no marked effect upon luminescence. The fluorescence is pink and the phosphorescence is dark red.

#### Orange Pigment No. 17

Some cadmium sulphate is dissolved in distilled water with a small trace of manganese sulphate (less than 1%) and the whole heated to dryness without adding the flux. The resulting white powder fluoresces pale yellow, and shows an orange yellow phosphorescence of much longer duration than the zinc compounds.

Zinc sulphate may be substituted for cadmium sulphate in the above formula and treated in the same manner. The resultant white powder fluoresces pink and phosphoresces red.

Some "chemically pure" calcium sulphide, as sold on the market, may be found to be already an active phosphorescent compound having a brownish-red color.

#### U. S. Patent 2,270,105 No. 18

Prepare a solution A of pure sodium tungstate dissolved in distilled water in the proportions of 108 grams of sodium tungstate to 1 liter of water, prepare a substantial equivalent amount of solution B of pure cadmium sulphate dissolved in distilled water in the proportions of 154 grams of cadmium sulphate to 1 liter of water, add approximately 1% of solution A to the whole of solution B and filter off the precipitate, add to the resulting filtrate the remainder of solution A and again filter off the precipitate, then wash the latter precipitate in distilled water, dry it, and heat it at approximately 875° C. for one hour in air.

#### No. 19

(1) 40 g. barium carbonate, 6 g. sulphur, 1 g. lithium carbonate and 0.47 g. rubidium carbonate are heated at dark red heat for 1 hr., powdered and mixed with a suitable pigment. (2) 100 parts calcium carbonate and 30 parts sulphur are heated at dark red heat for 1 hr. This is then ground with alcohol to which an amount of bismuth nitrate equal to 0.0001 the weight of the melt has been added. Finally the mixture is dried in air, heated at dark red heat for 2 hrs. and allowed to cool slowly.

British Patent 525,379	
No. 20	
Cadmium Phosphate	100
Manganous Chloride	5
Magnesium Chloride	10

Mix dry and heat in a silica tube, plugged with glass wool, for 3 hours at 800° C. Cool and wash with distilled water, six times, and dry at 180° C.

Luminescent Coatings for Discharge Lamps

#### U. S. Patent 2,257,667 Formula No. 1

For the preparation of a thallium-activated composition, germanium dioxide or silicic acid is mixed with 1-2 times its quantity of a pure oxide of beryllium, magnesium, or aluminum, up to about 30% of a thallium salt is added and the mixture is heated to 800-1200° C.

#### U. S. Patent 2,255,761 No. 2

Luminescent particles can be held in a porous structure comprising aluminum oxide or magnesium oxide.

#### British Patent 530,915 No. 3

The luminescent tungstate material contains a proportion of vanadium, less than 1% but so great that the loss of luminous output during life is materially decreased by its presence.

#### French Patent 845,284

No. 4	
Zinc Oxide	60
Silicon Dioxide	40
Beryllium Oxide	2
Manganese Dioxide	4
Lithium Chloride	1
Calcina for 3 hours at 100	0-1100

C. and slake with water.

## British Patent 538,379 No. 5 Magnesium Tungstate 15 Zinc Beryllium Silicate 70 Cadmium Borate 5 Zinc Ortho Silicate 10

#### Fluorescent Paint British Patent 542,006

Chrysene together with, if desired, not more than 1/30 of its weight of naphthalene (not more than 1%) is dispersed in, e.g., an aqueous solution containing gum arabic 10%, phenol 0.2%, glycerin 3%, and Darvan (a dispersing agent) 1.5%.

#### Luminous Paint

The pigment content per gallon of finished paint should be about 4½ lb. The vehicle must be free from lead, manganese and cobalt driers. Drying qualities are attained by using a fast drier, such as benzine. No grinding of the pigment and vehicle is recommended, as it injures the light properties. The vehicle should be reasonably clear. Some oils, such as linseed, cause a jellying. Soya bean oil has been found satisfactory in a synthetic alkyd varnish.

The batch is machine mixed and allowed to stand over-night, after which it is given a short mix and placed in cans, preferably of sizes not larger than single gallons.

Calcium Sulphide Luminous Pigment is non-poisonous and non-radioactive. The paint will keep in cans over a long period. There is no chemical action to cause deterioration.

Luminous Paint is best applied

over a base coat of white paint free from lead. This is imperative when it is applied over old paint which might contain lead.

A strong afterglow of better than 12 hours can be had with a good calcium pigment. The calcium sulphide has advantages over zinc and strontium sulphide luminous paint, the most outstanding being long afterglow and freedom from discoloration when exposed to direct sunlight.

Road Markers for Night Use Fluorescent signposts (made with

fluorescent pigments) and signs can be used which are either visible or invisible in ordinary light.

Fluorescent liquids, oils, or powders dropped on the trail or road will facilitate traveling at night by automobile, tank, or other vehicles which are provided with an ultraviolet lamp.

#### Improving Life of Fluorescent Powders

German Patent 702,995

The resistance of luminescent alkaline earth sulphides to air, light, and weathering is enhanced when about 10% boric anhydride is added.

#### Television Screen U. S. Patent 2,260,924

In preparing a fluorescent screen for use in television use is made of manganese activated cadmium silicate (55), silver activated zinc sulphide (30), and manganese activated zinc silicate (15), for a screen of substantially white fluorescence having an afterglow of about 0.02 second for eliminating flicker.

•				200
Porcelain Ename Formula N		hing		
Tenex		35	2.00.020.00	N PO
Gelva (2.5)		45	6.11 6.12 6.13 6.13 6.14 6.15	-: 03
Titanium Dioxide		20	Formula No. 8 Lb. Gal. 300 8.60 200 9.10 60 7.50 40 6.15 1188 23.50 37 5.70 8 1.00	
No. 2			nla	
Gelva (2.5)		55	m.	ř.
Cumar		20	200 300 300 300 300 300 300 300 300 300	- 01
Titanium Dioxide		25		
No. 3		40		
White Rosin		40		
Carnauba Wax		20 40	2.00.00.00.000	Z 10
Titanium Dioxide	anadia.		6.1 6.1 6.1 6.1 6.1 6.1 6.1 1.0 1.0	ન, જ!
Melt first two in sift into it the titanium			N <sub>G</sub>	
	n uiox	ide. Mix	ula	
well.			rm	10
20-Gallon Floor Er	amel	Liouid	ENAMELS   Formula No. 2   Formula No. 3   Formula No. 1   Lb.     500	⊣ જો
Formula N		nquiu	7 . 23 %	
Modified Alkyd	0. 1		* "" * * * * * * * * * * * * * * * * *	
Resin	112	lb.		
100% Phenolic	3.2.2	10.	N C · · · · · · · · · · · · · · · · · ·	27.20
Resin	28	lb.	ME 1.2. 3.5. 1.5. 1.5. 1.0. 1.0. 1.0. 1.0. 1.0. 1	⊣ લ
Perilla Oil	216	lb.	Vo	
Basic Carbonate			EN	
White Lead	7	lb.	m	
Mineral Spirits	66	gal.	0 . 0 . 0 . 0 . 0 . 0 . 0 . 0 . 0 . 0 .	.55
No. 2		0	For Lb. 100	,
Modified Phenol				
Alkyd Resin No				
227	150	lb.		
Tung Oil	24	lb.		
Polymerized Lin-				
* *		••		

lb.

gal.

3¾ lb.

216

68

Floor Varnishes and Floor Enamel
Vehicles
15–20 Gallon (East India)
Batu, Pale East India
or Black East India 100 lb.
Kettle Bodied Linseed
or Dehydrated
Castor Oil 15–20 gal.

seed Oil "Z-2"

Basic Carbonate

White Lead

Mineral Spirits

Lithopone (Enamel Grade)
Titanated Lithopone
Extender (Surfex)
Kettle Bodied Linseed Oil
Falkovar 203-UD
Mineral Spirits
Thin with
Kettle Bodied Linseed Oil
Falkovar 203-UD
Falkovar SKA
66% Ester Gum Cut
Mineral Spirits
Blown Soya Bean Oil
Cobalt Naphthenate (6%)
Lead Naphthenate (24%)

Mineral Spirits to 50% non-volatile content. Driers equivalent to 0.10% Ca., 0.10% Co., and 0.20% Pb., as metals based on weight of

oil present.

Heat resin and 5 gal. of oil to 620° F., in about 1 to 1¼ hours. Hold until cold "pill" is clear. Add remainder of oil. Reheat to 580° F. Allow to cool sufficiently to add mineral spirits and driers.

Indoor Enamel Vehicles
15 Gallon Length (East India)
Batu, Pale East India
or Black East India 100 lb.
Bodied Linseed Oil or
Dehydrated Castor
Oil 15 gal.

Petroleum thinner to 50% non-volatile content by weight. Driers equivalent to 0.10% Ca., 0.10% Co., and 0.20% Pb., as metals on weight of oil.

Heat the resin and 5 gallons of oil to 600°-610° F., in about 60-65 minutes. Hold until a cold "pill" indicates complete compatibility (about 10 minutes). Add remainder of linseed oil. Heat to 580° F. Hold until a cold bead is clear (about 5-10 minutes). Allow to cool to about 400° F. Add the petroleum thinner and then the driers.

Thermally Processed
Congo
Tool b.
Kettle Bodied Linseed
or Dehydrated Castor Oil
Petroleum thinner to 50% nonvolatile by weight. Driers equivalent to 0.10% Ca., 0.10% Co., and

0.20% Pb., as metals based on the weight of oil.

Heat the Congo to 650°-670° F. in about 1½ hours. Hold until foaming subsides and the hot resin runs off the paddle similarly to hot oil. Allow to cool.

Heat the processed Congo and all of the linseed oil to 580° F. in about 1 hour. Allow to cool to 400° F. and thin. Add the driers.

Vehicle for White Enamels Batavia Dammar A/D or A/E 75 lb.

Thermally Processed

Congo 25 lb.

Kettle Bodied Linseed
or Dehydrated Castor Oil 80 lb.

V. M. & P. naphtha to 55% non-volatile. Driers equivalent to 1.0% Pb., 0.04% Co., and 0.02% Mn., as metals on weight of oil.

- (1) Prepare the Congo by processing in the usual manner (See 15 gallon Congo-General Utility Varnishes).
- (2) Heat the dammar, processed Congo and oil to 560° F. Allow to cool sufficiently to thin. When thoroughly cool, add driers.

Non-Yellowing Utility Enamel
Titanium Dioxide,
Color Retentive 288 lb.
Zinc Oxide, Fine Particle Size Reactive 48 lb.
Soya Type Modified
Alkyd (32% Phthalic
Anhydride), 65%
Mineral Spirits Solution 226 lb.
Lead Naphthenate

8 lb.

24%

	ent AND OTHER COATINGS 297
Grind on 3 roller mill and reduce paste with: Soya Type Modified Alkyd (32% Phthalic Anhydride), 65% Mineral Spirits Solution 340 lb.	Ester Gum Modified Alkyd (15% Phthalic Anhydride), 80% Mineral Spirits Solution 635 lb. Mineral Spirits 175 lb.
Mineral Spirits 114 lb. Cobalt Naphthenate	Cobalt Naphthenate 6% 4 lb. Lead Naphthenate
6% 1.25 lb.	24% 9 lb.
Non-Yellowing Super White Architectural Enamel (Easy Lapping and Non-Sagging)	Synthetic Trim and Trellis Enamel Formula No. 1 Brown
Titanium Dioxide, Color Retentive 288 lb. Zinc Palmitate 4 lb.	Aluminum Stearate 1 lb. Linseed Oil Type Modified (29% Phthalic
Zinc Oxide, Fine Par- ticle Size Reactive 32 lb.	Anhydride), 70% Mineral Spirits Solu-
Soya Type Alkyd (29% Phthalic Anhydride), 85% Mineral Spirits Solution 288 lb.	tion 113 lb. Iron Oxide, Brown 200 lb. Mineral Spirits 52 lb.
Solution 288 lb. Lead Naphthenate 24% 3 lb.	Lead Naphthenate  24%  5 lb.  Grind fine and thin paste with:
Mix, grind and thin paste as follows:	Linseed Oil Type Modi- fied (29% Phthalic
Soya Type Alkyd (35% Phthalic Anhydride),	Anhydride), 70% Mineral Spirits Solu-
50% Mineral Spirits Solution 147 lb.	tion 402 lb. Linseed Oil, Raw 42 lb.
Soya Type Alkyd (29% Phthalic Anhydride),	Mineral Spirits 149 lb. Cobalt Naphthenate
85% Mineral Spirits Solution 75 lb.	6% 2 lb. No. 2
Mineral Spirits 159 lb. Cobalt Naphthenate 6% 3 lb.	Green Green, Medium Chrome 200 lb. Zinc Oxide 10 lb.
Lead Naphthenate 24% 6 lb.	Linseed Oil Type Modi- fied (29% Phthalic
Tint as desired.	Anhydride), 70% Mineral Spirits Solu-
Low Cost Synthetic White Enamel Titanium Dioxide	tion 404 lb. Grind and thin paste as follows:
(Calcium Base) 800 lb. Surfex 200 lb.	Linseed Oil Type Modified (29% Phthalic

Anhydride), 70% Mineral Spirits	,	Ferrous Resinate 0.45 Cobalt Acetate 0.25
Solution	336 lb.	Zinc Resinate 1.00
Linseed Oil, Raw Petroleum Naphtha Heavy	180 lb. 184 lb.	MILITARY ENAMEL PIGMENTS
Cobalt Naphthenat		Lusterless Orange Enamel
6% (Anti-skinning ager	2.5 lb.	Medium Chrome Orange 42 Yellow Iron Oxide 8
is optional)		Extenders 50
Guaiacol, Not over	1.2 lb.	Lusterless Red Enamel
M W.II		Red Oxide, Bright
Non-Yellowing Syn Enamel	thetic Flat	Synthetic 50 Extenders 50
Nuad L	3 lb.	Extenders 50
Multifex Pulp	50 lb.	Lusterless Umber Enamel
Lithopone, Titanate Titanium Dioxide	200 lb.	Yellow Iron Oxide 8 Lamp Black 2
Surfex	450 lb.	Red Iron Oxide 13
Celite 165 S	50 lb.	Extenders 77
Castor Oil "Z" Bod Dehydrated	y, 17 gal.	Lusterless White Enamel
Petroleum Naphtha	,	Rutile Titanium Dioxide 30
Heavy	20 gal.	Extenders 70
Soya Type Alkyd (32% Phthalic		Lusterless Yellow Enamel
Anhydride), 65%		Chrome Yellow 25
Mineral Spirits Solution	13 gal.	Medium Chrome Orange 5 Yellow Iron Oxide 3
Mineral Spirits	10 gal.	Extenders 67
Grind and then add	l:	Gloss Blue Enamel
Mineral Spirits Cobalt Naphthenate	6 gal.	Prussian Blue 50
6%	1/4 gal.	Rutile Titanium Dioxide 45
Lead Naphthenate	1/ 1	Tinting Pigments 5
24%	$\frac{1}{2}$ gal.	Gloss Dark Green Enamel
Insulating En	amel	Chrome Green 100
U. S. Patent 2,2		Gloss Gray Enamel
Rosin	50.00	Rutile Titanium Dioxide 95
Alkyd Resin Perilla Oil	150.00 205.50	Tinting Pigments 5
Fish Oil	15.00	Gloss Mustard Yellow Enamel
Chinawood Oil	73.50	Chrome Yellow 75
Manganese Resinate	e <b>0.3</b> 0	Yellow Iron Oxide 25

Gloss Olive Drab Enamel Yellow Iron Oxide 7 Lamp Black 7 Rutile Titanium Dioxide 18 Chrome Yellow 68	Lusterless Brown Enamel Yellow Iron Oxide 16 Red Iron Oxide 4 Lamp Black 1 Extenders 79
Gloss Red Enamel Toluidine Toner 100 Gloss White Enamel Rutile Titanium Dioxide 100 Gloss Yellow Enamel Chrome Yellow 90 Medium Chrome Orange 10 Semi-Gloss Black Enamel Carbon Black 5	Lusterless Coronado Tan Enamel Yellow Iron Oxide 17 Rutile Titanium Dioxide 7 Bone Black 2 Red Iron Oxide 2 Extenders 72  Lusterless Desert Drab Enamel Yellow Iron Oxide 16.0 Rutile Titanium Dioxide 2.5 Chrome Yellow 2.0
Extenders 95  Semi-Gloss Olive Drab Enamel Yellow Iron Oxide 19 Chrome Yellow 11 Lamp Black 3 Extenders 67	Lamp Black 0.5 Extenders 79.0  Lusterless Earth Drab Enamel Yellow Iron Oxide 15 Carbon Black 5 Red Iron Oxide 5
Infra-Red Paint Enamel Pigment Ferrite Yellow-Orange 14.8 Copper Phthalocyanine Blue 1.0 Red Iron Oxide (Medium Shade) 3.5 Chrome Yellow, Medium 0.7 Diatomaceous Silica 8.0 Asbestine 72.0	Extenders 75  Lusterless Gray Enamel Rutile Titanium Dioxide 20–27 Tinting Pigments 5 Extenders 78  Lusterless Green Enamel Chrome Green 18
Lusterless Blue Enamel Prussian Blue 8 Rutile Titanium Dioxide 5 Extenders 87 Lusterless Blue Drab Enamel	Yellow Iron Oxide 9 Lamp Black 1 Extenders 72  Lusterless Maroon Enamel Indian Red 50 Extenders 50
Copper Phthalocyanine Blue 0.5– 3.0 Rutile Titanium Dioxide 10 –21 Tinting Pigments as required Extenders 80	Lusterless Olive Drab Enamel Yellow Iron Oxide 18 Chrome Yellow 7 Lamp Black 3 Extenders 72

Lusterless Olive Drab Enamel, Infra Red Reflectant Antimony Sulphide Black 20.0 Chrome Yellow, Light 8.6 Ferrite Yellow 114 Asbestine 60.0

White Undercoats for Wood and Walls Indoors Formula No. 1 Pale East India Vehicle Pale East India Nubs 80 lb. (Macassar-Hiroe) Coal Tar Thinner, or high solvency Petroleum Naphtha or combination of either with low solvency Petroleum Naphtha 80 lb. Zinc Oxide 40 lb. Titanium Barium Pigment 200 lb. Asbestine 20 lb.

Dissolve the Pale East India in the coal tar thinner, using agitation but no heat. Strain out the undissolved material or allow it to settle. Grind the pigments in a portion of the vehicle thus prepared. Add the remainder of the vehicle.

Plasticizers may be used if desired. Linseed oil is preferred but other oils may be employed.

> No. 2 Manila Vehicle

Manila 60 lb. Denatured Alcohol or mixture of 50 lb. Denatured Alcohol and 10 lb. Petroleum Naphtha 60 lb. Titanium Dioxide 260 lb. Diatomaceous Earth 20 lb. Dissolve the Manila in the denatured alcohol, using agitation but no heat. Strain out undissolved matter or allow to settle.

Grind the pigments in a portion of the above vehicle. Add the remainder of the vehicle.

Add butanol to proper brushing consistency or more denatured alcohol for spraying consistency.

Plasticizers such as castor oil may be used if desired.

Gloss Enamel Formula No. 1 (Quick Drving) Pigment (38%)Cryptone BT-802 or 366 412.75 lb. 0.32 lb. Ultramarine Blue Vehicle (62%) Beckosol No. 1319 Sol. 64.5 gal. Boiled Linseed Oil 2.5 gal. Mineral Spirits 10.0 gal. Amsco, No. 460 Solvent 9.2 gal. Cobalt Naphthenate 6%0.5 gal. Zinc Naphthenate 8% 1.7 gal. No. 2

> (Slow Drying) Pigment (53.8%)

Albalith Blue Label-10 598 lb. XX-55 Zinc Oxide 106 lb. Ultramarine Blue 0.25 lb. Vehicle (46.2%)

Kettle Bodied Linseed Oil "Z body"

23.60 gal. Refined Linseed Oil 8.04 gal. Water 0.71 gal.

Mineral Spirits 26.74 gal. 10-Lb. Cut Low Acid

Ester Gum 11.71 gal. N-Glo-5Y (Gloss Oil, Limed)

9.14 gal.

Naphthenate Drier	
24% Pb	0.65 gal.
Naphthenate Drier	
6% Co	0.42 gal.

Calcimine Coater
Formula No. 1
Pigment (67%)
Albalith 351, 361, or 362
Whiting
Vehicle (33%)
Lived Livesed Vehicle \*\*

Limed Linseed Vehicle \*
(40% Non-volatile) 365
Kerosene 96
Water † 24

The entire vehicle is put into the mixer and the pigment is added gradually. The resulting paste is ground on a roller mill using a loose setting, or on a buhrstone mill. The finished product, after aging overnight, is heavy in body and will take a reduction of about three pints of mineral spirits per gallon for application.

No. 2
Calcimine Coater Liquid
Linseed Oil (Z-3body)
20 $\frac{1}{2}$  gal.
Lime
4 $\frac{3}{4}$  lb.
Mineral Spirits
36 gal.

Directions
Heat linseed oil to 575° F. (302°
C.) in about one hour. Hold be-

\*The vehicle is typical of the limed liquids on the market or prepared by paint manufacturers. They may contain linseed, perilla, fish, soya or combinations of oils and vary considerably in body producing properties. Some of these vehicles have normal acid number, others are neutral, and some alkaline. Some are free-flowing while others are gel-like. With some vehicles it may be necessary to include drier in the formulation.

†Some vehicles are too sensitive to water and in that case water should be replaced by kerosene or mineral spirits.

tween 575° F. and 585° F. (307° C.) until a very heavy string on a cold glass is obtained. This requires about 34 to 114 hours. Allow to cool to 300° F. (149° C.) and slowly add the lime which has previously been mixed to a smooth paste in about 1½ gal. of the Z-3 linseed oil. Mix in thoroughly and allow the lime to react. During reaction keep the temperature of the batch between 300° F. (149° C.) and 400° F. (204° C.).

When the reaction is completed, a dry pill on the glass is obtained. This requires about three quarters to one hour. Thin, adding the thinner slowly and in small quantities. It is important to incorporate the first few gallons of thinner very thoroughly. This will facilitate the incorporation of subsequent portions of thinner and ensure a vehicle free of lumps.

The temperature of liming is the governing factor in preparing vehicles of this type. At a temperature of 300° F. a gel-like varnish is obtained which has excellent nonpenetration properties but is difficult to handle and is liable to produce progressive bodying in the paint. Liming at a temperature of 400° F., decreases the non-penetrating properties but at the same time reduces handling and after-bodying difficulties.

Best results are obtained when the vehicle manufacturer blends several kettles of vehicle which have been limed at different temperatures and this procedure is recommended. The blend should be made so as to obtain the desired degree of non-penetration and yet produce a material which handles easily and will not produce after-bodying.

#### Automobile Finishing Enamel

Non-Vol	latile	Volatile	
Cryptone ZS-30	70	Ethyl Acetate	15
Titanium Dioxide	e 15	Butyl Acetate	20
Flor. Green Seal-	Zinc	Butanol	12
Oxide	15	Amyl Acetate	5
½ Sec. R. S. Cot	ton	Toluol	43
(Wet)	24	Zylol	5
Glyptal No. 2471	(As		
rosin)	24		
Dibutyl Phthalat	e 13		
	Non-Volatile	39%	
	Volatile	61%	

For application by spraying, thin 10 parts enamel to 6 parts volatile solvent mixture.

#### Primer

Iron Oxide	34%	Thinned 60-40 by weigh	nt with
Glyptal No. 2462 Solvent Naphtha	61% 5%	Mineral Spirits Solvent Naphtha	65%
Solveno Ivapitona	370	Turpentine	25% $10%$

#### Surfacer

40% Paste		60% Base Solution		
XX-50 Zinc Oxide	55.0%	7–10 Sec. Cotton (Wet)	4.5%	
Silica	14.0%	½ Sec. Cotton (Wet)	16.5%	
Ester Gum (Acid No.	·	Ethyl Acetate	20.0%	
6–8)	8.0%	Butyl Acetate	16.0%	
Lindol X	19.0%	Denatured Alcohol	8.0%	
Horcosol "5"	3.5%	Butanol	4.0%	
AA Black (Lampblack)	0.5%	Toluol	41.0%	

Semigloss Ename		ele
(Varnish) (V-	-255)	
Kettle Bodied "Q"		
Linseed Oil	100	gal.
Dehydrol (Dehy-		Ţ.
drated Castor Oil)	100	gal.
Aluminum Stearate	3	lb.
Fused Pb Resinate		
(16%)	211/4	lb.
Fused Co Resinate		
$(3\frac{1}{2}\%)$	9	lb.
Mineral Spirits	185	gal.

Heat the Dehydrol to 282° C. (540° F.). Allow to climb to 296° C. (565° F.) and hold at this temperature for a half inch string from the hot paddle. Add the "Q" oil and regain 296° C. (565° F.). Hold for ten minutes to ensure complete incorporation, cool to 288° C. (550° F.) and add the driers; allow to cool to 232° C. (450° F.) and add to aluminum stearate; cool and thin.

Semigloss Ena	mel	
Cryptone BA-19 8	380	lb.
Varnish V-255	$57\frac{1}{2}$	gal.
Aluminum Stearate		
Gel (6 oz. cut in		
Mineral Spirits)	$11\frac{1}{8}$	
Mineral Spirits	5%	gal.
Lead Naphthenate		
(24% Pb)	3∕8	gal.
Cobalt Naphthenate		
(6% Co)	1/8	gal.

This vehicle combination produces a semigloss possessing a high sheen. The sheen can be reduced by increasing the quantity of aluminum stearate gel and decreasing the mineral spirits. Example:—18% aluminum stearate gel and 2.5% mineral spirits result in a semigloss with a moderate to low sheen.

Prepare paste using all the pigment, aluminum stearate gel and approximately 37 gallons V-255, grind on roller or buhrstone mill and reduce with remaining vehicle. It is essential to include the aluminum stearate gel in the grind.

#### Preparations of Aqueous Shellac Solutions

It is possible to prepare solutions of shellac which are substantially water reducible. The method comprises primarily dissolving 100 g. shellac in 100 g. 74° O.P. methylated spirit and then adding to this solution 15-18 cc. of an ammoniacal solution (prepared by adding 1 part 0.880 ammonia to 2 parts water) with constant stirring. The resulting solution can then be thinned with water, and the films obtained from such solutions are moderately clear, glossy and fairly flexible if plasticized, for example with dimethyl-glycol phthalate.

Water Glass Paints, Aging

A very suitable mixture of this type which greatly shortens the second drying or aging period of water glass paint films consists of equal parts of water and sodium water glass (5 parts altogether) and 1 part of calcium hydrate or slaked special lime. Good results are also obtained with a lime mixture consisting of 5 parts of lean (blue) milk and 1 part of calcium hydrate. The underground must be air dry but still fresh since this promotes the aging of the film considerably.

Water Paint for Wood and Plaster U. S. Patent 2,226,030

U. S. Patent 2,226,	030
Blackstrap Molasses	3
Glue	3
Whiting	18
Hydrated Lime	24
Soapstone	5
Formaldehyde	1/2
Add water to use.	

Water Paint for Stone, Brick or Cement

#### U. S. Patent 2,246,620

White Cement	58.8
White Finishing Lime	17.8
Beach Sand	9.4
Zinc Sulphate	1.6
Calcium Chloride	10.0
Glue	0.4
Terpineol	0.4
Salt	1.6

#### Water Paint

water raint	
Canadian Patent 39	8,356
Zinc Oxide	4
Lithopone	10
Barium Carbonate	15
Whiting	18
Silica	5
Pyrophyllite	12
Mica, Silver	3

China Clay Litharge Casein Potassium Carbonate Mercuric Chloride	8 3 9 1 ½
Interior Emulsion Paints Resin Oil Emulsion	
Solution "A"	
Resin	62
Bodied Linseed Oil	50
Pine Oil	21
Mineral Spirits	62
Cobalt Linoleate Drier	
(6% Co.)	$1\frac{1}{4}$
Lead Linoleate Drier	
(16% Pb.)	$4\frac{1}{4}$
Oleic Acid	24
Solution "B"	
Powdered Casein	27
Preservative	3/8
2 Amino-2 Methyl-1	
Propanol	15
Water	536

Mix the resin, cut in the mineral spirits, with the bodied linseed oil, pine oil, driers, and oleic acid.

Place the case in in mixer, add the water slowly, stirring so that case in is wetted, add the preservative and emulsifier and continue stirring for several minutes.

Add Solution "A" slowly to Solution "B" with constant high speed agitation until emulsification is complete.

The emulsion contains six types of ingredients listed according to their functions:

- (1) Organic binders (resin, oil, casein)
- (2) Emulsifier (2 Amino-2 Methyl-1 Propanol plus oleic acid)
- (3) Wetting and dispersing agent (pine oil)

- (4) Metallic driers
- (5) Preservative (Moldex)
- (6) Water

The functions of 1, 4, 5 and 6 are obvious.

Pine oil acts as a pigment dispersing agent and aids in the emulsification and, incidentally, tends to prevent frothing and improve brushing.

The casein has a dual role, serving both as a binder and to improve the drying properties of the paint. As far as our own work has gone we have found a percentage of casein is a valuable constituent of resinoil emulsion paint.

The emulsifier is the critical ingredient upon which depends the success of the emulsion and the resulting paint. After the oil phase is broken up into tiny droplets the emulsifier becomes adsorbed on the surface of the oil droplets, forming a protective layer that prevents them from coalescing and breaking the emulsion. It must provide sufficient stability to the emulsion so that it will withstand grinding in of the pigment, and preserve original consistency in the can under unfavorable storage conditions. The protective layer around the oil phase must also resist rupture under the stress of brushing, and must above all allow the release of the water at the proper time so that a coherent paint film is deposited. It must also be present in low concentration so as not to interfere with drying or subsequent washability of the paint.

With the emulsion stabilized, it is simply a matter of mixing and grinding in the proper pigment (Albalith, Cryptone BA or Zinc Sulphide) into the emulsion on a stone or roller mill, using a loose setting. Illustrative semi-paste paint formulae are:

Semi-Paste Paints Formula No. 1	
Albalith-335, 332 or 836 *	790
Resin Oil Emulsion	622
No. 2	
Cryptone ZS-830	376
China Clay	230
Rosin Oil Emulsion	625

These semi-pastes are designed to be thinned 2–1 with water for brush application. The paints brush easily over porous or well sealed surfaces, hide well, are flat and reasonably washable as are the average flat wall paints on the market. The emulsions, if properly made, are stable with these pigments, but so far as this work has progressed, this cannot be said of calcium sulphate base pigments, since their solubility tends to break the emulsion.

The illustrative formulae of the emulsion and semi-pastes given here can be modified in many ways, but in making substitutions, or if the percentages of the ingredients are changed, the new system must be balanced or the breaking of the emulsion may follow.

Ester Gum-Oil Emulsion (V-344) Solution "A"

High Acid Ester Gum (Acid #18–20) 83 $\frac{1}{2}$ Mineral Spirits 83 $\frac{1}{2}$ Kettle Bodied Linseed Oil (Z 4–6) 65 $\frac{5}{2}$ 

Pine Oil	$27\frac{1}{2}$
Cobalt Linoleate Drier	
(6% Co.)	$1\frac{5}{8}$
Lead Linoleate Drier	
(16% Pb.)	$5\frac{5}{8}$
Oleic Acid	313/4
Solution "B"	-
Casein B-5	$36\frac{1}{2}$
Moldex	7/8
Ammonia (28–29%)	$20\frac{1}{8}$
Water	453
PP-17	

The ester gum, bodied linseed oil, and mineral spirits may be amalgamated by either cooking the gum and oil and thinning with mineral spirits, or by cold cutting the gum in mineral spirits and mixing in the oil. To the varnish thus prepared add driers and oleic acid.

Place the case in in a pony or other type mixer, add the water slowly, stirring so that the case in is wetted, add the preservative and the ammonia solution and continue stirring for several minutes.

Add Solution "A" slowly to Solution "B" with constant agitation until emulsification is complete.

#### Ester Gum-Oil Emulsion Semi-Paste

Interior

Albalith–836 1150 Ester Gum-Oil Emulsion V-344 540

The pigment and emulsion should be mixed together and milled on a roller mill or a buhrstone mill at a loose setting.

Reduction for brush application—two volumes of paste with one volume of water.

Note: In making tints, the tinting colors should be mixed or ground into the paste with the white

<sup>\*</sup>Cryptone BA-40 can be substituted for the Albalith if greater hiding power is required.

pigments. Less white hiding pigment will be required than in the white formula. Colors that are not affected by alkalies should be used since the paint must be kept on the alkaline side.

Ester Gum-Oil Emuls	sion
Semi-Paste	
Interior	
Albalith=332	915
Ester Gum-Oil Emulsion	
V-344	432
Water	176

The pigment, emulsion and the water should be mixed together and milled on a roller mill or a buhrstone mill at a loose setting.

Reduction for brush application—two volumes of paste with one volume of water.

Ester Gum-Oil Emulsi	on
Semi-Paste	
Interior	
Pigment (60%)	
Cryptone ZS-830	639
China Clay	213
Vehicle (40%)	
Ester Gum-Oil Emulsion	
V-344	477
Water	91
/Di 1 1 1 1	7 ,

The pigment, emulsion and water should be mixed together and milled on a roller mill or a buhrstone mill at a loose setting.

Reduction for brush application—two volumes of paste with one volume of water.

"Aquaplex" Resin Emulsion Semi-Paste Interior Formula No. 1 Pigment (58.1%)

Albalith-836, 335 or	
332 *	25
Vehicle (41.9%)	
Aquaplex AM-92 †	36
Casein Solution V-242	
or $V-243$	14
Pine Oil	4
Water	21
erri i i i	

The Aquaplex, casein solution, pine oil and water are mixed together and used as a combined vehicle. The desired quantity of combined vehicle is placed in a pony or dough mixer, and the pigment is gradually added with the mixer running. Continue mixing until a smooth paste is obtained.

A mixture of two parts of paste to one part of water by volume will be suitable for brush application on most surfaces.

No. 2	
Pigment~(56%)	
Cryptone ZS-830	16
Whiting	11.3
Vehicle (44%)	
Aquaplex AM-92 ‡	39.4
Casein Solution V-242	
or V-243	15.3
Pine Oil	5.8
Water	12.2

\*If Albalith-332 is used the resulting paste may be too heavy. If so, 2% less pigment and up to approximately 2% more water may be added without affecting the reduction properties for brush application.

† Aquaplex S-6 may be substituted for Aquaplex AM-92 if desired. The resulting paint will be slightly thinner in body and will become resistant to washing

more rapidly.

‡ Aquaplex S-6 may be substituted for Aquaplex AM-92 if desired. The resulting paint will be slightly thinner in body and will become resistant to washing more rapidly.

Mix and use as for No. 1.

Casein Solution (V-242)

For Use in Cold Water Paints U. S. Patent 1.893,608

Casein B-5	137.2
Borax	15.0
Sodium Fluoride	12.2
Ammonium Chloride	4.7
Pine Oil	14.0
Moldex	0.9
Water	751.0

The casein, sodium fluoride and ammonium chloride are heated at 168° F. with moderate stirring in about 75 gallons of water for about two hours. The borax dissolved in the remaining water (15.12 gallons) is then added and heating continued with rather vigorous stirring for 1½ hours. The pine oil and preservative are added and the solution allowed to cool.

Casein Solution (V-243)

For Use in Cold Water Paints Powdered Casein

B-5	147
Water	660
Borax	22
Pine Oil	$14\frac{1}{2}$
Moldex	1

The borax is put in solution by heating with about 10% of the water. The casein is soaked at 160–170° F. with moderate stirring for 1½–2 hours in the remainder of the water. The borax solution is then added to the soaped casein and heating is continued at 160–170° F. with more vigorous stirring for 1½ hours. The pine oil and preservative are then added and the solution cooled. Any water lost should be added to bring the volatile content up to 80%.

Casein B-5 29<sup>1</sup>/<sub>4</sub>
Moldex 3/<sub>8</sub>
2 Amino-2 Methyl-1

Propanol  $16\frac{1}{4}$  Water  $513\frac{1}{2}$ 

Dissolve the Piccolyte resin in the mineral spirits and mix with the lithographic oil #8, pine oil, driers, and oleic acid.

Place the casein and preservative in a pony or other type mixer, add the water slowly, stirring so that casein and preservative are wetted, add the 2 Amino-2 Methyl-1 Propanol, and continue the stirring for several minutes.

Add Solution "A" slowly to Solution "B" with constant agitation until emulsification is complete.

"Piccolyte" Oil Emulsion
(Semi-Paste)
Interior
Formula No. 1
Pigment (60.8%)
Albalith-836, 335 or 332 932
Vehicle (39.2%)
Piccolyte Emulsion
V-338 559
Water 42
The pigment, emulsion and water

should be mixed together and then

milled on a roller or a buhrstone mill at a loose setting.

Reduction for brush application—two volumes of paste with one volume of water.

"Piccolyte" Oil Emulsion (Semi-Paste) Interior No. 2

Pigment (54.5%) Cryptone ZS-830

Cryptone ZS-830 446 China Clay 274 Vehicle (45.5%)

Piccolyte Emulsion

V-338 559 Water 42

The pigment, emulsion and water should be mixed together and then milled on a roller or buhrstone mill at a loose setting.

Reduction for brush application

—two volumes of paste with one volume of water.

"Piccolyte" Oil Emulsion
Semi-Paste
Interior
Buff
No. 3
Pigment (60.7%)
Albalith-836 or 335
Yellow Iron Oxide
35

Piccolyte Emulsion V-338 559 Water 42

Vehicle (39.3%)

"Piccolyte" Oil Emulsion
Semi-Paste

No. 4
Cryptone BA-40 962 lb.
Piccolyte Emulsion
V-338 588 lb.

Resin Base Water Paint U. S. Patent 2,250,346

II C Dotont 9 250 246		
U. S. Patent 2,250,346	1b.	oz.
Triple Washed Calcium Carbonate	10 -25	
Fibrous Asbestine	8 –15	
Cold Water Glue	-	3-5
Domestic China Clay (Extra Fine)	5 -20	
Powdered Casein (Nitrogen Factor 7.07)	$2 - 3\frac{1}{2}$	-
Fine Steamed Mica (1,000 Mesh)	$\frac{1}{2}$ 7	
Zine Sulphide	20 - 40	_
Talc	1 - 7	
Alkyd Resin Solution	3 - 8	
Phenol	distinguish.	$3\frac{3}{4}-4\frac{1}{2}$
Borax (Powdered)		4-12
Neutral Soap (Flaked)		2-6
Common Laundry Starch	-	1-5
Tallow	$1\frac{1}{2}-2\frac{1}{2}$	
Lead Naphthenate Soap	<del>-</del>	1-4
Glycerin		0-8
Pine Oil		0-8
Sassafras Oil	-	0-16
100 Mesh Casein (Nitrogen factor 7.07)	13/4-4	-
Water	$\frac{1}{2}$ 3	
Powdered Gelatin	$\frac{3}{4} - 1\frac{1}{2}$	

Paint Oil
Limed Rosin Oiticica Oil
255 g. Heat to 550° F. in
45 mins.
Varnish Makers
815 g. Held 1¼ hrs. for body
Add
Linseed Stand-oil
320 g. Heat to 550° F. cool
and
Reduce with
Mineral Spirits
1040 g.

Coating Glass with Luminescents British Patent 530,531 Luminescent Powder 250 g. Ethyl Acetate 250 cc. Grind together for 24 hours and dilute with: Ethvl Acetate 250 cc. Methyl Methacrylate 200 cc. (40% Sol.) Shake for 1 hour and add: Camphor Apply to glass and heat slowly up to 400-450° C. in a current of air.

Frosting Glass
Sandarac Resin 7
Denatured Alcohol 31
Toluol 47
Xylol 15

Dissolve sandarac resin in the denatured alcohol by heating, then add the toluol and xylol gradually while the solution is still warm.

The solution is quite stable and can be stored indefinitely without the resin separating. The following application procedure has given best results:

The glass to be coated is thoroughly cleaned, then washed with

denatured alcohol and rubbed dry with a clean cloth. The frosting solution is diluted with approximately 5% by volume of either toluol or xylol and sprayed on the glass. Two spray coats, one with a vertical and the other with a horizontal stroke, should be applied. Using a small touch-up suction type spray gun, good results can be obtained by using 25 to 30 pounds pressure and holding the gun approximately 18 inches from the glass. Areas not to be frosted and the window frames may be masked with Scotch masking tape.

Glass Masking Coat for Spray Painting

ramung	
Kaolin	2.0
Glycerin	1.5
Water	4.5
Butyl Alcohol	0.25

Mix the above ingredients thoroughly. Apply to the glass with a brush and allow to dry. After painting with a spray gun, and allowing the paint to dry, the mask may be removed with a putty knife, a cloth or by washing with water, leaving the glass free of any paint.

This masking mixture can also be used to protect metal and similar surfaces during spray or brush painting.

Coating for Phonograph Records U. S. Patent 2,203,983

16.0
3.0
1.5
1.5
78.0

Air Filter Fiber Co		monium ferric oxalate 10,	
U. S. Patent 2,112		nium meta vanadate 5, t	
White Oil (Mineral)	23.0	dioxide 15, manganous sulp	
Water	36.5	magnesium sulphate 5, an	d water
Calcium Chloride	36.5	200 parts.	
Bentonite	4.0		
		Synthetic Transparent Fo	oils or
Electric Cable Co.		Coatings	
U. S. Patent 2,216		U. S. Patent 2,255,56	34
Rosin	25-75%	Formula No. 1	
Rosin Oil	20-50%	"Pliolite"	10
Polymerized Isobuty-		Chlorinated Diphenyl	$2\frac{1}{2}$
lene	5 – 25%	Naphtha	$87\frac{1}{2}$
		No. 2	
Electrical Cable She	athing	"Pliolite" or "Plioform"	10
Benzyl Cellulose	100	Paraffin Wax	2
Tritolyl Phosphate	36	Cumarone	$2^{-1}$
Kaolin, To suit		Naphtha	43
		Benzene	43
Decalcomania, "Cello	phane"	No. 3	
U. S. Patent 2,228		"Pliolite"	5
"Cellophane" or cellule	ose acetate	Dammar	7.5
transfers are made by coa		Petrolatum	1
Ester Gum	4	Benzene	86.5
Linseed Oil Varnish	8	Manager of the control of the contro	
Carbon Black	4	Painting Damp Surface	es
Carnauba Wax	1	The surface is prepared for	or paint-
		ing by removing the loose pa	
Transfer Coating ("I	Decal")	scale by wire brushing and	
U. S. Patent 2,228		ing. The dirt and excess r	
Ester Gum	4	are then wiped off the surf	

8

4

1

2

Transfer Foil Swiss Patent 211,932

Orange Toner (Optional)

Linseed Varnish

Carbon Black

Carnauba Wax

Flour starch 14, gallic acid 24, tannic acid 13, glycerol 39, tragacanth gum 1, carnauba wax 45, white wax 20, and paraffin wax 30 parts, is applied on paper. This paper is used with a paper treated with an aqueous solution of cane sugar 45, ammonium ferrous sulphate 40, am-

intandapure are then wiped off the surface and a liberal coating of turpentine is applied.

The turpentine has a two-fold effect: first, to replace the water remaining on the surface, by virtue of its preferential wetting property, and second, to "lift" any loose rust scale remaining on the surface after the mechanical cleaning. A primer coat of standard zinc dust-zinc oxide paint is then applied directly on the turpentine wet surface, thus providing the necessary rust inhibitive coating. In actual practice, a considerable interval may be allowed between the application of the turpentine and the primer, since the turpentine prevents further condensation of water on the steel.

Brush application of the primer is preferred to spray application, since it insures the intimate contact of the zinc dust with the surface. An 80:20 zinc dust-zinc oxide formula with a linseed oil vehicle has been used, but a synthetic vehicle, such as a phenolic, may be preferable, first, because of the more rapid drying of the synthetic resin formulation, and second, because of the improved water resistance of the film.

The usual drying interval is allowed after which the finish coat paint is applied. Just before the application of the second coat, the moist surface is again wiped with turpentine, but care must be taken to avoid an excess of the turpentine, since it might soften the surface of the primer.

Either an 80:20 zinc dust-zinc oxide paint or other suitable metal paint may be used as the finish coat. Colored zinc dust paints are available for finishing coats where a distinctive color scheme is desired.

It has been found that kerosene may be substituted for turpentine to replace moisture on the pipes, but its action is much slower and its assimilation into the paint less positive

Bodying Varnish (V-2	14)
Ester Gum (Acid	
No., 18)	200
China Wood Oil	950
Linseed "Q" Body	320
Lead Acetate	20
Mineral Spirits	1300
Heat gum, chinawood oil,	and 71/

gallons of the bodied linseed oil to 565° F. (296° C.). Hold until sign of string \* and chill with the balance of linseed oil. Add the powdered lead acetate on the down heat, cool to 400° F. (204° C.) and thin.

This varnish is used in minor quantities in connection with vehicles of low acid number to body lithopone flat wall paints. Paints containing bodying varnish may be increased in body by

(a) Increasing the per cent of the bodying varnish at the expense of the regular binder.

(b) Using a low acid number vehicle.

(c) Including a small amount of Zinc Oxide.

(d) Using a high consistency Albalith like Albalith-362.

(e) Using a "400 Series" pigment (Albalith-404, 424, Cryptone BA-435, Cryptone BT-445, 447).

## Varnish (V-172) (Metal Primer Vehicle)

(THE COMP I TOTALL A CINECI	,	
Bakelite XR-1329	100.00	
Chinawood Oil	391.00	
Lead Acetate	4.00	
Mineral Spirits	341.00	
Lead Naphthenate	5.75	
Manganese Naphthenate	1.00	
Cobalt Naphthenate	2.00	

Heat all the resin and one-half of the oil to 540-550° F., chill back with the balance of the oil and the lead acetate, and hold at 450° F. for a six inch string from cold glass. These cooking directions may be modified to suit plant conditions. Reduce with mineral spirits and add

\*To increase the stability of this varnish and prevent gelling in the can, it may be necessary to reduce the bodying time somewhat or alter the tung oil-linseed oil ratio slightly.

soluble drier: 14½ oz. of lead, 1¼ oz. of cobalt, and 5% oz. of manganese as metal.

This vehicle is not exceptionally fast drying, requiring from six to eight hours. It makes an excellent vehicle for all types of metal primers and finishing coats where color is not a factor. If properly cooked, this vehicle is not reactive with basic pigments.

Varnish (V-173)
(Metal Priming and Finishing
Paint Vehicle)
Glyptal No. 2455
Solution 412½ lb.

Raw Linseed Oil 112½ lb.
Mineral Spirits 32½ gal.
Naphthenate Lead

Drier

Naphthenate Cobalt
Drier 3 lb.

lb.

Naphthenate Man-

ganese Drier  $1\frac{1}{2}$  lb.

The above vehicle may be made by thinning the Glyptal solution with the mineral spirits, then adding the linseed oil and driers. If it is desired to prepare a paste with this vehicle, the linseed oil and part of the Glyptal solution may be used as the grinding vehicle and the paste reduced with the remainder of the vehicle.

Four-Hour Floor Varnish
Pentaerythritol
Abietate 166 lb.
Over-Poly. Linseed
Oil "ZZZ" \* 368 lb.
Litharge 4 lb.
V.M. Linseed Oil \* 4 lb.
Mineral Spirits 98½ gal.

1/2% Soln. Guaiacol in Dipentene	$3\frac{1}{2}$	gal.
Manganese Naph- thenate 6% Cobalt Drier 4%	4	lb. lb.
31-Gallon Varnish and Over-Poly. Linseed	d Ve	hicle

O TOL L OLJ . LILLINGOUG		
Oil "ZZZ" *	368	lb.
Pentaerythritol		
Abietate	166	lb.
Litharge	4	lb.
V.M. Linseed Oil *	4	lb.
½% Soln. Guaiacol		
in Dipentene	$3\frac{1}{2}$	gal.
Mineral Spirits	$98\frac{1}{2}$	gal.
Manganese Naph-		
thenate 6%	4	lb.
Cobalt Drier 4%	1	lb.

25-30-Gallon General Purpose Mixing Varnish and Vehicle Formula No. 1

Mild Mod. Phen.
Resin No. 78A
227 lb.
Hydrated Lime
5 lb.
Tung Oil
303 lb.
Poly. Linseed Oil

"Q" 32 lb.
Poly. Soy Oil "J" 117 lb.
Litharge 6½ lb.
Cobalt Resinate,

Fused 4½ lb.
Manganese Resinate,

Fused 2½ lb.
Kerosene 11 gal.
½% Soln. Guaiacol

in Dipentene 19 gal. Mineral Spirits,

To make 126 gal.

Mod. Alkyd Resin No. 225 226 lb. Hydrated Lime 10 lb.

Over-Poly. Linseed Oil "ZZZ" \*

120 lb.

<sup>\*</sup>From minimum 190 iodine number V. M. oil.

Poly. Linseed Oil		
"X" *	344	b.
Zinc Naphthenate		
10%	8 ]	b.
Lead Naphthenate		
24%	24 ]	b.
Manganese Naph-		
thenate $6\%$	5 ]	b.
Cobalt Drier 4%	16 l	b.
Kerosene	4 8	gal.
Mineral Spirits,		
To make	$142$ $\S$	gal.

Floor Varnish and Floor Enamel Vehicle: High Adhesion Primer and Primer Vehicle, 20-Gallon Oil Length A—Refined Lignin 526 lb. Liquor Over-Poly. Linseed Oil 263 lb. Maleic Resin No. 235 68 lh. Glycerin (Dynamite Grade) 18½ lb. Zinc Oxide. Lead Free 2½ lb. Mineral Spirits 31¾ gal. lb. B—Hydrated Lime 25Mineral Spirits 71/2 gal. Lead Naphthenate 24%9 lb. Cobalt Drier 4% lh.

C-E Viscosity 105 gal. Charge "A" into an open kettle. (The acid number of the mixture before reaction is 103.) Raise "A" smoothly and evenly in 2½ hours to 575°. Let cool to 545°. Hold 545° until 15 minutes from the time 575° first was reached. Let cool naturally to 410°. (The acid number is now about 50.) At 410° add the first

Mineral Spirits to

thinner. Then have the batch at 360°, firing up again if necessary.

Work in "B," consisting of a slurry of hydrated lime and thinner, holding batch at 360°. When "B" is all in, stir additional 15 minutes at 360° and then complete by addition of driers and mineral spirit to a viscosity of C to E as desired.

General Purpose Grinding Oil, Mixing Varnish and Paint Oil A-Refined Lignin Liquor 176 lb. Over-Poly. Linseed Oil \* 88 1h B-Calcined Magnesia 31/8 lb. V.M. Linseed Oil 10½ lb. Mineral Spirits 12gal. C—Hydrated Lime 141/4 lb. Mineral Spirits 3 gal. Mineral Spirits 521/2 gal. Lead Naphthenate 24% 21/4 lb. Manganese Naph-21/4 lb. thenate 6% Cobalt Drier 4% 21/1 lb.

Raise "A" to 400°. Cream "B" to a slurry and work into the batch, dispersing well. Gain 525°. Hold 525° until clear (1 to 5 minutes). Let cool naturally to 425°. Add 12 gallons of mineral spirits. Stir well. Hold batch at 360° and lime with "C" (stirred to a slurry). Stir 15 minutes at 360°. Fire off. Complete to "E."

<sup>\*</sup>From minimum 190 iodine number V. M. oil.

<sup>\*</sup>This is heat-polymerized linseed oil of such viscosity that in a Gardner-Holdt tube the bubble moves only the diameter of one bubble while the bubble in the "Z-6" Gardner-Holdt tube traverses the entire length of the tube.

#### Modified-Phenolic Varnish Formula No. 1

111-L Albertol

(B/S 1) 100 lb. China Wood Oil 20 gal. Heat to 585° F. in 30 minutes.

Add:

1 hr. Linseed Oil 5 gal. Cool to 545° F. and hold 13 minutes for viscosity. Add:

3½ hr. Linseed Oil 5 gal. Cool to 360° F. and reduce with:

Mineral Spirits 50 gal.

No. 2

Oiticica Oil—Viscosity

X-Y 20 gal.  $3\frac{1}{2}$  hr. Linseed Oil 5 gal. Heat to  $575^{\circ}$  F. in 30 minutes. Add:

111-L Albertol 100 lb.
Regain 575° in 15 minutes more and hold 2 minutes for string. Add: 3½ hr. Linseed Oil 5 gal.
Cool to 360° F. and reduce with:

Mineral Spirits 50 gal.

Quick Drying Varnish

Resin (Lewisol 150) 50 Chinawood Oil 60 Sunoco Spirits 164

Heat oil to 100° C., add resin; bring temperature to 273° C. in about one hour.

Hold at 273° for about 15 minutes, then cool to 232° C.

Add Sunoco spirits and finally add drier—about 85 cc. per gallon.

Drier (per 100 lb.)

Lead Drier 1 lb.
Cobalt Drier 3/4 lb.
Manganese Drier 1/2 lb.

Furniture Varnishes (Rubbing)

8 Gallon Length (Congo)
Thermally Processed

Congo 100 lb.

Bodied Linseed or De-

hydrated Castor Oil 8 gal. Petroleum thinner to 50% non-volatile by weight.

Driers equivalent to 0.10% Ca., 0.10% Co., and 0.20% Pb., as metals on the weight of oil.

The thermally processed Congo is prepared as follows: Heat the Congo to 650°-670° F. in about 1½ hours. Hold until foaming subsides and hot resin runs off paddle similarly to hot oil. Allow to cool.

This processed Congo is used to prepare the above vehicle as follows: Heat thermally processed Congo and linseed oil to 580° F. in about 1½ hours. Hold until a cold "pill" has very little tack (about 5 minutes). Allow to cool to about 400° F. Add petroleum thinner and then the driers.

The oil length may be increased to 10 gallons if greater flexibility and slightly softer film are desired.

General Utility Varnishes
15 Gallon Length (East India)
Batu, Pale East India
or Black East India 100 lb.

Bodied Linseed Oil or Dehydrated Castor Oil (viscosity of

about Z3) 15 gal. Petroleum thinner to 50% non-

volatile content.

Driers equivalent to 0.20% Pb.,
0.10% Ca., and 0.10% Co., as
metals on the weight of oil.

Heat the resin and 5 gallons of linseed oil to 600°-610° F. in about

60-65 minutes. Hold until cold "pill" indicates complete compatibility (about 10 minutes). Add remainder of linseed oil. Heat to 580° F. and hold until clear (about 5 minutes). Allow to cool to about 400° F. Add the petroleum thinner and then the driers.

The above vehicles may be used to prepare enamels for indoor ap-

plications.

15 Gallon Length (Congo)
Thermally Processed
Congo 100 lb.
Bodied Linseed Oil or
Dehydrated Castor
Oil (about Z3 viscosity) 15 gal.
Petroleum thinner to 50% non-

volatile content by weight.

Driers equivalent to 0.10% Ca.,
0.10% Co., and 0.20% Pb., as
metals on the weight of oil.

The Congo is thermally processed as follows: Heat the Congo to 650°-670° F. in about 1½ hours. Hold until foaming subsides and the hot resin runs off a paddle similarly to hot oil. Allow to cool.

The processed resin is used to prepare the above vehicle as follows: Heat the thermally processed Congo and linseed oil to 580° F. in about 50–60 minutes. Allow to cool to about 400° F. Add the petroleum thinner and then the driers.

The above vehicles may be used for preparing enamels for indoor applications.

Tinplate Baking Varnish
Oiticica Oil 75.0 kg.
Gain 120° C. in about 9 to 10
minutes. Add:

Teglac Z-152 79.8 kg. in portions to avoid accumulation

of resin, bringing to 190°-200° C. in 35 to 40 minutes. Continue heat to 295° C. in 60 to 65 minutes. Add: Standoil 46.2 kg.

Reheat to 260° C. in 90 to 100 minutes. Cool with turpentine to 180° C. and reduce with

Mineral Spirits 180.0 kg.

Lead and cobalt driers are added in varying proportions, according to the baking conditions which are to be used.

#### Medium Oil Metal Varnish U. S. Patent 2,248,961

This is a good, rapid drying coating composition for metal. This coating forms a single, transparent, flexible primer and surfacer coating which tenaciously binds itself to clean metal surfaces.

Medium Oil Varnish
Beeswax
Paraffin Wax
Boiled Linseed Oil
Mineral Spirits, Balance

The mineral spirits has an initial boiling point of 300°-310° F. and an end point of 390°-400° F. Enough mineral spirits is used to make a total of 100% by weight of all the ingredients.

Infra Red Paint Enamel Varnish Alkyd Resin 50 Ester Gum 20 Drying Oil 30

Varnish
Flexalyn (Diethylene
Glycol Abietate) 150
China Wood Oil 156
Bakelite 3360 50
Lead Naphthenate
(24% lead) 2

Viscosity

Color Hellige

Color Gardner

Manganese Naph-	
thenate (6%	
Manganese)	0
Cobalt Naphthenate	e
(6% Cobalt)	1
Varsol	291
Oil Length	10 gal.
% Solids Loss in	
Cooking	1.7
Time to 450° F.	25 min.
Time Held 450° F.	15 min.
Time to 565° F.	19 min.
Time Held 565° F.	none
Body	40"string
Time in thinning	8 min.
•	

The cooking procedure involves running the Bakelite 3360, 40 parts of China Wood oil, and the Flexalyn to 450° F. and holding until the reaction is complete. The balance of the oil is added and the temperature raised to 565° F. The varnish is held at this temperature for a 40" string off the cold pill, cooled, reduced, and the driers added.

6

12

#### Naval Spar Varnish

Ester gum, 87.5; rosin, grade WW, 25; lead rosinate, 25; raw tung oil, 109; varnish oil, 218; cobalt acetate, 0.75; petroleum spirits, 194; turpentine, 105; cobalt drier, 37.5; lead (naphthenate) drier, 45.

Mixing Varnish for Potable Fresh Water Tank Paint

Modified phenolic resin (Amberol No. 226), 105; raw tung oil, 348; petroleum spirits, 405; cobalt drier, 8; paint drier, 8.

Increased Length and Absence of "Buttering" in Varnishes Using Pigment Lakes

Ammonium Linoleate Paste S is applied in the acid phase in the manufacture of lakes after coupling. and gives better length and prevents buttering when the lake is incorporated in the vehicle. Suspension in the slurry is maintained by mechanical agitation. It may also be applied in the alkaline phase and precipitated in acid.

Heavy Kettle Bodied Linseed Oil (V-206)

(Non-reactive)

Neutral Refined Linseed Oil

Heat the oil to  $625^{\circ}$  F.  $(330^{\circ}$  C.). (Takes 2 hours.) Pull from fire and allow to cool to 575° F. (302° C.). Hold this temperature for one hour. Allow the oil to cool to 535° F. (280° C.) and hold at this temperature for the desired body (about 8 hours). Total time on fire, based on 250 gallon batch, is 13 hours.

Heavy Kettle Bodied Linseed Oil (V-201)

Neutral Refined Linseed

805 Heat to 575° F. (303° C.) and hold until a viscosity of "Z" (Gardner-Holdt Standard) is reached.

Limed Rosin Oiticica Oil Oiticica Oil 1.9 g. Heat to 425° F. in 25 minutes Add:

Hydrated Lime Heat to 425° F. and hold 20 minutes. Add:

W. W. Rosin

400 g.

Heat to 425° F. in 20 minutes more. Add:

Varnish Makers' Linseed

Oil

Cool.

Honey Oil Neutral Refined Linseed

Oil 685 Chinawood Oil 94

Heat the Chinawood oil and 80 gallons of linseed oil to 575° F. (307° C.) and hold for heavy string. Chill with the remainder of the linseed oil, stir until thoroughly incorporated and cool.

Gloss Oil

Refined Lignin Liquor 400 lb.

Freshly Hydrated

Lime 38 lb.
Kerosene 8 gal.
Mineral Spirits 50 gal.

Raise the refined lignin liquor to 400° F. Fire off. Add the lime, moistened with the kerosene, stirring. Fire on, regain 400°. Hold 400°, stirring gently, for 10 minutes. Fire off. Thin.

Paint Grinding Liquid
Refined Lignin Liquor 300 lb.
Hydrated Lime 26 lb.
China Wood Oil 300 lb.
Lead Drier
Cobalt Drier
Manganese Drier
Mineral Spirits 75 gal

Mineral Spirits 75 gal. Heat lignin liquor to 450° F. Dust in the hydrated lime, hold 450° and stirring. Add China wood oil. Gain 500° quickly. Advance to 565°. Hold between 535° and 550° to a soft, non-tacky pill (about 45 minutes). Let cool naturally to 400°. Add driers and reduce.

Flat Grinding Liquid Refined Lignin Liquor 400 lb. Hydrated Lime Lead Naphthenate (24% Pb.) 2 lb. Manganese Naphthenate (5% Mn.) 2 lb. Mineral Spirits 50 gal. Lignin liquor to 400° F. Hold 400°, introduce the hydrated lime with stirring until all in. Gain 500° rapidly. Gain 550° easily; hold 550° for 5 minutes. Fire off. Let cool naturally to 400°. Add driers and reduce.

Short-Oil Flat Grinding Formula No. 1	g Liquid
WW Rosin 10	8 lb.
Tung Oil 12	
Over-Poly. Linseed	1 10.
Oil "ZZZ" 3	9 lb.
011 000	3 lb.
	5 lb.
	$2\frac{1}{4}$ lb.
Magnesium Carbo-	01/ 11
	$2\frac{1}{4}$ lb.
Sod. Carbonate,	
Anhydrous	$\frac{1}{4}$ lb.
Litharge 1	_
Mineral Spirits 4	0 gal.
Cleaners' Naphtha,	
To make 4	0 gal.
No. 2	
Mild Mod. Phenolic	
Resin No. 78A 10	8 lb.
Over-Poly. Linseed	
Oil "ZZZ" * 19	0 lb.
Hydrated Lime	2½ lb.
	11/8 lb.
Magnesium Carbo-	,,,
	11/8 lb.
Sod. Carbonate,	
Anhydrous	1/4 lb.
*From minimum 190 iod	

V. M. oil.

Lead Resinate		
(20%)	$4\frac{1}{2}$	lb.
Mineral Spirits	40	gal.
Cleaners' Naphtha,		_
To make	40	gal.
		_
Varnish (V-	160)	
Flat Wall Ve	hicle	
W.W. Rosin	nucue	200
Slaked Lime		8
Heavy Bodied Lins	nod Oil	0
(5 hours at 575°]		790
Fused Lead Resina		190
	te	30
(16% Pb.)	) a sim a ta	
Fused Manganese F	tesmate	
(3½% Mn.)		12
Fused Cobalt Resin	ate	_
(5½% Co.)		9
Mineral Spirits		940
Melt the W.W. ros		
the lime in small po	rtions,	begin-
ning at about 400°		
After all the lime ha		
raise the temperatur		
(274° C.), and add t		
seed oil slowly, taking		
perature does not dro		
F. (246° C.). Add the		
order named and aft		
been thoroughly inco	rporate	d, cool
to 400° F. (205° C	).), and	thin.
These directions ma		
changed slightly depe		
ditions and equipmen	t in the	plant.
	-	
30-32-Gallon Inte	erior Sr	nar

30-32-Gallon Interior Spar				
Formula No. 1				
Ester Gum, Pale				
(Acid 12)	189	lb.		
Tung Oil	376	lb.		
V.M. Linseed Oil	12	lb.		
Litharge	41/2	lb.		
Cobalt Acetate	11/4	lb.		
Mineral Spirit, To		16		
make	116	gal.		

Gum Spirit Turpen-		
tine  No. 2	$3\frac{3}{4}$	gal.
Mod. Alkyd Resin		
No. 225	166	lb.
Over-Poly. Linseed		
Oil "ZZZ" *	364	lb.
Lead Naphthenate		
24%	16	lb.
Manganese Naph-		
thenate 6%	4	lb.
Cobalt Drier, 4%	4	lb.
Mineral Spirit, To		
make	87	gal.
Semi-Aromatic Sol-		0
vent	15	gal.
45-Gallon Flat and	— Under	coat

Formula No. 1 Mild Mod. Phenolic Resin No. 78A 107 lb. Over-Poly. Perilla Cil 474 lb. Hydrated Lime 13½ lb. Lead Resinate 20% 18 lb. Zinc Naphthenate 10% 8½ lb. Cobalt Drier lb. Mineral Spirit, To gal. make 160 No. 2 Mod. Phenol. Alkyd Resin No. 222A 130 lb. Over-Poly. Linseed Oil "ZZZ" \* lb. 300

Sealing Vehicle

\*From minimum 190 iodine number V. M. oil.

140

24

lb.

lb.

lb.

8½ lb.

Poly. Linseed Oil

Hydrated Lime

10%

24%

Zinc Naphthenate

Lead Naphthenate

Cobalt Drier 4% Mineral Spirit, To	8	lb.
make	159	gal.
58-60-Gallon Exte Formula No Mod. Phenol. Alkyd		ar
Resin No. 227 Poly. Perilla Oil	76	lb.
"X"	287	lb.
Tung Oil	72	lb.
Semi-Aromatic Sol-	:-	10.
vent	16	gal.
Lead Naphthenate		800
24%	$15\frac{3}{8}$	lb.
Manganese Naph-	76	1
thenate 6%	23/8	lb.
Cobalt Drier 4%	21/8	
Mineral Spirit, To	. 70	
make	43	gal.
No. 2		
Mod. Phenol. Alkyd		
Resin No. 227	80	lb.
Poly. Linseed Oil		
"X"*	232	lb.
Tung Oil	72	lb.
Poly. Linseed Oil		
"Z-2" *	51	lb.
½% Soln. Guaiacol		
in Dipentene	$2\frac{1}{4}$	gal.
Semi-Aromatic Sol-		
vent	11	gal.
Lead Naphthenate		
24%	10	lb.
Manganese Naph-		
thenate 6%	3	lb.
Mineral Spirit, To	401 /	
make	$46\frac{1}{2}$	gal.

Paper Varnish U. S. Patent 2,139,603

(a) Manila Copal 80 lb. Water 32 gal. Ammonia 7 gal.

\*From minimum 190 iodine number V. M. oil.

	(b)	Tung Oil Fat	ty	
		Acids	40	lb.
		Water	81/2	gal.
		Ammonia	3	gal.
	(c)	Cobalt Chlo-		
		$_{ m ride}$	15	g.
		Ammonia	200	ec.
		Pine Oil		pt.
	Em	ulsify (a) and	(b) separ	rately;
i	rloza	re (c) and th	en mix	all to-

Pale Liquid Drier
Gradually heat 84 parts (by weight) rosin, 18.5 parts cobalt hydroxide, 20 parts of a liquid such as kerosene or light solvent naphtha to 190–200° C. or until reaction is complete and all water is driven off. Allow to cool to 160° and thin with petroleum naphtha or coal tar naphtha. A basic zinc naphthenate can be made by heating 20 parts zinc

gether until uniform.

low to cool to 160° and thin with petroleum naphtha or coal tar naphtha. A basic zine naphthenate can be made by heating 20 parts zine oxide with 86 parts naphthenic acid (A.V. ca. 250). A reaction commences at about 70° C. and is completed at between 130 and 140° C., but heating is continued until all water is removed. The final product possesses zinc content of about 16%, but by using suitable proportions of the reactant materials it is possible to prepare a product with a still higher metal content.

"Piano Finish" for Caskets

First the casket must be puttied with a colored putty to match the desired shade, then sanded smooth with No. 6/0 or 7/0 finishing (abrasive) paper. After sanding, it should be dusted off well; then it is ready to be stained.

Stains
Oriental Walnut
Yellow (Conc. Dye)

Orange (Conc. Dye)	$1\frac{1}{2}$
Denatured Alcohol	32
Dark Oriental Walnu	:t
Orange (Conc. Dye)	$\frac{1}{2}$
Black (Conc. Dye)	$\frac{1}{2}$
Denatured Alcohol	32
$Light\ Walnut$	
Red (Conc. Dye)	<b>2</b>
Orange (Conc. Dye)	24
Black (Conc. Dye)	8
Denatured Alcohol	94
$Medium\ Walnut$	
Red (Conc. Dye)	2
Orange (Conc. Dye)	28
Black (Conc. Dye)	12
Denatured Alcohol	86
Medium Red Mahogar	iy
Red (Conc. Dye)	$1\frac{1}{2}$
Yellow (Conc. Dye)	$\frac{1}{2}$
Orange (Conc. Dye)	$1\frac{1}{2}$
Black (Conc. Dye)	$\frac{3}{4}$
Denatured Alcohol	16
$Dark\ Red\ Mahogany$	,
Red (Conc. Dye)	$3\frac{1}{2}$
Yellow (Conc. Dye)	$\frac{1}{2}$
Orange (Conc. Dye)	3
Black (Conc. Dye)	$1\frac{1}{2}$
Denatured Alcohol	<b>32</b>
PT 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 61

This stain is sprayed on. After letting it dry for an hour, sand the stained surfaces very lightly; then fill with paste filler, using about 12 lb. of filler to the gallon of reducer. This is a very important operation when making a finish of this kind, because if the pores are not filled properly the finish will look "hungry."

After filling, allow the surfaces to dry over night before applying the sealer coat. Use a lacquer sealer and spray it on freely—what you call a "wet coat." It is left to dry from two to three hours before hand sanding.

Use felt sanding blocks and No.

8/0 sandpaper to sand out all traces of orange peel. Then the surfaces are dusted off with an air duster, being careful to remove all dust from the corners and carvings.

Next comes the clear lacquer—about four wet coats. This should be a lacquer containing about 27% solids, reduced two parts lacquer to one part of good grade of reducer. A cheap lacquer evaporates too fast to allow the lacquer to flow out properly. The last coat of lacquer is followed with a mist coat of clear reducer.

The lacquered hardwood casket should then stand at least four days before being rubbed. Rub with No. 320 wet-or-dry sandpaper, using water as a lubricant with Ivory soap for a softener. After it is rubbed down, finish off with a portable rubbing machine. Apply rubbing compound to the surface and use a rotary disc fitted with a sheep's-wool pad to rub or buff the finish. Then clean up the buffed finish with a good cleaner and polish. This process produces a finish that has depth and a very high polish.

A "piano finish" can also be obtained by using two or three coats of rubbing varnish over a varnish sealer. When varnish is used, it should be left to harden for at least nine days before rubbing. The rubbing is done with pumice stone and water; then the surfaces are polished out with rottenstone.

Alcohol Resistant Finish for Wood

A good finish which is alcohol resistant can be procured on wood by mixing linseed oil with 25% white vinegar and rubbing the mixture thoroughly into the wood. If a high

gloss is desired it will be found necessary to apply several coats of the mixture.

### Wrinkle Finishes Varnish

Amberol F-7		•		640
Bodied Oiticica	1 O	il		422
Heat to 260°	C.	in	35	minutes.
Cool to 180° C.				

Reduce with:

Solvesso No. 2	100
Solvesso No. 1	500
Paint	
Carbon Plack Sunarha	14

Carbon Black, Superba	14
Varnish	700
Xylol	175
Cohalt Nonhthanata (1%	

Cobalt Naphthenate (1% Solution) 20 Grind in pebble mill.

Application: One coat directly on bare steel with spray gun. Bake at

110-120° C. for ½ hour or more.

To make finer wrinkle add oiticia standoil to paint after manufacture. Longer oil varnish (maximum 15 gal.) gives finer wrinkle in paint of lower bake.

To dilute use xylol or Solvesso

Paints of other colors can be made by grinding in suitable quantities of pigments. Pebble mill recommended.

#### Concrete Floor Finish

This is a two part finish consisting of a "Primer" coat which is in the nature of a colored concrete sealer and which dries in about a half hour. This is applied to the raw floor.

After this is dry, it is coated with a waterproof type water-wax into which is incorporated the same color as in the primer coat.

Floors treated with this combina-

tion are maintained by mopping scuffed or worn spots with additional colored wax finish as they occur. Treated and serviced in this way, floors never require refinishing and are always in perfect condition.

#### Primer

7 1 (1) 001		
Loba "C" Gum	100	lb.
Alcohol	27	gal.
Toluol	$13\frac{1}{2}$	gal.
Ethyl Acetate	41/2	gal.

Mix above together in closed tank. Add colors as desired using iron oxides for reds and browns and chrome oxide for green. Approximately one pound of color per gallon of primer is sufficient. This color must be ground into the primer on a colloid mill or on a closed ball or pebble mill as the primer dries so rapidly as to make other types of mills useless.

A standard gray color is made by adding to the above quantity, the following:

Titanium Oxide 25 lb.
Lithopone 25 lb.
Black Iron Oxide 5 lb.

Wax Formula

The wax finish coat is prepared by incorporating about one pound of color per gallon, to any standard type water-wax and running same through the colloid mill.

#### Limed Oak Finish

The wood used is selected white oak, therefore the use of any bleach is unnecessary. The work is well sanded and must be inspected carefully for any imperfections. Assuming that the work is in A No. 1 shape, it is given a coat of water stain, depending on the particular shade the specifications call for,

such as nigrosene and aniline powdered stains. After this stain dries, the surface is sandpapered carefully and then given a coat of clear lacquer sealer.

When the sealer is thoroughly dry, the surface is again smoothed the same as after the application of water stain. A coat of white wood filler is then applied. Of course, this wood filler can be tinted with any oil pigments such as raw sienna, burnt umber, raw umber, black, etc. This tint, of course, would be to match shades on specifications. This filler coat is applied with a brush, making sure to brush across the grain. After this material sets, but is not dry, it is wiped off with wiping rags, rubbing across the grain.

The pores of the wood then contain this filler, leaving a limed oak finish which is sometimes called silver gray oak finish. This is allowed to dry overnight and is then finished with another coat of clear sealer and one to three coats of clear lacquer. When the clear lacquer is dry, the surface is rubbed down with a rubbing compound and polished with a good wood wax.

#### Fumed Oak Finish

First, use a toner made up in the proportion of—

Tannic Acid 1 oz.
Pyrogallic Acid 1 oz.
Warm Water 1 gal.

Sponge the oak surface with this and, when dry, sand smooth. Then make a stain of the following ingredients and in the proportion indicated—

Potash Carbonate 3 lb. Potash Bichromate 2 oz. Walnut Crystals 2 oz. Ammonia (28°) 3 qt. Warm Water  $4\frac{1}{4}$  gal.

Note: Keep this material in an earthenware crock, glass jar or wooden keg.

After staining, let the surface dry and apply one coat of white shellac. Sand lightly with fine sandpaper, and wax. Do not fill the surfaces, as this would spoil the effect.

#### Weathered Wood Effect

A weathered or driftwood effect on new lumber may be obtained by treating the lumber with one or more applications of medium strong solution of ferrous sulphate (copperas). If desired, use a gray-green paint, reduced with turpentine as a stain and as a final finish use a spar varnish, thinned down with turpentine—about one quart to a gallon.

Flock Finishing

Flock finishing is the way of finishing various articles with rayon, cotton and wool to give the surfaces a felt or suede appearance.

It is applied on wood of the very softest kind, such as white pine, California red cedar and various plywoods. First, the wood has to be coated with a good synthetic oil undercoater. After drying overnight, the surfaces are "spackled" filling up any holes or crevices with a Swedish putty. Then the wood is sandpapered to produce a smooth surface. It is given a mist coat of silk-screen process gloss enamel. This paint is not used as in screen process work but is thinned for spraying purposes.

After leaving the mist coat set for 20 to 30 minutes, follow with a wet coat of the same enamel, making sure in this last application of paint that the article is evenly coated, so that when the flock is applied it will adhere to the enamel uniformly.

The article is now ready to receive the flock. Before this operation is started the flock gun should be put in readiness. That is, the container should be filled only threequarters full with flock and all adjustments should be made so that too much flock does not escape through the nose of the gun. The leason the container on the gun should only be filled three-quarters full is that the air coming through into the container must have a space in which to blow the flock around to scatter the particles. This is very important.

The air pressure for flocking should be between 40 and 60 lbs.—never more nor less. The air lines should be kept filtered to prevent oil and water accumulations. The best method is to coat the edges with flock and then spray the top surface.

It is best to let the flocked surface dry overnight, or, if the facilities of a baking oven are available, it can be baked dry at a temperature of 120° F. It is best, when anything is to be flocked, that the color, of the paint, match closely to the color of the flock. When the article is well dried the excess flock is then dumped off on paper so as to reclaim that which did not adhere to the surfaces being flocked.

#### Lacquer for Oxidized Brass

	Formula		
Titanium Dioxide (Low Oil	No. 1	No. 2	
Absorption)	4.4	9.15	
Carbon Black	1.4	0.35	
Talc	9.2		
Nitrocellulose (Dry Basis)	4.5 (125 sec.)	6.05 (5–6 sec.)	
† Dyal #7986 Resin Solution			
(50% total solids)	16.0 *		
† Dewaxed Dammar Solution	9.4	Same and the same	
Ester Gum (Acid No. 6-8)		9.85	
Alkyd Resin Solution (50%)		3.55	
Glycol Sebacate		4.15	
Blown Castor Oil	1.5 *	0.25	
Raw Castor Oil	<del></del>	0.20	
Ferrite Yellow		0.25	
Snow Floss		0.60	
** Solvent	53.6	65.60	

\*Up to 10% of the Dyal No. 7986, solid basis, may be substituted with blown castor oil, if necessary, to obtain greater flexibility of the film.

†Short oil, phenol modified alkyd resin.

† Dewaxed Dammar Solution Dewaxed Dammar Resin 43 Xylene 25

32

Anhydrous Denatured Alcohol (S.D. No. 1, 23G or 23H)

\*\* See page 324.

** Solvent,	Oxidized	Brass	Lacquer
-------------	----------	-------	---------

		Formula	
	No. 1		No. 2
Amyl Acetate			6.4
Butyl Acetate (Normal)	25.0		
Isopropyl Acetate (or Ethyl			
Acetate)			27.8
Anhydrous Denatured Alcohol			
(SD #1, 23G or 23H)	10.0		5.0
Butyl Alcohol (Normal)	6.0		
Lacquer Diluent Naphtha	32.0		14.5
Aromatic Petroleum Naphtha	12.0		35.5
Xylene	15.0		
Coal Tar Solvent Naphtha			10.8

#### Oxidized Bronze Lacquer Thinner

	_	Formula	
	No. 1		No.2
Phosphoric Acid (75%)	1.0		-
* Ethyl Acetate	9.0		
Butyl Acetate (Normal)	30.0		16.2
* Isopropyl Acetate			9.6
Denatured Alcohol (S. D. No. 1,			
23G or 23H)	12.0		10.0
Butyl Alcohol (Normal)	12.0		4.0
Lacquer Diluent Naphtha	36.0		36.4
Toluene (or Aromatic Petroleum			
Naphtha)			8.6
Xylene			15.2

<sup>\*</sup>Ethyl acetate and isopropylacetate are interchangeable.

Metal Lacquer		Ester Gum	10
Nitrocellulose, Wet		Glaurin (Diethylene	
(5 sec.)	11	Glycol Monolaurate)	3-4
Alkyd Resin (50%		Butyl Acetate	10
Solution)	15	Butyl Alcohol	5
Glaurin	4	Ethyl Acetate	8
Butyl Acetate	10	Toluol	48
Butyl Alcohol	5	The wet nitrocellulose	contains
Ethyl Acetate	7	35% alcohol.	
Toluol	48		
		Congo-Ethyl Cellul	nge .

Wood (Rubbing) Lacquer Nitrocellulose, Wet (½ sec.) 15 Congo-Ethyl Cellulose
(For Furniture Lacquer)
Congo (Thermally
Processed) 140 lb.

Ethyl Cellulose (Low Viscosity)	35	lb.
Castor Oil or other		
Plasticizer	7	lb.
Toluol	455	lb.
Denatured Ethyl Alcohol	70	lb.
Tul 1 C 11 1	~	
Dammar-Ethyl Cellulos	е цас	quer
Batavia Dammar A/E	500	lb.
Ethyl Cellulose		
(Low Viscosity)	125	lb.
Turpentine	1750	lb.

Linoleum Cemer	nt		
Batu Nubs and Chips		lb.	
High Solvency Petrolet			
Thinner	38	lb.	
Fuller's Earth (200			
Mesh)	25	lb.	
Dissolve the Batu in	petro	leum	1

750 lb.

thinner using agitation, but no heat.
Add the fuller's earth to the above

vehicle and stir thoroughly.

Other inert materials may be used in place of fuller's earth if it

is so desired.

Butanol

iture
90
10
70
20
10
70
20
10
90

Ethyl Cellulose (L. V.)	10
No. 5	
Pale East India Nubs	
or Chips	70
Ethyl Cellulose (L. V.)	20
Mineral Oil	10
No. 6	
Pale East India Nubs	
or Chips	70
Ethyl Cellulose (L. V.)	20
Dow Plasticizer No. 6	10
The colments used more he	h:al

The solvents used may be high solvency petroleum naphthas or mixtures of these with low solvency naphthas.

Pale East India gives smoother films than Batu, but either may be plasticized with practically any oils, the amount of oil used depend-

ing upon individual desires.

#### Fluorescent Christmas Ornament Lacquer

Many paints used on Christmas ornaments fluoresce brightly and may be used, under ultra-violet light, for this purpose.

A lacquer made from ordinary colorless lacquer and having a few per cent of fluorescent dye present can be used on Christmas ornaments.

Adding zinc orthosilicate or anthracene to the lacquer instead of the dyes produces different effects and more permanent paint.

Glass Fibers; Lacqu	uer for
U. S. Patent 2,21.	5,061
Cellulose Nitrate	14.0
Castor Oil	18.6
Pigment	23.4
Ethyl Acetate	17.6
Alcohol	26.4

Lacquer for Glued Surface	ces
Nitrocellulose (Dry	
Basis)	60
Dibutylphthalate	25
Flexoresin D A 4	15
Solvent, To suit.	

Spraying Pigmented Lacquer			
	]	Parts by	
Non-Volatiles		Weight	
1/4 Sec. Nitrocell	ulose		
(Dry Basis)		16	
Ester Gum		8	
Dibutyl Phthala	ate	7	
Titanium Dioxi	de	7	
Medium Green		3	
Volatiles	Solvent	Mixture	
Per Cent by			
Volume	$\mathbf{A}$	$\mathbf{B}$	
Butyl Acetate	30	18	
Butanol	15	9	
* Ethyl Acetate		12	
Ethyl Alcohol	10	. 6	
Toluol		55	
Xylol	45		
		,	

## Semi-Pigmented Airplane "Dope" Lacquer

Clear dope: wet nitrocellulose 10 parts, butyl acetate 10 parts, butyl alcohol 20 parts, ethyl acetate 23 parts, toluene 27 parts. Various color pastes, e.g., yellow paste: cadmium lithopone 32 parts, castor oil 11 parts, dibutyl phthalate 11 parts, cadmium yellow to color. Cream paste: zinc oxide 22 parts, castor oil 11 parts, dibutyl phthalate 11 parts, chrome yellow to color. Light blue paste: zinc oxide 22 parts, castor oil 11 parts, dibutyl phthalate 11 parts, prussian blue, etc., to color. Dopes are made from mixture of clear dope and pastes.

\* Including the ethyl alcohol ordinarily added with the nitrocellulose.

Acetate Dope for Aircraft	Cloth
Cellulose Acetate	
(20 sec.)	9
Triphenyl Phosphate	1
Acetone	31
Methyl Ethyl Ketone	31
Ethyl Acetate	14
Ethyl Lactate	14

	~ 1
Paper Coating Lacque Cellulose Acetate	er
(2-5  sec.)	13.3
Santicizer M-17	6.7
Santicizer 8	1.6
Acetone	20.0
Methyl Ethyl Ketone	8.3

1-Nitropropane

Alcohol

Artificial Leather	Coating	on	Cloth
Alcohol			58
Ethyl Acetate			22
Naphtha			18
Xylol			2
To 100 gal, sol	vent. add	1 1	76 lb

40.6

9.5

To 100 gal. solvent, add 176 lb film scrap.

#### Polyvinyl Acetal Acetate— Nitro Starch Lacquers

These compositions are valuable as quick drying high gloss and transparent lacquers for adhesives, printing ink base, fingernail lacquer, paper, furniture, and metal lacquers.

#### A. Volatile Solvent

In general a solvent mixture which will be a solvent for the amounts of nitrostarch and polyvinyl acetal acetate used. A good vehicle is as follows by *volume*:

Etnyl Acetate	2- 5%
Butyl Acetate	25-60%
Butyl Ether of	
Ethylene Glycol	2- 5%
Butyl Alcohol	3_10%

Toluene	10-35%
Xylene	5-21%
Petroleum Naphtha	5-15%
Dlacticizon	•

B. Plasticizer

Tricresyl phosphate, dibutyl phthalate, triacetin, etc.

3 to 5% of total weight of lacquer and about 10% of film forming ingredients.

#### C. Film Formers

- 1. Polyvinyl acetal acetate: 10 to 25% of total weight of lacquer
- 2. Nitro starch: 3 to 15% of total weight
- 3. Soft resin such as alkyds, ureaformaldehydes, sulfonamides: 5 to 80% of combined weight of (1) and (2).

The % of solids is determined by use and method of application; i.e. spraying, brushing, dipping.

# Formula No. 1 Polyvinyl Acetal Acetate 18 Nitrostarch 9 Plasticizer 3 Solvent Vehicle 70

#### No. 2

Polyvinyl Acetal Acetate 5–15 Nitrostarch 5–15 Soft Alkyd Resin 5–15 Solvent Vehicle, To give concentration desired.

#### No. 3

Finger Nail Lacquer	
Polyvinyl Acetal Acetate	15.5
Nitrostarch	6.0
Dibutyl Phthalate	2.0
Iron Oxide (Red)	1.0
Titanium Oxide	1.5
Solvent Vehicle	12

#### No 4

Furniture	Spray	Lacg	uer	
Polyvinyl Ac				
Nitrostarch	MARCH.	i atal	5	
Tricresyl Ph	osphate	3	3	

Butyl Acetate	38
Toluene	40

#### Solvent Resisting Ethyl Cellulose Film

This film is especially valuable in transparent pressure adhesive tapes, in the fabrication of laminated products having at least 1 ply of ethyl cellulose, and in transparent containers for oily and greasy substances.

The film is baked from 140° C. for 10 minutes to 50° to 80° C. for 16-64 hours, after being deposited from the solvent.

#### A. Solid Contents

65 to 90 parts medium ethoxy ethyl cellulose having an ethoxy content of 43.5 to 46.5%.

35 to 10 parts of a heat hardenable aryl sulphonamide – formaldehyde resin, such as p-toluene sulphonamide-formaldehyde, etc.

#### B. Solvents

The 2 solids are mutually compatible in a wide variety of common solvents or mixtures thereof, such as ethyl and butyl alcohol, ethyl, butyl, or amyl acetate, toluene, xylene, nitroethane, hexone, etc.

Substitutes for Dibutyl Phthalate In lacquers, dibutyl phthalate can often be replaced by "Glaurin" (diethylene glycol mono-laurate) 1-3% is used on weight of total solids. In synthetic rubbers, glycerin monoricinoleate (water insoluble grade) is an excellent replacement.

Optimum Surface Tension Lacquer
Solvent
Butyl Acetate 33 gal.

Butyl Alcohol	12	gal.
Toluol	20	gal.
Troluoil	35	gal.

Low Surface Tension Lacquer Solvent

Butyl Acetate	33	gal.
Butyl Alcohol	12	gal.
Troluoil	55	gal.

Ethyl Cellulose Lacquer Solvents

While ethyl cellulose is soluble in many single solvents, solvent mixtures are usually desirable to effect the proper combination of viscosity, film characteristics, and evaporation rate. A mixture of toluene and ethyl alcohol in the ratio of 70:30 or 80:20 is satisfactory in many cases. Where faster drying is required in lacquers for roller coating or dipping, a suggested mixture consists of: toluene, 40; ethyl acetate, 40; ethyl alcohol, 20.

Another mixture which is advantageous in spraying lacquers has these proportions:

35
40
15
10

# Duplicator Solvent U. S. Patent 2,228,108 Ethylene Glycol Monomethyl Ether 10 Water 10 Alcohol 80

Suspension of Pigments

A frequent difficulty in the storage, shipment and utilization of pulp colors or pigments in water is that of maintaining a uniform dispersion. Much time is lost in redispersing colors caked at the bot-

tom of a container or tank. Often the caking is such as to prevent reformation of the original fine particle size, resulting in complete loss of color.

This problem can easily and inexpensively be solved by the use of Diglycol stearate. As little as 1/10% of this added to the weight of the color mix will produce the desired result. In the case of heavy pigments, such as titanium dioxide, a higher percentage is usually desirable. A 2% or 3% stock dispersion of Diglycol stearate is made by adding the stearate to boiling or hot water and stirring until room temperature is reached. The proper amount of this is added to the pulp color with agitation, or to the diluted pulp color. If desired, the color may first be stirred into the stock solution, water being added afterwards. The method of addition is quite flexible and easily managed. A typical color dispersion is as follows: 50% dry color, 49.9% water, 1/10% Diglycol stearate.

An interesting property of the foregoing formula, when coated on paper, is the glaze obtainable by stoning or calendering. This coating shows a higher degree of water resistance than might ordinarily be expected. It, therefore, is of interest in replacing casein as a binder and glazing agent in many paper coating operations.

Exterior House Paint Pigments White

r ormuta	1 INO. 1	
35% Leaded Ox	ide 45	lb.
White Lead	18	lb.
Titanium Dioxic	de 15	lb.
Inert	22	lb.

No. 2			Non-Chalking Titan-		
Pigment—725	411/	lb.	ium Dioxide	8	lb.
White Lead	161/	lb.	Inert	30	lb.
Titanium Dioxide	$13\frac{3}{2}$	lb.	No. 6		
Inert	20	lb.	White Lead	19	lb.
White and Ti	nts		Pigment—725	$45\frac{1}{2}$	lb.
No. 3	1000		Non-Chalking Titan-		
White Lead	60	lb.	ium Dioxide	$7\frac{1}{2}$	lb.
Zinc Oxide	30		Inert	23	lb.
Inert	10	lb.	Colloidal Shellac Dis	-	
No. 4	10	10.	Shellac	•	
White Lead	40	lb.	1	100 200	_
, ,	40		Methyl Acetone Mix until dissolved. Ac		
Pigment—725	9	lb.		ua wit	n vig-
$Inert \ Tints$	9	10.	orous mixing:	10 15	
			Triethanolamine		
No. 5	00	11.	Allow to stand for 24	nours	. Add
White Lead	32	lb.	slowly with stirring:		4 1
Zinc Oxide	30	lb.	Water	3	4 l.

Thinning Shellac Solutions

1 111111111	Diffilat	Doiumons
To convert shellac		Use alcohol
In 5-lb. cut to 3 -lb. cut		3½ pints to gallon shellac
In 5-lb. cut to $2\frac{1}{2}$ -lb. cut		<sup>2</sup> / <sub>3</sub> gallon to gallon shellac
In 5-lb. cut to 2 -lb. cut		1 gallon to gallon shellac
In 5-lb. cut to 1 -lb. cut		2½ gallons to gallon shellac
In 4-lb. cut to 3 -lb. cut		1 quart to gallon sheliac
In 4-lb. cut to $2\frac{1}{2}$ -lb. cut		3½ pints to gallon shellac
In 4-lb. cut to 2 -lb. cut		34 gallon to gallon shellac
In 4-lb. cut to 1 -lb. cut		21/8 gallons to gallon shellac

Cutting Liquid Shellac Without Adding Alcohol

By the addition of 4-oz. of ammonia to one gallon of 5-lb. white liquid shellac, the shellac in this alcoholic liquid solution is rendered sufficiently soluble so that  $2\frac{1}{2}$  to 3 gallons of water can be safely added to the mixture, thus giving a resultant three to four gallons.

Telephone Transmitter Membrane Coating

U. S. Patent 2,281,940 Polymerized Isobutylene 100

· · · · · · · · · · · · · · · · · · ·	
Stearic Acid	1
Ethyl Cellulose	10
Paraffin Wax	20
Carbon Black, To suit	

Wash for Galvanized Iron	Before
Painting	
Alcohol	60
Toluol	30
Carbon Tetrachloride	5
Hydrochloric Acid	
(Concentrated)	5
The solution is freely ap	plied to
the galvanized iron with a	brush.

Cleaner for Aluminum Be	fore
Painting	•
Butyl Alcohol	40
Isopropyl Alcohol	30
Phosphoric Acid (85%)	10
Water	20

The cleaner is applied and allowed to remain on the surface for two minutes, followed by slight scrubbing with a bristle brush and thorough rinsing with water.

#### Paint Remover Formula No. 1

z orinada z i o.	_	
Tripoli	26	oz.
Mineralite	30	oz.
Neutral Soap Powder	24	oz.
Water	50	oz.
Denatured Alcohol	$13\frac{1}{2}$	oz.
(Mix in a paint mill.)		
No. 2		

Wax-like materials (e.g. paraffin wax) are incorporated into paint removers mainly to retard solvent evaporation. Certain pigments possessing a leafy structure may be satisfactorily substituted for the paraffin wax. A suggested formula is: film scrap 3 parts, methyl acetate 9 parts, ethyl alcohol 8 parts, methylene chloride 32.5 parts, talc or powdered mica 20 parts. Better results are obtainable with the powdered mica if this be used in conjunction with a vinyl acetate resin. thus, polyvinyl acetate resin of high viscosity 3 parts, ethyl alcohol 8 parts, methylene chloride 32.5 parts, ethyl acetate 9 parts, powdered mica 25 parts.

Benzol-Free Paint Remover
By-Product Alkane
Chlorides 25
Acetone 50

Alcohol, Denatured	25
Paraffin Wax	2-3

Varnish and Paint Removing Composition U. S. Patent 1.483.587

A paste is made by mixing furfural with an inert powder ingredient such as corn starch, using such proportions as to obtain as thick a paste as possible and yet have one that may be applied with a brush. The paste is applied to a varnish surface and allowed to remain for ten or twenty minutes. The outer portion of the paste will have dried out slightly, but the inner portion will be still moist with furfural.

By the use of a knife blade. scraper, stiff brush, cloth or other suitable means, the paste residue and loosened varnish film may be entirely removed, leaving the clean surface of the material. This surface is now ready for the application of a fresh coat of varnish or paint, there being no wax or other deposit to interfere. Varnish coats may be moved from wood by this method without harming the original surface in any way. Although the paste will remain moist for a long period of time, it should not be allowed to remain on the surface for so long a time as to be too dry for satisfactory removal. This method works successfully no matter what the position of the surface. It permits the ready removal of varnish from vertical, inclined, or inverted surfaces as well as from horizontal surfaces and is very economical of solvent material.

Although furfural itself may be made into the starch paste and work satisfactorily for removing many types of surface coatings, a mixture of furfural and furfuryl alcohol as the liquid ingredient of the paste is advantageous in removing certain coatings, especially those containing large amounts of shellac or cellulose esters.

#### Varnish Remover

	Acetone	1	qt.
	Alcohol	1	qt.
	Water Saturated with		
	Soda Ash	$\frac{1}{2}$	pt.
	Benzene	1	qt.
	Shake and apply. Ke	ep v	vet 20
n	ninutes, wipe and scrap	e off.	•

Phenol Formaldehyde Varnish Remover

U. S. Patent 2,127,469
Nitric Acid (d. 1.42) 10
Sulphuric Acid (d. 1.84) 90
Apply at 85° C. and wash off thoroughly.

Improved Crack Filler

Because crack filling materials often work out of floors, the filler itself may not necessarily be at fault. As floors made out of oak and other hard woods are usually waxed, the cracks oftentimes hold more or less wax as well, which prevents the filling material from adhering to the sides of the cracks. The same result may also be caused when varnish or shellac trickles into the cracks.

To prevent such trouble, clean the cracks out thoroughly by scraping and remove all dust. For a satisfactory filling, use sifted sawdust made from the same wood as the floor. Enough sawdust for crack filler may be procured quickly by sawing some of the wood. Mix the sawdust to a paste with the fairly strong solution

of glue or casein. By adding coloring matter to the mixture it may be darkened to match the color of the wood. As soon as the filler is pressed well into the crack, smooth it down and clean the surplus away before the filler has time to harden.

#### Wood Sealer

ii ood beare	4
Pontianak Bold	
Scraped	50 lb.
Cellosolve	100 lb.
Mix the ingredients u	ntil a homo-

geneous solution is obtained.

A film of this material requires about ten to fifteen minutes for an initial set and it may be sanded lightly at the end of one hour.

Preserving Wooden Fence Posts

Formula No. 1

Mercuric Chloride 1 tbsp.

Sodium Chloride 1 tbsp.

Put into ¾ in. hole in post near ground.

No. 2

Creosote 70
Fuel Oil 30
As much as post will absorb is to be used.

No. 3

Creosote 25 Fuel Oil 75

Impregnate under pressure of 120 lb./sq.in., allowing complete absorption.

#### Adobe Preservative

U. S. Patent 2,137,247

Paint surfaces with solution of:
Vinyl Acetate 10 g.
Acetone 55-60 cc.

Acetone 5
Thinned with

Toluol 200-1000 cc.

Fireproof Plaster British Patent 531,039	Plaster Primer White Lead, Semi-	r	
Slag Wool 30 Asbestos 26	0 Paste 10 Interior Varnish	00 4	lb. gal.
Iron Filings 18 Potassium Silicate (d. 1.33) 30	5 Bodied		gal. gal.

#### CHAPTER FOURTEEN

#### PAPER

#### Grease-Proof Coating for Containers

U. S. Patent 2,122,907

Animal Glue	100	oz.
Glycerin	10-500	oz.
Formaldehyde	50-1500	oz.
Water	200-1500	oz.

In the formation of the coating, the time at which the tanning reaction takes place is controlled by carefully controlling the temperature of the coating. In the mixing of the ingredients forming the coating, the temperature of the mixture is carefully kept below the reacting temperature of the tanning agent during the coating process, the exact temperature used depending upon the length of time of delay required in the operation. In the case of formaldehyde, the temperature maintained below 130° F. during the coating process, to prevent reaction between the tanning agent and the tannable material. When the coating operation is completed, the surface coated is immediately subjected to temperatures above the reaction temperature of the tanning agent, or above 130° F. if formaldehyde is used. This promotes the tanning reaction, and an insoluble material possessing the required properties is produced. This method obviates the low temperature drying to produce a continuous film, which was necessary in previous methods. The materials are accordingly dried much faster in the present method.

# Grease Proof Paper Coating U. S. Patent 2,256,853 Clay 87.7 Polyvinyl Alcohol 1.3 Thin Boiling Cooked Corn Starch 11.0

Greaseproofing Paper Australian Patent 113,451

To make paper greaseproof it is treated in a mixture of anhydrous lanolin 6, paraffin wax 2, white petroleum jelly 2, white spirit 4 (or less). To this mixture is added 1/16 part of eucalyptus oil or similar substance to mask the odor. The mixture is heated to over 56°, the paper dipped in it and passed over rolls heated at the same temperature followed by rolls at 4°.

Alkali Resistant Paper or Board U. S. Patent 2,231,562

Dip in a 30% solution of ammonium chloride or acetate and dry.

Waterproofing Writing Paper Formula No. 1

The paper is spread horizontally over a glass plate and is then given coating on both sides with a 2% solution of a wetting agent or glyceryl monostearate strength. Thereupon the paper is hung up to dry.

The paper is then spread over a glass plate and painted or sprayed with a vulcanizing latex mixture e.g.

Mixture 1	
Creamed Latex	100.0 ml.
Kaolin	15.0 g.
Sulphur	1.5 g.
Zinc Oxide	1.5 g.
Ultra-Accelerator	
(e.g. P extra N)	0.5 g.
Casein Solution	
(10%)	5.0 ml.
Wetting Agent Solu-	
tion $(5\%)$	20.0 ml.
Paraffin Emulsion	
(20%)	5.0 ml.

The creamed latex is added after all of the other ingredients have been thoroughly mixed in a ball mill.

Before application, this entire mixture is diluted with 10 to 20 ml. of water. It is preferable to apply a diluted mixture twice, than a more concentrated mixture only once. Air bubbles should be avoided as much as possible. A thin rubber layer is more than sufficient. Paper properly prepared is tinted only very slightly yellow.

After the paper has been waterproofed on both sides in the manner here described, the following mixture is applied:

Mixture 2
Refined Glass Powder 30 g.
Wetting Agent Solution (5%) 30 ml.
Creamed Latex 100 ml.
Konnyaku Meal Solution (1%) 50 ml.
One single application suffices.

The solution of Konnyaku meal, either through centrifuging or sieving through a cloth, must be freed of the undissolved grains and other coarse particles. In view of the fact that Konnyaku meal is subject to a very considerable degree of enzymic and bacteriological decomposition through which it becomes inactive, the above-described mixture is best prepared shortly before being applied and, where necessary, kept in a refrigerator. The addition of "Santobrite" (sodium pentachlorophenate), as a preserving agent, is to be recommended.

When the paper has become dry, it is covered with talcum powder, and, if necessary, the edges are neatly cut. It must be remembered, however, that the paper ceases to be waterproof where it is cut or where the rubber layer has been otherwise damaged. Such places will have to be treated once more with vulcanizing latex (Mixture 1).

Paper prepared in the manner above described has been found to be very satisfactory by those to whom samples had been submitted. It can readily be written on with pencil, though it is not well adapted to ink. On the other hand it takes print very well and can also be used for typing.

The appearance of the paper depends in a large measure upon the even application of the rubber layers. The best method would be to do this mechanically. Highly sized smooth paper is less adapted to being treated than the cheaper kinds of paper. Very good results are obtained with ordinary typewriting paper.

If paper is soaked in a 6% solution of Pliolite in toluol, a good waterproof paper is obtained. The superfluous solution that has not soaked into the paper must be removed as well as possible to prevent

its producing streaks after drying.

The waterproofing is still better if 10% of solidified paraffin is added

to the Pliolite.

Paper so treated has almost the same appearance as ordinary paper.

Integral Waterproofing, Paper Pulp British Patent 528,308

A hot solution of sodium stearate (15 g.) in water (10) is added to a melt of paraffin wax (3 lb.) and mineral oil ( $\frac{1}{3}$  lb.), and rapidly stirred to give an emulsion which is used in proofing a paper pulpcork mixture.

Moisture Proofing for Paper
U. S. Patent 2,290,563

Ethyl Cellulose (Low
Viscosity) 20%

Hydrogenated Rosin 15%

Paraffin Wax
(m.p. 136° F.) 50–55%

Ester Gum 0–10%

12-Hydroxystearin 15–5%

Insectproof Paper or Felt
U. S. Patent 2,129,659
Apply to paper or felt, the following mixture:

coating or impregnant.

The above is applied molten as a

Asphalt Paint 73
Lead Arsenate, Powd. 25
Nicotine Sulphate 1
Clay, Powd. 1

Pest-Resistant Paper Australian Patent 113,158

Sheets of paper or cardboard are coated with a solution consisting of:

ated with a	solution consisting	U.
Formalin		5
Glycerin		5
Ammoniun	n Hydroxide	2
Casein		5
Water	8	3

In the process, several sheets of paper are put together, and in between, is placed one sheet coated with the above solution to which some blue coloring matter has been added. The resultant laminated sheet is then coated on both sides with a somewhat similar solution consisting of:

Formalin 10
Glycerin 2
Boric Acid 1
Sulphuric Acid 1
Water 86

The paper products so treated may be manufactured into packing boxes, bags, wrappings and similar packaging products.

Casein Coating for Paper
U. S. Patent 2,229,620
Clay 90
Calcium Carbonate 10
Casein Solution (23%) 11

Paper-Coating Emulsion
Carnauba Wax 50 lb.
Stearic Acid 7 lb.
Borax Soap 10 lb.
Water, To make 50 gal.

This is added to a clay-casein mixture to produce a coating on paper which can be readily frictioncalendered to give a high finish.

> Paper Sizing Canadian Patent 398,980 Formula No. 1

Formula 140. 1	
Scale Wax (Paraffin)	608
Rosin	1216
Stearic Acid	36
Corn Starch	122
Caustic Soda	130
Water	3168

No. 2	
Starch	20%
Sodium Silicate	15%
Glue, Animal	1%
Water, To make	100%
After treating with abo	ove, apply:
Aluminum Sulphate	12%
Water	88%

Paper Sizing Emulsion
Petroleum Resin 37
Clay, Colloidal 18
Casein 1 1/5
Caustic Soda 1
Water, To suit

#### Millson's Fluorescent Paper Coating

#### Formula No. 1

Barium Sulphate Shellac Emulsion \*

Amount to make coating of proper consistency.

Add enough fluorescent dye to make fluorescent in the desired shade and intensity. Fluorescent dyes which can be used are: rhodamine, uranine, fluorescent blue G, brilliant flavine, acriflavine, diazo scarlet PRD, yellow OX, red BX, and red 6G.

#### No. 2

Barium Sulphate 50 g. Shellac Emulsion \* 50 cc. Fluorescent dye 0.2–0.5 g.

#### Fluorescent Documents Formula No. 1

The paper to be printed, or lithographed, is dipped or rolled with a

\*Shellac emulsion is prepared by dissolving 940 grams of shellac in 5200 cc. water containing 250 cc. ammonium hydroxide.

fluorescent dye and allowed to dry. The solution of dye is made with:

Water 100 Fluorescent Dye 0.2– 0.6

The amount of dye is governed by the characteristics of the dye itself and the purpose for which it is intended. Dyes used are: acriflavine, uranine, fluorescein, rhodamine, eosine, diazo scarlet PRD, auramine, umbelliferone, and others.

#### No. 2

By printing as usual and then spraying lightly with a colorless and non-fluorescent lacquer. An ordinary atomizer may be used. Before the lacquer dries the surface is dusted lightly with anthracene or other brightly fluorescing substance. Sheets so treated are laid flat and allowed to dry in that position.

#### No. 3

The sheet is printed as usual and then dipped or sprayed with ordinary lubricating oil, petrolatum, or a benzene solution of the ester of a polyhydric alcohol (Diglycol Stearate). This method is not suited for tissue-thin maps and papers.

#### No. 4

An ordinary map which cannot be altered is placed under a layer of brightly fluorescent "cellophane." This "cellophane" can be prepared by dyeing ordinary colorless "cellophane" with organic and fluorescent dyes which retain their luminescence after drying. The "cellophane" may be stapled to the document, stuck with colorless tape, or merely laid on top.

sired.

Self Sealing Waxed Pa	per
U. S. Patent 2,233,18	
Paper is coated with a	melted
mixture of:	
Paraffin Wax	20
Crepe or Synthetic	
Rubber	2-3
Ester Gum	80
This gives a transparent,	
grease- and waterproof	
which can be heat sealed	above

Heat-Sealable Waxed Paper
for Foods
U. S. Patent 2,227,516

Paper is coated with:
Paraffin Wax
100

Rubber or Polymerized
Isobutylene
1-3

Titanium Dioxide,
Colloidal
5-15

Sodium Benzoate
1-3

70° C.

Waxed Paper Impregnant
Paraffin Wax (150° F.
M. P.) 186
Carnauba Wax No. 1
Yellow 14

Paper Milk Container Coating
U. S. Patent 2,253,655
Water 1 gal.
Glyceryl Monostearate 4 oz.
Glycerin 2 oz.

Increased Translucency of Coated Paper

The addition of 5% YUMIDOL (Sorbitol Syrup) and 1/100% of WETANOL (Wetting Agent) based on the total amount of the moisture content of the paper, will give increased transparency to paraffin wax soatings on paper. The paper should be saturated to a moisture

content of 11% and dried down to about 6%. It aids prevention of buckling of the paper on overcoating with paraffin wax, and helps give a more translucent coating.

Paper Transparentizing	Oil
Peanut Oil	6.00
Chlorinated Rubber	1.00
Toluol	4.75
Tricresyl Phosphate	0.25
Dehydrated Castor Oil	2.25
Glaurin	0.75
Dilute with toluol or xylol	as de-

Paper-Pulp Board Australian Patent 112,862

Glue 25, water 75, an aqueous solution of sodium silicate 1, betanaphthol 0.02, and Venice turpentine 0.01 lb. On top of this come more layers of paper, cloth, or like material and the whole is pressed. When the board is dry its upper side is sized with a composition containing water 40, borax 4, shellac 20 lb., and sulfonated castor oil 10 oz. Pigments may be added if desired.

#### Stereotype Mat U. S. Patent 2,112,023

Paper of suitable moisture content is treated with:

Glue	5
Urea	5
Inorganic Filler	40
Water	90
	_

It is then dried and calendered and passed through 1% formaldehyde solution for fixing.

Paper Towel and Napkin Softener
U. S. Patent 2,268,674
Urea 20
Glycerin 10

Talc 10
Water 60
Mix well and apply to paper.

Deciphering Charred Documents
The method consists in treating
the charred document with chloral
hydrate which appears to have a
clarifying action on the burned figures or letters. This is applied in the
form of a 25% solution of chloral
hydrate in alcohol. This is repeated
several times, the document being
dried at 60° C. between each application, until a mass of chloral hy-

drate crystals forms on the surface. At this stage, a similar solution, to which 10% of glycerin has been added, is applied and the document dried as before. It may then be photographed; the most suitable type of plate being a contrasty non-color sensitive one.

The method has proven equally satisfactory for typewritten and printed material. With certain modifications it has also been found to restore writing. Moreover, the reading matter is restored equally on both sides of the paper.

#### CHAPTER FIFTEEN

#### PHOTOGRAPHY

## D-7 Developer For Professional Films and Plates Stock Solution A

DUCK DOIGHOU	12			
	Avoird	upois	Metr	ic
Water, 125° F. (50° C.)	16	OZ.	500	CC.
Elon	1/4	OZ.	7.5	g.
Sodium Bisulphite	1/4	OZ.	7.5	g.
Pyro	1	OZ.	30.0	g.
Potassium Bromide	60	gr.	4.2	g.
Water, To make	32	oz.	1.0	1.
Stock Solution	В			
Water	32	OZ.	1.0	1.
Sodium Sulphite, Desiccated	5	OZ.	150.0	g.
Stock Solution	C			
Water	32	OZ.	1.0	1.
Sodium Carbonate, Desiccated	$2\frac{1}{2}$	OZ.	75.0	g.
Dissolve chemicals in the order given.	, , , , , ,	1	Cando	ne

Tray Development: Take 1 part of A, 1 part of B, 1 part of C and 8 parts of water.

Develop about 7 minutes at 68° F. (20° C.).

Tank Development: Take 1 part of A, 1 part of B, 1 part of C and 13 parts of water.

Develop about 10 minutes at 68° F. (20° C.).

This developer can be used for two or three weeks if the volume is maintained by adding fresh developer in the proportion of 1 part each of A, B, and C to 4 parts of water. It is usually necessary to increase the development time as the developer ages.

## D-8 Developer For High Contrast on Films and Plates

Water Avoirdupois Metric 750 cc.
Sodium Sulphite Desiccated 3 oz. 90.0 g.
Hydroquinone 1½ oz. 45.0 g.
Sodium Hydrovide 11/4 0Z. 37.9 g.
Potassium Bromide 1 oz. 50.0 g.
Water, To make 32 oz. 1.0 l.

Dissolve chemicals in the order given. Stir the solution thoroughly before use.

For use, take 2 parts of stock solution and 1 part of water. Develop about 2 minutes in a tray at 65° F. (18° C.).

For general use, a developer which is slightly less alkaline and gives almost as much density can be obtained by using 410 grains of sodium hydroxide per 32 ounces of stock solution (28 grams per liter) instead of the quantity given in this formula.

#### D-11 Developer For Contrast on Films and Plates

	Avoirdupois	${f Metric}$
Water, 125° F. (50° C.)	16 oz.	500 cc.
Elon	15 gr.	1.0 g.
Sodium Sulphite, Desiccated	$2\frac{1}{2}$ oz.	75.0 g.
Hydroquinone	130 gr.	9.0 g.
Sodium Carbonate, Desiccated	365 gr.	25.0 g.
Potassium Bromide	73 gr.	5.0 g.
Cold Water, To make	32 oz.	1.0 l.
Dissolve chemicals in the order given		

Develop about 5 minutes in a tank or 4 minutes in a tray at 68° F. (20° C.).

When less contrast is desired, the developer should be diluted with an equal volume of water.

### D-19 Developer For Rapid Development of Films and Plates

onto of a terroo area a taroos	
Avoirdupois	Metric
16 oz.	500 cc.
32 gr.	2.2 g.
3 oz. 90 gr.	96.0 g.
128 gr.	8.8 g.
1 oz. 265 gr.	48.0 g.
73 gr.	5.0 g.
32 oz.	1.0 l.
	Avoirdupois 16 oz. 32 gr. 3 oz. 90 gr. 128 gr. 1 oz. 265 gr. 73 gr.

Dissolve chemicals in the order given.

Develop about 5 minutes at 68° F. (20° C.) according to the contrast desired.

It is desirable to use the F-10 Fixing Bath with this developer.

## D-32 Developer For Warm Tones on Lantern Slide Plates Stock Solution A

	Avoirdupois	Metric	
Water, 125° F. (50° C.)	16 oz.	500 cc.	
Sodium Sulphite, Desiccated	90 gr.	6.3 g.	

Hydroquinone Potassium Bromide Citric Acid Cold Water, To make	50 10	gr. gr. gr.	7.0 3.5 0.7 1.0	g. g.	
	ck Solution B				
Cold Water	32	oz.	1.0	1.	
Sodium Carbonate, Desiccate	d 1	oz.	30.0	g.	
Sodium Hydroxide		gr.	4.2	g.	

Dissolve chemicals in the order given.

For use, take 1 part of A and 1 part of B. For still warmer tones, 1 part of A and 2 parts of B. Stir thoroughly before use. Develop about 5 minutes at 68° F. (20° C.).

# D-52 Developer For Warm Tone Papers Stock Solution

	Avoirdupois	Metric
Water, 125° F. (50° C.)	16 oz.	500 cc.
Elon	22 gr.	1.5 g.
Sodium Sulphite, Desiccated	$\frac{3}{4}$ oz.	22.5 g.
Hydroquinone	90 gr.	6.3 g.
Sodium Carbonate, Desiccated	$\frac{1}{2}$ oz.	15.0 g.
Potassium Bromide	22 gr.	1.5 g.
Cold Water, To make	32 oz.	1.0 l.

Dissolve chemicals in the order given.

For use, take 1 part of stock solution to 1 part of water. Develop not less than  $1\frac{1}{2}$  minutes at 70° F. (21° C.).

Note: More bromide may be added if warmer tones are desired.

#### D-61a Developer For Professional Films and Plates Stock Solution

Avoirdupois	Metric
16 oz.	500 cc.
45 gr.	3.1 g.
3 oz.	90.0 g.
30 gr.	2.1 g.
85 gr.	5.9 g.
165 gr.	11.5 g.
24 gr.	1.7 g.
32 oz.	1.0 l.
	16 oz. 45 gr. 3 oz. 30 gr. 85 gr. 165 gr. 24 gr.

Dissolve chemicals in the order given.

Tray Development: Take 1 part of stock solution to 1 part of water. Develop about 6 minutes at 68° F. (20° C.).

Tank Development: Take 1 part of stock solution and 3 parts of water. Develop about 12 minutes at 68° F. (20° C.). Add stock solution (diluted 1:3) at intervals to maintain the volume, or the replenisher, D-61R, to maintain the strength of the solution.

# D-72 Developer For Papers, Films, and Plates Stock Solution

-	Avoirdu	pois	Meti	ric
Water, 125° F. (50° C.)	16	oz.	500	cc.
Elon	45	gr.	3.1	g.
Sodium Sulphite, Desiccated	$1\frac{1}{2}$	oz.	45.0	g.
Hydroquinone	175	gr.	12.0	g.
Sodium Carbonate, Desiccated	$2\frac{1}{4}$ (	OZ.	67.5	g.
Potassium Bromide	27	gr.	1.9	g.
Water. To make	32	oz.	1.0	ĺ.

Dissolve chemicals in the order given.

For papers, dilute 1 to 2 and develop about 45 seconds at 70° F. For films and plates dilute 1 to 1 and develop about 4 minutes in a tray or 5 minutes in a tank at 68° F. (20° C.).

# $\begin{array}{c} \text{D-76 Developer} \\ \textit{For Low Contrast on Films and Plates} \end{array}$

		Avoir	rdupois	${ m Metr}$	ic
Water, 12	25° F. (50° C.)	24	oz.	750	cc.
Elon		29	9 gr.	2.0	g.
Sodium S	Sulphite, Desiccated	3 oz. 148	5 gr.	100.0	g.
Hydroqui	none	73	3 gr.	5.0	g.
Borax, G	ranular	29	gr.	2.0	g.
Water, T	o make	/ 32	2 oz.	1.0	~
- · · · · ·					

Dissolve chemicals in the order given.

Average development time about 16 minutes at 68° F. (20° C.). See individual recommendations listed for each material.

The useful life of this developer can be increased 5 to 10 times by use of the D-76R Replenisher.

A faster working developer can be obtained by increasing the quantity of borax. By increasing the borax quantity ten times, from 29 grains to 290 grains per 32 ounces (from 2 grams to 20 grams per liter), the development time will be about one-half that of regular D-76.

## D-82 Developer High Energy: For Underexposures

나는 그리고 하는 것이 없는 것이 없다면 하는 것이 없는 것이었다면 없는 것이 없는 것이었다면 없는데 없어요.			a control	irdupois	Metric
Wood Alcohol 1½ fl. oz. 48.0 cc.			24	oz.	750 cc.
	Wood Alcoho	lc	1	½ fl. oz.	48.0 ec.

Dissolve chemicals in the order given.

Develop about 5 minutes in a tray at 68° F. (20° C.).

The prepared developer does not keep more than a few days in a full bottle or about 2 hours in an open tray. If wood alcohol is omitted and the developer is diluted, the solution is not so active as in the concentrated form.

D-85 Developer
For Kodalith Films, Plates, and Papers

Avoirdu	ipois		Metr	ic
64	oz.		2.0	l.
4	oz.		120.0	g.
1	oz.		30.0	g.
150	gr.		10.5	g.
1	oz.		30.0	g.
3	oz.		90.0	g.
90	gr.		6.3	g.
1	gal.		4.0	1.
	64 4 1 150 1 3 90	Avoirdupois 64 oz. 4 oz. 1 oz. 150 gr. 1 oz. 3 oz. 90 gr. 1 gal.	64 oz. 4 oz. 1 oz. 150 gr. 1 oz. 3 oz. 90 gr.	64 oz. 2.0 4 oz. 120.0 1 oz. 30.0 150 gr. 10.5 1 oz. 30.0 3 oz. 90.0 90 gr. 6.3

Dissolve the chemicals in water which half fills a narrow mouthed bottle. After adding each chemical, place the stopper in the bottle so that only a small quantity of air is present during agitation. When all the chemicals have been dissolved, add cold water until the solution reaches the position occupied by the stopper. Insert the stopper tightly to exclude the air. Allow the developer to stand about two hours after mixing. Cool to 65° F. (18° C.) before use. If only a portion of the contents of the bottle is used at one time, it is suggested that the balance be saved by filling a bottle of smaller size which should then be stoppered tightly.

Time of Development: For line negatives, 1½ to 2 minutes at 65° F. (18° C.); for half-tone negatives, not over 2½ minutes at 65° F. (18° C.). With a correctly timed exposure, the image should appear in 30 to 45 seconds at the temperature specified.

This developer has the property of cutting off development very sharply in the low densities thus insuring clear dot formation in the half-tone negatives.

<sup>\*</sup>Use crystalline boric acid as specified. Powdered boric acid dissolves with great difficulty and its use should be avoided.

g.

0.8 g.

A long life developer.		
Water (52° C.)	750	cc.
Metol	1.5	g.
Anhyd. Sodium Sul-		
phite	45	g.
Sodium Bisulphite	1	g.
Hydroquinone	3	g.
Sodium Carbonate,		

No. 47 M-H Developer

Monohydrate Potassium Bromide Water, To make

Do not dilute for use.

Tank Development: 6-8 minutes at 20° C. with occasional agitation. For longer developing times dilute 1 part developing solution with 1 part water, and develop 12-16 minutes at 20° C.

Tray Development: 5-7 minutes at 20° C.

### No. 45 Pyro Developer

Stock solutions should be kept in stoppered bottles to prevent oxidation by air.

Solution A		
Sodium Bisulphite	9.8	g.
Pyro	60	g.
Potassium Bromide	1.1	g.
Water, To make	1	1.
Solution B		
Anhyd. Sodium Sul-		
phite	105	g.

phite 105 g. Water, To make 1 l. Solution C

Sodium Carbonate,
Monohydrate 85 g.
Water, To make 1 l.

Tank Development: Take 1 part each of solutions A, B, and C, and add 11 parts water. Develop 9-12 minutes at 20° C.

Tray Development: Take 1 part each of solutions A, B, and C, and

add 7 parts water. Develop 6–8 minutes at 20° C.

Store solutions separately until just before use.

No. 72 Glycin Developer

Water (52° C.)

For commercial films in reproduction work. Also suitable for roll, pack, and sheet film.

800 cc.

Anhyd. Sodium Sulphite 125 g.
Anhyd. Potassium
Carbonate 250 g.
Glycin 50 g.
Potassium Bromide 1 g.
Water, To make 1 l.

Tank Development: Take 1 part stock solution and 15 parts water, and develop 20-25 minutes at 20° C.

Tray Development: Take 1 part stock solution and 4 parts water, and develop 5-10 minutes at 20° C.

> High Contrast Developer U. S. Patent 2,181,861

-,-,-	,	
Water	16	oz
Hydroquinone	105	gr.
Sodium Sulphite	350	gr.
Sodium Carbonate	560	gr.
Potassium Bromide	63	gr.
Sodium Hydroxide	210	gr.
Potassium Alum	280	gr.
Use full strength at	65° F.	-,

No. 42 M-H Tank Developer A soft-working tank developer for pack, roll, and portrait films. Water (52° C.) 750 cc.

Metol 0.8 g.

Anhyd. Sodium Sulphite 45 g.

Hydroquinone 1.2 g.

Sodium Carbonate,

8 g.

Monohydrate

Potassium Metabisul-			
phite	4	g.	
Potassium Bromide	1.5	g.	
Water, To make	1	1.	
Do not dilute for use.			
Develop 15–20 minutes	at 2	20°	C.

No. 17 Borax Tank Developer Fine grain developer. Soft gradations with Agfa direct copy, portrait, and press films.

Water (52° C.) 750 cc. 1.5 g. Metol Anhyd. Sodium Sulphite 80 g. Hydroquinone 3 g. 3 Borax g. Potassium Bromide 0.5 g. Water, To make 1. Do not dilute for use.

Tank Development: 10-15 minutes at 20° C. for fine grain films. 12-20 minutes at 20° C. for direct copy and portrait sheet films.

Tray Development: 8-12 minutes at 20° C. depending on film and density desired.

No. 70 Hydroquinone Caustic Developer

For process film used in reproduction work.

Solution A	
Water (52° C.)	750 cc.
Hydroquinone	25 g.
Potassium Metabisul-	
phite	25 g.
Potassium Bromide	25 g.
Cold Water	1 1.
Solution B	
Cold Water	1 1.
Sodium Hydroxide	36 g.
Mix equal parts of	A and B
mmediately before use	e. Develop
within 3 minutes at 20°	C.

No. 22 M-H Title Developer For development of cine title film and positive film to obtain high contrast.

Water (52° C.)	750	cc.
Metol	0.8	g.
Anhyd. Sodium Sul-		_
phite	40	g.
Hydroquinone	8	g.
Sodium Carbonate,		
Monohydrate	50	g.
Potassium Bromide	5	g.
Water, To make	1	1.
Do not dilute for use.		
Develop 5-8 minutes	at 20°	C.

No. 64 Rapid M-H Tropical Developer

A clean working developer, useful for rapid development or development at high temperatures.

	Water (52° C.)	750	cc.	
	Metol	2.5	g.	
	Anhyd. Sodium Sul-			
	phite	25	g.	
	Hydroquinone	6.5	g.	
	Sodium Carbonate,			
	Monohydrate	16	g.	
	Potassium Bromide	1	g.	
	Water, To make	1	1.	
	Do not dilute for use.			
	Develop 3-4 minutes	at 20°	C., 6	)T
_	-3 minutes at 29° C.			

No. 90 High Contrast M-H Tray Developer

Particularly designed for use with commercial and process films to produce negatives of brilliant contrast.

thoo modulation or warrand		
Water (52° C.)	750	cc.
Metol	5	g.
Anhyd. Sodium Sul-		
phite	40	g.
Hydroquinone	6	g.
Sodium Carbonate,		
Monohydrate	40	g.

Potassium Bromide 3 g. Water, To make 1 l.	Hydroquinone Sodium Carbonate,	2 g.
Do not dilute for use.	Monohydrate	15 g.
Develop 4–6 minutes at 20° C.	Potassium Bromide	1 g.
	Water, To make	1 1.
No. 40 M-H Tray Developer	Do not dilute for use.	
A brilliant developer for roll,	Develop 4-6 minutes	
pack, and sheet film.	20,0105 1 0 111114008	
Water (52° C.) 900 cc.	Rapid Develo	ner
Metol 4.5 g.	U. S. Patent 2,13	
Anhyd. Sodium Sul-	Monochloroquinol	1.500
phite 54 g.	Metol	1.500
Hydroquinone 7.5 g.	Potassium Sulphocya	
Sodium Carbonate,	nide	0.003
Monohydrate 54 g.	Sodium Sulphite	80.000
Potassium Bromide 3 g.	Quinol	5.000
Water, To make 1 l.	Borax	5.000
For use dilute 1 part stock solu-	Water	1000.000
tion with 2 parts water.	vv abel	1000.000
Develop 4–5 minutes at 20° C.	High Speed Day	-lonon
Develop 4-5 influtes at 20°C.	$egin{aligned}  ext{High Speed Deve} \ Champlin \ No. \end{aligned}$	
No. 61 M-H Tray Developer	Metol	10 gr.
For use with commercial films to	Sodium Sulphite 1	466 gr.
give negatives of normal contrast.	Diethylene Glycol	
Water (52° C.) 750 cc.	Triethanolamine	30 min.
Metol 1 g.	Chlorohydroquinone	
Anhyd. Sodium Sul-	Water, To make	32 fl. oz.
phite 15 g.	Develop 5.5–6.5 minu	

# D-61R Replenisher For D-61a Developer Stock Solution A

Stoom Solution	/AA AA		
	Avoird	upois	Metric
Water, 125° F. (50° C.)	96	oz.	3.0 1.
Elon	85	gr.	5.9 g.
Sodium Sulphite, Desiccated	6	oz.	180.0 g.
Sodium Bisulphite	55	gr.	3.8 g.
Hydroquinone	170	gr.	11.9 g.
Potassium Bromide	45	gr.	3.1 g.
Cold Water, To make	$1\frac{1}{2}$	gal.	6.0 l.
Stock Solution	on B		
Sodium Carbonate, Desiccated	8	OZ.	240.0 g.
Water, To make	64	oz.	2.0 1.
Dissolve chemicals in the order given			

Dissolve chemicals in the order given.

For use take 3 parts of A and 1 part of B and add to the tank of developer as needed. Do not mix solutions A and B until ready to use.

# D-76R Replenisher For D-76 Developer

		Avoird	upois	Metric	
Water, 125° F. (50° C.)		24	oz.	750.0 cc.	
Elon		44	gr.	3.0 g.	
Sodium Sulphite, Desiccated	3 oz.	145	gr.	100.0 g.	
Hydroquinone		1/4	OZ.	7.5 g.	
Borax, Granular		290	gr.	20.0 g.	
Water, To make		32	oz.	1.0 l.	

Dissolve chemicals in the order given.

Use the replenisher without dilution and add to the tank to maintain the level of the solution.

#### No. 17 Replenisher

Add 14 to 21 cc. replenisher to No. 17 for each 36 exposure 35 mm. film developed. Maintain original volume of developer, discarding if necessary some used developer. No increase in original developing time is necessary.

Water (52° C.)	750	cc.
Metol	2.2	g.
Anhyd. Sodium Sul-		
phite	80	g.
Hydroquinone	4.5	g.
Borax	18	g.
Water, To make	1	1.

## No. 47 Replenisher

Add 14-21 cc. replenisher to No. 47 for each 36-exposure 35 mm. film developed. Maintain original volume of developer, discarding some used developer if necessary. No increase in original developing time is necessary.

Water (52° C.)	750	cc.
Metol	3	g.
Anhyd. Sodium Sul-		, T
phite	45	g.
Sodium Bisulphite	2	g.

6 g.
12 g.
1 1.

#### Fine Grain Developer

This formula gives satisfactory enlargements up to 5 diameters.

	4 Chloro-2-methylami	no-	
	phenol	10 g.	
	Sodium Sulphite	25 g.	
	Potassium Carbonate	50 g.	
	Potassium Bromide	1 g.	
	Water	1 l.	
	Develop at 18° C. for	10-15 mir.	ŀ
u	tes.		

## Blue Print Developer

A	
Hydrogen Peroxide	10
Sulphuric Acid, Diluted	10
Water	100
В	
Chrome Alum	1
Potassium Citrate	2
Water	100

To use, mix 100 parts (vol.) of A with 50 of B, for developing blue prints made with ferric ammonium oxalate and potassium ferricyanide.

#### Direct Reversal Process on Paper

The steps in processing exposed Eastman Direct Positive Paper and the times required for each chemical treatment are as follows:

1. Development (45 sec.—1 min.) D-88

2. Bleach (30 sec.) R-9

3. Clearing (30 sec.) CB-1

4. Re-exposure to light

5. Redevelopment (30 sec.) Black and White, D-88; Sepia, T-19

6. Fixation (if desired, but not necessary) (30 sec.) F-1

It is necessary to wash the prints well in running water for at least 15 seconds between the different solutions. Where the recommended redeveloper for black and white is used, it is necessary to expose the paper to artificial light or daylight before redevelopment. If convenient, the white light can be turned on as soon as the prints are placed in the clearing bath. If brown tones are desired, the sulphide redeveloper may be used when it will be unnecessary to use white light.

Prints of slightly greater brilliancy may be secured by fixing in the regular fixing bath (F-1) after redevelopment in D-88. It is important to wash for at least 10 minutes to insure removal of the fixing bath from the print. It is not necessary to use the fixing bath after the sulphide redeveloper.

### D-88 Developer

For Development and Redevelopment of Direct Positive Paper

	Avoirdupois	${f Metric}$
Water, 125° F. (50° C.)	96 oz.	750.0 cc.
Sodium Sulphite, Desiccated	$6\frac{1}{2}$ oz.	48.8 g.
Hydroquinone	$3\frac{1}{4}$ oz.	24.4 g.
Boric Acid Crystals *	$\frac{3}{4}$ oz.	5.6 g.
Potassium Bromide	150 gr.	2.6 g.
Sodium Hydroxide †	$3\frac{1}{4}$ oz.	24.4 g.
Cold Water, To make	1 gal.	1.0 l.
~		

Dissolve chemicals in the order given.

Use full strength at 70° F. (21° C.). Develop 45 seconds to 1 minute.

#### T-19 Sulphide Redeveloper For Direct Positive Paper

10, 10,000 1	course a aper	
	Avoirdupois	$\mathbf{Metric}$
Sodium Sulphide, Desiccated	290 gr.	20.0 g.
Water, To make	32 oz.	1.0 l.
Use full strength at 65° to 70° F.	(18° to 21° C.).	

\* Crystalline boric acid should be used as specified. Powdered boric acid dissolves

only with great difficulty, and its use should be avoided.

† It is desirable to dissolve the caustic soda in a small volume of water in a separate container and then add it to the solution of the other constituents. Then dilute the whole to the required volume. If a glass container is employed in dissolving the caustic soda, the solution should be stirred constantly until the soda is dissolved, to prevent cracking the glass container by the heat evolved.

#### R-9 Bleach Bath For Direct Positive Paper

	Avoirdupois	Metric
Water	1 gal.	1.0 1.
Potassium Bichromate	$1\frac{1}{4}$ oz.	9.4 g.
Sulphuric Acid, C.P.	$1\frac{1}{2}$ fl. oz.	12.0 cc.

Use full strength at 65° to 70° F. (18° to 21° C.). For more rapid bleaching, however, the quantities of acid and bichromate may be increased.

# CB-1 Clearing Bath For Direct Positive Paper

	Avoirdupois	Metric
Sodium Sulphite, Dessicated	12 oz.	90.0 g.
Water, To make	1 gal.	1.0 1.
Use full strength at 65° to 70° F. (1	8° to 21° C.).	

Motion Picture Positi	ve Film
Developer	
Sodium Thiosulphate	100 g.
Potassium Bromide	35 g.
Sodium Pyrosulphite	165 g.

#### Intensifiers

If negatives need intensification or reduction, it is best to give them such treatment immediately after they have been washed. Much time is saved and the negatives, when dry, are ready for finishing.

Precautions: Stains are sometimes produced during intensification or reduction unless the following precautions are observed: 1. The negative should be fixed and washed thoroughly before treatment and be free of scum or stain. 2. It should be hardened in the formalin hardener SH-1 before the intensification or reduction treatment. 3. Only one negative should be handled at a time and it should be agitated thoroughly during the treatment. Following the treatment, the negative should be washed thoroughly and wiped off carefully before drying.

The mercury intensifier is recommended where extreme intensification is desired but where permanence of the resulting image is not essential. If permanence is essential, either the chromium or the silver intensifier should be used.

# In-1 Mercury Intensifier For Films and Plates

Bleach the negative in the following solution until it is white, then wash thoroughly.

	Avoirdupois	Metric
Potassium Bromide	3/4 oz.	22.5 g.
Mercuric Chloride	$\frac{3}{4}$ oz.	22.5 g.
Water, To make	32 oz.	1.0 l.

The negative can be blackened with 10% sulphite solution, a developing solution, such as D-72 diluted to 1 to 2, or 10% ammonia [1 part concentrated ammonia (28%) to 9 parts water], these giving progressively greater density in the order given. To increase contrast greatly, treat with the following solution:

	Solution A				
		Avoird	upois	Met	ric
Water		16	OZ.	500.0	cc.
Sodium Cyanide *	•	$\frac{1}{2}$	oz.	15.0	g.
	Solution B				
Water		16	OZ.	500.0	cc.
Silver Nitrate Crystals		$\frac{3}{4}$	oz.	22.5	g.
	7 7 17 17	• , ,	CL III	1 17	

To prepare the intensifier, add the silver nitrate, Solution B, to the cyanide, Solution A, until a permanent precipitate is just produced; allow the mixture to stand a short time and filter. This is called Monckhoven's intensifier.

Redevelopment cannot be controlled as with the chromium intensifier, In-4, but must go to completion.

\*Warning: Cyanide is a deadly poison and should be handled with extreme care. Use rubber gloves and avoid exposure to its fumes. Cyanide reacts with acid to form poisonous hydrogen cyanide gas. When discarding a solution containing cyanide, always run water to flush it out of the sink quickly. Cyanide solutions should never be used in poorly ventilated rooms.

## Mercury Intensifier

For increasing the printing density of thin, flat negatives.

Potassium Bromide	10 g.
Mercuric Chloride	10 g.
Water To make	1 1.

Negatives to be intensified must be thoroughly washed first, or yellow stains may result on the intensified negative. Immerse film in above solution until thoroughly bleached, then wash in water containing a few drops of hydrochloric acid. Redevelop the bleached negatives in 5% sodium sulphite or any standard developer. Surface scum that forms during storage of the bleaching solution does not affect the bleacher, but should be removed before using the solution.

Chromium Intensifier
Convenient to use and gives permanent results.

Potassium Bichromate 9 g.

Hydrochloric Acid 6 cc.

Water, To make 1 l.

Immerse negative until bleached, then wash 5 minutes in water, and redevelop in bright but diffused light in a metol-hydroquinone developer such as No. 47. Wash 15 minutes before drying. Intensification may be repeated for increased effect.

Any blue coloration of the film base after intensification may be removed easily by washing the film 2-3 seconds in water containing a few drops of ammonia, or in a 5% solution of potassium metabisulphite, or in a 5% solution of sodium sulphite. This should be followed by thorough washing in water.

# In-4 Chromium Intensifier For Films and Plates Stock Solution

	Avoirdupois	Metric
Potassium Bichromate	3 oz.	90.0 g.
Hydrochloric Acid, C.P.	2 fl. oz.	64.0 cc.
Water, To make	32 oz.	1.0 l.

For use, take 1 part of stock solution to 10 parts of water.

Harden the negative first in the formalin hardener SH-1. Bleach thoroughly at 65° to 70° F. (18° to 21° C.), then wash five minutes and redevelop fully in artificial light or daylight (not sunlight) in any quick-acting, non-staining developer which does not contain an excess of sulphite; for example, about 10 minutes at 68° F. (20° C.) in D-72, diluted 1:3. Then rinse, fix for five minutes, and wash thoroughly. Greater intensification can be secured by repeating the process.

Warning: Developers containing a high concentration of sulphite, such as D-76, are not suitable for redevelopment, since the sulphite tends to dissolve the bleached image before the developing agents have time to act on it.

Negatives intensified with chromium are more permanent than those intensified with mercury.

Note: See precautions on handling negatives given above.

# In-5 Silver Intensifier For Films and Plates

The following formula is the only intensifier known that will not change the color of the image on positive film on projection. It gives proportional intensification and is easily controlled by varying the time of treatment. The formula is equally suitable for positive and negative film.

Stock Solution No. 1 (Store in a brown bottle)

(Store in a pro	wn bottie)	
	Avoirdupois	Metric
Silver Nitrate Crystals	2 oz.	60.0 g.
Distilled Water, To make	32 oz.	1.0 l.
Stock Soluti	on No. 2	
Sodium Sulphite, Desiccated	2 oz.	60.0 g.
Water, To make	32 oz.	1.0 l.
Stock Soluti	on No. 3	
Sodium Thiosulphate	$3\frac{1}{2}$ oz.	105.0 g.
Water, To make	32 oz.	1.0 l.
Stock Soluti	on No. 4	
Sodium Sulphite, Desiccated	$\frac{1}{2}$ oz.	15.0 g.
Elon	350 gr.	24.0 g.
Water, To make	96 oz.	3.0 l.
,		

Note: See precautions on handling negatives given above.

Prepare the intensifier solution for use as follows: Slowly add 1 part of Solution No. 2 to 1 part of Solution No. 1, shaking or stirring to obtain thorough mixing. The white precipitate which appears is then dissolved by the addition of 1 part of Solution No. 3. Allow the resulting solution to stand a few minutes until clear. Then add, with stirring, 3 parts of Solution No. 4. The intensifier is then ready for use and the film should be treated immediately. The mixed intensifier solution is stable for approximately 30 minutes at 70° F. (21° C.).

The degree of intensification obtained depends upon the time of treatment which should not exceed 25 minutes. After intensification, immerse the film for 2 minutes with agitation in a plain 30% hypo solution. Then

wash thoroughly.

The stability of the mixed intensifier solution and the rate of intensification are very sensitive to changes in the thiosulphate concentration. A more active but less stable working solution may be obtained by using a stock solution No. 3 prepared with 3 ounces of hypo per 32 ounces (90 grams per liter) instead of the quantity in the formula. The directions for preparing the working solution are the same as before but the mixed intensifier will not keep over 20 minutes at 70° F. (21° C.).

For best results, the intensifier should be used in artificial light; the solution tends to form a precipitate of silver quite rapidly when exposed

directly to sunlight.

Re-development Intensifier

A simple method of intensification for negatives consists of bleaching in the ferricyanide and bromide formula used for the sepia toning of prints (T-7a) and blackening with sodium sulphide exactly as in print toning.

Monckhoven's Intensifier
For reproduction film. Gives great
intensification and contrast for line
drawings and half-tone reproduction work.

Solution A	
Potassium Bromide	23 g.
Mercuric Chloride	
(Poison)	23 g.
Water, To make	1 l.
Solution B	
Cold Water	1 l.
Potassium Cyanide	
(Poison)	23 g.
Silver Nitrate	23 g.
The silver nitrate and	potassiun

cyanide should be dissolved in sepa-

rate lots of water, and the former added to the latter until a permanent precipitate is produced. Allow to stand 15 minutes and filter, the filtrate being Solution B.

Place negatives in Solution A until bleached through. Then rinse and place in Solution B. If intensification is carried too far, the negative may be reduced with a weak solution of hypo.

Wet Collodion Intensification As a wartime measure to conserve potassium bromide and iodine, the developed negative can be bleached in:

Sodium Bromide	4
Copper Sulphate	3
Water	80

The bleached image is then blackened as usual with a silver nitrate solution, and the blackened negative in turn bleached with:

Ammonium Bichromate 1 Hydrochloric Acid 2 Water 80

Reduction ("cutting") of the negative can be carried out with a very dilute solution of plain hypo, and the negative finally blackened with sodium sulphide solution.

Uranium Intensifier for Movie Film

Many times when amateur movie film is returned from processing, the images are washed out and dull, due many times to overexposure, or shooting against the light. To correct the images and make them project better, use the following mix-ture:

Potassium Ferricyanide 3 g.
Uranium Nitrate 3 g.
Sodium Acetate 3 g.
Glacial Acetic Acid 30 cc.
Distilled Water 300 cc.

Mix all the above materials and soak the movie film in this solution for 3 to 5 minutes depending on the depth of color desired. Now remove from the toning bath and wash in water for 5 minutes. Dry between cellulose sponges and hang up to dry. This intensifier works best when prepared freshly and will give fine grain images which project very nicely. The above formula gives brownish-red images, on black and white film, but for most purposes this make no difference, and can be used for titles for color films.

#### Reducers

Reducer formulae may be classified into three types as follows:

A. Subtractive or cutting reducers which remove equal quantities of silver from the high, intermediate, and low densities respectively. They have the effect of clearing up the shadow areas and therefore appear to increase the image contrast but they do not change gamma. They are useful for treating fogged or overexposed images.

R-2 Acid Permanganate

R-4 Farmer's Reducer (Amateur)

R-4a Farmer's Reducer (Professional)

B. Proportional reducers which remove density in an amount which is proportional to the original density. They therefore lower gamma and also visual contrast and correct for overdevelopment.

R-4b Two-Solution Farmer's ReducerR-5 Acid Permanganate-Persulphate

R-8 Modified Belitzski (also a cutting reducer)

C. Super-proportional reducers which remove density increments which bear a greater proportion to the original density as the magnitude of the original density increases. They therefore reduce the highlight densities without destroying shadow detail and are useful for treating overdeveloped negatives of contrasty subjects.

R-1 Acid-Persulphate

# R-1 Reducer Super-Proportional: For Great Reduction of Contrast

#### Stock Solution

•	Avoirdupois	Metric
Water	32 oz.	1.0 l.
Ammonium Persulphate	2 oz.	60.0 g.
Sulphuric Acid, C.P.*	3/4 dr.	3.0 cc.

For use, take 1 part stock solution and 2 parts water.

Treat the negative in the formalin hardener (SH-1) and wash thoroughly before reduction. When reduction is complete, immerse in an acid fixing bath for a few minutes and wash thoroughly before drying. If reduction is too rapid, dilute the solution with a further volume of water.

Note: See precautions on handling negatives given above.

#### R-2 Reducer

## Cutting: For Clearing Shadow Areas

#### Stock Solution A

	Avoirdupois	s Metric
Water	32 oz.	1.0 l.
Potassium Permanganate	$1\frac{3}{4}$ oz.	52.5 g.
Stock	Solution B	
Water	32 oz.	1.0 l.
Sulphuric Acid, C.P.	1 fl. oz	. 32.0 cc.

The best method of dissolving the permanganate crystals in Solution A is to use a small volume of hot water (about 180° F.) (82° C.) and shake or stir the solution vigorously until completely dissolved; then dilute to volume with cold water. When preparing Stock Solution B, always add the sulphuric acid to the water slowly with stirring and never the water to the acid, otherwise the solution may boil and spatter the acid on the hands or face causing serious burns.

The negative must be thoroughly washed to remove all traces of hypo before it is reduced. For use, take 1 part A, 2 parts B and 64 parts of water. When the negative has been reduced sufficiently place it in a fresh acid fixing bath (F-5) for a few minutes, to remove yellow stains, then wash thoroughly.

If reduction is too rapid, use a larger volume of water when diluting the solution for use. This solution should not be used as a stain remover as it

Note: See precautions on handling negatives given above.

<sup>\*</sup>Always add the sulphuric acid to the water slowly with stirring and never the water to the acid, otherwise the solution may boil and spatter the acid on the hands or face causing serious burns.

has a tendency to attack the image before it removes the stain. Use S-6 for removing developer stains.

Note: If a scum forms on the top of the permanganate solution or a reddish curd appears in the solution, it is because the negative has not been sufficiently washed to remove all hypo, or because the permanganate solution has been contaminated by hypo. The separate solutions will keep and work perfectly for a considerable time if proper precautions against contamination are observed. The two solutions should not be combined until immediately before use. They will not keep long in combination.

A close observance of the foregoing instructions is important. Otherwise an iridescent scum will sometimes appear on the reduced negatives after they are dry; and this is difficult, if not impossible, to remove.

# R-4 Farmer's Reducer Cutting: For Amateur Use for Clearing Shadow Areas Solution A

	Avoirdupois	Metric
Water	1 oz.	32.0 cc.
Potassium Ferricyanide	15 gr.	1.0 g.
Sol	ution B	,
Water	32 oz.	1.0 1.
Sodium Thiosulphate	1 oz.	30.0 g.

Add A to B and immediately pour over the negative to be reduced. The reducer solution decomposes rapidly after mixing together the A and B solutions and therefore should be used at once. When the negative has been reduced sufficiently, wash thoroughly before drying. Local areas may be reduced by applying the solution with a cotton pad.

This formula is less active than R-4a.

Note: See precautions on handling negatives given above.

# R-4a Farmer's Reducer Cutting: For Clearing Shadow Areas Stock Solution A

,- *	Avoirdupois	Metric
Potassium Ferricyanide	$1\frac{1}{4}$ oz.	37.5 g.
Water, To make	16 oz.	500 cc.
Stock S	Solution B	
Sodium Thiosulphate	16 oz.	480.0 g.
Water, To make	64 oz.	2.0 1.

For use take: Stock Solution A, 1 ounce (30 cc.), stock Solution B, 4 ounces (120 cc.), and water to make 32 ounces (1 liter). Add A to B, then add the water and pour the mixed solution at once over the negative to be reduced, which preferably should be contained in a white tray. Watch closely. When the negative has been reduced sufficiently, wash thoroughly before drying.

Solutions A and B should not be combined until they are to be used. They will not keep long in combination.

Note: See precautions on handling negatives given above.

#### R-4b Farmer's Reducer

Proportional: For Lowering Contrast

Farmer's Reducer also may be used as a two-bath formula by treating the negative in the ferricyanide solution first and subsequently in the hypo solution. This method gives almost proportional reduction and corrects for over-development. The single solution Farmer's Reducer gives only cutting reduction and corrects for overexposure.

Stock	Solution	A
DUUL	DOLGUIOT.	

	Avoirdupois	${f Metric}$
Potassium Ferricyanide	½ oz.	7.5 g.
Water, To make	32 oz.	1.0 l.
Stock Sol	ution B	
Sodium Thiosulphate	$6\frac{3}{4}$ oz.	200.0 g.
Water. To make	32 oz.	1.0 1.

Treat the negatives in Solution A with uniform agitation for 1 to 4 minutes at 65–70° F. (18–21° C.) depending on the degree of reduction desired. Then immerse them in Solution B for 5 minutes and wash thoroughly. The process may be repeated if more reduction is desired. For the reduction of general fog, one part of Solution A should be diluted with one part of water.

Note: See precautions on handling negatives given above.

#### R-5 Reducer

#### Proportional: For Lowering Contrast Stock Solution A

	Avoirdupois	${f Metric}$
Water	32 oz.	1.0 l.
Potassium Permanganate	4 gr.	0.3 g.
Sulphuric Acid (10% Solution) *	$\frac{1}{2}$ fl. oz.	16.0 cc.
Stock So	olution B	
Water	96 oz.	3.0 1.
Ammonium Persulphate	3 oz.	90.0 g.

For use, take one part of Solution A to three parts of Solution B. When sufficient reduction is secured the negative should be cleared in a 1% solution of sodium bisulphite. Wash the negative thoroughly before drying.

\*To make a 10% solution of sulphuric acid, take 1 part of concentrated acid and add it to 9 parts of water, slowly with stirring. Never add the water to the acid, because the solution may boil and spatter the acid on the hands or face, causing serious burns.

Note: See precautions on handling negatives given above.

#### R-8 Reducer

Semi-Proportional: For Lowering Contrast and Clearing Shadow Areas This is the only single solution reducer which keeps well in a tank.

	Avoirdu	pois	Met	ric
Water, 125° F. (50° C.)	24	oz.	750	cc.
Ferric Chloride	365	gr.	25	g.

Potassium Citrate * Sodium Sulphite, Desiccated Citric Acid Sodium Thiogulabete	2½ oz. 1 oz. 290 gr.	75 g. 30 g. 20 g.
Sodium Thiosulphate	$6\frac{3}{4}$ oz.	200 g.
Water, To make	32 oz.	1 l.

Dissolve chemicals in the order given.

Use full strength for maximum rate of reduction. Treat negatives 1 to 10 minutes at 65° to 70° F. (18° to 21° C.). Then wash thoroughly. If a slower action is desired, dilute one part of solution with one part of water. The reducer is especially recommended for the treatment of dense, contrasty negatives.

Note: See precautions on handling negatives given above.

#### Flattening Reducer

Used for lessening density and contrast of heavy negatives.

Potassium	Ferricyanide		35	g.
Potassium	Bromide		10	g.
Water, To	make		1	1.

Bleach in the solution and after thorough washing redevelop to the desired density and contrast in Agfa No. 47 or some other negative developer. Conduct operation in subdued light.

#### TONING FORMULAE

Three distinct methods of toning are possible:

(1) Toning by direct development.

(2) Toning by replacement of the silver image with inorganic salts (metal tones).

(3) Toning with dyes (dye tones).

1. Toning by Direct Development

The color of the silver image produced by development is determined by the size and condition of the silver particles composing the image. It is possible to control the size of these particles and therefore the color of the image by modifying the nature of the developer.

The range of colors obtainable, however, is not very great and it is usually easier and more certain to produce such slight modifications of color either by delicate dye tinting or by giving a short immersion in one of the diluted toning baths.

2. Toning by Replacement of the Silver Image with Inorganic Salts

Since most toning processes intensify the original silver image, it is best to commence with a slide or positive print which is somewhat on the thin side. Experience will dictate the most suitable image quality to yield the best results with various toning processes.

<sup>\*</sup>Sodium citrate should not be used in place of potassium citrate because the rate of reduction is slowed up considerably.

#### 3. Dye Toning

It is not possible to obtain more than a limited number of tones by the use of colored inorganic compounds owing to the limited number of such compounds. Certain inorganic compounds, however, such as silver ferrocyanide, can be used as mordants for basic dyes such as Victoria Green, Safranine, etc. If, therefore, a silver image is converted more or less to a silver ferrocyanide image and then immersed in a solution of a basic dye,

a mordanted dye image is produced.

Immersion of a silver image in an acid solution of potassium ferricyanide will produce a satisfactory mordant image of silver ferrocyanide but, if the image is left too long in the acid ferricyanide bath, the mordanting action of the silver ferrocyanide image is destroyed. By incorporating uranium (uranyl) nitrate in the bath, brown uranyl ferrocyanide is deposited along with the silver ferrocyanide which serves as a signal to indicate when the film should be removed from the mordanting bath. When the black silver image just commences to turn brown, sufficient silver ferrocyanide has been formed to mordant basic dyes strongly but, if the time of immersion is prolonged so that the image is appreciably colored, it will not mordant as well.

## Stability of Solutions

All toning baths containing potassium ferricyanide are sensitive to light, the ferricyanide being reduced to ferrocyanide, with the resulting formation of a sludge of the metallic ferrocyanide. When not in use, tanks should be covered to prevent exposure to daylight, and small volumes of solution should be placed in dark brown bottles.

It is important that no metallic surface, however small, come in contact with the solution. Glass trays are best, but enameled trays can be used if they are in good condition, with no cracks or chipped spots. Wooden or stoneware tanks with hard rubber faucets should be used for large scale work. Motion picture film should be wound on wooden racks, free of metal pegs.

## Toning Baths for Papers

While most of the toning processes are quite simple, the final tone obtained is affected by a number of factors. Successful production of the desired tone depends upon the proper control of every step from the exposure of the sensitive paper to the final drying of the tone print. Therefore, it should be emphasized that uniform quality of black-and-white prints is a prerequisite to consistent success in toning.

## Sepia Tones on Prints

A shade of brown is suitable for many subjects. There are three principal methods of producing pleasing sepia tones. These are: (1) production of brown silver sulphide by direct combination of silver and sulphur with the T-1a Hypo-Alum Sepia Toner; (2) production of silver sulphide indirectly by oxidation of the silver to silver bromide which is then con-

verted to silver sulphide with the T-7a Sulphide Sepia Toner; and (3) deposition of gold on the silver image, with the T-21 Nelson Gold Toner. The different chemical actions of these three processes provide for the treatment of all brands of photographic papers.

## T-1a Hypo Alum Sepia Toner For Warm Tone Papers

	Avoirdupois	Met	ric
Cold Water	90 oz.	2800	cc.
Sodium Thiosulphate	16 oz.	480	g.
Dissolve thoroughly, and add the following	ing solution:		
Hot Water 160° F. (70° C.)	20 oz.	640	cc.
Potassium Alum	4 oz.	120	g.
F773			_

Then add the following solution (including precipitate) slowly to the hypo-alum solution while stirring the latter rapidly.

Cold Water	2	oz.	64.0	ec.
Silver Nitrate Crystals	60	gr.	4.2	g.
Sodium Chloride	60	gr.	4.2	g.
After combining above solutions				
Add Water, To make	1	gal.	4.0	1.

For use, pour into a tray supported in a water bath and heat to 120° F. (49° C.). At this temperature prints will tone in 12 to 15 minutes depending on the type of paper. Never use the solution at a temperature above 120° F. (49° C.). Blisters and stains may result. Toning should not be continued longer than 20 minutes at 120° F. (49° C.).

In order to produce good sepia tones, the prints should be exposed so that the print is slightly darker than normal when developed normally

 $(1\frac{1}{2}$  to 2 minutes).

The prints to be toned should be fixed thoroughly and washed for a few minutes before being placed in the toning bath. Dry prints should be soaked thoroughly in water. To insure even toning, the prints should be immersed completely, and separated occasionally, especially during the first few minutes.

After prints are toned, they should be wiped with a soft sponge and warm water to remove any sediment, and washed for one hour in running water.

The bath is particularly suitable for use with papers having slightly warm tones, such as Vitava Athena and Azo, in which the images are composed of comparatively fine grains. Vitava Opal and Vitava Projection, also tone well in T-1a.

Note: The Silver nitrate should be dissolved completely before adding the sodium chloride and immediately afterward, the solution containing the milky white precipitate should be added to the hypo-alum solution as directed above. The formation of a black precipitate in no way impairs the toning action of the bath if proper manipulation technique is used.

H	ypo Alum Toner		
	Solution A		
Water		2350	cc.
Hypo		450	g.
	Solution B		
Water		30	cc.
Silver Nitrate		1.25	g.
	Solution C		
Water		30	cc.
Potassium Iodide		2.5	g.

Add B to A and then add C. Then add 105 g. of potassium alum and heat to boiling, or until solution becomes milky.

Tone prints 20-60 min. at 43-52° C., agitating slightly until toning is complete. Be sure blacks are entirely converted before removing prints from toning bath, otherwise double tones will result.

T-7a Sulphide Sepia Toner For Cold Tone Papers Stock Bleaching Solution A

	Avoird	lupois	Metric
Potassium Ferricyanide	$2\frac{1}{2}$	oz.	75 g.
Potassium Bromide	$2\frac{1}{2}$	oz.	75 g.
Potassium Oxalate	$6\frac{1}{2}$	oz.	195 g.
Acetic Acid (28% Pure) *	$1\frac{1}{4}$	fl. oz.	40 cc.
Water	64	oz.	2 l.
Stock Toning Sol	ution B		
Sodium Sulphide, Desiccated	$1\frac{1}{2}$	oz.	45 g.
Water	16	oz.	500 cc.
Prepare Bleaching Bath as follows:			
Stock Solution A	16	OZ.	500 cc.
Water	16	OZ.	500 cc.
Prepare Toner as follows:			
Stock Solution B	4	OZ.	125 cc.
Water, To make	32	OZ.	1 l.
FT1			

The print to be toned should first be washed thoroughly. Place it in the Bleaching Bath, and allow it to remain until only faint traces of the half-tones are left and the black of the shadows has disappeared. This operation will take about one minute.

Rinse thoroughly in clean cold water.

Place in Toner Solution until original detail returns. This will require about 30 seconds. Give the print an immediate and thorough water rinse; then immerse it for five minutes in a hardening bath composed of 1 part

\*To make 28% acetic acid from glacial acetic acid, dilute 3 parts of glacial acetic acid with 8 parts of water.

NOTE: Particular care should be taken not to use trays with any iron exposed, otherwise blue spots may result.

of the stock hardener F-1a and 16 parts of water. The color and gradation of the finished print will not be affected by the use of this hardening bath. Remove the print from the hardener bath and wash for one-half hour in running water.

This toning bath tends to give warm tones, an advantage with papers such as Velox. With the inherently warm-tone papers, such as Azo, Vitava Athena, Vitava Opal, Vitava Projection, and Kodalure, it tends to produce rather disagreeable yellow tones. Kodabromide tones well in this bath.

#### T-21 Nelson Gold Toner For Warm Tone Papers

The Nelson Gold Toner has the advantage that a variety of excellent brown tones may be obtained by varying the time of toning, that is, the prints may be removed at any time from the bath when the desired color is reached.

#### Stock Solution A

	Avoirdupois	Metric
Warm Water 125° F. (50° C.)	1 gal.	4.0 l.
Sodium Thiosulphate (Hypo)	2 lb.	960.0 g.
Ammonium Persulphate	4 oz.	120.0 g.

Dissolve the hypo completely before adding the ammonium persulphate. Stir the bath vigorously while adding the ammonium persulphate. If the bath does not turn milky, increase the temperature until it does.

Prepare the following solution and add it (including precipitate) slowly to the hypo-persulphate solution while stirring the latter rapidly. The bath must be cool when these solutions are added together.

Cold Water	2 oz.	64.0 cc.
Silver Nitrate Crystals	75 gr.	5.2 g.
Sodium Chloride	75 gr.	5.2 g.

Note: The silver nitrate should be dissolved completely before adding the sodium chloride.

#### Stock Solution B

Water	8 oz.	250.0 cc.
Gold Chloride	15 gr.	1.0 g.

For use, add 4 ounces (125 cc.) of Solution B slowly to the entire quantity of Solution A while stirring the latter rapidly.

The bath should not be used until after it has become cold and has formed

a sediment. Then pour off the clear liquid for use.

Pour the clear solution into a tray supported in a water bath and heat to 110° F. (43° C.). During toning the temperature should be between 100°

and 110° F. (38° and 43° C.).

Prints to be toned should be washed for a few minutes after fixing before they are placed in the toning solution. Dry prints should be soaked thoroughly in water before toning.

Keep at hand an untoned black-and-white print for comparison during toning. Prints should be separated at all times to insure even toning.

When the desired tone is obtained (5 to 20 minutes), remove and rinse the prints in cold water. After all prints have been toned, return them to the fixing bath for five minutes, then wash for one hour in running water.

The bath should be revived at intervals by the addition of Gold Solution B. The quantity to be added will depend upon the number of prints toned and the time of toning. For example, when toning to a warm brown, add 1 gram (4 cc.) of gold solution after each fifty, 8 x 10-inch prints or their equivalent have been toned. Fresh solution may be added from time to time to keep the bath up to the proper volume.

### Uranium, Iron, and Dye Tones on Prints

Tones on paper may be obtained with uranium (T-17) ranging from chocolate to brick red. This formula may also be used as a mordant bath for dye tones. The paper stock usually becomes tinted unless it is protected by squeegeeing temporarily to another support coated with rubber cement. Blue tones may be obtained with an iron toning bath (T-12).

Toned images obtained with these formulae are not absolutely permanent since they consist of a mixture of silver with one or more of the following compounds: silver ferrocyanide, dye, ferric ferrocyanide, and uranyl ferrocyanide. On exposure to the atmosphere, which usually contains traces of hydrogen sulphide, the silver and uranyl ferrocyanides are converted to silver or uranyl sulphide which is usually apparent as a metallic sheen on the surface of the toned print. This sulphiding of the image can be prevented almost completely by treating the prints with Print Lacquer.

In all these processes, the final tone depends not only on the time of toning but also on the density of the original print.

Important: Prints to be toned by any of the following methods should be washed thoroughly, and treated in the HE-1 Hypo Eliminator, to insure freedom from hypo. If hypo is present, inferior tones will result.

# T-12 Iron Toner For Blue Tones on Kodabromide Velox and Azo Paners

Water, To make

10. 200 10.000 0.0 1100000.	5110000, 1 00000, wild 2100.	L aport
	Avoirdupois	Metric
Ferric Ammonium Citrate	58 gr.	4.0 g.
Oxalic Acid Crystals	58 gr.	4.0 g.
Potassium Ferricyanide	58 gr.	4.0 g.

32 oz.

Dissolve each chemical separately in a small volume of water, about 8 ounces (250 cc.) and filter before mixing together. This solution does not keep well except in brown bottles.

Immerse the well-washed print in the toning bath for 10 to 15 minutes until the desired tone is obtained. Then wash until the highlights are clear.

# T-17 Mordant Bath For Dye Toning Stock Solution

	Avoirdupois	Metric
Uranium (Uranyl) Nitrate	116 gr.	8.0 g.
Oxalic Acid	58 gr.	4.0 g.
Potassium Ferricyanide	58 gr.	4.0 g.
Water, To make	32 oz.	1.0 1.

Directions for Mixing: First dissolve each chemical separately in a small volume of water. Then add the oxalic acid solution to the uranyl nitrate solution and finally add the ferricyanide solution. If the potassium ferricyanide solution is not clear, filter it before adding to the uranium nitrate and oxalic acid solution. If the uranyl nitrate is added directly to the potassium ferricyanide, a brown precipitate will be obtained which will not dissolve readily in the oxalic acid. After mixing, the bath should be light yellow and perfectly clear. The solution should not be exposed to light any more than necessary.

For Use as a Toning Bath (Chocolate to Brick Red): Dilute 1 part of the stock solution with 2 parts of water. As the toning time is increased, the tone changes from chocolate to brown and finally to brick red. The print may be removed at any stage.

Wash until the highlights are clean; this usually requires from 10 to 15 minutes. Prolonged washing should be avoided.

For Use as a Mordant for Dye Toning: Dilute 1 part stock solution with 4 parts of water.

Treat the well-washed print about 2 minutes until the image turns a light chocolate color. Rinse for about 1 minute or less in running water to remove the yellow stain from the highlights. Then immerse for 10 to 15 minutes in the T-17b Dye Bath:

# T-17b Dye Bath for Papers For Use with Papers After the T-17 Mordant Bath

	Avoirdupois	Metric
Dye (1:1000 Solution)	x fl. oz.	x cc.
Acetic Acid, 1% Solution	63/4 fl. dr.	25.0 cc.
Water, To make	32 oz.	1.0 l.

x = Volumes of 1:1000 \* Dye Solution for Various Colors as Follows:

A TOIGITION OI 1.10	oo bookaana so.				
			Avoirdupois	Metric	
Tone No. 1 Red	Safranine A		$3\frac{1}{4}$ fl. oz.	100 cc.	
Tone No. 2 Yellow	Auramine		31/4 fl. oz.	100 cc.	
Tone No. 3 Orange	(Equal parts Nos.	1 and 2)	$3\frac{1}{4}$ fl. oz.	100 cc.	
Tone No. 4 Blue-					
Green	Victoria Green		31/4 fl. oz.	100 cc.	

<sup>\*</sup>The 1 to 1000 stock solution of the dye is prepared by dissolving one part of dye in 1000 parts water (1 gram in 1 liter, or 15 grains in 32 ounces).

Tone No. 5 Brilliant

TOHO TIO, O DITHIAMO					
Green	(Equal Parts Nos. 2 and 4)	$3\frac{1}{4}$	fl.	oz.	100 cc.
Tone No. 6 Blue	Methylene Blue BB	$3\frac{1}{4}$	fl.	oz.	100 cc.
Tone No. 7 Violet	Methyl Violet	$5\frac{1}{2}$	fl.	dr.	20 cc.

Mixtures of the following may also be used.

Victoria Green plus Methyl Violet Methyl Violet plus Auramine Victoria Green plus Methylene Blue Methyl Violet plus Victoria Green

The dye toned print should be washed in running water until all extraneous color is removed from the highlights, but prolonged washing should be avoided.

### Toning Baths for Slides and Transparencies T-9 Uranium Toner

For Brown to Red Tones on Slides or Films

	Avoird	upois	$\mathbf{Metric}$
Uranium (Uranyl) Nitrate	35	gr.	2.5 g.
Potassium Oxalate	35	gr.	2.5 g.
Potassium Ferricyanide	15	gr.	1.0 g.
Ammonium Alum	85	gr.	6.0 g.
Hydrochloric Acid, 10% Solution	$1\frac{1}{4}$	dr.	5.0 cc.
Water, To make	32	oz.	1.0 l.
Dissolve chemicals in the order given.			

The solution should be perfectly clear and pale yellow in color. It is light sensitive, however, and should be stored in the dark.

The maximum toning effect is produced in about 10 minutes, the tone

passing from brown to red during this time.

After toning, wash for about 10 minutes; the washing should not be prolonged, especially if the water is slightly alkaline, since the toned image is soluble in alkali.

# T-10 Sulphide Toner For Warm Sepia Tones on Lantern Slides Solution A

			Avoird	lupois	Metric
	Potassium Ferricyanide		1	oz.	30.0 g.
	Potassium Bromide		$\frac{1}{2}$	oz.	15.0 g.
è	Water, To make		32	oz.	1.0 l.
		Solution B			
	Sodium Sulphide, Desicca	ated	13	gr.	0.9 g.
	Water, To make		32	oz.	1.0 l.

The well washed slide, or film, is thoroughly bleached in Solution A, washed for 5 minutes, and immersed in Solution B for about 2 minutes until thoroughly toned. The slide should then be washed thoroughly for 10 to 15 minutes before drying. The transparency of the tone is much improved by the addition of a little hypo to the B solution, say, 66 grains per 32 ounces or 4.5 grams per liter,

#### T-11 Iron Toner For Blue Tones on Slides or Films

	Avoirdupois	Metric
Ammonium Persulphate	7 gr.	$0.5\mathrm{g}.$
Iron and Ammonium Sulphate	20 gr.	1.4 g.
Oxalic Acid	45 gr.	3.0 g.
Potassium Ferricyanide	15 gr.	1.0 g.
Ammonium Alum	73 gr.	5.0 g.
Hydrochloric Acid, 10% Solution	1/4 dr.	1.0 cc.
Water, To make	32 oz.	1.0 l.

Dissolve chemicals in the order given.

The method of compounding this bath is important. Each of the solid chemicals should be dissolved separately in a small volume of water; the solutions then should be mixed strictly in the order given, and the whole diluted to the required volume. If these instructions are followed, the bath will be pale yellow in color and perfectly clear.

Immerse the slides or films from 2 to 10 minutes at 68° F. (20° C.) until the desired tone is obtained. Wash for 10 to 15 minutes until the highlights are clear. A slight permanent yellow coloration of the clear gelatin will usually occur, but should be too slight to be detectable on projection. If the highlights are stained blue, then either the slide (film) was fogged during development, or the toning bath was stale or not mixed correctly.

Since the toned image is soluble in alkali, washing should not be carried out for too long a period, especially if the water is slightly alkaline.

## Mixed Iron and Uranium Tones

By mixing the uranium (T-9) and iron (T-11) toning solutions in different proportions, tones ranging from reddish-brown to chocolate are produced. Analogous results may be obtained by immersing the film or slide in each solution successively for varying times.

#### T-17 Mordant Bath For Dye Toning Stock Solution

	Avoirdupois	Metric
Uranium Nitrate	116 gr.	8.0 g.
Oxalic Acid Crystals	58 gr.	4.0 g.
Potassium Ferricyanide	58 gr.	4.0 g.
Water. To make	32 oz.	1.0 l.

Follow the directions for mixing given under T-17.

For use, take 1 part of stock solution and 4 parts water.

Time of Mordanting: Immerse the film (slide) at 65° to 70° F. (18° to 21° C.) until a very slight chocolate colored tone is obtained; then remove film at once. If mordanting is prolonged much beyond this point, inferior tones will be produced. With a new bath this will require from 1½ to 2 minutes, but the time will need to be increased as the bath ages. The

solution may be revived at intervals by adding a little of the concentrated stock solution.

Time of Washing After Mordanting: Wash until the highlights are free from yellow stain; this usually takes about 10 to 15 minutes. Do not prolong the washing for more than 20 minutes or some of the mordant will be washed out.

## T-17a Dye Bath

For Use with Slides or Films After the T-17 Mordant Bath

	Avoirdupois	${f Metric}$
Dye	3 gr.	0.2 g.
Acetic Acid, 10%	$1\frac{1}{4}$ dr.	5.0 cc.
Water, To make	32 oz.	1.0 l.

Thoroughly dissolve the dye in hot water, filter, add the acid, and dilute to volume with cold water.

The following dyes are suitable for toning:

Safranine A	$\operatorname{Red}$
Chrysoidine 3R	Orange
Auramine	Yellow
Victoria Green	Green
Methylene Blue BB	${f B}$ lue
Methyl Violet *	${f Violet}$

Time for Dye Toning: Immerse the mordanted and washed film (slide) in the dye bath for 2 to 15 minutes at 65° to 70° F. (18° to 21° C.) according to the color desired. The quantity of dye which mordants to the image increases with time. In case an image is over-dyed, some of the dye may be removed by immersing in a 0.2% solution of ammonia; then rinse before drying.

If, after dyeing 10 minutes, the image does not mordant sufficient dye, remove the film (slide), wash thoroughly, immerse again in the mordanting bath, wash, and re-dye.

Intermediate Dye Tones: Intermediate colors may be obtained either by mixing the dye solutions or by immersing the film (slide) in successive baths. For example, if a reddish-orange tone is desired, first tone for a short time in the Safranine bath and then in the Chrysoidine bath, or the two baths may be mixed in suitable proportions and the tone secured with a single treatment.

\*For methyl violet use one-quarter the quantity of dye given in the formula.

#### T-18 Toner

#### For Double Tones on Slides or Films

Double Tones: This bath tones the halftones white and the shadows blue. If the resulting image is immersed in any of the basic dye solutions, which are used for dye toning (T-17a), the dye is mordanted to the half-

tones while the shadows remain more or less blue. By varying the dye solution used, the color of the halftones may be varied at will.

	Avoirdupois	Metric
Ammonium Persulphate	7 gr.	0.5 g.
Iron and Ammonium Sulphate	20 gr.	1.4 g.
Oxalic Acid	45 gr.	3.0 g.
Potassium Ferricyanide	15 gr.	1.0 g.
Hydrochloric Acid, 10%	$\frac{1}{4}$ dr.	1.0 cc.
Water, To make	32 oz.	1.0 l.

The instructions for preparing the bath are the same as for the Iron toning bath (T-11).

Directions for Use: Tone until the shadows are deep blue. Then wash 10 to 15 minutes. Immerse in the basic dye solution used for dye toning for 5 to 15 minutes until the desired depth of color in the halftones is obtained. Wash 5 to 10 minutes after dyeing until the highlights are clear.

# T-20 Single Solution Dye Toner For Slides or Films

	Avoirdupois	Metric
Dye *	x gr.	x g.
Wood Alcohol (or Acetone)	$3\frac{1}{4}$ fl. oz.	100.0 cc.
Potassium Ferricyanide	15 gr.	1.0 g.
Acetic Acid (Glacial)	11/4 dr.	5.0 cc.
Water, To make	32 oz.	1.0 l.

The nature of the tone varies with time of toning and eventually a point is reached beyond which it is unsafe to continue as the gradation of the toned image becomes affected. Average toning time at 68° F. (20° C.) is from 3 to 9 minutes.

me dye used as ronows.	
3 gr.	0.2 g.
3 gr.	0.2 g.
6 gr.	0.4 g.
,	3 gr.

 Auramine
 6 gr.
 0.4 g.

 Victoria Green
 6 gr.
 0.4 g.

 Rhodamine B
 6 gr.
 0.4 g.

## Tinting Slides or Films

Tinting consists of immersing a film or slide in a solution of an acid dye which colors the gelatin layer, causing the whole picture to have a veil of color over it. Motion picture positive films may be purchased in a wide variety of tinted bases which obviate the necessity for actual coloring.

Sheets of water colors or liquid water colors recommended for coloring photographs may be used for tinting slides or film transparencies. In the case of most colors the absorption of the color is hastened by the addition of 1 volume of glacial acetic acid to 1000 volumes of the dye solution. Bathing for 3 to 4 minutes in the acid dye solution is usually ample. After tinting, the slide should be rinsed in water for a few seconds and wiped

off with a moist tuft of absorbent cotton. If the color is too strong, it should be washed in water or a 2% solution of ammonia.

Pleasing effects may also be secured by combined tinting and toning such as a blue tone followed by an orange, red, or yellow tint. The clear portions or highlights thus assume the color of the tinting solution while the half-tones and shadows show a color intermediate between the tint and tone used.

Slides fixed in plain or acid hypo (F-24) take colors better than those fixed in an acid hardening fixing bath.

#### Non-Hardening Citric Acid Short-Stop Bath Formula No. 1

Water		1	l.
Citric Acid		15	g.
	No. 2		
Water		1	l.
Sodium Bisulphite		40	g.

# SB-1 Stop Bath Acid Rinse for Papers

	Avoirdupois	${f Metric}$
Water	32 oz.	1.0 l.
Acetic Acid (28%)	$1\frac{1}{2}$ oz.	48.0 cc.

Rinse prints for at least 5 seconds. Capacity: about 25 8 x 10-inch prints per quart (liter).

## SB-1a Stop Bath

## Acid Rinse for Films, Plates, and Papers for Graphic Arts

	Avoirdupois	Metric
Water	32 oz.	1.0 l.
Acetic Acid (28%)	4 fl. oz.	125.0 cc.

The action of this bath instantly checks development and prevents uneven spots and streaks when the prints or negatives are immersed in the fixing bath.

# SB-5 Stop Bath Nonswelling Acid Rings for Photofinishing

Wondering Acta Italise for	Avoirdupois	Metric
Water	16 oz.	500 cc.
Acetic Acid (28%)	1 fl. oz.	32.0 cc.
Sodium Sulphate, Desiccated	$1\frac{1}{2}$ oz.	45.0 g.
Water To make	39 07	101

Agitate the films when first immersed in this bath and allow them to remain about three minutes before transfer to the fixing bath.

This bath should be replaced after approximately 25 rolls have been processed per quart (liter), when about 24 ounces (720 cc.) of developer will have been carried into the rinse bath by the film.

Short-Stop and Hardening Bath

Water		1	1.
Potassium Chrome Alum		20	g.
Sodium Bisulphite		20	g.

Note: Leave films in hardening solution for five minutes at 68° F. It is important that the solution be prepared immediately before use and be replaced at least once per week, since it does not keep well.

#### SB-3 Hardening Bath

#### For Use at 65° to 75° F, with Films and Plates

	Avoirdupois	Metric
Water	32 oz.	1.0 l.
Potassium Chrome Alum	1 oz.	30.0 g.

This bath is intended for use in hot weather after development and before fixation in conjunction with F-5.

Agitate the negatives for a few seconds when first immersed in hardener. Leave them in the bath for 3 to 5 minutes to secure maximum hardening. This bath should be renewed frequently.

## SB-4 Hardening Bath

## For Use at 75° to 90° F. with Films and Plates

This solution is recommended for use in conjunction with the High Temperature Developer (DK-15), when working above 75° F. (24° C.).

	Avoirdupois	Metric
Water	32 oz.	1.0 l.
Potassium Chrome Alum	1 oz.	30.0 g.
Sodium Sulphate, Desiccated	2 oz.	60.0 g.

Agitate the negatives for 30 to 45 seconds when they are first immersed in the hardener, or streakiness will result. Leave them in the bath for at least 3 minutes between development and fixation. If the temperature is below 85° F. (29° C.) rinse for 1 to 2 seconds in water before immersing in the hardener bath.

The hardening bath is a violet blue color by tungsten light when freshly mixed, but it ultimately turns a yellow-green with use; it then ceases to harden and should be replaced with a fresh bath. The hardening bath should never be overworked. An unused bath will keep indefinitely, but the hardening power of a partially used bath decreases rapidly on standing for a few days.

#### SH-1 Special Hardener

For After Treatment of Films and Plates

	Avoirdupois	${ m Metric}$
Water	16 oz.	500 cc.
Formaldehyde (40%)	$2\frac{1}{2}$ dr.	10.0 cc.
Sodium Carbonate, Desiccated	73 gr.	5.0 g.
Water, To make	32 oz.	1.0 l.

This formula is recommended for the treatment of negatives which normally would be softened by a chemical treatment as for the removal of stains or for intensification or reduction.

After hardening for three minutes, negatives should be rinsed and immersed for five minutes in a fresh acid fixing bath and then washed thoroughly before they are given any further chemical treatment.

## F-1a Hardener

Stock Solution for Preparing F-1 Fixing Bath

	Avoirdupois	Metric
Water 125° F. (50° C.)	14 oz.	425 cc.
Sodium Sulphite, Desiccated	2 oz.	60.0 g.
Acetic Acid (28%)	6 fl. oz.	190.0 cc.
Potassium Alum	2 oz.	60.0 g.
Cold Water, To make	32 oz.	1.0 l.

Dissolve the chemicals in the order given. The sodium sulphite should be dissolved completely before the acetic acid is added. After the sulphiteacid solution has been mixed thoroughly, add the potassium alum with constant stirring.

For use, add 1 part of cool stock hardener solution slowly to 4 parts of a 25% cool hypo solution (2 pounds of hypo to the gallon of solution). If the hypo is not thoroughly dissolved before adding the hardener a precipitate of sulphur is likely to form.

### F-5a Hardener

Stock Solution for Preparing F-5 Fixing Bath

	Avoirdupois	Metric
Water 125° F. (50° C.)	20 oz.	600 cc.
Sodium Sulphite, Desiccated	$2\frac{1}{2}$ oz.	75.0 g.
Acetic Acid (28%)	$7\frac{1}{2}$ fl. oz.	235.0 cc.
Boric Acid Crystals	$1\frac{1}{4}$ oz.	37.5 g.
Potassium Alum	$2\frac{1}{2}$ oz.	75.0 g.
Cold Water, To make	32 oz.	1.0 l.

Dissolve chemicals in the order given.

Add one part of the cool stock hardener solution slowly to 4 parts of cool 30% hypo solution (2½ pounds per gallon of solution), while stirring the hypo rapidly.

PHOTOC	GRAPHY	371
No. 201 Acid Hardening Fixer May be used on paper or film, may be stored indefinitely, and may be used until exhausted. When the fixing bath froths, turns cloudy, or takes longer than 10 minutes to fix completely, it must be replaced.  Solution A	Then Add Water to Make Note: The hardening prope bath decrease rapidly with temperature above 70° F.  Fixing Baths U. S. Patent 2,203, Formula No. 1 Sodium Thiosulphate	age and at
Water (52° C.) 500 cc. Hypo 240 g. Solution B	(Hypo) Sodium Sulphite	223 g. 16 g.
Water (52° C.) 150 cc. Anhyd. Sodium Sulphite 15 g. Acetic Acid (28%) 45 cc. Potassium Alum 15 g. Add solution B to A. Fix 5–10 min. at 20° C. Do not dilute for use.	Sodium Acetate Citric Acid Potassium Alum For use, add sufficient make 1 liter of solution. No. 2 A	18 g. 11 g. 20 g. water to
Acid Hardener for Film	Water Hypo	80 oz. 2 lb.
Hypo 220 g. Sodium Sulphite 15 g. Sodium Acetate 18 g. Citric Acid (Crystals) 11 g. Alum 22 g. Water 1000 cc.	B Water (125° F.) Sodium Sulphite Distilled Vinegar Boric Acid, Crystals Potassium Alum Allow B to cool, then ac	16 oz. 2 oz. 16 oz. 1 oz. 2 oz.
Photographic Acid Hardening Fixer U. S. Patent 2,214,216	stirring well.	id it willio
Sodium Thiosulphate 120 Sodium Bisulphite 30 Aluminum Gluconate 30	Hypo Sodium Sulphite Sodium Acetate Sodium Hydrogen Sul-	
Citric Acid, Hardening Fixing Bath Solution No. 1 Water (125° F.) 500 cc. Sodium Thiosul- phate 250 g. Solution No. 2	phate Potassium Alum Chrome Alum Water, To make No. 202 Chrome Alun For use in hot weather.	Should be
Water (125° F.) 150 cc. Sodium Sulphite, Anhydrous 11 g.	used fresh as it does not hardening action. Solution A Water (52° C.)	2.5 l.
Citric Acid 5½ g. Potassium Alum 5½ g. Add Solution No. 2 to Solution No. 1 and		2.5 f. 960 g. 60 g.
NOTHINGH TWO I MAN	· · · · · · · · · · · · · · · · · · ·	-

Water, To make Solution B	3	1.	Slowly pour B into A with rapid stirring. Do not dilute for use. Do
Water Potassium Chrome	1	1.	not dissolve alum at a temperature higher than 66° C. Rinse films thor-
Alum Sulphuric Acid, C.P.	60 8	g. cc.	oughly before fixing. Fix 5-10 min. at 20° C.

# F-1 Fixing Bath

	For Papers		
		Avoirdupois	Metric
Water		64 oz.	2.0 l.
Sodium Thiosulphate (Hy		16 oz.	480.0 g.
Then add the following ha	rdener solution	n slowly to the	cool hypo solu-
tion while stirring the latter	rapidly.		
Water, 125° F. (50° C.)		5 oz.	160 cc.
Sodium Sulphite, Desiccat	ed	1 oz.	30.0 g.
Acetic Acid (28%)		3 fl. oz.	96.0 cc.
Potassium Alum	•	1 oz.	30.0 g.
Dissolve chemicals in the	order given. (S	lee directions un	der F-1a).
If it is desired to mix a sto	ck hardener so	lution, use F-1a	•

# F-5 Fixing Bath For Films, Plates, and Papers

	Avoirdupois	${f Metric}$
Water, 125° F. (50° C.)	20 oz.	600 cc.
Sodium Thiosulphate (Hypo)	8 oz.	240.0 g.
Sodium Sulphite, Desiccated	$\frac{1}{2}$ oz.	15.0 g.
Acetic Acid (28%)	$1\frac{1}{2}$ fl. oz.	48.0 cc.
Boric Acid Crystals	$\frac{1}{4}$ oz.	7.5 g.
Potassium Alum	$\frac{1}{2}$ oz.	15.0 g.
Cold Water, To make	32 oz.	1.0 l.

Films or plates should be fixed properly in 10 minutes (cleared in 5 minutes) in a freshly prepared bath. The bath need not be discarded until the fixing time (twice the time to clear) becomes excessive, that is, over 20 minutes.

# F-16 Fixing Bath Chrome Alum: for Films and Plates Solution A

	Avoirdupois	Metric
Sodium Thiosulphate (Hypo)	2 lb.	960 g.
Sodium Sulphite, Desiccated	2 oz.	60.0 g.
Water, To make	96 oz.	3.0 1.

#### Solution B

		Avoirdupois	Metric
Water	1	32 oz.	1.0 l.
Potassium Chrome Alum		2 oz.	60.0 g.
Sulphuric Acid, C.P.		$\frac{1}{4}$ fl. oz.	8.0 cc.

Pour solution B into solution A slowly while stirring A rapidly. This bath, when freshly mixed, is recommended for use in hot weather, but it rapidly loses its hardening properties with or without use, when it should be replaced by a fresh bath. With an old bath there is a tendency for scum to form on the surface of the film. Any such scum should be removed by swabbing with cotton before the film is dried.

F-24 Fixing Bath
Non-Hardening: for Special Processes

	Avoirdupois	Metric
Water, 125° F. (50° C.)	16 oz.	500 cc.
Sodium Thiosulphate (Hypo)	8 oz.	240.0 g.
Sodium Sulphite, Desiccated	145 gr.	10.0 g.
Sodium Bisulphite	365 gr.	25.0 g.
Cold Water, To make	32 oz.	1.0 l.
Sodium Bisulphite	365 gr.	25.0 g.

Dissolve chemicals in the order given.

This bath may be used for films, plates or paper when no hardening is desired.

For satisfactory use, the temperature of the developer, rinse bath, and wash water should not be higher than 68° F. (20° C.).

Non-Hardening Bisulphite Fixing | Both

11001	
Sodium Thiosulphate	240 g.
Sodium Bisulphite	35 g.
Water. To make	1 l.

Note: The above fixing bath does not contain a hardening agent. However, hardening of the films in the fixing bath is unnecessary assuming that the films are treated in a fresh hardening shortstop bath prior to fixation.

No. 203 Non-Hardening Metabisulphite Fixer

Used in color work with Printon Film where high accuracy of registration is required.

Hypo	1900 g.
Potassium Metabisul-	
phite	270 g.
Water, To make	4 1.
The metabisulphite	should be

added only when the hypo solution is cool. Fix 5-10 min, at 18° C.

Pinakryptol Yellow Desensitizer For orthochromatic films.

Pinakryptol Yellow 1 g.
Water, To make 1 l.

(50% alcohol may be used in place of water to improve the keeping quality of the desensitizer.) Do not dilute for use. Immerse film in total darkness for 2 min. at 18° C. Orthochromatic film may then be handled in bright red light. (Safelight Filter No. 107 with a 25 watt bulb.) Panchromatic film may then be developed in bright green light. (Safelight Filter No. 103 with a 25 watt bulb.)

Pinakryptol yellow must not be mixed with the developer.

Pinakryptol Green Desensitizer
For high speed panchromatic film.
Pinakryptol Green 1 g.
Water, To make 500 cc.

(50% alcohol may be used in place of water to improve the keeping quality of the desensitizer.) For use dilute 1 part stock solution with 11 parts water. Immerse films in total darkness for 2 min. at 18° C. Development may then be carried out in bright red light. (Safelight Filter No. 107 with a 25 watt bulb.)

The stock solution may be used directly in the developer in the proportion: 1 part desensitizer to 30 parts developer. After 2 minutes development in total darkness, bright

red light may be used.

Blue Print Paper Sensitizer British Patent 539,066

Water	1000
Triethylamine Oxalate	150
Sodium Ferrocyanide	40
Potassium Ferricyanide	10
Ferric Ammonium Oxalate	e 150

Photogravure Spirit Sensitizer

A solution of ammonium bichromate is prepared, of three times the strength required. This should be neutralized by ammonia if the sensitive material is to be kept. Twice its volume of methylated spirits or denatured alcohol should then be added. Keep in the dark.

The sheet of tissue to be sensitized is brushed with the solution, the strokes being made to cross each other to avoid irregularity.

Litho Plate Sensitizers
U. S. Patent 2,025,996
Formula No. 1
Process Glue 100 cc.

Water	100	cc.
Pyridin Bichromate (8% Sol.)	50	cc.
No. 2	90	cc.

For sensitizing stainless steel plates for litho purposes:

Distilled Water	32
Egg Albumen (Scales)	9
В	
Distilled Water	6
Ammonium Bichromate	$2\frac{1}{4}$
C	. –
Process Glue	$1\frac{1}{2}$

Allow the albumen to dissolve overnight, then add B to A, followed by C.

11/2

Ammonia (28%)

Photolithographic Deep Etch Sensitizer Formula No. 1

Separately dissolve 1/4 pound each of yellow dextrin and gum arabic in as little water as possible to make a paste. The two solutions are then mixed together, and 71/2 ounces of ammonium bichromate solution (ammonium bichromate, 2 ounces: water 10 ounces) then added, together with 1 ounce of stronger ammonia water. Distilled water is finally added to the mixture until the solution tests 15° Baume. The speed of the whirler during coating should not exceed 50 r.p.m. Development of the image takes place with lactic acid and calcium chloride solution (37° Bé).

No. 2

Water 500 cc.
Yellow Dextrin 500 cc.
Potassium Bichromate 80 g.
Ammonium Bichromate 40 g.
The bichromates are dissolved in

a small quantity of water, then

added to the dextrin mixture. In warm weather or when the work-room temperature rises above 72° F., it is recommended to add 5 grams of albumen to the mixture. The color of the bichromated dextrin mixture is rather dark; any foam created in mixing should be removed by filtration.

Litho Washout Solution

For strengthening litho images on metal plates for offset printing:

TITOCON PROTOCOL TO THE PROTOC	
Asphaltum	2 lb.
Beeswax	3 oz.
Stearin	2 oz.
Transfer Ink	1 oz.
Lavender Oil	2 oz.
Japan Liquid Drier	4 oz.
Mix thoroughly by heat	ing, then
add one gallon of turpenti	ne.

Lithographic Plate Conditioning

Solution
U. S. Patent 2,231,045
Chromium Phosphate
(10% Solution) ½-2 oz.
Gum Arabic (14° Bé
Solution) 1-4 oz.
Water, To make 1 gal.

Lithographic Etch U. S. Patent 2,230,156

A solution for etching chromium coated plates is made of:

Hydrochloric Acid (37%) 1 pt. Propylene Glycol 3 pt.

Dot Etching

As a substitute for expensive potassium ferricyanide (Farmer's reducer) used in dot etching (correcting) photolitho halftones on dry plates and films, use the following:

Water	25
Copper Sulphate	. 1
Salt	1

Add sufficient ammonia to clear the solution, which should be a rich ultramarine color:

 $\mathbf{R}$ 

Нуро	5
Water	25

For use, take equal parts of A and B.

## PHOTOENGRAVING

Aluminum Etching

For etching purposes, the hard variety of aluminum is preferable, since the soft type of metal does not etch as sharply. As photomechanical sensitizers, bichromated albumen (ink top) and cold enamel can be used; glue enamel is not as satisfactory, although the glue print can be burnt in on aluminum with less injury to the metal than would normally be the case with zinc.

Aluminum can be etched in either an aqueous or alcoholic solution of copper chloride; also with a 10 to 15% hydrochloric acid solution, previously saturated with sodium

chloride.

Relief and Intaglio Etching Formula No. 1

4
6
4
40
15
45
15
100

No. 3

Relief Etchings on Hammered Aluminum

Ferric Chloride, Lump	100
Alcohol (96%)	200
Saccharic Acid	1

Oxalic acid may be substituted for the saccharic variety and in the same quantity.

No. 4	
Ferric Chloride, Lump	<b>2</b>
Water	40
Hydrochloric Acid	2

The chloride is dissolved first and the acid then added; the strength of the bath should be at least 35° Bé, as weaker baths are likely to attack the acid resist (image) in the increased time required for etching.

No. 5	
Ammonium Persulphate	5
Sulphuric Acid	1
Water	100

Brass Etching

Name plate work, on a large scale usually is performed by printing acid-resisting designs on brass sheets by the tin printing (offset) principle, but the metal can be sensitized with any of the photoresists used in photoengraving. For better adhesion of the image, subject the brass plate to action of the following graining bath (instead of immersing the polished sheets in ferric chloride solution):

#### Formula No. 1

Alum		1
Water		40
Nitric	Acid	1

When using glue enamel as a sensitizer, it will be found that the tarnish or discoloration, sometimes present on copper plates after burning-in of the print, is absent on brass, the print, as a result, standing out with greater contrast (brilliance). However, even with this graining bath, the blue print on brass may display a tendency to lift, to prevent which, harden the developed image by immersing it

from one to five minutes in the following bath:

No. 2	
Water	16
Denatured Alcohol	$1\frac{1}{2}$
Ammonium Bichromate	30
Chromic Acid	5

Brass not infrequently etches somewhat faster than copper: the simplest mordant is a solution of ferric chloride. For machine etching of glue prints, the bath should be as strong as possible (at least 45° Bé), since weak (watery) iron solutions soften the enamel image.

orden die enamer image.	
No. 3	
Tray Etching	
Water	45
Hydrochloric Acid	30
Potassium Chlorate	18
No. 4	
Water	200
Potassium Chlorate	5
Nitric Acid	10
Ferric Chloride, Lump	15
No. 5	
Water	200
Potassium Chlorate	10
Nitric Acid	20
Hydrochloric Acid	40

Etching solutions containing potassium chlorate should stand overnight before use, in order to permit the initial escape of harmful gases. The solutions should not be used after they assume a brown color.

No. 6	•
Water	40
Chromic Acid	4
Denatured Alcohol	4

The bath is rather slow in action and the high chromic acid content necessitates guarding against chromium dermatitis (bichromate poisoning). In mixing this solution, be sure to first dissolve the chromic acid in the water, then slowly add the alcohol, stirring during the addition. Chromic acid brought into contact with strong alcohol may cause explosion.

#### No. 7

A two-solution procedure for brass etching consists of giving the first "bite" (etch) in:

Ferric Chloride Solution, 3:1 500 Nitric Acid (45°) 100 Chrome Alum 100

Water 1000 followed by a "finishing" (final) etch with:

Water 1000 Acetic Acid 30 Nitric Acid 75 Chromic Acid 50

## Bronze Etching

Because of its hardness and resistance to acids, bronze (broadly considered as an alloy of copper and tin) is more difficult to etch than either brass or copper. Because of the necessity of powerful etching agents, the best photoresist for bronze probably is bichromated albumen (ink top).

Etching is commenced with a strong solution (40-45° Bé) of ferric chloride, after appreciable depth is obtained, the plate is rolled up with stiff etching ink, dusted with powdered asphalt or rosin (colophony), after which the plate is etched either in a strong nitric acid bath, or with the following solution (aqua regia):

Nitric Acid 18
Hydrochloric Acid 82
The solution may be diluted with water according to the speed of etching desired.

Celluloid Etching

This is sometimes etched either in relief or intaglio, employing as sensitizers either bichromated albumen, glue or gelatin. With glue or gelatin, the image obviously cannot be burnt-in, but it can be hardened sufficiently to withstand etching by immersing the developed print for some time in a warm saturated solution of chrome alum.

Difficulty is sometimes experienced with the image failing to adhere to the celluloid; to remedy this, rub the celluloid with a 5% solution of glacial acetic acid in denatured alcohol, the treatment providing a "tooth" to the surface to which the image will adhere.

For etching celluloid bearing ink images, a strong solution of glacial acetic acid can be used. Bichromated glue or gelatin images can be etched with any of the familiar solvents of celluloid: acetone, amyl acetate, or ether-alcohol mixtures. Acetone probably will prove the most convenient for the purpose.

# Copper Etching Formula No. 1

Ferric Chloride, Lump
Distilled Water
Sulphuric Acid
30

For very delicate work (though slow in action), the so-called "Dutch mordant," often used by artistetchers (dry point), is used:

#### No. 2

Water	70	
Hydrochloric Acid	10	
to which is added in the form	of	a
boiling solution:	0	

Potassium Chlorate	2
Water	20
The solution can be	diluted with

water, if desired. The bath acts more rapidly when heated to a temperature of 85° F.

Lead Etching

The low melting point (620° F.) of lead precludes anything but cold enamel as the photoresist, thus dispensing with the necessity of heating the plate in the creation of an acid resist. The metal can be etched in dilute solutions of either nitric or glacial acetic acid, and in the following special mordant:

Water	40
Tin Chloride	$2\frac{1}{2}$
Alcohol	4

In practice, the acid solutions will be found most efficient.

Magnesium Etching

As photoresists, either the glue enamel or cold enamel processes can be used; if the latter is employed, the alcohol developing bath must be used only for the magnesium plates, and not for zinc plates.

Magnesium alloys are most efficiently etched in dilute solutions of nitric acid. For tray etching, the strength of the bath should not exceed 3° Bé; for machine etching, the bath should not be stronger than 8° Bé. Even with such dilute solutions, etching of the alloy proceeds so rapidly that the plate is quickly covered with bubbles, which must be periodically brushed off to determine the progress of etching.

Molybdenum Etching

Etchings on this metal are seldom requested, but it can be performed with concentrated sulphuric acid, nitro-hydrochloric acid (aqua regia), or in the following mixture:

Water	1000
Potassium Ferricyanide	360
Caustic Soda	36

Monel Etching

Photoresists can be either glue enamel or carbon tissue images, the medium for etching being a 50° Bé solution of ferric chloride. A solution of this strength is obtained by dissolving 6¾ pounds of lump ferric chloride in sufficient water to make one gallon of solution.

Nickel Etching

Pure nickel can be etched in strong nitric acid solutions, employing any of the familiar photoresists of photoengraving. The metal and its alloys can also be etched in:

Nitric Aci	d (70%)	50
Acetic Aci	d (50%)	50
XX7	1	

Water may be added as desired for control of etching.

Plastic Etching

Although certain plastics can be etched with alcohol, acetone, bensol, caustic alkalies and modern hydrocarbon solvents, the most reliable method of platemaking with synthetic resins (plastics) is by direct molding from relief or intaglio etchings.

The wide range of plastics and the different chemical nature of such materials render difficult any specific formulae for the purpose.

Silver Etching

The bichromated albumen and cold enamel processes serve as the best photoresists. Decorative designs on silver can be etched to a

matt finish in chlorine-free nitric acid of 24° Bé; for deeper etching, the action is continued with 18° nitric acid.

A strong solution of chromic acid is a good mordant for silver, as is also a mixture of potassium bichromate and sulphuric (or nitric) acid, and a mixture of dilute sulphuric acid with potassium permanganate.

A convenient etching bath for sil-

ver is:

Nitric Acid	1
Hydrochloric Acid	1
Water	12

Photoink resists capable of withstanding the action of nitric acid on silver are sometimes difficult to obtain, wherefore the following suggestion is made: the ink image (print) is dusted with powdered asphaltum and a short etch given with ferric chloride solution (40° Bé). The silver chloride formed by this action must be removed (dissolved) from the plate with a strong hypo (sodium thiosulphate) solution, after which the plate is moistened with a dilute gum arabic solution (in the lithographic manner) and another application of ink given, followed by dusting with asphaltum.

Etching with ferric chloride and treatment with hypo is repeated, and the entire operation duplicated until it is possible to apply an ink-powder resist sufficiently strong to withstand etching with nitric acid as in ordinary line (relief) etching.

Stainless Steel Printing Plate Etch U. S. Patent 2,266,430

The following formula has been patented for etching stainless steel plates in the production of printing surfaces:

Saturated Ferric Chloride	
Solution	4
Concentrated Nitric Acid	1
Commercial Hydrofluoric	
Acid	1

Stainless Steel Etching

Heavily reinforced (powdered) ink images probably prove the best resist. Solutions for etching stainless steel comprise:

Formula No. 1	
Ferric Chloride, Lump	5
Hydrochloric Acid	50
Water	100
No. 2	
Copper Chloride	5
Hydrochloric Acid	100
Denatured Alcohol	100
Water	100
No. 3	
Potassium Ferricyanide	10
Potassium Hydroxide	10
Water	100
CITAL TO A 1 TO A 1	*

The latter solution must be used in the form of a hot bath.

Steel Etching

The grade of steel best suited for etching is that known as "cemented steel," which possesses a very fine-grained and uniform metallic structure.

Modern practice has found that ferric chloride (42° Bé solution) gives good results, especially with ink and glue enamel images.

For those not partial to ferric chloride, a host of other formulae have been evolved, among which are acid baths:

Formula No. 1	
Nitrie (or Hydrochlorie)	
Acid	1
Water	. 8
No. 2	
Glacial Acetic Acid	4

Absolute Alcohol	1
Nitrie Acid (1.28)	1

The acetic acid and alcohol are mixed together and allowed to stand for one-half hour, after which the nitric acid is added very gradually.

No. 3	
Nitric Acid	30
Water	120
Alcohol	120
Oxalic Acid	1
No. 4	

Iodine	<b>2</b>
Potassium Iodide	5
Water	40
No. 5	

2(0.0	
Silver Nitrate	1
Distilled Water	9
Nitric Acid	17
Alcohol	6

This solution improves with keeping. Before etching, the plate is washed, for a few seconds, in a 4% bath of nitric acid, after which the above mordant is applied for three minutes. The plate is then washed with distilled water containing 6% of alcohol and the etching repeated -the operation can be carried out as often as desired.

### No. 6 32 Mercuric Chloride 2

Alum Alcohol

Water

The chloride and alum are dissolved in the water by the acid of gentle heat, and the alcohol then added to the mixture.

No. 7	
$\mathbf{A}$	
Nitric Acid, C. P.	5
Distilled Water	5
Metallic Silver	1
В	
Nitric Acid, C. P.	5

Distilled	Water	5
Mercury		1

The solutions are prepared separately and when the respective metals have been dissolved in the acid mixtures, the solutions are combined and the mixture stored in a glass-stoppered bottle. When ready for use, the mixture is diluted with an equal quantity of distilled water.

The solution has little effect when simply poured upon the plate: galvanic action must first be generated by bending a strip of zinc so that one end comes into contact with a spot of bare steel and the other end dips into the solution on the steel surface. This starts the action of the acid immediately, when the zinc can then be laid aside, as the acid will continue to corrode the steel until the solution is exhausted.

# Zinc Etching Formula No. 1

Sulphuric Acid	12
Potassium Nitrate	4
Water	40

The potassium nitrate is dissolved in the water and the acid then gradually added until bubbling ceases.

No. 2	
Hydrochloric Acid	10
Nitric Acid	$2\frac{1}{2}$
Water	40

# Glass Etching

Certain military equipment requires graticules, gratings and designs etched on glass. Creation of the designs can be performed by engraving on the glass plate covered with an acid-resisting ground (wax), then etching the glass areas exposed in the engraving. A related process is the litho transfer of acid-resisting images on the glass surface, but for quantity production and certainty of result, the photoengraver will prefer strictly photomechanical methods, based on the etching of glass plates bearing photoresists.

Photomechanical glass etching (photohyalography) is performable in several ways; an efficient sensitizer (photoresist) for the glass asphaltum (bitumen). though the comparatively low sensitivity of this agent and the wartime difficulty of obtaining proper grades of light-sensitive asphaltum rather precludes its use. Bichromated gelatin images (carbon tissue) also can be used as etching resists, but their fragility does not long withstand the powerful and penetrating action of hydrofluoric acid (or its salts), with the result that the etching is limited as to depth.

The bichromated albumen process (ink top) can be used to good effect, though it requires heating of the glass plate. The thoroughly cleaned glass surface is sensitized with the albumen mixture (any formula giving good results on zinc will do), and the plate then exposed under a negative (or positive). The exposed surface is next rolled up with ink composed of two-thirds of good transfer ink and one-third good proving ink, taking care to apply a uniform and fairly heavy film of ink.

After development of the print under the tap, the plate is dried and the print dusted with powdered asphalt, whereupon the plate must be heated to fuse the powder with the ink; this heating is best done in a temperature controlled oven.

Etching can be carried out with

a strong hydrofluoric acid solution (40%), the action being complete in from 15 to 30 seconds. A slower acting solution, promoting very uniform action, is obtained by mixing:

distribution and distribution of	*******
Water	1000
Potassium Bifluoride	250
Hydroehloric Acid	250
Potassium Sulphate	140

As previously inferred, hydrofluoric acid is a powerful oxidizing agent, inclined to fuming, and causing very ugly burns on human skin. Because of liberated fumes, etching with hydrofluoric acid should not be performed in the vicinity of lenses, prisms, halftone screens or other optical equipment: the fumes from the acid may etch the glass to a matt surface.

Etching should be carried out in a well ventilated chamber: a good idea would be to place the tray of acid next to an open window and to have a draft of air from an electric fan play on the tray, the air blast quickly and continuously carrying the fumes through the window and off the premises. With all the cited precautions, it seems hardly necessary to warn against inhaling the fumes, or of splattering either the clothes or skin with the etching solution.

Of course, stout rubber gloves should be worn while handling the glass and etching bath: the bath itself should be contained in gutta percha or hard rubber trays; possessing the property of etching glass, hydrofluoric acid will also attack the glaze on porcelain, stoneware or earthenware receptacles.

Actual etching time depends on the chemical nature of the glass and the degree of depth desired. Before etching, both the edges of the glass and its back must be protected with asphalt varnish; a point to be remembered is that if the etched areas are to be smooth and transparent, the glass plate must be immersed in the solution; if, however, a matt effect is desired in the etched parts, it is only necessary to expose the glass surface to the fumes of the acid.

For etching in the bath itself, it will frequently be found that the acid etches cleaner and sharper after using it several times; this has led to the suggestion of dissolving a few small pieces of glass in the bath before using it for etching purposes.

On termination of etching, the plate must be washed very quickly and with a very large volume of water: this is necessary because the resist (top) lifts almost in the same moment that the washwater comes into contact with the acid remaining on the plate, after withdrawal from the bath. The ink resist can then be removed with turpentine and the etched lines filled in with a black pigment, should such be desired.

Objections sometimes voiced against the ink resist are the necessity of heating the plate (to fuse or melt the powder) and the tendency of the top to lift during etching, especially if weak acid baths are employed to afford greater latitude (control) in etching.

Preference might therefore be had for a glue image in conjunction with a wax ground, the process carried out by first soaking the glass plate for several hours in:

Water						16
Potassium	Bic	hro	ma	te	Steel	1
Sulphuric	Acid	1	W.	2	1075	1

The glass is then scrubbed, rinsed well and dried in a dust-free place. It is next polished on the face side with gasoline, then coated with:

Best Turpentine 16
Asphalt, Powdered 3½
Beeswax 2½

To dissolve the wax, first heat the turpentine; after the wax has been dissolved in the warm fluid, add the asphaltum and stir until completely dissolved.

The dry wax coating is then washed with a 10% solution of ammonia, rinsed in clean water, and the wax-coated plate sensitized with:

Process Glue 5 oz. Water 16 oz.

Ammonium Bichro-

mate 88 gr. Ammonia 10 drops

Sensitization of the plate is performed with the aid of a whirler, but no heat is used, as this would melt the wax coating.

The sensitized plate can then be exposed under a line negative (or positive) and the print developed in warm water, the insoluble (light-affected) glue image forming a stencil on the wax-asphalt resist. After drying the print, the plate is immersed in turpentine, which removes the bare areas of the resist, or those not covered with glue.

Etching of the plate follows along the previously outlined procedure, and after completion of etching, the resist and glue image can be removed by soaking the plate in hot turpentine, which penetrates the glue image and attacks the wax coating, permitting its removal from the glass surface by gentle rubbing with a stiff bristled brush. Glass Blueprints

Production of blueprints on glass as used in photomechanical processes can be performed by sensitizing the glass plate (on a whirler) with:

Water	28
Process Glue	5
Ammonium Bichromate	
(20% Sol.)	3
Ammonia (28%)	$\frac{3}{4}$

The exposed print is developed in water and the insoluble image then dyed by immersing it for 5 minutes in a bath containing one ounce of dye to one gallon of water.

Half Tone Zinc Etching Mordant
U. S. Patent 2,245,219
Cupric Sulphate
(20% Sol.) 95 cc.
Acid Sodium Sulphate
(35% Sol.) 5 cc.
Darvan No. 1 (Dispersing Agent) 0.005 g.

Glue Enamel Process Formula No. 1

A
Distilled Water 10
Process Glue 6
B
Distilled Water 6
Ammonium Bichromate 1

The solutions are made up separately; B is then poured into A and the mixture stirred with an eggbeater. Allow the solution to stand in a cool dark place for 24 hours before filtration and use.

For halftone color etching, an enamel is preferred which has a tendency to "gray-out" and thus promote soft tones.

No. 2

Water 16

Le Page's Process Glue 6
Albumen (Liquid) 4
Ammonium Bichromate 1
No. 3
A
Gum Arabic, Purified 3 oz.
Water 9 oz.
B
Ammonium Bichromate 184 gr.
Water 5 oz.

Albusol 3 oz.

Prepare each solution separately: when dissolved, add B to A, followed by C, then mix thoroughly with an eggbeater.

Gum arabic has been used in conjunction with (rosin) colophony (resino-colloid process), the aim being to either eliminate burning-in of the image or to reduce the degree of heat required for the operation, a not inconsiderable factor with the enamel process on zinc. A representative formula is:

No. 4 Colophony (Rosin) 15 gr. Absolute Alcohol 85 min. Ammonia 85 min. B Water 1 oz. Gum Arabic 123 gr. Potassium Bichromate 15 gr. Ammonia 17 min.

The solutions are prepared separately, then mixed together and the whole passed through filter paper. The image is developed with warm water; after drying, the plate is heated to the melting point of colophony (100°–140° C.), whereupon the image is ready for etching.

Gelatin may be used instead of

fish (process) glue as the colloid for photoengraving enamel:

No. 5

Water (125° F.) 20 oz. Coignet Gelatin 2 oz. Potassium Bichromate 120 gr.

The mixture must obviously be employed in a warm condition at the time of coating the plate.

Metagelatin, or gelatin which has lost its normal setting power is also used. The metagelatin is prepared by heating this mixture:

Metagelatin

Gelatin 500 g.
Water 800 cc.
Ammonia 125 cc.
for one hour, or until the gelatin no longer sets. It is employed as follows:

No. 6

Water 100 cc.

Metagelatin 10 g.

Egg Albumen 100 cc.

Ammonium Bichromate 6 g.

The developed image can be burnt-in to a dark color in the creation of an acid resist.

An impure form of gelatin, glue, can also be used for some enamel purposes. The first step is to clarify the glue:

Purifying Glue

Cologne Glue 100 g. Water 600 cc.

Clarification is performed by initial soaking of the glue in water for 12 hours, after which it is dissolved by heating and 3 grams of dry egg albumen (previously dissolved in a little water) is added to the glue solution. The mixture is then heated on a water bath for 15 minutes at a boiling temperature (212° F.), filtered, and allowed to cool. Of the clarified glue, 60 cc. is mixed with

3.5 grams of dry egg albumen (dissolved in 30 cc. of water), to which is added 30 cc. of a 10% ammonium bichromate solution, followed by filtration of the bichromated mixture.

No. 7

Ammonia  $3\frac{1}{2}$  oz. Potassium Carbonate 15 gr. Casein  $\frac{1}{2}$  oz.

The mixture is allowed to stand for some hours, during which time the casein will uniformly dissolve. When in complete solution, the mixture is rendered light-sensitive by the addition of  $3\frac{1}{2}$  ounces of a saturated solution of ammonium bichromate, then filtered. The sensitized solution keeps only a few days.

Dextrin is another substitute for fish glue in the enamel process, the dextrin produced by mixing and heating

Wheat Starch 500 g.
Sodium Bicarbonate 25 g.
in dry form until the starch beginning to the starch begi

in dry form until the starch begins to assume a yellow color. The mixture is then cooked in 1000 cc. of water, thus providing a stock solution, which is used as follows:

No. 8

Stock Dextrin Solution 100 cc. Ammonium Bichromate 14 g. Ammonia 20 cc. Distilled Water 300 cc.

Mix the ingredients in a mortar, grinding the mass until the bichromate has been entirely dissolved. After filtration through flannel, the solution is used in the ordinary manner of the enamel process.

No. 9

Water		10	oz.
Le Page's G	lue	4	oz.
Albumen		1	oz.

Glucose 40 gr. Ammonium Bichromate 120 gr.

It is suggested to harden the developed image for 2 to 3 minutes in a chromic acid bath (chromic acid, 22 grains; water, 16 ounces) before whirling dry and burning-in.

Photoengraving Resist British Patent 512,914 Formula No. 1

Dicinnamyl Acetone 4 g.
Pale Kauri Resin 6 g.
Ethyl Methyl Ketone 60 g.
Toluene 30 g.
Benzyl Alcohol 1 g.
Crystal Violet Base 0.2 g.

This resist can be used in conjunction with bichromated albumen as the active sensitizer. On application to the metal, the resist is almost colorless, but dries to a blue-green color; this changes to a blue or violet tint during exposure to light.

# No. 2

Polyvinyl Alcohol
(Powdered) 50 g.
Cold Water 500 cc.

Allow the powder to swell in the water until the mixture becomes thick, then heat at a temperature of 185°-194° F. until a clear solution is obtained. Cover the mixture and allow to cool somewhat, then add:

Ammonium Bichromate 5 g. Water 250 cc.

If desired, the bichromated solution of alcohol can be further diluted with an additional 250 cc. of water. The image is developed in water, dyed in a 1% solution of safranin and methyl violet (2:1),

then hardened in a 1% solution of ammonium molybdate. Following this, the image is burnt-in to a brown color before etching.

Photo-Sensitive Coating for Photo-Engraving Whites of Two Eggs Ammonium Bichro-

mate 75 gr.
Liquid Glue 34 oz.
Water 16 oz.
Iron Ammonium

Citrate 25 gr. Ammonia Solution (26° Bé) 15–20 drops

Mix the ammonium bichromate and iron ammonium citrate with one-half the water. Beat up the white of eggs, add the glue, ammonia and remaining water, stirring well. Mix the two resulting solutions. Let stand in a dark place for 24 hours; then decant. Keep the clear liquid in a dark place.

Photo-Engravers' Glue Ink Top

 $\begin{array}{ccc} \text{Water} & 50 & \text{oz.} \\ \text{Le Page's Glue} & 3\frac{1}{2} & \text{oz.} \\ \text{B} \\ \text{Water} & 50 & \text{oz.} \\ \end{array}$ 

Ammonium Bichromate 11/4 oz.

Mix the solutions separately, then add B to A, and filter as with regular glue enamel. The exposed print is rolled up lightly with etching ink, after which the image is developed with water in the manner of bichromated albumen prints.

Photomechanically Etched Name Plates

The preferred metal for name

plate work is "etching" brass, though for military name plates, aluminum, stainless steel, terneplate and zinc also are used. The metals range in thickness from .025 to .070 inch and must be free from deep scratches and other surface defects. Specific etching depth is not often required; the depth must, however, be sufficient to provide good relief to the letters and permit convenient blackening (or coloring) of the etched areas. Actual depth of etching ranges from .002 to .010 inch, depending on the metal, its thickness and the nature of the name plate design.

As previously stated, the procedure given is for brass, but the general routine can also be carried out with other metals, substituting cold enamel or bichromated albumen (ink top) as sensitizers for aluminum, zinc and metals of the ferrous type. To facilitate subsequent handling, a quarter-inch hole is perforated in each of the four corners of the sheet, the holes accommodating hooks whereon the sheets are hung during the various phases of name plate making.

The first step in the operation is to provide the "gang" or master negative bearing the required number of duplicate images, which can then be printed down (exposed) on the sensitized metal as a single unit. The position and spacing of the images must be very accurate, so as to permit convenient blanking (guillotining of stamping out) of the individual name plates from the sheet after etching. Since the name plate design must "read right" (appear in normal position) on the metal, lateral reversal of the nega-

tive image (as required in photoengraving) obviously is not necessary.

Image-duplication in the master negative can be carried out in several ways, the simplest being to make velox or photographic reproductions to the proper size and required number from the original copy, then accurately arrange and paste the prints to respective positions on a heavy cardboard or thin metal support. While requiring no equipment other than a camera. printing frame and layout table, this method naturally is somewhat laborious and time-consuming, although it is practically the only procedure open to those not possessing photocomposing (step-andequipment. This latter equipment may take two forms: a "step-and-repeat back" or controlled-movement plateholder in the rear of a darkroom camera of the process type, or a photocomposing machine, wherewith the photographic surface may be sectionally and progressively exposed under a negative (or positive) until the required number of duplicate images have been recorded.

The step-and-repeat camera is the more convenient arrangement since it permits direct recording of negative images, whereas with a photocomposing machine, either a positive master image would be required (a "negative" drawing or negative print could be used), or the "gang" image would have to be converted to a negative by contact printing on another plate, or by chemical reversal (transformation) of the positive into the required negative image. Chemical reversal is not to be generally recommended: not all

brands of plates lend themselves to this treatment, and should failure ensue, not only the plate but also the time of step-and-repeat exposures would be irretrievably wasted.

The number of images in the master (gang) negative will naturally be governed by the size of the name plate design, also by the number of duplicate images to appear on the metal sheet. Although film could be used, gelatin dry plates of the process type are the safest medium, since film negatives are liable to sizealteration and image-distortion because of atmospheric influence, and wet collodion plates are prone to gradual drying of surface during the time required for exposing a number of images.

The master negative should be protected against abrasion and scratches liable to occur when repeated exposures must be made from the same negative. A "hard" negative varnish could be applied to the plate, but there is merit in the idea of protecting the face of the negative with a thin (.001 inch) sheet of Kodapak, a transparent cellophanelike material impervious to humidity and moisture. This treatment has the advantage in that the protecting sheet can be removed after surface damage, whereas a varnished negative would probably require makeover should its surface be badly scratched or otherwise damaged.

With an accurately composed master negative at hand, the next step is cleaning of the metal plates prior to their sensitization. With brass plates first immerse the sheets in: No. 32B Cleaner (International Chemical

Company) 4 oz. Water 1 gal.

The time of immersal is five minutes with a bath temperature of 200° F. The sheets are then rinsed in cold water, after which they are immersed in:

Sodium Cyanide 4 oz.
Water 1 gal.
remaining in the bath (75–100° F.)
for ten seconds. Following a rinse
in cold water, the plates are
scrubbed with No. 400 pumice, then
rinsed thoroughly in cold water,
whereupon the metal is ready for
sensitization.

As a sensitizer and photoresist for brass plates, use

Photoengraving Glue 32 Water 85 Ammonium Bichromate 3

The solution should be carefully filtered through absorbent cotton and should possess a specific gravity of approximately 1.07. The stock mixture is best contained in brown or non-actinic bottles.

Coating (sensitizing) of the metal plates is performed on a centrifuge or whirler, a specific quantity (depending on the size of the plate) of the bichromated glue mixture being poured on the center of the plate and allowed to distribute. After removal of the plate from the whirler, the coated sheet is dried for 30 minutes at 100–110° F., the operation of coating and drying performed in a clean, dimly lit room, so as to prevent "fogging" of the light-sensitive coating and resultant scummy prints.

(While the glue enamel process gives good results on brass, cold

enamel or bichromated albumen may be preferred by some as photoresists for aluminum, steel and zinc, primarily because burning-in of the developed image is dispensed with; further, with albumen-ink images, the photoresist, after etching, is more easily removed than is the case with either glue or cold enamel images.)

The metal plate bearing the lightsensitive glue coating is next locked in contact with the master negative in a vacuum printing frame, and the plate exposed to the light of an arc lamp in the regular manner of photoengraving. After exposure, the print is developed in lukewarm water as is done with glue prints on copper and zinc, the plate being further cleaned and the image sharpened by lightly swabbing the print with wet cotton to aid removal of all soluble and partially soluble glue particles.

The developed print is then dried at room temperature, whereupon the image is burnt in (baked) at a temperature of 400–450° F., with heating continued until the print assumes a light brown color. The photoresist, so created, is then ready for etching.

Prior to etching, the back of the plate is painted with a shellac solution to protect this area against action of the etching solution. The shellac solution is prepared by first mixing a stock solution (orange shellac, 4 pounds; denatured alcohol, 1 gallon), which is used in the following proportion:

Shellac Solution 3 qt.
Denatured Alcohol 1 qt.
Methyl Violet ¼ oz.

The methyl violet dye has, for its purpose, greater visibility of the applied coating, thus aiding in proper coverage of the back of the plate.

On drying of the protective backing, the glue print is given a scumremoval treatment by wiping its surface with a soft cloth dampened with the following solution:

Hydrochloric Acid 3
Denatured Alcohol 7

At this stage, hooks are inserted in the holes at the corners of the sheets and the plates then placed in a pitch lined wooden tank containing a ferric chloride etching bath at 40° Bé (ferric chloride, 7 pounds; water, 1 gallon). The bath is agitated by air during the etching period and the sheets brushed lightly several times during this period in order to remove possible oxidation and foreign substances from the surface of the metal. Time of etching depends on the etchability of the brass, the depth required and the prevailing room temperature of the bath as well as the strength of solution.

Etching completed, the glue photoresist is removed from the sheets by immersing the plates in:

Sodium Hydroxide 4 oz. Water 1 gal.

The solution is used at a temperature of 200–212° F. and the plates kept in the bath until the glue image has thoroughly loosened or left the plate, when the sheets are then rinsed in cold water and immersed in:

Sodium Cyanide 4 oz. Water 1 gal.

This bath is used at a temperature not to exceed 100° F. and the plates immersed until all vestiges of the glue image have been removed. The sheets are again rinsed in cold water, dried, and are then ready for lacquering and finishing.

Stripping Film Gelatin Solution A solution to aid adhesion. Fill a 32-ounce bottle half full of water. Add ½ ounce granulated gelatin (stir while adding), and 2 ounces 28% acetic acid. Add enough cold water to fill the bottle.

# Stripfilm Cement

As an adhesive and to prevent line and halftone stripfilm negatives from curling when stripped on glass plates, this cement is recommended:

Water (125° F.)	32
Gelatin	$\frac{1}{2}$
Process Glue	1/2
Acetic Acid (28%)	4

Soak the gelatin in cold water, then dissolve in the above quantity of warm water, after which add the glue and acetic acid. In use, apply a thin film of cement to the glass plate before putting down the stripfilm negatives, then squeegee the films into good contact with lintless blotting paper.

# Negative Cleaner

For ridding the surface of gelatin negatives from finger marks and dirt of all kinds, the following is used:

### Formula No. 1

Ethyl Alcohol	18
Wood Alcohol	2
Strong Ammonia	- 1

Rub the solution over the surface of the negative with a pledget of absorbent cotton.

# No. 2

Petrolatum	1 oz.
Carbon Tetrachloride	20 oz.
Glacial Acetic Acid	1/4 oz.

The solution is rubbed lightly on the negative with a soft chamois skin; after drying, polish the negative surface until none of the cleaner is visible.

# Glass Cleaner

For cleaning copyboard and printing frame glasses as well as general photographic glassware, a wetting agent is of utility:

### Wetanol or Aerosol OT

(Wetting Agent)	1 oz.
Denatured Alcohol	10 oz.
Water	5 gal.

# TC-1 Tray Cleaner For General Use

	Avoirdupois	Metric
Water	32 oz.	1.0 l.
Potassium Bichromate	3 oz.	90.0 g.
Sulphuric Acid, C.P.	3 fl. oz.	96.0 cc.

Add the sulphuric acid slowly while stirring the solution rapidly.

For use, pour a small volume of the tray cleaner solution in the vessel to be cleaned. Rinse around so that the solution has access to all parts of the tray; then pour the solution out and wash the tray six or eight times with water until all traces of the cleaning solution disappear. This solution will remove stains caused by oxidation products of developers and some silver and dye stains. It is a very useful cleaning agent.

# TC-2 Tray Cleaner For Removal of Silver Stains

# Solution A

	Avoirdupois	${f Metric}$
Water	32 oz.	1.0 l.
Potassium Permanganate	73 gr.	5.0 g.
Sulphuric Acid, C.P.*	$2\frac{1}{2}$ dr.	10.0 cc.

<sup>\*</sup> Add the sulphuric acid slowly while stirring the permanganate solution rapidly.

### Solution B

	Avoirdupois	${f Metric}$
Water	32 oz.	1.0 l.
Sodium Bisulphite	145 gr.	10.0 g.

For use, pour Solution A into the tray and allow it to remain for a few minutes, then rinse with water. Apply Solution B, and wash thoroughly.

This formula is satisfactory for the removal of most types of general stains but it is especially recommended for the removal of silver stains.

# S-5 Hand Stain Remover

### Solution A

	Avoirdupois Metric	
Potassium Permanganate	$\frac{1}{4}$ oz. 7.5 g.	
Water	32 oz. 1.0 l.	
Solutio	on B	
Sodium Bisulphite	16 oz. 480.0 g.	
Water	32 oz. 1.0 l.	

Rub the hands with a small amount of Solution A, rinse in water; then pour a small quantity of Solution B into the palm of one hand, rub it quickly over the hands, and, when free of stain, wash them thoroughly with water. If the original stain is not entirely removed, repeat the treatment with Solutions A and B.

If it is desired to immerse the hands in Solution B, 1 part of the solution should be diluted with 4 parts of water.

### S-6 Stain Remover

# For Removal of Developer Stain on Negatives

Developer or oxidation stain may be removed by first hardening the film for 2 or 3 minutes in the formalin hardener (SH-1), then washing for 5 minutes and bleaching in:

# Stock Solution A

4 . 6 2	Halley Edward	Life of the second	de indentari.	Avoir	dupois	Metric
	Potassium	Permangana	te	75	gr.	5.2 g.
	Water, To	make	igia a prope	32	oz.	1.0 l.

# Stock Solution B

Cold Water	16	CZ.	500.0	ee.
Sodium Chloride	21/2		75.0	
Sulphuric Acid, C.P.	/ =	fl. oz.	16.0	47
Water, To make		oz.	1.0	

Use equal parts of A and B. The solutions should not be mixed until ready for immediate use since they do not keep long after mixing. All particles of permanganate should be dissolved completely when preparing Solution A, since undissolved particles are likely to produce spots on the negative. Bleaching should be complete in 3 or 4 minutes at 68° F. (20° C.). The brown stain of manganese dioxide formed in the bleach bath is best removed by immersing the negative in 1% sodium bisulphite solution. Then rinse well and develop in strong light, preferably sunlight, with any non-staining developer such as D-72 diluted 1 part to 2 parts of water. Then wash thoroughly.

Warning: Developers containing a high concentration of sulphite (such as D-76) should not be used for redevelopment because the sulphite tends to dissolve the bleached image before the developing agents act upon it.

# Washing Test and Hypo Elimination

Very small traces of hypo retained in films or prints greatly accelerate the rate of fading of the image. It is extremely difficult to test for small quantities of hypo but the following test (HT-1a) will indicate when the film or prints may be considered reasonably free from hypo. If prints give a negative reaction by this test it is no guarantee that they may not ultimately fade.

# HT-1a Hypo Test Solution For Testing Thoroughness of Washing

	Avoire	dupois	Meti	ric
Distilled Water	6	OZ.	180.0	cc.
Potassium Permanganate	4	gr.	0.3	g.
Sodium Hydroxide	8	gr.	0.6	g.
Water (Distilled), To make	8	oz.	250.0	cc.

Films or Plates: Take 8 ounces (250 cc.) of pure water in a clear glass and add ¼ dram (1 cc.) of HT-1a. Then take a 6-exposure film, size 3½x4¼ in. or equivalent from the wash water and allow the water from it to drip for 30 seconds into the glass of test solution. If a small percentage of hypo is present the violet color will turn orange in about 30 seconds and with a larger concentration the orange color will change to yellow. In either case the film should be returned to the wash water and washed until further tests produce no change in the violet color.

Papers: Take 4 ounces (125 cc.) of pure water in a clear glass and add ¼ dram (1 cc.) of HT-1a. Pour ½ ounce (15 cc.) of this diluted solution

into a clear 1-ounce glass container. Then take six prints, size 4x5 in. or equivalent, from the wash water and allow the water from them to drip for 30 seconds into the ½ ounce of the dilute test solution. If a small quantity of hypo is present the violet color will turn orange in about 30 seconds and become colorless in one minute. In either case the prints should be returned to the wash water and washed until further test shows no change in color.

Note: Oxidizable organic matter if present in the water reacts with the permanganate solution and changes its color in the same manner as hypo. The water

should therefore be tested as follows:

Prepare two samples of the permanganate test solution using distilled water. Then add a volume of the tap water to one test sample equal to that of the wash water drained with the film or prints into the other sample. If the sample to which tap water has been added remains a violet color this indicates the absence of organic matter and it will be unnecessary to make the test in duplicate. If the color is changed slightly by the tap water, however, the presence of hypo in the film or prints will be shown by the relative color change of the two samples. For example, if the tap water sample turned pink and the wash water sample became yellow it would indicate the presence of hypo, while if both remained the same shade this would indicate the absence of hypo.

When complete removal of hypo is important, prints should be treated in the HE-1 Hypo Eliminator.

# HE-1 Hypo Eliminator For Professional and Amateur Use

	Avoirdupois	Metric
Water	16 oz.	500.0 cc.
Hydrogen Peroxide (3% Solution)	4 fl. oz.	125.0 cc.
Ammonia (3% Solution)	$3\frac{1}{4}$ fl. oz.	100.0 cc.
Water, To make	32 oz.	1.0 l.

Note: Prepare the solution immediately before use and keep in an open container during use. Do not store the mixed solution in a stoppered bottle or the gas evolved may break the bottle.

Directions for Use: Wash the prints for about 30 minutes at 65° to 70° F. in running water which flows rapidly enough to replace the water in the vessel (tray or tank) completely once every 5 minutes. Then immerse each print about 6 minutes at 70° F. in the HE-1 Hypo Eliminator solution and finally wash about 10 minutes before drying. At lower temperatures, increase the washing times.

Life of HE-1 Solution: About fifty 8x10-inch prints or their equivalent

per gallon (4 liters).

Test for Hypo: Process with the batch of prints, an unexposed white sheet of photographic paper (same weight and size as majority of prints in batch). After the final wash, cut off a strip of this sheet and immerse it in a 1 per cent silver nitrate solution for about 3 minutes; then rinse in water and compare while wet with the wet untreated portion. If the hypo has been completely removed, no color difference should be observed. A

yellow-brown tint indicates the presence of hypo. The depth of the tint increases with increased hypo content. A positive test with silver nitrate may also be obtained in the absence of hypo if hydrogen sulphide or wood extracts are present in the water supply.

# Occasional Effects when Using the Peroxide-Ammonia Treatment (HE-1)

1. Slight tendency for prints to stick to belt on belt driers. To prevent this effect bathe the prints about 3 minutes in a 1 per cent solution of formaldehyde prior to drying.

2. An almost imperceptible change in the image tone. To prevent this effect, add 15 grains of potassium bromide to each quart (1 gram per liter)

of the peroxide-ammonia bath (HE-1).

3. A very faint yellowing of the whites (undetectable on buff papers). To minimize this effect, bathe the prints in a 1 per cent sodium sulphite solution for about 2 minutes immediately after treatment in HE-1 and prior to the final wash.

Note: With buff papers, it is possible to use a higher concentration of peroxide (maximum about 500 cc. of 3% solution per liter) and thus extend the exhaustion life to about eighty 8x10-inch prints per gallon. This more concentrated bath is not recommended for use with white papers because the yellowing would be objectionable.

# GP-1 Gold Protective Solution For Increasing the Permanency of Silver Images

	Avoirdupois	Metric
Water	24 oz.	750.0 cc.
Gold Chloride (1% Stock Solution)*	$2\frac{1}{2}$ fl. dr.	10.0 cc.
Sodium Thiocyanate	145 gr.	10.0 g.
Water, To make	32 oz.	1.0 1.

Add the gold chloride stock solution to the volume of water indicated. Dissolve the sodium thiocyanate separately in 4 ounces (125 cc.) of water. Then add the thiocyanate solution slowly to the gold chloride solution

while stirring the latter solution rapidly.

For Use: Immerse the well washed print (which preferably has received a hypo elimination treatment) in the Gold Protective Solution for 10 minutes at 70° F. (21° C.) or until a just perceptible change in image tone (very slightly bluish black) takes place. Then wash for 10 minutes in running water and dry as usual.

Approximate Exhaustion Life: Thirty 8x10-inch prints per gallon. For best results the GP-1 solution should be mixed immediately before use.

Films and Plates: The above procedure may also be used with fine-grained images of films and plates when maximum permanency is desired.

\*A 1% stock solution of gold chloride may be prepared by dissolving the contents of one tube (15 grains) in 3½ ounces of water (1 gram in 100 cc. of water).

Diazo Printing

Diazo type printing is very useful for making dry, accurate copies of typewritten, printed, or sketched material in a very short time.

# Formula No. 1 French Patent 794,590

The paper on which reproduction is to be made is coated with a small portion of a mixture of 22 parts of stannic chloride double salt of 4 diazo 1 dimethyl aniline, 20 parts of boric acid, 50 parts of tartaric acid, 2 parts of phloroglucinol, and 1000 parts of water. The paper is dried in the dark and exposed to ultraviolet light under a transparent positive. The paper is then treated with gaseous ammonia and the image is developed.

No. 2 British Patent 413.093

The paper is coated with a small portion of a mixture of 5 parts metol, 4 parts potassium nitrate, and 200 parts water. It is then dried in the dark and exposed to ultra-violet light under a transparent positive. A light sepia print is obtained.

No. 3 British Patent 297,363

The paper is coated with a solution of the diazo compound of H acid, dried in the dark, exposed to ultra-violet light under a transparent positive and developed with ammonia.

Making Photographic Prints on Wood

Beat thoroughly the whites of one or two eggs, and let stand for one or two hours. In this interval the albumen will be reduced to a liquid form. Mix it with powdered English oxide

of zinc, and place a smooth coating on the surface of the wood, making it as thin as possible. After the surface is thoroughly dry, sensitize it with a solution of Eastman Silver Nitrate (Eastman Hydrometer test about 50). The sensitized surface should be thoroughly dried in a dark place, after which it will be ready for printing, in sunlight or under strong artificial light. After being printed, it should be fixed with a weak solution of plain hypo for about five or ten minutes, and then washed.

Ferrotype Polish
(For Metal Photographic Plates)
Beeswax 40 gr.
Carbon Tetrachloride 4 oz.

Fingerprinting by Photography

Several methods for rendering the hands luminescent prior to photographing them can be employed. The hands may be dusted with a brightly fluorescing phosphor such as zinc-beryllium silicate or magnesium tungstate, illuminated with intense ultra-violet light, and photographed with a camera having two 4A filters. Or, the hands can be dipped in a fluorescent dye such as neutral acriflavine and after drying photographed in the same manner. The whole hand may be thus photographed and reduced on microfilm. On enlargement the fingerprint becomes clear enough for the usual study. This method is applicable for rapid fingerprinting (without soiling) of a great many persons, the record including the palm and its characteristics.

Saving Overexpose	d Film
Bathe the negative fo	r 5 min. in:
Potassium Bromide	110 gr.
Water	40 oz.
Then develop for 10-	-15 min. at
65-68° F. in:	
Water	16 oz.
Potassium Metabisul-	-
phite	4 gr.
$\mathbf{Metol}$	3 gr.
Sodium Sulphite	180 gr.
Hydroquinone	90 gr.
Sodium Carbonate	110 gr.
Potassium Bromide	16 gr.

Motion Picture Screen
U. S. Patent 2,215,061
Glass cloth is coated with:
Cellulose Nitrate 14.0
Castor Oil 18.6
Pigment, White 23.4
Ethyl Acetate 17.6
Alcohol 26.4

Photo Flash Lamp Filler
U. S. Patent 2,252,241

Aluminum 85%
Zinc 6%
Cadmium 9%

Flashlight Powder
German Patent 705,162

Magnesium, Powdered 2.4 g.
Zirconium, Powdered 6.5 g.
Potassium Chlorate 5.0 g.
Nitrocellulose Solution 5.0 cc.

Photographic Hints
1. To eliminate air bells on photographic films during developing, add 1-5 cc. of glycerin to each liter of solution.

2. To prevent curling and cracking, particularly in cold weather, add about one ounce (30 cc.) of glycerin to each quart (liter) of final rinse water. Even better is the procedure advocated in a Government photography manual. Here it is advised that the prints be placed in a glycerin bath after the completion of the final washing. This bath is composed of 1 part of glycerin to from 5 to 10 parts of water, and the print is allowed to remain in this bath for at least five minutes. Then without further washing, the print is placed on the drier.

Do not discard these solutions; they may be used over and over again. From time to time, however, it will be necessary to add a little glycerin to overcome the diluting effects of the water carried over on the prints from the washing and rinsing procedures.

3. To lend brilliance and durability, a print varnish, especially suitable for use on bromide prints, can be made from:

30	gr.
60	gr.
	gr.
30	min.
1	fl. oz.
ol, tl	nen add:
1	fl. oz.
	60 10 30 1 ol, tl

Add a small quantity of whiting or powdered pumice to precipitate the gum wax. Shake well at intervals and allow to stand for several days. Decant and filter the clear liquid. Bottle until needed.

# CHAPTER SIXTEEN

# POLISHES AND ABRASIVES

	Oil Polish		Gum Tragacanth	1
	U. S. Patent 2,275,8	596	Water	84
	Formula No. 1		No. 7	
	Mineral Spirits	169.00	Light Mineral Oil	56
	Mineral Oil, Light	187.50	Potassium Stearate	1
	Glyceryl Monoricinoleat		Paraffin and Carnauba	
	Ricinoleic Acid	11.03	Waxes	3
	Water	624.75	Water	40
	Caustic Potash Solution			
	(8.6%)	19.25	Liquid Wax Polish	
	No. 2	10.20	Heavy Panoline	165
	Sulphonated Petroleum	Oil 2	Mineral Seal Oil	75
	Sodium Oleate	4	Paraffin Wax	$13\frac{1}{2}$
	Light Mineral Oil	38	Carnauba Wax	$1\frac{1}{2}$
	Red Oil	3	Varnolene	24
	Water	53		
	No. 3	99	Emulsion Polish	
	Mineral Oil	50	1. Carnauba Wax	10
	Ammonium Oleate	3	2. Petromix No. 5	6
	Water	47	3. Deodorized Kerosene	34
	Pine Oil, To suit	41	4. Water	5 <del>1</del>
	No. 4		1 and 2 are melted togeth	
		10	3 and heat to 180° F. Heat	
	Light Blown Castor Oil	10 20	200° F. and add to above w	
	Light Mineral Oil		I .	/Ion Son
	Xylene	9 1	ring.	
	Potash Soap	_	Pure Carnauba Polis	ah.
	Water	60	1. Carnauba Wax	10
	No. 5	. 0.		
	Mineral Oil	25 10	2. Petromix No. 5 (Emul	
	Naphtha	10	sifier)	4
	Stearic Acid	4	3. Butyl Cellosolve	
	Triethanolamine	2	4. Water	85
Water 59		Melt 1 and 2, then add 3		
	No. 6	μ	at 200° F. with constant st	irring.
	Kerosene	5	0 1 0 7 7	• •
	Light Mineral Oil	5	Carnauba-Shellac Pol	
	Glycerin	4	1. Carnauba Wax	10
	Gum Arabic	1	2. Petromix No. 5	4

3. Butyl Cellosolve	1
4. Water	65
5. B Solution	20
Directions as for pure	Carnauba
polish.	
$^{`}$ B Solution	
Dry Powdered Shellac	20
Water	79
Ammonium Hydroxide	1
Heat to boiling. Makes	a clear so-
lution.	

1	Naphtha Emulsion Sho	e Cle	ane
	High Viscosity Methy	1	
	Cellulose	1.0	
	Water	100.0	cc.
	2-Amino-2-Methyl-1,		
	3-Propanediol	2.3	g.
	Stearic Acid	6.2	g.
	Low-Boiling Naphtha	200.0	cc.

The methyl cellulose is dispersed in the water and to this dispersion is added the amino-methyl-propanediol. The stearic acid is dissolved in the naphtha and this solution is poured into the methyl cellulose dispersion and thoroughly agitated.

# Shoe Polish Paste (To be packed in tubes) Candelilla Wax Diglycol Stearate Stroba Wax Varsol Water 250 225–300

Melt first three ingredients together and, after removing flame, stir in Varsol. Add the water (at 90° C.) slowly, with vigorous stirring, to the wax-solvent mixture.

Polish for Transparent Plas	stics
Diatomaceous Silica	100
Emulsone B (Emulsifying Gum)	10
Water	600
Naphtha	300

Battleship Linoleum Polish			
Ceresin Wax	27.2		
Carnauba Wax	25.0		
Rezo Wax B	2.2		
Naphtha	72.0		
Rubbing Type Paste Formula No. 1	Wax		
Carnauba Wax	150		
Paraffin Wax	166		
Beeswax	76		
Durez 420 Resin	34		
Heat to approximatel 325° F. to melt.	y 300° to		
Add the following:			
Mineral Spirits	1280		
Turpentine	32		
Stir and cool to 160°	F. Dump		
into containers.			

No. 2	
Carnauba Wax	14.0
Beeswax	14.0
Paraffin Wax	14.0
Stearic Acid	5.0
Amino Methylpropanol	2.5
Water	80.0

The first four ingredients are melted together on a boiling water bath. The amino methylpropanol is stirred into the wax melt, the temperature of which should not exceed 100° C. to 105° C. at this point, and the boiling water is added with vigorous agitation.

Tous agreement.	
Bright Drying Waxe	es for Fruit
Coating	
U. S. Patent 2,2	275,659
Formula No	o. 1
Carnauba Wax	30.0
Soap	6.5
Water	260.0
Bentonite	0.3-2.6
No. 2	-
Carnauba Wax	30.0 g.
Oleic Acid	3.3 g.
~ 12 ~ 3	. 0.

0.5 g.

Caustic Soda

Triethanolamine 2.7	g.	Blown Castor Oil	10
Berax Shellac Solu-	8,	Ammonia Soap	3
tion 60.0	cc.	Water	54
Water 260.0		***************************************	
Bentonite 0.3–2.6			~.
No. 3	0,	Automobile Polish and	Cleaner
Carnauba Wax 30.0	ø.	Formulae	
Oleic Acid 3.3		Formula No. 1	
Caustic Soda 0.5		Ortho Dichlorbenzene	11/2 gal.
Triethanolamine 2.7		Pine Oil	$\frac{1}{2}$ gal.
Borax Shellac Solu-	ρ,	Kerosene or V.M.P.	72 8
tion 60.0	ĊC.	•	9½ gal.
Water 260.0		Diatomaceous Silica	72 80
Gelatin 0.3–1.3		(Fine) 1	1 lb.
No. 4	ρ.	Diatomaceous Silica	
Carnauba Wax 30.0	gr.		1½ lb.
Oleic Acid 3.3		Cream Tripoli 4	. –
Caustic Soda 0.5			$3\frac{1}{2}$ gal.
Triethanolamine 2.7			$2\frac{1}{2}$ gal.
Borax Shellac Solu-	₽.	Glycerin or Glycol	3/8 gal.
tion 60.0	cc		
Water 260.0		Mix thoroughly the pine	
Irish Moss,	8.	sene, etc., and the chlorber	
Bleached 0.2–0.65	o .	the abrasives and bentonit	
Dieactied 0.2-0.08	8.	with the glycerin and w	
Automobile Polishes smooth homogeneous paste. Add the			
Formula No. 1		oil mixture to the abrasiv	
Mineral Oil	42	slowly with vigorous agi	
Castor Oil	5	fully incorporated. (A	
Ammonia Soap	$\overset{\circ}{2}$	pump can be used to adv	antage for
Xylol	5	this thorough mixing.)	
Water	46	No. 2	
No. 2	10	Spindle Oil	4% gal.
Mineral Oil	38	Light Fuel Oil	23/8 gal.
Castor Oil	10	Diatomaceous Silica	· ·
Potash Soap	1	(Fine) 4	5 lb.
Water	51	Diatomaceous Silica	
No. 3	91	(Finest) 4	5 lb.
Coal-Tar Naphtha	9		2 lb.
Mineral Oil	27	Water 3	
Blown Castor Oil	6	The abrasives and ber	•
The state of the s	3	thoroughly mixed into	
Ammonia Soap	55	The oils are mixed tog	
Water No. 4		added to the abrasive wat	
	16		
Coal-Tar Naphtha	16	with vigorous stirring un	on eminist.
Mineral Oil	17	fication is complete.	

No. 3	Diatomaceous Earth	13
Carnauba Wax 27 lb.	Water	62.3
Spermaceti 50½ lb.	No. 8	
Ozokerite 44 lb.	Mineral Oil	10 -
Kerosene or V.M.P.	Blown Castor Oil	1
Naphtha 32 gal.	Gum Tragacanth	0.5
Diatomaceous Silica	Glycerin	4
(Finest) 65 lb.	Ammonia Water	0.1
Cream Tripoli 131 lb.	Diatomaceous Earth	10
Bentonite 16 lb.	Water	74.4
Coloring Pigment or	No. 9	
Dye, To suit	Mineral Oil	6
Water 131/4 gal.	Petroleum Naphtha	4
Borax 3½ lb.	Glycerin	5
Trisodium Phosphate 31/4 lb.	Gum Tragacanth	0.4
Soap Chips (Finest	Triethanolamine	0.1
Grade) 16¼ lb.	Fatty Alcohol Sulphate	0.1
Water $13\frac{1}{4}$ gal.	Diatomaceous Earth	10
No. 4	Water	74.4
Mineral Oil 15	No. 10	
Glycerin 2	Mineral Oil	9
Gum Tragacanth 0.1	Carnauba Wax	0.6
Diatomaceous Earth 11	Glycerin	5
Water 71.9	Gum Tragacanth	0.5
No. 5	Ammonia Water	0.3
Kerosene 9	Diatomaceous Earth	11
Mineral Oil 5	Water	73.6
Gum Tragacanth 0.25	No. 11	
Glycerin 4	Mineral Oil	17
Denatured Alcohol 5	Carnauba Wax	0.5
Diatomaceous Earth 13	Glycerin	3
Water 63.75	Gum Tragacanth	0.5
No. 6	Diatomaceous Earth	11
Petroleum Naphtha 5	Water	68
Mineral Oil 8	No. 12	
Gum Tragacanth 0.7	Mineral Oil	8
Glycerin 3	Carnauba Wax	1
Denatured Alcohol 6	Glycerin	5
Diatomaceous Earth 14	Gum Tragacanth	0.2
Water 63.3	Triethanolamine Oleate	0.2
No. 7	Diatomaceous Earth	17
Light Mineral Oil 7	Water	68.6
Water-Soluble Gum 0.5	No. 13	•
Glycerin 4	Mineral Oil	8
Ammonium Chloride 0.2	Petroleum Naphtha	8
Alcohol 13	Carnauba Wax	1.5

Paraffin Wax	0.5
Glycerin	5
Gum Tragacanth	0.1
Ammonia Soap	1.5
Diatomaceous Earth	13
Water	62.4
No. 14	
Mineral Oil	7
Kerosene	3
Carnauba Wax	2
Glycerin	7
Triethanolamine	0.1
Gum Tragacanth	0.4
Diatomaceous Earth	12
Water	68.5
No. 15	
Kerosene	11
Carnauba Wax	1.7
Glycerin	4
Ammonia Water	0.2
Gum Tragacanth	0.4
Diatomaceous Earth	11
Water	71.7
No. 16	
Mineral Oil	9
Castor Oil	3
Stoddard's Solvent	18
Carnauba Wax	0.8
Soda Soap	0.5
Bentonite	2
Diatomaceous Earth	7
Water	59.7
No. 17	00
Mineral Oil (60–80 sec.)	6
Petroleum Naphtha	O
Petroleum Naphtha (95–140° C.)	6
Oleic Acid	2
Carnauba Wax	1
Amino Methylpropanol	1
Diatomaceous Earth	11
Water	73
The first four ingredie	

The first four ingredients are melted together and the diatomaceous earth is stirred into this melt to make a thick paste. The amino methylpropanol and water—mixed

together and warmed to approximately 75° C.—are then added to the warm melt with very vigorous agitation.

Automobile Deste Cleaner			
Automobile Paste Cleaners Formula No. 1			
Mineral Oil	6		
Kerosene	6		
Pine Oil	2		
Sodium Oleate	4		
Tripoli	45		
Water	37		
No. 2	91		
Mineral Oil	9		
Petroleum Naphtha	21		
Carnauba Wax	4		
Paraffin Wax	$ar{2}$		
Sodium Silicate	3		
Sodium Stearate	3		
Tripoli	26		
Water	32		
No. 3			
Kerosene	19		
Carnauba Wax	5		
Paraffin Wax	. 3		
Sodium Soap	2		
Gum Tragacanth	1		
Tripoli	33		
Water	37		
No. 4			
Soap	4.05		
Water	16.35		
Glycerin	6.75		
Kerosene	19.30		
Dibutyl Phthalate	3.55		
Mild Abrasive	50.00		
Homogenize in a paint m	111.		

Burnishing Polishes for Automobile Maintenance

Dissolve 1 ounce by weight of oxalic acid in 1 quart of water.

In another container containing 1 gallon of water, dissolve 5 ounces by weight of Nelgin and 1 ounce by weight of Moldex. To it add 1 pound of ammonium hydroxide and while stirring add 72 fluid ounces of Stetsol. Make sure the Stetsol is added very slowly, while being stirred vigorously for at least 1 hour. Then add 2 pounds of diatomaceous earth slowly to which the dissolved oxalic acid had been previously added. Stirring should continue until a creamy consistent mass has been obtained.

This polish is applied to the body of the car with a semi-wet cloth and rubbed slightly for a few minutes, and followed up with a dry cloth.

# Silver Polish A. Pastes

Formula No. 1	
Diatomaceous Earth	15-20
Soap, Hard	3-8
Soda Ash	0.5 - 1.5
Water	72-80
No. 2	
Diatomaceous Earth	16.5
Soap, Hard	2.5
Sodium Silicate	1
Water	80
No. 3	
Diatomaceous Earth	10
Soap, Hard	4
Soda Ash	4
Sodium Metasilicate	1
Water	81
No. 4	
Diatomaceous Earth	30
Soap, Hard	10
Soda Ash	0.5
Trisodium Phosphate	0.5
Water	59
B. Liquid	
Diatomaceous Earth	82.5
Soap, Hard	17
Soda Ash	0.5

$C.\ Powder$	
Amorphous Silica	25
Soda Soap	5
Pine Oil	5
Aluminum Polish	
Formula No. 1	
Tripoli	53
Ammonium Stearate	5
Stearic Acid	4
Iron Oxide	1
Petroleum Naphtha	36
Water	1
No. 2	
Dolomitic Limestone	85.5
Soda Soap	13
Sodium Silicate	1.5

Jewelry Polish

Mix together, thoroughly, 15 grams of powdered ferric oxide and 5 grams of powdered calcium carbonate.

Add enough water to a portion of the mixture to make a paste and then rub the jewelry with the paste by means of a cloth. Rinse with water.

# Formula No. 1 Rottenstone, Powdered 45 g. Alumina, Levigated 15 g. Paraffin Wax 1 g. Pine Oil 20 cc. Kerosene 30 cc.

Metal Aircraft Polish

No. 2		
Rottenstone, Powdered	45	
Alumina, Levigated	15	g.
Paraffin Wax	1	g.
Pine Oil	15	cc
Diglycol Laurate	5	cc
Kerosene	30	cc

Metal	Roller	Polish
Chromium	Oxide	

86

Silica Gel	2	
Stearin	10	
Kerosene	2	
Metal Polish		
Formula No. 1		
Silica Abrasive	6.0	
Triethanolamine Oleate	3.0	
Bentonite	0.5	
Orthodichlorobenzene	10.0	
Oleic Acid	0.5	
Water	80.0	
No. 2		
Soap Flakes 30	00 g.	
Borax	30 g.	
Tri Sodium Phosphate 3	30 g.	
Water 300	00 cc.	

150 cc.

300 cc.

900 g.

Ammonia (Strong)

Denatured Alcohol

Pine Oil

Silica

60 cc. Heat about 2/3 of the water and dissolve in it the soap and the salts. Put the silica in a pail and mix with the pine oil. Add ammonia to the soap solution and add this slowly, triturating constantly to ensure a homogeneous mixture. (If ammonia is added too early to the hot solution, it will partly evaporate. If trituration is insufficient or solution added too quickly, the suspension must be passed through a sieve, or an emulsion mill.) Once a good paste is formed, it may be thinned with more solution, and when thin enough, the rest can be added, all at once. Stir until it becomes thick again, usually a few minutes. The rest of the water is best added cold to hasten the cooling of the product. When cold, stir in alcohol. The emulsion is perfectly miscible with water, but every such addition requires good mixing. It is then stable. Cleaning qualities are good.

No. 3		
Kerosene	1	pt.
Pulverized Silica	20	g.
Concentrated Ammonia	5	cc.
Liquid Soap		cc.
Shake thoroughly before	usir	ng the
above.		

Military Leather Dres	sing
Beeswax, Yellow	65
Acrawax C	2
Turpentine	33

Polish for Patent Leather Yellow Wax or Ceresine 3 oz. Spermaceti 1 oz. Turpentine 11 oz. Asphaltum Varnish 1 oz. Borax 80 gr. Frankfort Black 1 oz. Prussian Blue 150 gr.

Melt the wax, add the borax, and stir until smooth. In another pan melt the spermaceti; add the varnish, previously mixed with the turpentine; stir well and add to the wax; lastly add the colors.

# Furniture Polish Formula No. 1

Turpentine 1 pt. Beeswax 1 lb.

Melt the beeswax and work in the turpentine.

10. 2			
Dragon's Blood	6	gr.	
Linseed Oil	1/2	fl. o	z.
Castor Oil	2	fl. o	z.
Mineral Oil	3	fl. o	z.
Turpentine	$\frac{1}{2}$	fl. o	z.
Antimony Tri-			
chloride	1/2	fl. o	z.
Hydrochloric Acid	1/4	fl. o	z.
Acetic Acid	3/4	fl. o	z.
Alcohol	1/2	fl. o	z.
Water	1	fl. o	z.

Mix the first five ingredients. Then mix the next five in the order given. Add the first mixture to the second and emulsify by agitation.

# No. 3 Non-Rubbing

21022 2020 2222	
Castile Soap	10
Water	160
Carnauba Wax	40
Water	150
Formaldehyde	2

Dissolve the soap in the water and heat to boiling. Add the carnauba wax in small pieces. Stir constantly until a smooth homogeneous emulsion is obtained, then cool to 60° C. by adding the remaining water. Filter through cheesecloth and add the formaldehyde as a preservative.

### No. 4

Linseed Oil, Boiled 95 lb. Linseed Oil, Raw 120 lb. Diglycol Oleate 6 lb. Alcohol 17 lb. Turpentine 135 lb.	Vinegar	123	lb.
Diglycol Oleate 6 lb. Alcohol 17 lb. Turpentine 135 lb.	Linseed Oil, Boiled	95	lb.
Alcohol 17 lb. Turpentine 135 lb.	Linseed Oil, Raw	120	lb.
Turpentine 135 lb.	Diglycol Oleate	6	lb.
	Alcohol	17	lb.
- · · · · · · · · · · · · · · · · · · ·	Turpentine		
Petroleum Spirits 226 lb.	Petroleum Spirits	226	lb.

# Bright Drying Floor Polish (Non-Rubbing)

These polishes are composed of mixtures of aqueous Manila resin solutions with carnauba wax emulsions. The following resin solution is recommended:

# Formula No. 1

Manila DBB or Loba C,		
Ground	240	
Monoethanolamine	45-50	
Water	2090	

Dissolve the monoethanolamine in 700 of water, stir, and add the resin. Heating the mixture to 50°-55° C. helps the resin to dissolve more rapidly. Finally, add the re-

mainder of the water and allow to cool. Strain.

This resin solution is mixed with a carnauba wax emulsion to give the final product. Established wax emulsion formulae are satisfactory, but the following may be used if desired:

Carnauba Wax	240
Triethanolamine	28
Linoleic Acid	45
Borax	18
Water	2412
Melt the wax to 90°-95°	C.

In a separate container, dissolve the triethanolamine in 200 grams of water, stir at 90° C., and add the linoleic acid. Stir the mixture for five minutes at 85°-90° C. and then add the resulting cloudy viscous solution to the wax. Stir the wax-soap mixture at 90°-95° C. for five minutes.

Dissolve the borax in 50 grams of boiling water, add and stir until a hot drop off a spatula is clear (14–15 minutes). The remainder of the water is then added cautiously at a temperature of 95°-100° C. When the mixture starts to thin out, the addition of the water may be made more rapidly. Allow to cool to room temperature and add water to compensate for evaporation loss.

The polish is made by mixing the resin solution and the wax emulsion in the desired proportions. The emulsion is stirred and the resin solution is added. Stirring is continued in order to obtain a homogeneous mixture.

No. 2

110. 2		
Carnauba Wax, Ref	fined	15.0
Durez 420 Resin		15.0
Oleic Acid		4.5
Heat to 300-325°	F. unt	il fluid.

Cool to 210° F., add th	ne following
at boiling point:	
2-Amino-2-Methyl	
Propane Propane	1.0
Sodium Hydroxide	0.4
-	5.0
Water	
Stir in until mixture	
jelly-like. Add the follo	wing slowly
with good agitation:	*
Water, Hot	210.0
Cool rapidly and add	:
Casein Solution 10%	* 25.0
No. 3	
Carnauba Wax	18 oz.
Pine Oil	$1\frac{1}{2}$ oz.
Soap	$1\frac{1}{2}$ oz.
Hot Water	3 oz.
Cook till transparent.	·
	·
Sodium Silicate Hot Water	
	0 02.
Cook 5 minutes. Ma	ke up to 4
quarts.	
No. 4	
Carnauba Wax	8½ lb. 16½ lb.
Candelilla Wax	$16\frac{1}{2}$ lb.
Borax	2 lb.
Duponol W.A. Paste	$5\frac{1}{2}$ lb.
Dissolved in	72
Water	2 gal.
Cook till smooth. Mai	
gal. with boiling water.	ke up to so
	1-
In a separate kettle, co	
Gum Loba C	30 lb.
Water	30 gal.
Ammonia (26°)	150 oz.
until the gum is comp	oletely dis-
* Casein Solutio	
Casein	10.0
Borax	1.5
Pine Oil	0.2
Preservative	0.2
Water at 160° F.	15.0
Mix thoroughly and add Water at 160° F.	15.0
Mix thoroughly and add	
Ammonia in water, 7% of	28% 1.0
Water at 160° F.	70.0
Mix until smooth.	

solved, and add to the wax emulsion. Make up the volume of the finished mixture to 100 gal.

No. 5	
Candelilla Wax	64
Oleic Acid	24
2 Amino, 2 Methyl,	
1 Propanol	11
Water, To make	500

Very translucent, thin emulsion which dries to a transparent, bright film.

# Floor Treatments Wood Floors

Unfinished wood floors should be mopped or scrubbed with warm water and a mild soap. Scouring with powdered pumice or steel wool may be desirable in some cases. A solution of trisodium phosphate, sodium metasilicate (about ½ oz. per gallon of water), or washing soda (about 2 oz. per gallon of water). may be used for cleaning oily or greasy floors. After using soap or other cleaning agent, the floor should be thoroughly rinsed off with clear water and wiped as dry as possible. It is advisable to scrub a small area at one time and to avoid flooding the floor with cleaning solution or rinse water. Strong solutions of soaps, alkalies, alkaline salts, and the too free use of water may darken wood and may in time soften it and raise the grain. Oak floors are readily darkened by strong alkaline solutions. Where wood is badly stained or discolored. bleaches (such as oxalic acid solution; oxalic acid is a poison if taken internally) may be used, or the floor may be scraped or machine-sanded.

Varnished and shellacked floors should be dusted clean with a soft

brush or dry mop, and then rubbed with an oiled mop or a cloth slightly moistened with floor oil, kerosene, or furniture polish. In general, varnished and shellacked surfaces should not be treated with water, but if badly soiled they may be wiped with a mop or cloth wrung out of warm, slightly soapy water, then with a rag or mop moistened with clear water, wiped dry at once and polished with an oiled mop or cloth. The appearance of badly worn varnished wood may be improved by rubbing with a floor wax.

Oiled floors and painted floors should be swept with a soft brush and then rubbed with an oiled mop or cloth. Occasionally, they may be washed with slightly soapy water, rinsed off with a wet cloth or mop, wiped dry and then polished with an oil mop or cloth.

Waxed floors may be cleaned with a soft brush or mop free from oil since oil softens the wax. The film of dirt and wax which darkens the surface may be removed with a cloth wrung out of warm soapy water. The use of a rag moistened with gasoline or turpentine would be a better and more rapid procedure; however, these liquids are very inflammable and care should be taken to avoid having open flames in the rooms. Gasoline and turpentine brighten as well as clean the surface, whereas water dulls and whitens wax. If a water-cleaning method has already whitened a waxed floor, the luster and color may be restored by rubbing with a woolen cloth or a weighted brush; if necessary a little wax may be applied. Many kinds of spots on waxed floors may be removed by rubbing with a little turpentine or gasoline and refinishing with a very thin coat of wax. The entire coating of wax (and dirt) can be removed from wood floors by rubbing first with number 00 steel wool dipped in gasoline or turpentine and then with a soft cloth, after which the floor may be refinished.

Varnish or paint can be removed from a wood floor by scraping and planing, or by applying a paint and varnish remover. The first method, although tedious and laborious, is the better and is necessary if the floor has been stained. After a floor has been scraped, planed, and sandpapered, it can be finished as though it were new.

Removing paint or varnish from floors with paint and varnish removers must be done carefully so as not to damage the finish on baseboards and moldings. The commercial "solvent type" of paint and varnish removers are satisfactory for this purpose and are labeled with instructions for using. A solvent type of paint and varnish remover may be prepared as follows: Dissolve 3 parts of paraffin (in shavings) in 50 parts of benzol, then add 25 parts of denatured alcohol and 25 parts of acetone.

After this mixture has been applied to the surface with a brush and allowed to stand for a few minutes, the paint or varnish will be soft so that it can be scraped off with a putty knife or rubbed off with steel wooi or excelsior. When a putty knife is used as a scraper it will prove more effective if the end of the blade is ground to a sharp edge. By holding the putty knife in a vertical position and scraping across the grain of the wood, there is no

danger of splintering the floor. This paint and varnish remover and others of this type should be used only where there is good ventilation and no open flame of any kind, as they contain highly inflammable materials.

Caustic soda or household lye solutions are also used for removing paint and varnish, but should not be used on oak floors. These solutions should be handled with care and not allowed to come in contact with the skin, clothing or surfaces other than the one being treated. Rubber gloves should be worn. The caustic soda or lye may be dissolved in plain water and the solution applied while hot, but better results will be obtained if the caustic soda is mixed with a starch solution, such as is used in starching clothes. About 3 or 4 tablespoons of caustic soda is generally added to one quart of the starch solution. This mixture is applied while hot to the floor, using a cotton swab, a fiber (not bristle) brush, or a long-handled scrubbing brush. After a few minutes the softened paint or varnish may be scraped or rubbed off. The floor should then be washed several times with clear water, allowed to dry thoroughly, sandpapered or rubbed smooth, and dusted before it is refinished.

Strong, hot solutions of trisodium phosphate (2 or 3 pounds of the salt dissolved in one gallon of water) are also used for removing paint and varnish coatings. This chemical is safer to handle than caustic soda.

If shellac varnish alone has been used on a floor, it can be removed by flooding a small area at a time with denatured alcohol and, after a few minutes, rubbing with steel wool, or scraping as above.

In refinishing an old wood floor, it is first made as tight, level, and smooth as possible. It may need to be planed, sandpapered or rubbed down with steel wool. Any remnants of tacks must be drawn or driven below the surface. Then scrub the wood with hot water and soap or other detergent and rinse with clear water. If the wood is badly stained. spread over it a bleach solution made by dissolving a teaspoon of oxalic acid (poison) in a cup of hot water, and let stand overnight. Then thoroughly rinse the floor with clear water to remove all of the bleach (and cleaning agents) and let dry. The thoroughly dried floor may be stained, varnished, oiled, painted, or waxed. After applying the first coat of finish, it may be necessary to fill cracks and holes with a commercial "crack filler" colored to match the floors.

After cleaning and drying, wood floors are generally waxed. Floor wax should be applied in very thin coats and thoroughly rubbed with a heavy waxing brush or motordriven brush, or a heavy block wrapped in burlap or carpet. In preparing a new or refinished floor for waxing, it is common practice to apply a coat of shellac varnish or other quick-drying varnish before waxing. If this is done it is better to have a very thin coating of shellac. as thicker coatings will, in time, crack or peel, which will necessitate complete refinishing. The wax can be applied directly to close-grained woods such as maple or pine, or to such open-grained wood as oak, if a "silicate wood filler" is first applied.

This treatment requires more waxing, and therefore more labor, in the original job, but the finish is likely to be more durable. However, floors finished in this way often darken more readily than if the wax is applied over a thin coat of shellac.

# Floor Waxes or Polishes

In making either of the following waxes be very careful to heat only by setting the vessel containing the waxes in hot water and to have no flames in the room, since both gasoline and turpentine are very inflammable.

# Formula No. 1

Carnauba Wax	2
Ceresin	2
Turpentine	3
Gasoline (sp. gr. about 0.73)	3

Melt the waxes by heating in a vessel placed in hot water, add the turpentine and gasoline, and cool the mixture as rapidly as possible, while vigorously stirring to produce a smooth creamy wax.

### No. 2

Turpentine	1 pt.
Beeswax	4 oz.
Aqua Ammonia	
(10%)	3 fl. oz.
Water	1 pt.

Mix the beeswax and turpentine and heat them by placing the vessel in hot water until the beeswax dissolves. Remove the mixture from the source of heat, add the ammonia and the water, and stir vigorously until the mass becomes creamy. This wax should be applied lightly on varnished or shellacked floors and any excess wiped off at once, as the ammonia may attack the varnish or shellac. When this wax is used on unfinished oak flooring, the

ammonia may cause a slight darkening of the wood.

The newer water-wax emulsions, commonly called non-rubbing liquid waxes, are now widely used on wood, cement, linoleum, rubber, tile, cork, asphalt tile, mastic, and other floorings. Many of these preparations dry rapidly and require little or no polishing. These water-wax emulsions usually consist of carnauba wax (and other waxes) dispersed in a water solution of soap. Sometimes emulsifying agents other than soap are used. A small amount of resins is often used in preparing these emulsions. Synthetic as well as natural products may be used in some of these preparations. A simple carnauba wax-soap-water emulsion may be prepared for experimental purposes as follows:

Dissolve 1 part by weight of castile soap in 16 parts of clean, soft water, and heat the solution to boiling. Add to the boiling soap solution with constant stirring 4 parts by weight of a good grade of carnauba wax (cut into small pieces). When a smooth homogeneous emulsion is obtained, cool to a temperature of 135° F. by quickly adding, with constant stirring, the necessary quantity of cold water. (This should take about 14 to 16 parts more of water.) Let cool, filter through cheese-cloth, and stir in about 0.5% of formaldehyde as a preservative. The product so obtained should be of the color and consistency of cream. A thicker or thinner product may be made by decreasing or increasing the quantity of water used, taking care to maintain the given ratio between soap and wax. This wax mixture may require polishing or buffing after drying in order to obtain a glossy surface.

Carnauba Wax	72.0	g.
Oleic Acid	9.1	cc.
Triethanolamine	10.6	cc.
Borax	5.4	g.
Water (Boiling)	500.0	cc.
Shellac (Dry Flakes)	10.0	g.
Ammonia (28%)	1.75	cc.
Water	100.0	cc.

1. Melt the wax and add the oleic acid. Temperature should be about 90° C. (194° F.). Placing the container in boiling water keeps the polish at a good temperature.

2. Add the triethanolamine slowly, stirring constantly. This should make a *clear* solution.

3. Dissolve the borax in about 5 cc. of the boiling water and add to (2). Stir for about 5 minutes. This gives a clear, jelly-like mass.

4. Add the rest of the boiling water, slowly with constant stirring. An opaque solution should be obtained. Cool.

5. Add the 100 cc. of room-temperature water to the shellac and then the ammonia and heat until the shellac is in solution. Cool.

6. Add the shellac solution to the wax solution and stir well. The resulting solution should give a clear film when applied to linoleum, mastic floors, etc., and one that is not too slippery.

Cement (Concrete) Floors

Unpainted cement floors may be scrubbed with hot water and a scouring powder, or with hot water and washing soda (laundry soda or "modified soda"), sodium metasilicate or trisodium phosphate followed by scouring powder. The floor should first be wetted with clear wa-

ter and then with the hot solution of washing soda (about 2 to 21/2 oz. per gallon of water), sodium metasilicate or trisodium phosphate (about  $\frac{1}{2}$  oz. per gallon of water), sprinkled uniformly with the scouring powder, rubbed or mopped, and then rinsed thoroughly with clear water to remove alkaline salts and scouring powder. The use of soap on unpainted or untreated cement floors is not recommended, as a scum of lime soap may be formed on or in the surface of the floor. Painted cement floors should be washed or mopped with plain water. If very dirty a slightly soapy water might be used, followed by thorough rinsing with clear water, but such treatment should not be used as a general or frequent procedure.

Occasionally cement or concrete floors are waxed. The waxes commonly used on wood floors can be used on painted or unpainted cement floors. As these waxes generally vary in color from yellow to brown, they should be used sparingly, as any wax or oil that may penetrate into the floor will tend to darken it. Waxes have been applied in a molten condition to unpainted or untreated cement floors as a special floor treatment, but this treatment is not in general use. Waterwax emulsions (such as a mixture of carnauba wax and resins dispersed in water) are used for polishing cement floors and preventing their "dusting." Wax treatments also make the floors water repellent. Concrete or cement surfaces with deposits of oil or grease, such as driveways and the floors of garages, shops and engine rooms, may be cleaned with sodium metasilicate

powder (about 4 oz. per gallon of water), trisodium phosphate (about 4 oz. per gallon of water), or a mixture of 60% trisodium phosphate and 40% soda ash (about 1/2 to 1 1b. of the mixture per gallon of water). An abrasive powder (scouring powder) may be mixed with the above solutions. These detergents should be used with very hot water and the surface should be rubbed with a wire brush, or an abrasive powder and a mop. If the deposits are thick and of long standing, the powdered detergents may be sprinkled over them and moistened with a little water; after standing about 1/2 hour the surface should then be scrubbed, using very hot water. After scrubbing, the surfaces should in all cases be thoroughly rinsed with plain water. Instead of the foregoing treatment, the oil and grease can be mopped off with kerosene and the mopped areas covered with a layer of sawdust for a few days. After sweeping off the sawdust, the surfaces can be further cleaned with the above detergent solutions if necessary.

The following procedure has been found effective in removing old oil stains: First scrub the surface with a hot solution of trisodium phosphate (about 3 to 4 ounces per gallon of water), using an abrasive powder with the solution if there is a dark-colored film on the surface. Then mix whiting with some of the hot trisodium phosphate solution to form a thick paste; cover the stained area with the paste and leave until dry; scrape off the dried paste and rinse the surface with clear, hot water. Repeat this poultice treatment if necessary. In the

case of badly soiled concrete or cement floors the appearance may also be improved by sprinkling over the scrubbed floor a layer (about 1/4 inch thick) of dry hydrated lime, allowing to stand for several hours, and then removing the covering layer. In some cases it may be desirable to repeat the washing and the treatment with lime several times. Fine, dry coal ashes may be used instead of the hydrated lime. Solvents, such as carbon tetrachloride or a mixture of carbon tetrachloride (%) and gasoline (1/3) can be effectively used on the washed and dried floor in conjunction with the hydrated lime or ashes.

# Vitreous Tile or Ceramic and Terrazzo Floors

It is good practice to clean these floorings periodically with a vacuum cleaner. The routine washing of these floors is usually carried out by first wetting them with clear water and then mopping with hot water containing a small quantity of an alkaline cleaner, such as washing soda (about 2 oz. per gallon of water), trisodium phosphate, or sodium metasilicate (about ½ oz. per gallon of water). Badly soiled areas on the floor may be cleaned with a scouring powder or a little scouring powder may be sprinkled over the soiled areas before applying the alkaline cleaning solution. Occasionally, the entire floor should be scrubbed with a scouring powder or with an alkaline cleaner and the scouring powder. A motor-driven scrubbing machine is a desirable appliance. After cleaning, the floors should be thoroughly rinsed with plain water and wiped dry. If water is left standing on a tile floor it may loosen the cement that holds the tiles in place. Soaps are not generally used on these floors owing to the tendency to "build up" slippery films, especially if the water is not soft or the rinsing has not been thorough. However, such floors are sometimes wiped up with a cloth wrung out of hot, soapy water, rinsed off, and wiped dry. If soft water is used and the surfaces are thoroughly rinsed after cleaning, it is believed that soap would be satisfactory, but more expensive, for the routine cleaning of these floors.

Marble and Travertine Floors

Travertine floors should be first cleaned with a vacuum cleaner and then treated the same as terrazzo floors. It is good practice to clean marble floors periodically with a vacuum cleaner.

- 1. Various cleaning preparations have been studied with a view of determining the effects on marble of certain ingredients from a long period of use. The laboratory experiments, as well as an examination of actual installations of marble, have indicated that injury may result from injudicious use of harsh grits or from such salts as sodium carbonate, sodium bicarbonate, and trisodium phosphate.
- 2. The usual type of grit employed in trade cleaning preparations is not appreciably injurious to marble floors or other unpolished marble. Polished marble should rarely be cleaned with preparations containing a scouring agent or abrasive which is harder than the marble.
- 3. As a rule, the volcanic ash grits are less severe in their abrading action than crushed quartz. This

is evidently due to the difference in shape of the particles.

- 4. While it is seldom if ever necessary to use a cleaning preparation of the scouring type on polished marble, when it is in stock for cleaning the floors of a building it is apt to be wrongly used on the polished marblework. For this reason a preparation of the type is desirable which has a grit that will not injure polished marble. Available minerals which seem to meet this requirement are soapstone and talc.
- 5. A trial preparation consisting of 90% powdered soapstone and 10% soap powder appears to be as effective in cleaning marble floors as any of the present trade preparations. Such a composition can be used on polished marble without appreciable injury.
- 6. Injury which may result from the frequent use of such detergents as sodium carbonate, sodium bicarbonate, or trisodium phosphate is mainly a physical effect due to these salts crystallizing in the pores. This action has been demonstrated to be severe enough to cause disintegration of marble when such salts are employed without proper precautions.
- 7. Experiments have indicated that marble work may be safely cleaned with such detergents if the surface is rinsed with clear water before applying the cleaning solution.
- 8. Although soap has been found objectionable for use on marble in certain instances, nevertheless if used with soft water it will give entirely satisfactory results and prove to be the safest detergent for general service.

- 9. Preparations containing a coloring ingredient of different color than the marble may gradually impart their color to the marble. This, however, may be prevented by a preliminary rinsing, as described in 7.
- 10. Ammonia water has been used to some extent in cleaning polished marble, but a limited number of tests in this investigation have indicated that it may cause yellow discolorations.
- 11. Acids dissolve marble, and even the use of such weak acids as oxalic will prove injurious. Although cleaning of interior marble with acids has been practiced to some extent, it is usually done through ignorance of the real effects.
- 12. Stains which have penetrated the marble usually have to be removed by means of a poultice treatment. Several types of stain demand special treatment, and there is no single cure for all cases. Methods have been found for eradicating practically all of the common stains occurring on interior marble.

Linoleum Floorings

Untreated floorings should be swept daily with a soft floor brush or an oil-treated mop. Anything spilled on the flooring should be wiped up as soon as possible with a damp cloth; and occasionally, as the flooring needs it, it should be washed. Care should be exercised in washing these surfaces. Preparations containing free alkali, alkaline salts, or abrasives should not be used. The safest procedure is to use a lukewarm solution (soft water) of a mild or neutral soap and to rinse all soapy water off with plain soft

water after washing. The surfaces should be finally wiped dry with mops or cloths. Care should be taken not to flood the surfaces with water. since any water that seeps through the edges of seams may affect the cementing material and may cause the burlap backing to mildew or rot. Linoleum in kitchens, pantries, or entries will look brighter and wear better if the clean, dry, unwaxed surface is given an occasional coat of a pale, quick-drying lacquer ("Linoleum Lacquer"). Never lacquer over wax. The lacquered surface after drying may be waxed, but this is not generally done. The lacquered surface may be cleaned daily with a dust mop or, whenever required, with a damp cloth. These floors should be relacquered occasionally, depending upon the severity of wear.

In rooms or places where the wear on the floors is not particularly heavy, the clean, dry linoleum should be waxed and polished. Any good floor wax is suitable for linoleum. A wax prepared according to formula (1) is satisfactory. Paste wax can be used but "liquid" wax is easier and more economical to apply. The water-wax emulsions are also used. Care should be taken not to put the wax on too thickly as it is likely to smear and give a greasy appearance to the floor. Too much wax will cause the floor to be slippery. After applying the wax, it should be polished for some time with a weighted floor brush or an electric polishing machine. Daily care of a well-waxed and polished floor should consist in going over it with a dry dust-mop. Washing is seldom necessary—perhaps two or

three times a year. Waxing not only adds to the appearance of the linoleum but provides a wearing surface and protects the floor. An occasional polishing may be necessary on the main traveled areas. Rewaxing will be required from time to time depending upon the amount of traffic. Depending upon the service conditions, the floor may require scrubbing at times, after which a coat of new wax should be applied. "Linoleum tile" floors and linoleum floors subjected to much wear should be given one or two coats of a linoleum lacquer and then waxed and polished. After the wax has dried for a short time on the "tile" floors, run a polishing machine equipped with a fine-bristled brush over the floor in both directions in order to work the wax into the surface. Sweep off any dust or wax particles and polish with an electric polishing machine. Lacquered and waxed floors should be cared for as outlined for surfaces that have been waxed directly. Before lacquering an old linoleum or "linoleum tile" floor, it must be thoroughly cleaned with a cloth dampened with gasoline and frequently squeezed out in fresh gasoline during the cleaning, in order to remove all grease and wax. Then the entire floor should be scrubbed with lukewarm soapy water, rinsed thoroughly with plain water, and allowed to dry.

The life of a linoleum floor covering can be prolonged by applying a pale, transparent varnish but this treatment is not recommended, as many varnish coatings become slightly yellow. This mars the design effect in patterns and may produce a decided discoloration over

plain surfaces. Some varnishes will turn white when water is spilled on them. The same objections may apply to shellac. Floor oils and sweeping compounds containing oil should not be used on linoleum, as these materials may leave a film of oil on the surface to collect dust and dirt. Varnished surfaces can be waxed to produce a "dull polish."

Rubber Floors

To clean unpolished floors, brush off loose dirt with a soft push-broom and wash a small section of the floor with a clean mop wrung out of a solution of washing soda ("modified soda" or laundry soda) or trisodium phosphate (about a quarter of a cupful of the cleaner dissolved in 12 to 16 quarts of clear, cold water). Cleaning may also be done by mopping with clear, cold water containing 2 to 4 ounces of ordinary household ammonia per gallon. Rinse the mop in a second pail of clear, cold water, wring the mop, and wipe the section of floor clean of solution. Continue this process until the entire floor is cleaned. After the floor has dried, buff it thoroughly with a rotary electric buffing machine (for large areas) or a weighted hand buffer to which a piece of rough carpet or similar material is attached as a buffing surface. Daily cleaning can often be satisfactorily done by sweeping with a soft, dry brush, or with a soft push-broom, and an occasional washing with a clean mop wrung out of clear, cold water. When very dirty, the floors should be cleaned with a washing solution as outlined above. Frequent systematic buffing of unpolished floors materially reduces the number of washings required. Owing to the de-

velopment of the bright-drying waxwater emulsions (polishes) free from oils, fats and organic solvents, it is now general practice to polish rubber floors. The wax or polish enhances the appearance of the floors and prolongs their life. After cleaning, drying, and buffing as outlined above, the floor is ready to polish if all dirt and marks have been removed. Pour the polish into a shallow receptacle, dip the applicator \* into the polish and apply a thin coat over a small area with a wiping motion. Do not rub hard. Repeat until the entire floor is covered. Let dry until hard (about 30 minutes) and then buff. Immediately apply a second thin coat, let dry, and again buff thoroughly. The polish should be applied in as thin coats as possible to avoid streaking and at least two coats should be applied. If the polish wears off in certain sections of the floor, clean and repolish only these sections rather than the entire floor. Systematic buffing keeps the polished floor in good condition and reduces the number of washings required. When the polished floor becomes soiled, remove the loose dirt with a soft brush or a soft pushbroom and wipe the floor with a clean mop dampened with clear, cold water. This treatment should not remove the polish. If this procedure does not clean the floor, it should be treated as outlined above. using a washing solution. When necessary, the wax or polish can be removed from rubber floors with a

\*Made of lamb's wool, soft absorbent cloth, or felt. The felt applicator, made of 4 or 5 strips of felt ½ inch thick stood on edge and bound together, is very satisfactory. solution of trisodium phosphate in warm water (about 2 ounces per gallon) with the aid of 00 steel wool. The addition of a small quantity of household ammonia to the solution will hasten the removal of the wax (and dirt).

Stains may be removed from rubber floors by rubbing the stained area with a fine abrasive powder or with number 00 steel wool. If this is ineffective, the spot may be rubbed carefully with a clean cloth dampened with acetone (inflammable), gasoline (flammable), or carbon tetrachloride (non-inflammable). Gasoline, acetone, and carbon tetrachloride have a softening action on rubber if in contact with it long, but the softening is not permanent.

Cleaning materials containing oil (certain sweeping compounds and other detergents) and coarse abrasives, or caustic alkali should not be used on rubber floors. Soap may soften and swell rubber flooring. Although this effect is minimized with careful rinsing, the safest procedure is to avoid the use of any soap. Waxes or polishes containing oils, fats, or organic solvents should not be used. Do not use hot water or excessive amounts of water when cleaning rubber floors. The floor should not be flooded with water. Avoid using more of the cleaning compound than specified and thoroughly mop or rinse the surface in order to remove all of the cleaning solution. Rubber floors should not be varnished. Buffing machines should not be used for scrubbing with water and cleaning agents. The advice or recommendation of the manufacturer of the rubber flooring should be secured before using unknown cleaning preparations or applying untried methods.

### Cork Tile and Cork Carpet Floorings

Many cork floorings are installed without any surface treatment other than sanding to a smooth surface. These floorings are commonly referred to as "natural" cork and often may be cleaned by dry sweeping with a hair floor brush. The entire surface is then buffed or polished with suitable pads, a polishing machine or floor-polishing brush. Care should be taken to overlap the polished sections. If the floor can not be cleaned in this manner, it should be swept with a soft brush and then mopped with a lukewarm soapy solution made with a mild or neutral soap and clean, soft water. A separate container of clean, lukewarm, soft water and a separate mop should be used for rinsing. The rinse water should be changed frequently, so that both rinsing water and mop are always clean. Only a small area (say about 50 sq. ft.) of flooring should be washed at one time and it should be thoroughly rinsed with clean water and wiped dry. Water should not be left on the floor.

Where cork flooring is subjected to much heavy and dirty traffic, it should be varnished with a pale, transparent spar varnish, and then waxed and polished. With cork tile it is good practice to apply a filler before varnishing. The varnish usually requires overnight to dry. A dull or mat finish may be secured in place of the glossy varnish by scrubbing the varnished floor with a neutral soap and water and rottenstone

or finely powdered pumice. These treatments form protective coatings, but the treated floors require careful and frequent attention. The floors should be washed clean and allowed to dry thoroughly before applying filler, varnish or wax. The waxes used for linoleum may be used on cork floors. Liquid floor wax is generally used and is applied in a thin, even coat and rubbed in. When the wax is nearly dry (tacky). apply a second coat of wax in the same manner. When the second coat becomes tacky, polish thoroughly with a polishing machine, a weighted brush, or a clean soft cloth. The appearance of the surface improves with frequent polishing. The waterwax emulsions that dry rapidly and require little or no polishing are also widely used for waxing cork floors.

Waxed cork floors are cleaned by rubbing with a dry mop or polishing brush, followed by sweeping with a brush or a vacuum cleaner.

A polishing machine is a useful appliance for large areas. Cork floors should be polished or buffed with a brush or machine whenever they appear dull or dingy. The floors should be rewaxed from time to time, depending on traffic conditions and exposure to dirt. The floors should be rewaxed before the old wax is worn off. Areas (doorways. traffic lanes, etc.) subjected to the most wear may be rewaxed when necessary without going over the entire floor. Before rewaxing the floor all old wax must be removed by rubbing the surface with a cloth dampened with gasoline (inflammable), followed by vigorous scrubbing with warm water and soap, rinsing with clean water and drying. If this does not remove the wax, the dried surface should be resanded.

Lacquer suitable for linoleum may be used on cork floors in lieu of waxing. The surface should be thoroughly cleaned and dried before applying the lacquer. Two or three coats of lacquer are used for the first treatment in order to fill the pores of the flooring and give a smooth, dirt-resistant surface. Further coats may be applied as the appearance requires. "Natural" cork floors which have been varnished may be kept clean by sweeping with a dust-mop, soft brush, or a damp cloth or mop.

Stains and spots may be removed from cork floors by rubbing with fine emery paper or number 00 steel wool. In some cases the spot or stain may be rubbed with a cloth dampened with acetone (inflammable) or with carbon tetrachloride. The cleaned areas should then be buffed and waxed, or varnished and then waxed.

Asphalt Tile and Mastic Floors

These "soft composition" floors are sold under various trade names and, in general, have a base of asphalt, bitumen or resin. Cleaners and polishes containing abrasives, oils or organic solvents (gasoline, turpentine, carbon tetrachloride, etc.) should not be used. These floors should be washed by mopping with a neutral soap and lukewarm soft water. Scrubbing machines with soft polishing brushes have been used for large areas. After cleaning and drying, these floorings (especially the asphalt tile) are generally waxed in order to cover the surface with a protective film. The water-emulsion waxes free from oils and volatile organic solvents are the safest waxes to use on these floorings. This type of wax can be applied with a cotton cloth mop or wool applicator. The wax should be spread as thinly as possible on the surface of the floor, using the mop or applicator in one direction only. In a short time the wax should dry to a hard, lustrous finish.

Asphalt tile floors should not be buffed or burnished until the wax or other treatment is completely dry. The treated floors may be maintained by sweeping with a brush, a dry mop, or by buffing with mechanical buffers. Scrubbing with water and a neutral soap may be required at times (probably two or three times a year). Oils, soaps or other detergents containing abrasives, and sweeping compounds containing free oil should not be used on the untreated or the treated floors. The floor treatments should be renewed at intervals, depending upon the severity of wear.

Before treating an asphalt tile floor with an unknown preparation, moisten a white cloth with the preparation and rub over the surface of one tile. If the color of the tile shows on the cloth it indicates that the solvent in the preparation has dissolved part of the surface of the tile and shows conclusively that the preparation would not be safe to use. It would be safer to get the advice of the manufacturer of the flooring before using unknown cleaning preparations.

Plastic Magnesia Cement Floors

These floors contain magnesium oxychloride as the cementing material and are known by various names ("Sorel Cement," "Hard Composi-

tion," "Magnesite," "Woodstone," etc.). These floors may be cleaned by first wetting with clear water and then mopping with a neutral soap and warm soft water (a soft soap, such as a linseed oil-potash soap is often used). After cleaning and drying, the floors may be given a protective coating of wax (water-wax emulsion) or of special varnish or lacquer. The treated floor may be cleaned by sweeping with a dry mop or soft brush, and occasional washing, and buffing with a weighted brush or polishing machine. The waxing or other treatment is renewed as conditions require.

Slate Tile Floors

These floors may be cleaned by mopping with a neutral soap (a paste soap is often used) and warm soft water. After cleaning and drying, the floors may be waxed with a water-wax emulsion or given a coat of pale varnish or lacquer. The treated floor can be kept in good condition by sweeping with a dry mop or soft brush, and an occasional buffing with a weighted brush or polishing machine.

Cheap Abrasive Wheel
U. S. Patent 2,124,279
Abrasive 40
Iron Filings 40
Ammonium Chloride 2–10
Add enough water to wet mass thoroughly; press and allow to set until cold.

**Bonded Abrasive Wheels** 

The use of a good grade of animal hide glue is essential. Bone glue, fish glue, and cold glue preparations are relatively inefficient.

Mix by weight only and never

heat more than a three hours' supply at any time. For average conditions in the polishing room the following table of mixtures should act as a guide for setting up wheels.

Size of Alundum Grain % Glue % Water 24-36 50 50 46-- 54 45 55 60-- 70 40 60 80--- 90 35 65 100-120 33 67 150-180 30 70 220-240 25 75

Soaking the glue allows it to dissolve more readily on heating. Use cold pure water and soak:

Ground glue—One hour or more
Flake glue—Six hours or more
Cake glue—Twelve hours or
more

The glue should be melted in a water-jacketed heater. When the wheels and grain are preheated, apply the glue at a temperature of 140° F. With wheels and grain at room temperature, use glue at 160° F. Keep a thermometer in the gluepot as a constant check on temperature, even though the pot is regulated by a thermostat.

It is important that all equipment used be kept clean.

Composition for Impregnating
Grinding Wheels
U. S. Patent 2,240,302

 Hydrogenated Cottonseed Oil
 90
 -97
 %

 Salt
 0.75 7.5%

 Sulphur
 0.75 7.5%

 Turpentine
 0.75 7.5%

Removing Scratches from Glass Scratches on glass may be eradicated by using a paste made of glyc-

80.0

erin, water and rouge (iron oxide) mixed to the desired consistency. A hard felt pad is dipped in this paste and rubbed briskly back and forth over the scratched surface until the markings disappear. The paste can be washed away by simply flushing with water. This paste is particularly suitable for removing shallow scratches. Deeper gougings require more specialized treatment and coarser abrasives to start with. For this latter purpose emery powder will often serve, and glycerin makes

a satisfactory medium in which to suspend the powdered abrasive.

Dental Abrasive Pas Carborundum (100–200	ste
Mesh)	70
Glycerin	30
Lapping Compound for or Bronze	Brass
Silica (325 Mesh)	16.5
Soap Flakes, White	2.5
Sodium Silicate	1.0

Water

### CHAPTER SEVENTEEN

### PYROTECHNICS AND EXPLOSIVES

### Meal Powder

Mount a 50 gallon wood barrel on two uprights so that it will revolve freely on centers fastened to the heads. On one center attach a crank and cut a hole (closed by a suitable plug) into side of barrel for putting in and removing the necessary ingredients. Place in the barrel 300 to 500 lead balls about one inch in diameter. When it is desired to make meal powder, put into the barrel a thoroughly mixed

composition as follows:

Saltpeter, Double Refined 15 lb.
Willow Charcoal 3 lb.
Sulphur, Flour 2 lb.

The barrel is now revolved for about 500 turns. The longer it is turned, the stronger the powder will become. Great care must be exercised to see that no foreign matter such as nails, gravel, etc. find their way into the barrel as this might result in an explosion.

### Green Parade Torches

Barium Chlorate				5
Barium Nitrate	40	1 -	30	. 0
Potassium Chlorate	11		30	4
Potassium Perchlorate	11		e.	• •
K. D. Gum	6		0	
Sulphur, Ground	- 0		2	• •
Sal Ammoniac			3	• •
Shellac	1		• •	
Calomel			• • •	1
Calonier				2

### Blue Parade Torches

Dide rarage 1	orcnes		
Potassium Perchlorate	5	24	24
Paris Green	2		
Copper Ammonium Sulphate	, -	6	• •
Copper Ammonium Chloride	•	O	6
Dextrin	1		· ·
Calomel	1		
Sugar of Milk		9	
Sulphur	•••	Q	
Stearine	7- 10-	9	9
Asphaltum			1

Purple Parade Torches	
Strontium Nitrate	7
Potassium Perchlorate	9
Black Oxide of Copper	6
Calomel	3
Sulphur	5

### Amber Parade Torches Strontium Nitrate 36 Sodium Oxalate 8 Shellac 5 Sulphur 3 Potassium Perchlorate 10

## Aluminum Torches Potassium Perchlorate 13 Fine Aluminum Powder 6 Flake Aluminum 5 Dextrine or Lycopodium 1 A beautiful modification to this is the

Red and Aluminum Torch This should be 7/8" diameter, 18" long and of the following composition:

# Formula No. 1 Strontium Nitrate 35 Potassium Perchlorate 7 Shellac 4 Coarse Flake Aluminum 4 Lycopodium 1 No. 2

13

3

Strontium Nitrate

Sulphur

Mixed Aluminum 3
Before ramming, this formula should be moistened with a solution of 1 part shellac in 16 parts of alcohol and 1 part of this solution used to every 36 parts of composition. As this mixture is somewhat difficult to ignite it is necessary to scoop out a little from the top of

torch and replace it with starting fire.

Starting Fire	
Saltpeter	6
Sulphur Flowers	4
Fine Charcoal	1

### Extra Bright Torch

An aluminum torch of heretofore unheard of brilliance and giving an illumination, in the 1 inch diameter size, of what is said to be 100,000 candle power is made as follows:

Barium Nitrate	38
Mixed Aluminum	9
Sulphur	2
Vaseline	1

Rub the Vaseline into the barium nitrate; mix sulphur and aluminum separately; then mix with barium nitrate and vaseline. A starting fire for this also is required, as follows:

Starting Fire	
Barium Nitrate	4
Saltpeter	3
Sulphur	1
Shellac	1

### Port Fires

These are small torches 3%" diameter, 12" long, used in exhibitions for lighting other pieces of fireworks. They are rammed with rod and funnel and a good mixing is:

Form	ula No. 1	No. 2
Meal Powder	1	
Sulphur	2	4
Saltpeter	5	5
Charcoal		1

	White Fire			
	Formula No. 1	No. 2	No. 3	No. 4
Saltpeter	3	12	8	7
Sulphur	1	2	$\overset{\circ}{2}$	$\dot{f 2}$
Metallic Antimony	1			
Antimony Sulphide	ī	1		• •
Realgar		_	· · 1	11/
Tteatgat	• • •	_	1	$1\frac{1}{2}$
	Blue Fire			
	Formula No. 1	No. 2	No. 3	No. 4
Potassium Perchlorate	roimula 110. 1		110. 5	
Potassium Chlorate		1.0		24
	6	16	8	• • •
Paris Green	4		6	• •
Shellac	• • • • • • • • • • • • • • • • • • • •	• 2 •	$\frac{1}{2}$	
Stearine	1		1	2
Barium Nitrate	<b>4</b>		7	
Calomel		12	1	
Sal Ammoniac	- 1			
Copper Ammonium Chl Asphaltum	oride	4		6
Lactose	• •		• •	1
Lactose	* · · · ·	6	•••	
	Red Fire			
	Formula No. 1	No. 2	No. 3	No. 4
Strontium Nitrate	80	10. 2	16	14
Potassium Chlorate	20			
Shellac	20	4	8	4
		• • •	3	
Red or Kauri Gum	12	3		
Asphaltum	• •	• •	·	3
Charcoal		1		
Dextrin	1	*	• •	
Fine Saw Dust	12			
Rosin		1		
Lampblack	1	•	••	
	Pink Fire			
	Formula	No. 1	No. 2	No. 3
Strontium Nitrate		48	16	18
Saltpeter		12	4	7
Sulphur		5	2	2
Charcoal		4	ī	1/2
Red Gum			3	$2^{72}$
Dextrin			9	
2 Carolli		• • •	• •	1/2

FIROTECHNICS	AND EXP	LOSIVE	8	421
Yello	ow Fire			
Barium Nitrate		:	36	
Sodium Oxalate			6	
Sulphur			3	
Red Gum			5	
			U	
Gree	en Fire			
$\mathbf{F}$	ormula No	. 1	No. 2	No. 3
Barium Nitrate	8	3	9	4
Chlorate of Potash	4		3	2
Shellac	*		1	$\frac{1}{1}\frac{1}{2}$
Red Gum	2	)		- /2
Dextrin		•	1/16	
Fine Saw Dust	• •			• •
Sal Ammoniac			$\frac{1}{2}$	• •
Sai Ammoniae	1		• •	• •
Smokeless Tableau Fire	1		Red	
DIIIOION LUNIOUU LIIO	Strong	tium Ni		8
For theatrical or indoor use, col-		Acid	diade	5
ored fires are very objectionable on	Charc			$\frac{3}{2}$
account of the choking smoke they	) Chian			1
give off. The following mixings give	~~~~~		Y	1
	1	-	Freen	
a fire, producing very little smoke,		m Nitre	ite	4
which quickly dissipates after fire		Acid		2
is burned.	Charc	coal		1
Railwe	ay Fuses			
	la No. 1	No. 2	No. 3	No. 4
	18 INO. I	10. 2	140. 9	
Potassium Perchlorate	40	10	1.0	$\frac{21/_{2}}{19}$
Strontium Nitrate	48	18	16	18
Saltpeter	12	7	4	01/
Sulphur	5	2	5	$2\frac{1}{4}$
Fine Charcoal	4	1/2	1	
Red Gum	10	2	1	• •
Dextrin		1/2		
Sawdust				1
Moisten with kerosene before ra	mming.			
		, ,		
Fuses are provided with a slip	1			s similarly
cap which is used for igniting them.			paste of	
The end of the torch is capped with			of Manga	
paper onto which is painted a mix-		phous I	Phosphoru	
ture of	Glue			3
			Red	
Potassium Chlorate 6	Stron	tium N	itrate	30
Antimony Sulphide 2		sium C		8
Glue 1	Red (			7
Cite -				

Saw-dust may be added as needed. The torches are usually ¾" diameter and 12" long and should burn, with the above mixing, 8 to 10 minutes.

Bengola or Blue Lig	ght
Saltpeter	12
Sulphur	2
Antimony Sulphide	1

Distress signals are the same except that they burn red. The regulation Life Boat equipment consists of 6 to 12 enclosed in a water tight copper can. The following formula is suitable:

Distress Signal (Red)	
Potassium Chlorate	5
Strontium Carbonate	$1\frac{1}{2}$
Shellac	1
Dextrin	1/2
	-

Roman Candle Composition				
Powdered Saltpeter	18	lb.		
Fine Powdered Char-				
coal	11	lb.		
Flowers of Sulphur	6	lb.		
Dextrin	1	lb.		
Water	1	gal.		

	Sky-Ro	${ m ckets}$		
	1 to 3 oz.	4 to 8 oz.	1 to 3 lb.	4 to 8 lb.
Saltpeter	18	16	16	18
Mixed Coal	10	9	12	12
Sulphur	3	4	3	3

### Tourbillions (Geysers, Whirlwinds, Table Rockets)

This is a modification of the sky rocket and ascends to a height of about 100 feet, in a spiral manner and without a stick. They are made by ramming a 3 lb. rocket case with one of the following mixtures:

_					. 0~ .	
		Formula N	To. 1	1	No. 2	
	Saltpeter		8		5	
	Meal Powder		7		12	
	Charcoal		2		3	
	Sulphur		2		3	
	Steel Filings		3		• •	
		Pin Wheels				
l Po	owder		10		8	
Gr	ain Powder	8	5		8	

and the second of the second o	rin wheels			
Meal Powder		10	8	2
Fine Grain Powder	8	5	8	
Aluminum			3	
Saltpeter	14	4	16	1
Steel Filings	6	6		3000
Sulphur	4	1	3	1
Charcoal	3	1	8	

Serpents or Nigger Chasers (Squibs)
Meal Powder33Saltpeter25Sulphur11Mixed Coal $1\frac{1}{2}$ $\frac{3}{4}$ FFF Grain Powder43
Starting Fire for Gerbs Meal Powder 4 Saltpeter 2 Sulphur 1 Charcoal 1
Gerbs
Meal Powder       6       4         Saltpeter       2          Sulphur       1          Charcoal       1       1         Steel Filings       1       2
Tourstains
Fountains Meal Powder 5 Granulated Saltpeter 3 Sulphur 1 Coarse Charcoal 1 FF Rifle Powder 34
Flower Pots
Flower Pots Saltpeter 10 Sulphur 6 Lampblack 3 FFF Rifle Powder 6
Canadas
Cascades 1½" case 2" case
Granulated Saltpeter 18 16
Saltpeter 18 16 Mixed Charcoal 4 4
Sulphur 3 3
Iron Borings 6 7
II Doilings
Triangle Composition
Saltpeter 18 12
Sulphur 2 8
Mixed Charcoal 5 5
Rifle Powder FFF 12 12

Wheel Cas	es (	Dri	vers)	-
Meal Powder			8	3
Saltpeter			3	2
Sulphur			1	1
Mixed Charcos	al		1	1
F Rifle Powde	r		1	
Lampblack			$\frac{1}{2}$	
Steel Filings,	Го s	uit	, -	
	xon	S		
Meal Powder				4
Sulphur				2
Saltpeter				2
Mixed Charco	aı			1
Japane	ese	Star	s	
Formula				0. 2
Lampblack	12	OZ.	6	OZ.
Potassium				
Chlorate	8	oz.	4	OZ.
Saltpeter	1	OZ.	٠	
Water	18	OZ.	9	OZ.
Alcohol	4	OZ.	2	oz.
Dextrin	1	OZ.		
Gum Arabic			$\frac{1}{2}$	OZ.
Mix the dext	rin	and	d sa	ltpete
(formula 1) well	l to	geth	er ar	id ad
sufficient water				
liquid. Boil the b	alar	ice (	of the	wate
and add the chli	orat	e of	note	assiur

er ld y er and add the chlorate of potassium to it. Put the lampblack in a large pan and pour the alcohol over it working it in as well as possible. Now add the chlorate of potassium dissolved in the hot water and stir with a stick until cool enough for the hands. Lastly add the dextrin and saltpeter. Remember that you cannot mix it too well and the effect will be in proportion to the evenness with which this has been done.

415	White Star	rs	
	Formula	No. 1	No. 2
Saltpeter		50	54
Sulphur		15	15

Paris Green Stearine

Copper Ammonium Chloride Lactose

Red Arsenic 15	9	Yellow Stars	
Dextrin 3	3	Formula No. 1 No.	o. 2
Black Antimony	15	Potassium Chlorate 16	16
Red Lead	6	Shellac or Red	
Shellac	1	Gum 3	3
		Fine Charcoal 4	1
Red Stars		Barium Nitrate 3	
Formula No.	1 No. 2	Sodium Oxalate 1	7
Potassium Chlorate 6 Shellac or Red	24	Dextrin $1\frac{1}{2}$	1
Gum 1	3		
Fine Charcoal 2		Exhibition Pumped Stars	
Strontium Carbonate	4	Green (Not for Shells)	
Strontium Varbonate Strontium Nitrate 6	_	Barium Chlorate 12	
		Potassium Chlorate 8	
Dextrin ½	$1\frac{1}{2}$	Calomel 6	
Blue Stars		Shellac 2	
Potassium Chlorate	24	Picric Acid 2	
Paris Green	9		1/2
Barium Nitrate	8	-	$\frac{72}{2}$
Shellac		Red	72
Dextrin	5	(For hand pumps, not suitable	for
	$1\frac{1}{2}$	Shells.)	3 10I
Green Stars		Strontium Nitrate 8	
Potassium Chlorate	6	Potassium Chlorate 4 10	
Barium Nitrate	6	Picric Acid 1½ 11/2 11	1/2
Fine Charcoal	2	Shellac 1½	3/4
Shellac or KD Gum	1	Fine Charcoal 1 1	
Dextrin	1/2	Dextrin ½	3/4
Calomel	1/2	Strontium Carbonate 3	
Exhib	ition Blue	Stars (Pumped)	
Potassium Chlorate		48 18 1	16
Calomel			12
Black Copper Oxide		6	
Asphaltum		<b>c</b>	
Dextrin		44/	
Paria Cham		-/4	

1 4

2

PYROTECHNICS A	IND EXPLOSIVES	425
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	Stearine Saltpeter  Electric Spreader Stearine Dust Potassium Chlorate Granulated Coal Potassium Bichromate Dextrin  Granite Stars Saltpeter Zinc Dust Fine Charcoal Sulphur Dextrin	$1\frac{1}{2}$ tars $36$ $7\frac{1}{2}$ $6$ $6$ $1$ $14$ $40$ $7$ $2\frac{1}{2}$ $1$
Gold and Silver I For Meal Powder Saltpeter Sulphur Fine Charcoal Lampblack Red Arsenic Shellac Dextrin Lead Nitrate	Rain (Cut Stars) rmula No. 1 No. 2  16 10 1  10 1  2 1 1 3	No. 3 4 1 2
For Potassium Chlorate Potassium Perchlorate Aluminum Powder, Mediu Shellac Lycopodium  Magnesi Saltpeter Magnesium Powde  Comet Star	1  Tum Stars  er 5  Composition	
For Saltpeter Meal Powder Sulphur	rmula No. 1 No. 6 6 3 1	Z

Fine Charcoal   3					
Powdered Antimony   Lampblack   2	Fine Charcoal		3	1	
Lampblack		monv			
Lance Compositions   Red Lances   Formula No. 1   No. 2				2	
Red Lances	•				
Formula No. 1		Lance Compositi	ons		
Potassium Chlorate   16					
Strontium Nitrate   3		Formula N	To. 1	No. 2	2
Strontium Carbonate   3	Potassium Chlo	rate	16	16	
Shellac   1/8   1/4			3		
Lampblack   1/8   1/4		onate			
Green Lances					,
Formula No. 1   No. 2   No. 3	Lampblack		1/8	1/	4.
Formula No. 1   No. 2   No. 3		Green Lances	•		
Barium Nitrate       7       4       4         Barium Chlorate				No. 2	No. 3
Shellac	Potassium Chlorate		7	16	
Shellac       2       4       1         Calomel       3       2         Lampblack       1/8          Picric Acid       1          White Lances         Formula No. 1       No. 2       No. 3       No. 4         Saltpeter       9       14       5       8         Sulphur       1       4       2       2         Antimony Sulphide       2            Antimony, Metallic       3       1          Meal Powder        1           Red Arsenic        1            Blue Lances       Formula No. 1       No. 2       No. 3       No. 4         Potassium Chlorate       20       16       12          Potassium Perchlorate        24           Paris Green        5           Copper Sulphate       6            Copper Ammonium Sulphate         6         Shellac       4	Barium Nitrate		7	4	4
Calomel       3       2         Lampblack       ½8          Picric Acid       1          White Lances         Formula No. 1       No. 2       No. 3       No. 4         Saltpeter       9       14       5       8         Sulphur       1       4       2       2         Antimony Sulphide       2           Antimony, Metallic       3       1          Meal Powder        1          Red Arsenic        1          Blue Lances         Formula No. 1       No. 2       No. 3       No. 4         Potassium Chlorate       20       16       12         Potassium Perchlorate        24         Paris Green        5         Copper Ammonium Sulphate           Copper Ammonium Chloride        6         Shellac       4       1         Stearine        1½2       ½2         Calomel       4       3       3         A       1 <td< td=""><td>Barium Chlorate</td><td></td><td></td><td></td><td>5</td></td<>	Barium Chlorate				5
Lampblack   Pieric Acid   1			<b>2</b>		
No. 2   No. 3   No. 4					2
White Lances   Formula No. 1   No. 2   No. 3   No. 4			• •		
Formula No. 1	Pierie Aeid		• •	1	
Formula No. 1		White Lances			
Saltpeter       9       14       5       8         Sulphur       1       4       2       2         Antimony Sulphide       2            Antimony, Metallic       3       1          Meal Powder       1        1         Red Arsenic       1        1         Blue Lances         Formula No. 1       No. 2       No. 3       No. 4         Potassium Chlorate       20       16       12          Potassium Perchlorate        24        24         Paris Green       5             Copper Sulphate       6          6         Shellac       4       1         6         Shellac       4       1         6         Shellac       4       3				No 2	NTo 4
Sulphur       1       4       2       2         Antimony Sulphide       2           Antimony, Metallic        3       1          Meal Powder        1            Red Arsenic        1	Saltneter				
Antimony Sulphide 2 Antimony, Metallic 3 1 Meal Powder 1 1 Red Arsenic 1   Blue Lances Formula No. 1 No. 2 No. 3 No. 4  Potassium Chlorate 20 16 12 Potassium Perchlorate 20 16 12  Paris Green 5 Copper Sulphate 6 Copper Ammonium Sulphate 3 Copper Ammonium Chloride 3 Shellac 4 1 Stearine 11½ 1½ 2 Calomel 4 3 3 Dextrin 1		-			
Antimony, Metallic  Meal Powder  Red Arsenic   Blue Lances  Formula No. 1  Potassium Chlorate  Potassium Perchlorate  Paris Green  Copper Sulphate  Copper Ammonium Sulphate  Copper Ammonium Chloride  Shellac  Stearine  Calomel  Dextrin  3  1  No. 2  No. 3  No. 4  24  24  25  26  16  10  10  10  10  10  10  10  10  1			-	.—	
Red Arsenic		*			
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$		*		1	
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	Red Arsenic	• •		• •	1
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$					
Potassium Chlorate         20         16         12           Potassium Perchlorate					
Potassium Perchlorate	D. I. C. I.				No. 4
Paris Green       5         Copper Sulphate       6         Copper Ammonium Sulphate       3         Copper Ammonium Chloride       6         Shellac       4       1         Stearine       1½       ½       2         Calomel       4       3       3         Dextrin       1       1       1       1		20	16	12	
Copper Sulphate       6         Copper Ammonium Sulphate       3         Copper Ammonium Chloride       6         Shellac       4       1         Stearine       1½       ½       2         Calomel       4       3       3         Dextrin       1       1       1		* * * * * * * * * * * * * * * * * * * *			24
Copper Ammonium Sulphate       3         Copper Ammonium Chloride       6         Shellac       4       1         Stearine       1½       ½       2         Calomel       4       3       3         Dextrin       1       1       1       1			Э	• •	• • •
$ \begin{array}{cccccccccccccccccccccccccccccccccccc$		-	• •		
			• •	J	
Stearine $ \begin{array}{ccccccccccccccccccccccccccccccccccc$			: •	1.	U
Calomel 4 3 3 Dextrin 1			11/2		2
Dextrin 1	Calomel				
		1		*	
	Asphaltum		*		

		A THO	121
	Yellow Lances		
	Formula No. 1	No. 2	No. 3
Potassium Chlorate	16	4	4
Sodium Oxalate	2	$\overline{2}$	$\overset{-}{2}$
Shellac	3	1	1
Charcoal	1/2	_	-
Barium Nitrate		• • •	1
200			
Cannon	Cracker Composition		
	Formula No. 1	No. 2	No. 3
Potassium Chlorate	60	6	6
Washed Sulphur	23	3	2
Sulphuret of Antimony	5		
Metallic Antimony			1
Charcoal		1	
Saltpeter	12		• •
CI.			
Chir	ese Fire Crackers		
	Formula No. 1	No.	2
Saltpeter	50	45	
Sulphur	25	18	
Charcoal	25	25	
Chlorate, Potassiu	m	8	
Sand, Fine	• • • • • • • • • • • • • • • • • • • •	' 4	
1	Flash Crackers		
	Formula No. 1	No. 2	No. 3
Saltpeter	50		
Sulphur	30	25	30
Aluminum Powder, Fine	20	25	40

Chlorate, Potassium A very important as well as extremely difficult part of the Chinese cracker is to make the fuse. Very tender and skilled fingers are required to produce this insignificant looking yet most requisite adjunct. A thin strip of the finest Chinese tissue paper, about 34" wide and 14" long is laid on a smooth damp board; a little stream of powder is poured down its center from a hollow bamboo stick and with the tips of soft skinned fingers which seem to have an attraction for the paper and placed against the right hand lower corner, a rolling motion in the general direction of the upper left hand corner causes the paper to roll up into a twine like fuse. The slightest touch of paste secures the end and prevents unrolling. When dry it is cut into the required lengths and is ready for use

50

30

	Flash Crackers		
	Formula No. 1	No. 2	No. 3
Potassium Perchlorate		50	30
Potassium Chlorate	6		
Washed Sulphur	3	25	30
Pyro Aluminum	1	25	40
Charcoal	1		

Magic Serpent (	Black)
Naphtha Pitch	10
Linseed Oil	2
Fuming Nitric Acid	.7
Picric Acid	$3\frac{1}{2}$

Reduce pitch to fine powder; add linseed oil and rub in well; add strongest fuming nitric acid, little at a time. Allow to cool for one hour. Wash several times with water, the last time allowing mass to stand in the water for several hours. Thoroughly dry; powder fine and add picric acid, rubbing it in well. Moisten with gum arabic water and form into pellets about the size of a No. 4 star.

Ruby and Emerald Shower	Stick
Strontium Nitrate	6
Coarse Aluminum	6
Potassium Perchlorate	2
Shellac	1

Dissolve shellac in alcohol and add other ingredients, previously well mixed. Stir thoroughly to consistency of thick glue and dip sticks, previously arranged in holder, so they may be placed in drving rack.

Steel Sparkler	
Formula No. 1	
Fine Steel Filings	12
Fine Aluminum Powder	1
Potassium Perchlorate	6
Dextrin or Gum Arabic	2
Water, To suit	
The steel must be protected	l from

corrosion with paraffin. The gum should be made of the consistency of mucilage. Mix the ingredients thoroughly and add gum solution until a mixture is obtained that will adhere to the wires when they are dipped into it. This varies in different sections and with different runs of ingredients. In practice, bunches of wires are dipped at once and slowly withdrawn in a current of warm, dry air which causes the mixture to adhere evenly.

### No. 2

A sparkler of great brilliance and which is very effective may be made as follows: Take 3 lb. dextrin and add to same, little at a time, 12 pt. of water, stirring continually so as to avoid lumps. Mix intimately 10 lb. potassium perchlorate with 7 lb. pyro-aluminum or finely powdered aluminum and add this to the gum water, stirring until a perfectly smooth mixture is obtained. Wood sticks may now be dipped into it to the desired depth while it is contained in a deep vessel, and placed in a suitable rack for drying. It may be necessary to dip the sticks several times dependent on how much composition it is desired to have on them. In this case they should be dried with the composition end up, the first time so that not too much composition accumulates on the end beyond the stick.

Spark Pot Meal Powder	2	Borax Glue	9
Fine Charcoal	1	-	_
Sawdust	1	Waterproof Flare Compos	
Dawdusu	-	U. S. Patent 2,123,20	1
$\mathbf{S}$ moke			-10%
Formula No. 1		Magnesium, Pow-	
Saltpeter	4		-25%
Lampblack	1		-65%
Charcoal	1	Mix cautiously.	
Realgar	1	Military Caraly Cara	
Rosin	1	Military Smoke Screen Formula No. 1	18
No. 2		Zinc Dust	05
Saltpeter	12	Carbon Tetrachloride	$\frac{25}{50}$
Pitch	8	T. Control of the con	20
Borax	$2\frac{1}{2}$	Zinc Oxide Kieselguhr	5
Chalk	$1\frac{1}{4}$	No. 2	ีย
Sand	1	Zinc Dust	28
Sulphur	1	Hexachlorethane	50
		Zinc Oxide	$\frac{50}{22}$
White Smoke		· ·	
Formula No. 1	_	Non-Poisonous Safety M	atch
Potassium Chlorate	3	Composition	
Lactose	1	U. S. Patent 2,103.698	
Sal Ammoniac, Finely	9	Reduced Iron	28
Powdered	3	Potassium Chlorate	25
No. 2	16	Manganese Dioxide	1
Sulphur Flowers	10	Burnt Clay	18
Saltpeter Fine Charcoal	1	Collodion Solution (4%)	80
Tine Charcoar		Waterproofing Matche	
Black Smoke		One of the simplest ways to	
Hexachloroethane	24	proof matches requires on	
Alpha Naphthylamine	6	they be coated with a well	l-mixed
Anthracene	2	solution of:	_
Aluminum Powder	4	Glycerin	1
Roman Candle Compositio	n 6	Collodion	50
DIG 1 (D:11)		(N.B. The coating should	be ap-
Red Smoke (Bright)	1	plied only to the heads	of the
Potassium Chlorate	1	matches. In working with the	
Lactose	3	collodion care should be ta	iken to
Paranitraniline Red	ð	keep open flames away.)	
Brown-Yellow		Black Powder	,
Potassium Nitrate	45	Potassium Nitrate	74.0
Sulphur	12	Charcoal	15.6
Pitch	30	Dextrin	10.4

Quick Match, Military

Boil a mixture of water and starch in the proportion of 2 quarts of water to 4 ounces of laundry starch until the mixture forms a jelly. Add the black powder for the impregnating mixture in the proportion of 6 pounds to this quantity of starch mixture, and stir until the mass is thoroughly incorporated. The strands of wick should be thoroughly impregnated with the mixture of black powder, starch, and water.

When mealed quickmatch is specified, the wick shall be thoroughly impregnated with the impregnating mixture and coated while wet with the black powder which passes through a screen having 0.0041 inch openings.

Smokeless, Flashless Gunpowder
U. S. Patent 2,228,309
Nitrocellulose
(13% N.) 76 -79 %
Dinitrotoluol 21 -24 %
Diphenylamine 0.8-1.2%

Cellular Smokeless Powder
U. S. Patent 2,230,100
Nitrocellulose 225.00
Sugar 11.25
Butyl Acetate,
Secondary 83.00
Toluol 90.00
Diphenyl Amine 1.35

Tumble until completely colloidal and then extrude and cut. Finally dry and age.

Ammunition Primer
U. S. Patent 2,136,801
Mercury Fulminate 30
Potassium Dinitrophenyl
Azide 5

Barium Potassium Nitrate 35 Antimony Sulphide 25 Lead Bihypophosphite 5

Primary Detonator
U. S. Patent 2,127,106

Nitrogen Tetrasulphide 65–35

Potassium Chlorate 35–65

Explosive Powder
Sugar (50% Solution) 24
Potassium Nitrate 33
Coal, Powdered 10
Potassium Chlorate 33
Granulate and dry carefully.

Safety Explosive U. S. Patent 2,215,608 Potassium Chlorate 65.0 Manganese Dioxide 1.3 Sodium Nitrate 5.0 Pyridin 1.4 Sulphur 1.3 Sugar 26.0 Iron Filings 1.0

Coal Mining Explosive
British Patent 530,818
Potassium Chlorate 58–60
Coal Tar Pitch 10–12
Sugar 3
Potassium Dichromate 1
Sodium Chlorate 26

Mining Explosive U. S. Patent 2,215,608 Potassium Chlorate 65.0 Manganese Dioxide 1.3 Sodium Nitrate 5.0 Pyridine 1.4 Sulphur 1.3 Sugar 26.0 Iron Filings 1.0

### CHAPTER EIGHTEEN

### RUBBER, RESINS, PLASTICS AND WAXES

Rubber from Plants	No. 3
U. S. Patent 2,221,304	Glyceryl Diricinoleate 10
Lucerne, Clover, Rag-Weed,	Alcohol 10
Golden-Rod, Sugar Cane	No. 4
or Corn Stalks 20	U. S. Patent 2,083,176
Crude Petroleum 64	Glycerin 50
Mix together for 16 days, the	
add:	Graphite, Powdered 1/5
Benzol 1½	No. 5
and mix; then draw off liquid an	d Glycol Bori-borate 10
mix with:	Water 20
Carbon Black 3	No. 6
Benzol 11/4	Polyglycol Hexaricinoleate 10
Tale 4	Isopropyl Alcohol 10
Magnesium Oxide 4	No. 7
Caustic Soda ½	British Patent 489,103
Water $1\frac{1}{2}$	Glycerin 80
Mix well and add slowly, wit	h Almond Oil 4
mixing:	Lavender Oil 4
Sulphur Chloride 10	Sugar 4
Mold with heat and pressure.	Petrolatum 3
	Lemon Peel 2
Non-Sticking Rubber Powder	Lemon Juice 3

Non-Sticking Rubber Powder Dutch Patent 48,223

Add 1% tryptic enzyme to latex containing ammonia. Heat to 40° C. and leave for 24 hours, then spray dry.

Preserving Rul	
Formula No.	1
Glycerin	8
Alcohol	8
Water, To make	100
No. 2	
British Patent 48	89,103
Lemon Juice	5-15%
Glycerin	85-95%

Reconditioning Rubber Articles Rubber articles such as boots, mats, hose and the like that have become cracked and brittle may often be restored to some degree of usefulness and value by the employment of a so-called "Glycerin process." This process is particularly applicable for reconditioning rubber articles which have grown hard and lost their elasticity because they were stored under adverse conditions such as dry heat or left exposed to extreme cold.

The process is quite simple. First clean the article by thoroughly scrubbing it with a fairly stiff brush dipped in warm water to remove all dirt and grime. This should be continued until the washings are clean and bright. Next, place the item in a solution made of one part of ammonia to two parts of water. Allow it to remain in this solution for an hour or two, then rinse the article with a dilute solution of glycerin and water. Wipe off and dry thoroughly. Such rubber goods should be stored in a cool place, away from the light.

Cheap Eraser R	ubber
Rubber	10.00
Factice, White	14.50
Paraffin Oil	11.00
Lithopone	13.00
Lime	1.50
Sulphur	1.40
Diphenylguanidine	0.15
Hexamethylene Tetr	a-
mine	0.05
Pumice Stone	14.00
Glass, Ground	8.50
Whiting	25.90
Cure 20 minutes in	press at 5

Cure 20 minutes in press at 50 pounds steam pressure.

Leatherlike Stiff Ru	bber
Tire Reclaim, Whole	32.00
Rubber	25.00
Carbon Black	30.00
Zinc Oxide	5.00
Stearic Acid	1.00
Pine Tar	3.00
Sulphur	1.30
Diphenylguanidine	0.40
Shellac	2.30
0 04 1 1	

Cure 24 minutes at 50 pounds steam pressure.

Synthetic Rubber Gear and Pinion

Composition			
British Patent 513,991			
Perbunan	100		
Aldol α-Naphthylamine			
Resin	5		
Dibenzyl Ether	3		
Pine Tar ·	<b>2</b>		
Zinc Stearate	5		
Zinc Oxide	10		
Magnesium Carbonate,			
$\operatorname{Light}$	10		
Clay, Active	10		
Carbon Black, Active	60		
Sulphur	$\frac{1}{2}$		
Tetramethylthiuram			
Disulphide	$2\frac{1}{2}$		
Carbon Black, Semi-			
Active	25		

Rubber-Like Material (for use as backing, doubling or anchoring coating requiring no strategic materials)

### Solution A

Add 5 pounds casein to 19 pounds water, stirring well to break up any lumps. Add 1.1 pounds borax and heat solution to 160° F. with constant agitation. On reaching temperature, shut off heat and continue stirring until casein is completely dissolved.

### Solution B

To 43 pounds of water, add 1½ pounds Darvan and stir well. Add 33 gallons of Tysenite (60% dispersion) and stir vigorously.

Add solution A to solution B and stir well. Now add 33 pounds Flexalyn and stir until a homogeneous mix results. This solution can now be spread on fabric or paper by means of a doctor knife and dried to form a rubbery material.

Rubber Substitute
(Plasticized Poly Vinyl Alcohol)
In tubing, linings, coatings that retain flexibility and resistance.

The process consists of making dispersions of mechanical plasticizers with water, with or without soluble plasticizers for PVA (Polyvinyl Alcohol) by means of emulsification. This dispersion is then thoroughly mixed with powdered PVA and sheet molded in a press at elevated temperature. Ten to twenty per cent mechanical plasticizer from group of oxidized linseed oil, turpentine, mineral oil Vistanex, or Neoprene latex is preferred.

Formula No. 1

Formula No. 1	
Water	38.5
PVA	1.5
Oxidized Linseed Oil	10.0
Turpentine	4.0
No. 2	
Water	24.0
PVA	1.0
Oxidized Linseed Oil	10.0
Turpentine	4.0
Glycerin	25.0
No. 3	
Water	38.5
PVA	1.5
Mineral Oil	10.0
Turpentine	4.0
No. 4	
Water	24.0
PVA	1.0
Mineral Oil	10.0
Turpentine	4.0
Glycerin	25.0

Total weight of each of the above is mixed with 100 g. powdered PVA.

Rubber Substitute U. S. Patent 2,213,549 Gluten 12 oz.

Spirits of Turpen-		
tine	100	cc.
Sulphuric Acid	28	drops
Glycerol	100	ee -

Reclaiming Rubber Australian Patent 110,487

Old rubber is shredded and put in a mixer where it is treated with superheated steam at 400–500° F. and atmospheric pressure for 3–6 hours. At the end of this period the heat is shut off and the mass allowed to cool to 300° F. The whole mass is then further cooled to 200° F. During the entire process the mass is agitated. In case a highly plastic product is desired, 5–10% of a mineral oil is added to the shredded rubber.

Artificial Rubber Latex
British Patent 541,539
Wool Wax 75
Bentonite 40
Mill the above into
Rubber 400
at 50-70° C. Then emulsify with water. Soap and compounding ingredients may be added.

Latex Stabilizer and Pigment Disperser

A ½-1% dispersion of glyceryl monostearate in water will stabilize latex and permit the suspension of 300 times its weight of whiting.

Golf Ball Cover Composition
U. S. Patent 2,109,948
Deresinated Balata 20
Vulcanized Rubber Latex 15
Glue 5
Pigment 6

Acetaldehyde

### Increased Adhesion of Rubber to Cloth

About 4% ammonium stearate paste, when used in raw rubber mixes, increases the adhesion of the rubber to cloth on vulcanization. Replacing stearic acid incorporated into raw rubber mix, by ammonium stearate paste, also has a tendency to prevent the dry material from flying off in mixing.

### Tack Elimination of Raw Rubber Sheets

Diglycol stearate is being used very successfully to prevent tack of raw rubber sheets. A fluid dispersion of Diglycol stearate in water, concentration between ½–2%, is made by heating and stirring. This mixture may be applied either by spray or dip, and will not affect future working of the rubber. A similar dispersion is also being used as a lubricant in the cutting of rubber gaskets.

Preventing Adhesion of Rubber to Metal
British Patent 528,959
Graphite 35
Castor Oil 61
Alcohol 4

### Synthetic Rubber German Patent 658,172 Buna N

Butadiene	20	lb.
Acrylonitrile	20	lb.
Water	50	lb.
Sodium Phosphate	175	g.
Citric Acid	100	g.
Aquarex D	280	g.
Potassium Cyanide	20	g.
Carbon Tetrachloride	250	g.
Sodium Perborate	15	g.

pH should be about 6	.5	
$Buna\ S$		
Butadiene	20	lb.
Styrene	20	lb.
Water	50	lb.
Aquarex D	1,300	g.
Sodium Phosphate	680	g.
Sodium Perborate	135	g.
Carbon Tetrachloride	510	g.
Acetaldehyde	60	g.

60 g.

The polymerization takes place very readily at room temperature and is completed in approximately three to five hours for making Buna N and in about 40 hours for Buna S.

The reaction vessel should contain a stirrer in the center; and after all materials except butadiene are weighed out and put into the vessel, the lid is tightly closed. The butadiene is added afterward and filled into the reaction vessel through a tube and valve on the side or bottom of the vessel. This arrangement works very satisfactorily as the butadiene, being a gas at normal temperature, is shipped in steel containers under pressure and therefore can be transferred easily into the reaction vessel.

Aquarex D, for instance, is used as emulsifier for the monomers and has proved very satisfactory and better than Nekal, sodiumoleate, or other metal-soaps formerly used as emulsifiers. The amount and the choice of emulsifiers and catalysts have a decided effect on the softness of the final product; therefore this has to be borne in mind, and the amounts in the recipes should not change too widely.

The pH of the system should be 6.5, i.e., not exactly neutral all the time; if this is not the case, separa-

tion of the emulsion and coagulation occur sometimes. At the end of the reaction the buna latex is separated from the unfinished part by decantation. The remainder is always used again by adding it to a new batch. To stop the reaction one must add phenyl-beta-naphthylamine to the buna latex. This addition should never take place in the reaction vessel itself as phenyl-beta-naphthylamine would have a pronounced effect as negative catalyst on the new batch. When exposed to sunlight and air, natural rubber oxidizes; while buna-type rubbers, when undergoing the same conditions, tend to polymerize further and also to cyclicize. This action is prevented by adding a stabilizer, the same phenyl-beta-naphthylamine as mentioned above, which also acts as antioxidant and age resister.

Formula No. 1	
Buna S	100
Pine Tar	5
Zinc Oxide	5
Micronex	50
Sulphur	2
Captax	$1\frac{1}{2}$
NT- O	

Buna S-Basic Formula

110	
Buna S	100
Sulphur	<b>2</b>
Stearic Acid	1
Zinc Oxide	5
Thionex	$\frac{1}{2}$
Channel Black	65

Buna S Compound—	High Heat
Resistance	
Buna S	75.00
Synthetic 100	25.00
Altax	0.75
Cantax	0.75

Monex			0.10
Aminox			1.00
Stearic Acid			2.00
Zinc Oxide			5.00
Micronex			50.00
Sulphur			2.00
The full tioning	666	5	narte o

For frictioning, add 5 parts of pine tar to above stock.

Butyl Rubber—Cable or	Wire
Insulation	
Butyl Rubber	100
Zinc Oxide	5
Stearic Acid	3
Sulphur	<b>2</b>
Tuads	1
Captax	$\frac{1}{2}$
Clay "W" (Moore &	
Munger)	100
Whiting	50
Paraffin Wax	3
Process Oil	5

Butyl Rubber	(Molded Goods)
Butyl Rubber	100
Zinc Oxide	5
Stearic Acid	3
Sulphur	<b>2</b>
Gastex	50-100
Tuads	1
Captax	$\frac{1}{2}$

Perbunan Balloon Fabric Compound

Compound	
Perbunan	100
Zine Oxide	5
Stearic Acid	$\frac{3}{4}$
Gastex	50
Sulphur	<b>2</b>
Altax	$1\frac{1}{4}$
Diphenylguanidine	$\frac{1}{2}$
Pine Tar	25
Rosin, Wood FF	20
Tobin, Wood = -	her nacci

Break down Perbunan by passing 30 times through cold tight mill. Then add fillers in regular manner. Dissolve in methyl ethyl ketone.

Thiokol Printing Roller ("25" Shore Durometer) Thiokol F or Thiokol D 100.0 Neoprene E 20.0 Rapeseed Oil Brown Sub, 20.0 Hard 0.1 Diphenylguanidine Altax 0.2Cycline Oil 40.0 Gastex 20.0 10.0 Zinc Oxide

Cure: 2½ hours at 278° F. under pressure. Cool under pressure before removing to prevent blowing.

Reclaiming Synthetic Rubber Mix the ground scrap (2-3 mm.) with pine tar (softener) at 80-90° C. for 1 hr.; heat 4 hr. in steam at 45 lb.; mill cold for 15-20 min.

Opaque Resin
Limed Rosin 25
Stearic Acid 25
Heat and stir until uniform.

Polystyrene Resin
U. S. Patent 2,232,930
Styrene 99.95–90%
Cinnamic Acid 0.05–10%
Polymerize at 100–140° C. for three days.

Polymerization Inhibitor British Patent 531,973 Stabilization of vinyl acetate is effected by 0.01-0.1% copper abietate.

> Synthetic Resin British Patent 533,288

Dimethylol urea and a monohydroxy carboxylic acid ester, the carboxylic acid residue of which contains less than 8 carbon atoms in the molecule, are heated together. In

particular not more than ½ molecule proportions of dimethylol urea is added slowly to 1 molecule proportion of a monohydroxy monocarboxylic acid ester heated to 100° and the heating is continued. Methyl, ethyl and isobutyl glycolates are used. Phthalic acid is a good catalyst.

Water White Synthetic Resin
U. S. Patent 2,230,326
Adipic Acid 1 mol.
Dioctylamine 1 mol.
Heat at 136-270° C., with stirring, for 30 min.

Varnish Resin, Synthetic U. S. Patent 2,126,242

A mixture of glycerin 1 part and tung oil 4.8 parts is heated at 230° until the product (glyceryl tungate) is soluble in an equal volume of methyl alcohol. The varnish base is then made by heating a mixture of glyceryl tungate 100 parts, ester gum 120–290 parts, and ortho dibutyl phthalate 40 parts at 230° until it sets to a homogeneous resin on cooling.

Casting Phenolic Resins

A heat-setting phenolic liquid resin is poured into a suitable mold of glass, rubber or lead, and then is heated at 172° for two days. This product will be slightly yellow. However, objects of various colors may be obtained by adding pigments before casting. If a clear resin is not desired wood flour may be added as a filler before casting to yield an opaque product at a cheaper cost.

This resin may be set at room temperature by adding hydrochloric

acid or this composition may be heated in order to obtain a solid casting in a shorter period of time.

Resin Coating for Food Cans
Cellulose AcetoButyrate 57–47
Tricresyl Phosphate 18
Glyceryl Phthalate 35
Warm and mix in dough mixer.

Thermoplastic U. S. Patent 2,284,432

Plasticize sulphur with about 8% of aluminum stearate, 20% of silica powder, 12% of woodflour, 4% of sugar and up to 9% of rubber.

Adhesive Thermoplastic Coating
Ethyl Cellulose 47
Tricresyl Phosphate 18
Glyceryl Phthalate 35
Mix in heated dough mixer.

Electrical Conducting "Cellophane"
U. S. Patent 2,211,582

Cellophane sheets are first coated with powdered 70:30 brass suspended in a suitable vehicle and then exposed to hydrogen chloride gas to remove oxide films from the particles and render the film conductive. The sheets are then plated in the ordinary way.

Heat Stable "Vinylite" Coating
U. S. Patent 2,130,924
Less than 2% quinoline (based on "vinylite") is used in the coating.

Polyvinyl Butyral Coating (Non-Curing) for Raincoats Olive Drab Polyvinyl Butyral 100

"Kronisol"	58
Castor Oil, AA Raw	2
Dibutyl Sebacate	20
Chrome Yellow	4
Thermax	$3\frac{1}{2}$
Titanium Dioxide	4
Iron Oxide	$\frac{1}{2}$
Stearic Acid	3/4
Clay No. 33	100
Acrawax C, Powdere	
Mix together powder	
to form a uniform mix	. Mill on hot
mill about 230° F.	

Calender with rolls at about 230° F. Dust with talc. For spreading work, dissolve in alcohol-butanol 50-50. Dilute with toluol. Coating does not crack at 0° F. or stick

at 180° F.

Vinyl Chloride-Acetate Copolymer
Raincoat Material Coating
Olive Drab

Vinylite VYNS 12 lb. 8 oz. Vinylite VYNW 12 lb. 8 oz. Castor Oil. Baker's P6 3 lb. 2 oz. Dioctyl Phtha-15 lb. 12 oz. late Tricresvl Phos-6 lb. 4 oz. phate Lead Sulphate, 2 lb. 8 oz. Basic Acrawax C, Pow-6 oz. dered 20 lb. Clay No. 33 2 lb. Chrome Yellow 1 lb. 12 oz. Thermax Titanium Dioxide 2 lb. 8 oz. Iron Oxide

Mill, after mixing all ingredients together, on a hot mill about 220° F. Calender with rolls at about

Calender with rolls at about 220° F. Dust with talc. For spreading work, dissolve in methyl ethyl ketone-cyclohexane mixture. Film

does not crack at 0° F. or stick at 180° F.

Plastic	
U. S. Patent 2,284,43	32
Sulphur	25-45
Aluminum Stearate	2-6
Silica, Powdered	5-9
Wood Flour	3-7
Sugar	1-2
Rubber	1-4

### Cheap Plastic British Patent 542,794 Sawdust 45 Starch 45 Rosin 10

Boil together, with sufficient water, to make a plastic mass. Mold or roll under heat and intermittent pressure to allow escape of surplus water.

Plastic, Self-Hardening		
British Patent 522,171		
Cement	99	
Bentonite	10	
Mixture of Rubber Latex		
(e.g., Revertex) with		
water	50	
()		

Inexpensive Plastic from Wood
Pulp or Sawdust
Wood
Cresol

50
60

10

Hydrochloric Acid

A very plastic product is formed by heating the above materials for 6 hours at 70° C., washing with water, drying, grinding, pressing at 125° C. and 5000 pounds per square inch for 15 minutes. This may be baked to further harden it.

Strong and hard products may be formed by adding castor oil or glycerin, about 20 parts, to the above mixture before heating.

Other waste cellulosic material, such as corn-stalks, peanut hulls, may be used in place of wood.

Plastic Dentures	
Methyl Methacrylate	
Powder	10
Methyl Methacrylate	
Liquid	8

To form a methyl methacrylate molded piece, mix until viscous and stringy, placing in a mold such as a hand screw press, and applying pressure while heating in boiling water for 30 minutes. This may be used for a denture material and for other objects which are to be transparent or colored.

Acrylic Resin for Mounting Specimens

Methyl methacrylate liquid, containing 1% of benzoyl peroxide, is placed in a test tube in warm water and heated at about 80° C. until it becomes syrupy. The object to be mounted is then placed in a suitable container, covered with the methyl methacrylate syrup and heated in an oven at 60–70° C. until the liquid solidifies (about 24 hours). The specimen, for example a butterfly, is thus permanently preserved in a hard, transparent, glass-like mounting. Sunlight accelerates the hardening.

 $\begin{array}{c} \hbox{Ethyl Cellulose Plastic} \\ \hbox{U. S. Patent 2,215,249} \\ \hbox{Ethyl Cellulose} & 99-90\% \\ \hbox{Esparto Wax} & 1-10\% \end{array}$ 

Vegetable Cellulose Plastic U. S. Patent 2,130,783 Sawdust, Bagasse or Other Vegetable Fibers

The state of the s	
(Ground)	100
Water	100
Aniline	20
Heat with steam a	
160 lb. per sq. in. for	
with water, dry and g	rind. Mold at
135-190° C. at 1500-3	500 lb. sq. in.
with or without	
Furfuraldehyde	7

Phonograph Record Composition
U. S. Patent 2,206,636
Vinyl Resin 90.0
Chromium Oxide 7.5
Carbon Black 50.0
Calcium Stearate 1.0
Carnauba Wax 1.5
Chlorinated Naphthalene 4.5

Cast Styrene Plastic
Styrene 200
Benzoyl Peroxide 1

The benzoyl peroxide is dissolved in the liquid styrene, the solution is poured into the desired mold which is preferably sealed and the whole is heated for five days at 45° C.

It is also possible to remove the syrupy product before complete polymerization, and use this to impregnate various materials.

Luminous Plastic
British Patent 534,008
Luminous Calcium Sulphide 1
Methyl Methacrylate,
Granular 6
Mix and heat in a mold at 150° C.

Optical Lens Plastic British Patent 530,834

Ninety per cent of monomeric methyl methacrylate and 10% of methacrylic anhydride give a resin for optics when polymerized at 60° for 24 hours, then subsequently heated to 130° for 8–12 hours.

Shellac Injection Molding	
Compound	
Shellac	300
Jute	200
Kaolin	100
Pigment	15
Calcium Stearate	9
70.00	

Mix and knead in dilute ammonia, dry, run through steam heated rollers, crush and cure at 85–90° for 1½ hr. before molding.

Plastic Compounds

A coutchouc-like mass can be prepared from a mixture of glue, gelatin, and glycerin. These ingredients should be liquefied under gentle heat. (1 part gelatin, 0.5 part glue and 1.1 to 1.4 parts glycerin.) To the liquefied mixture should be added 0.03 to 0.05 part of sodium chromate dissolved in 0.1 part of water.

A permanently elastic plastic mass may be prepared by dissolving glue in a strong sodium chloride solution, heating the liquefied mass for 10 minutes at 212° F. and finally adding a quantity of formaldehyde to "set" the mass. The more formaldehyde used the harder the mass will be.

French Plastic Mass 43.00 g. Gelatin Magnesium Sulphate 2.25 g. Magnesium Carbonate 5.00 g. Zinc Oxide 5.00 g. Hydrogen Peroxide 2.25 cc. Carbon Dioxide, Saturated Aqueous Solu-4.75 cc. tion White Mineral Oil of Medium Density 4.75 cc. 40.00 cc. Water Add the water to the gelatin. Let

stand in a warm place until a completely uniform viscous mass has formed (frequent stirring of the mass will facilitate a steady formation of the liquid, also application of gentle heat will be of assistance in this respect). Replace the water which may have been lost through evaporation. When the liquid is perfectly uniform, add the carbon dioxide solution, hydrogen peroxide, and the mineral oil. Stir until the mass is uniform. Then add the powdered magnesium sulphate, magnesium carbonate, and zinc oxide to form a perfectly smooth paste. If desired, either 1 g. of sodium chromate (dissolved in 3 cc. water) or 2 cc. formaldehyde (40%) may be added which will render the mass moisture resisting.

Artificial Wood	
Formula No. 1	
Magnesium Carbonate	1000
Hydrochloric Acid	100
Calcium Carbonate	10
Casein	100
Wood Flour	800
Turpentine	20
Resin	100
Venetian Turpentine	25
Powdered Cork	75
Lead Acetate	10
Water	1650
No. 2	
Powdered Straw	1
Wood Flour	1
Asphalt	2
Magnesite, Calcined	1
Borie Aeid	$\frac{1}{2}$
Ammonium Chloride	1/2
Rosin	1/2

These ingredients are converted into a solid paste by adding sufficient magnesium chloride solution (30° Bé) and compressed under application of heat.

### Wall Board and Coating Plastic U. S. Patent 2,269,509

Cook oat flour in water in the proportion of one pound of oats to twenty pounds of water. The mixture of oats and water is cooked until the mixture assumes a consistency like that of hot jelly. To prevent the liquid binder from souring, and as a mold retardent, an oil ingredient is added to the mixture of oats and water, either during or after the cooking operation, as a preservative. Sassafras oil or oil of cloves has been found to have excellent preservative properties when added to the mixture of oat flour and water in the proportion of onehalf teaspoonful of the oil to the mixture of oats and water.

A preferred material for use as a base for the composition is newspapers. These may be subjected to the action of a comminutor to condition them for mixing with the binding solution. Sander dust, i.e., the residual product which comes from a sanding machine in the form of dust, is also an excellent base material for the composition, although because of the desirable properties inherent in newspaper flour, better results are had when the sander dust and newspaper flour are mixed in proportions of about half and half of each. In the place of newspapers, however, any other fibrous materials may be used, such as asbestos, straw, wood or rag pulp, wood shavings, etc.

In the preparation of one formula, the product of which is intended for use for interior purposes, the oats is

ground to a fine flour and the flour stirred into cold water. Heat is thereupon applied to the mixture to bring the temperature of the mixture to 212° F. At some time either before, during or immediately after application of heat, a preservative, such as sassafras oil, is added to the mixture. Thereupon, finely divided newspapers or other fibrous material is mixed into the oat flour solution in sufficient quantity to bring the final product to the desired consistency for application. The fibrous base material may be mixed with the oat flour solution while the latter still is hot, although better results will be had if the solution is first cooled to room temperature. For use as plaster to be applied with a trowel, approximately three pounds of fibrous material is used with a solution consisting of one pound of oats and twenty pounds of water. If a stiffer mixture is desired which can be handled with the hands and molded into various desired shapes, fibrous material is added as found necessary. For use as wall board and the like, or when intended to be cast into shapes, approximately four pounds of fibrous material is used with a solution consisting of one pound of oats and thirty pounds of water.

The second formula is designed to produce a material intended primarily for exterior use, such as in place of stucco, shakes, shingles, and the like. In the preparation of this formula the oats is ground to a fine flour as before, and stirred into a cold solution of magnesium chloride having a density of approximately 10° Bé. Heat is thereupon applied to the mixture to bring the tempera-

ture of the mixture to 212° F. Thereupon, the solution is cooled to room temperature and calcined magnesite is stirred into the solution, the amount of calcined magnesite used being in the proportion of 21/2 pounds of calcined magnesite to each one pound of oat flour used in the solution. Thereafter, the selected fibrous material is mixed into the solution in sufficient quantity to bring the final product to the desired consistency for application. If the compound is to be applied with a trowel, approximately three pounds of fibrous material is used with a solution consisting of one pound of oat flour, twenty pounds of magnesium chloride solution, and two and one-half pounds of calcined magnesite. If the mixture is to be handled with the hands and molded or cast into various shapes, fibrous material may be added as found necessary without increasing the liquid content of the binder solution.

Molded Wood Flour Products
Non-shrinking molded products
can be made from wood flour by a
binder of Portland cement and
"GC" powdered silicate of soda,
with a little water.

 $\begin{array}{ccc} \text{Wood Flour} & 10 \\ \text{Portland Cement} & 10 \\ \text{"GC" Silicate of Soda} & 10 \\ \text{Water} & 3\frac{1}{2} \end{array}$ 

Mix thoroughly, add water to dampen the mass, and mold under heavy pressure. Such products are durable and water resistant, though they are not refractory. Similar products can be made with part or all mineral filler instead of wood flour, but the proper amount of such

heavier material should be much greater than of the flour.

A mixture which sets up to form a hard product capable of being tooled like hard wood is prepared by mixing wood-flour and fine ball clay in proportion of about three to two, adding water, a little at a time, until the mass is of molding consistency and then adding one part of "SS-C-Pwd." silicate of soda. This mixture is lighter and less rock-like than the above formula, but it is not water resistant. The addition of some zine oxide would improve it in this respect.

### Molding Composition U. S. Patent 2,221,304 Petroleum 64Alfalfa 20 Sulphur Chloride 10 Talc 4 Magnesium Oxide 4 Caustic Soda 21/2 Water 11/2 Carbon Black 3 Benzene 11/4 Mold under heat and pressure.

Beeswax Compound, Cable Impregnating Beeswax (Yellow or Brown) 50 Paraffin Wax 50

Electrical Insulating Wax
British Patent 538,411
Hydrogenated Castor Oil 80
Paraffin Wax 20

Sticky Non-Oxidizing Wax
Formula No. 1
Hydrogenated Rosin 90
Flexo Wax C 5
Partially Polymerized
Petroleum 5

No. 2	
Hydrogenated Rosin	80
Flexo Wax C	10
Partially Polymerized	
Petroleum	10
	-
Cobbler's Thread	
(Sticky Wax)	)
Rosin (X Grade)	74
Glaurin (Plasticizer)	1
Petrolatum	20
Water	5
	-
Hard Synthetic V	Wax
Durocer	95
Glyceryl Tristearate	5
Slow Burning W	Tav
Durocer Durocer	90
Arochlor	10
1110011101	-
Hot Melt Wax Co	ating
(Non-Blocking	
U. S. Patent 2,29	
Ethyl Cellulose	5-20%
Hydrogenated Castor	, , ,
Oil	25 - 55%
Rosin or Synthetic	
Resin	15-40%
Paraffin Wax	,
$(m.p. > 40^{\circ} C.)$	15-30%

### DENTAL WAXES Sticky Wax

For temporarily cementing small pieces of plaster or similar materials together in order to make molds from broken plaster impressions. Also to hold small pieces of metal together for investment before soldering.

Formula No. 1
Rosin 16
Yellow Beeswax 8
Vermilion 1
Melt on water bath and stir to-

,	5, 111101100 111(1
gether, pour on a glass slab and with wet fingers into pencils or point molds.  No. 2	our Gum M Prepared Vermilio
	4 Rosin
	1 Ceresin
100211	1 Paraffin
No. 3	Laramin
	1 Wax fo
Guill 2 states	4 Rosin
	7 Yellow I
Inglit Tellow Itoshi	1 EHOW I
Pink Base Plate Wax Formula No. 1	Gold In
White Beeswax 5	
Paraffin Wax 2	
1111101100 1100 1, 1111010	1 Yellow (
Melt the waxes and add the	
kanet root. Leave on the fire u	ntil   Carnaub
the desired shade of pink is	ob- Dye, To
tained, strain through cheese cl	oth Melt the
into tin molds, about 1/32 or 1	
of an inch thick. Have the mo	
coated with a film of glycerin.	
polish the sheet wax, pass betw	een constantly
the rubber rollers of a wash wring	
No. 2	add the dy
White Beeswax 4	-
Gum Turpentine 1	
	3   suitable to
, 0111111011	4 tor. Lamp
No. 3	aniline dy
(To be used in hot weather.)	purpose. (
White Beeswax 2	
Ordao rarponina	4 are recom
	1
, 0111111011	2 States
No. 4	Stearic A
To be used in cold weather.	Paraffin
White Beeswax 2	1
order marponing	6 Tamara
	2 pentir
	2 Gum Da
No. 5	NT-1'-
Hard Base Plate Wax	Nationa

50

Yellow Beeswax

IICS AND WAXES	443
Gum Mastic	6
Prepared Chalk	3
Vermilion	4
No. 6	-
Rosin	1
Ceresin	3
Paraffin Wax	6
	U
Wax for Partial Impressi	ons
Rosin	1
Yellow Beeswax	16
E-manufacture and the second s	
Gold Inlay Impression Wa	axes
Formula No. 1	
Yellow Beeswax	10
Gum Dammar	10
Yellow Ceresin	20
Hard Paraffin (120° F.)	30
Carnauba Wax	30
Dye, To suit	
Melt the beeswax, ceresin, p	araffin
nd carnauba wax in a po	
ish on a water-bath, add th	

Melt the beeswax, ceresin, paraffin and carnauba wax in a porcelain dish on a water-bath, add the gum dammar in small portions and stir constantly until a uniform mass is obtained. Remove from the fire and add the dyestuff.

Gold inlay waxes should be colored deeply with a dye, especially suitable to the needs of the operator. Lamp black or an oil-soluble aniline dye are best suited for this purpose. (The red and blue "Cerasine" or "Sudan Red" aniline dyes are recommended.)

No. 2 Price's Acid 110 Wax 10 15 ick (Larch Tur-10 ne) ammar 110 No. 3 nal Bureau of Standards Carnauba Wax 25

60

Ceresin	10
Beeswax	5
Oil soluble aniline dye in	n suitable
colors may be added.	
No. 4	

Paraffin Wax (55° C.)

No. 4
Carnauba Wax (Light) 10

Paraffin Wax (70° C.) 35 Beeswax, Pure 55

Melt the carnauba wax on a low flame, avoiding foaming; add the paraffin and after complete melting add the beeswax.

Carving Wax for Tooth	Forms
Carnauba Wax	- 80
Ceresin	128
White Wax	64
Zinc Oxide	48
Saturated Solution	
Acriflavine in Alcohol	1
Engraver's Wax	
Yellow Beeswax	1
Tallow	1
Burgundy Pitch	2

Jewelers Wax

Heat common rosin in a suitable vessel until it flows freely, then add, slowly, and with constant stirring, plaster of Paris until on dropping a small portion on a plate or marble slab and allowing it to cool, then prying it off with the point of a knife it springs off with a metallic ring. With too little plaster it is soft and bends; with too much it is hard and brittle and loses its adhesiveness. This is used by jewelers for a variety of purposes; to cement pieces of thin metal to chucks for turning, to cement stones into fittings, and tools into metal and wooden handles. It is handy in a dental laboratory for cementing

felt and brush wheels to the chucks of the polishing lathe.

### Modeling Compounds Formula No. 1

Stearin 25 Gum Dammar 50 Powdered Soapstone 85

Carmine, Enough to color Melt the stearin on a water-bath, dd the gum dammar, and, when

add the gum dammar, and, when melted, stir in the powdered soapstone, tinted with the carmine.

### No. 2

Stearic Acid	20
Oleic Acid	4
Gum Copal	19
Seed-Lac	17
Powdered Soapstone	40
No. 3	
Manila Copal	30
Light Colored Rosin	30
Carnauba Wax	10
Stearic Acid	5
Powdered Soapstone	75
Carmine, Enough to color	
No. 4	

No. 4	
Best Light-Colored	
Rosin	50
Gum Copal	2
Yellow Ceresin	8
Gum Turpentine	5
Powdered Soapstone	50
Menthol	$\frac{1}{2}$
Fresh Slaked Lime	10
Color with Florentine	Lake (for
red).	

### Brake-Block Composition U. S. Patent 2.268.280

U. D. Fatent 2,208,2	<i>1</i> 00
Silica Sand	23
Asbestos Powder	11
Asbestos Cement	33
Coke Dust	22
Linseed Oil	- 11

Brake Lining Impres	gnant
China Wood Oil	1
Bakelite No. 7112	1
Petropol No. 2138	1
	3
Xylol No. 2	
	10
Asphalt Pitch (A-1)	10
Gilsonite	180
China Wood Oil	<b>7</b> 0
Linseed Oil	20
Petropol No. 2138	50
Detroloum Nanhtha	440
A Chamimpregnation of 1	lining, bake
for 2 hours at 250° F. an	d 1 hour at
10r 2 1100115 20 200 21 110	

### Shoe-Filler British Patent 532,471

350° F.

Soft wax tailings 24, and B rosin 15 lb. are melted together and cooled to 100° C. One pound of oleic acid is then added, followed by 1/5 lb. of sodium hydroxide in water then a hot paste of 2/3 lb. of bentonite in 8 lb. of water. This mixture is poured into a charge of 11 lb. of granular cork and well mixed therewith. Castor oil, if added up to 2 lb., confers increased flexibility.

# Shoe Stiffener U. S. Patent 2,238,337 Rubber Resin Containing Box Toe Scrap Cumarone Resin Asbestos Fiber Stiffener 130 400 100 200

Artificial Asphalt (Bitumen)

Addition of 30–40% 200-mesh coal to a heavy hydrocarbon oil (550–300 seconds Furol) and heating at 400° F. for at least one hour produces an asphaltic material quite satisfactory for many purposes

where a bituminous material must be employed.

Increasing Softening Point of Asphalt

Melting Acrawax C with asphalt raises its softening point. 10% Acrawax C raises softening point of asphalt from 150–250° F.

Synthetic Brewers' Pitch
U. S. Patent 2,122,543
(Flexible impervious lining for barrels, drums and cans.)
Ester Gum
Japan Wax
Petrolatum
Apply hot.

Elastic Stuffing Box Packing Australian Patent 112,147

For steam, acids, and ammonia the following composition is used: asbestos fiber 20–30, ozokerite 5–10, graphite 5–10, magnesium oxide, 20–30, and amorphous carbon or graphite 20–30%. For water and compressed air the 20–30% of asbestos is replaced by asbestos 10–15 and rubber chips 10–15%, the other ingredients remain the same. For oil, gasoline and kerosene 10% of granulated cork is added to the first composition.

### Neoprene Gasket and Packing British Patent 516,777 400 Neoprene 30 Pine Tar Magnesia, Light Calcined 60 140 Softener 8 Anti-Oxidant 200 Soft Black 250 Channel Black 1 Sulphur 500 Wood Wool 40 Zinc Oxide

Compressed Fiber Board U. S. Patent 2,215,245

Wood fibers, in suspension in water, are compacted then compressed at approximately 200 to 250° and not more than 3000 pounds per sq. in. into a coherent mat, and impregnated (before or after compacting or compressing) with a fatty acid pitch solution or emulsion (e.g., pitch 300, kerosene 700, and some paraffin), and the pitch is hardened by an oxidizing bake at approximately 150°.

Flooring Base Composition
German Patent 698,682 (1940)
Shredded Waste Paper 6.5 l.
Glue 0.5 l.
Cement 2.0 l.
Water 1.0 l.

Mix thoroughly; press into forms and dry. This is elastic and holds nails firmly.

Hydrocolloid Dental Impression Composition U. S. Patent 2 234 383

U. S. Patent 2,234,383 Formula No. 1 Agar-agar (No. 1 Kobe,

Strip) 30.00
Borax 0.42
Potassium Sulphate 4.20
Water, To make 210.00

The agar-agar is washed in fresh water for about half an hour and then drained. The wet agar-agar is heated and stirred in a steamjacketed kettle until a smooth sol is obtained. The borax (as a saturated solution in water) is then added slowly, with constant stirring, and the potassium sulphate is then added. The stirring and heating is continued until the product is smooth and homogeneous, and water

is added or evaporated until a final weight of 210 lb. results. The material may then be packaged for shipment. The resulting pH value of the above mixture will be in the neighborhood of pH 8.3, depending somewhat upon the character of the agaragar, the pH of this raw material having been found to vary to some degree, and the pH of the water used.

 No. 2

 Agar-agar (No. 1 Kobe, Strip)
 30.00

 Manganous Borate (Powdered)
 1.05

 Potassium Sulphate
 4.20

 Water, To make
 210.00

The agar-agar is washed in fresh water for about half an hour and then drained. In this washing the agar-agar soaks up almost all the water needed for the batch, so that ordinarily no additional water is necessary. The wet agar-agar is heated in a steam-jacketed kettle and stirred constantly at a moderate rate. After an hour or two of heating and stirring, the agar-agar will have formed a fairly smooth sol. Hot water may be added at this point, if necessary, to bring the total weight of the material to a little over 210 pounds. The manganous borate powder is added at this time. as by sifting through a fine mesh screen (or by ball-milling in a small quantity of water, and adding the wet mix), and added to the agaragar sol under continuous stirring. The potassium sulphate may then be added in the form of fine crystals or powder or in water solution. The stirring and heating is continued until the manganous borate is uniformly distributed and the potassium sulphate is dissolved (if added

as a solid), and longer if necessary to evaporate any excess water which may have been added, so as to end with a final weight of 210 pounds. The hot sol may then be filled into suitable containers and packaged for shipment.

No. 3	
Agar-agar (No. 1, Kobe	е,
Strip)	30.00
Borax	.70
Barium Chloride	.93
Potassium Sulphate	4.20
Water, To make	210.00

The agar-agar gel may be made up as described in connection with the first example, and the barium chloride added in crystal form and the mixture stirred until the barium chloride is dissolved, after which the dry borax is added a little at a time. This method requires a strong stirring apparatus to keep the material properly stirred, as the borax will cause the material to become extremely viscous if added too rapidly. A slow and careful addition of the borax is desirable. As a modification of this method, the barium borate may be prepared by separately reacting the barium chloride with the borax, filtering and washing the material, and adding the white precipitate to the gel as in accordance with the first described example.

### CHAPTER NINETEEN

### SOAPS AND CLEANERS

### Transparent Soap Formula No. 1

An inexpensive soap may be made from 45 stearin, 55 castor oil, 30 sugar solution (sugar 1 and water ½), 50 caustic soda 37° Bé, and 35 alcohol. Fatty acid content of such soap is from 60–70%.

### No. 2

50 kg. cocoanut oil fatty acids, 40 kg. tallow fatty acids, 20 kg. distilled vegetable oil fatty acids, about 56 kg. (38° Bé) caustic soda, 52 kg. denatured alcohol, 2.4 kg. potash, 3.2 kg. common salt, 2 kg. sodium nitrate, 1.6 kg. calcined soda ash, 44.8 kg. water. Careful adjustment to neutrality and formulation at a low temperature are very important in producing the desired clarity.

Soft Soap (Dark	:)	
Scybean Oil Fatty		
Acid	680	lb.
Arachis Oil Fatty		
$\mathbf{A}\mathbf{c}\mathbf{i}\mathbf{d}$	130	lb.
Tallow	80	lb.
Rosin	30	lb.
Caustic Potash		
(50° Bé)	270	lb.
Sodium Carbonate	50	lb.
Water	350	lb.
T10		
Liquid Soap		
Cocoanut Oil	225	lb.
Sunflower Oil	75	lb.
Caustic Potash		

(36° Bé)

Calcium Chloride	18 lb.
Boric Acid	5 lb.
Water	170 lb.
VV 250C1	170 10.
PECTIN SOAP	S
Liquid Soap	
Soap	50.0
Pectin	22.5
Sodium Silicate (38° Bé	
Sodium Sincate (36 De	3) 21.3
Paste Soap	
Tallow Fatty Acids	20
Olive Oil Fatty Acids	20
Palm Oil Fatty Acids	20
Caustic Soda (38° Bé)	27
Pectin	45
Water	15
Bentonite or Sodium	

Soap from Waste Fat

Silicate

55

Although waste fat is always of commercial value, in some instances it might be found an economic advantage to convert the fat into a soap suitable for household cleansing purposes. This can readily be effected by the saponification of the fat by means of caustic soda. The following process will give a satisfactory soap for general cleansing purposes: fat 36 lb., caustic soda 43/4 lb. (may be increased slightly to complete saponification of fat), water 4 gallons. The soap should be prepared in an iron vessel capable of being heated. The caustic soda should be dissolved in the water and

220 lb.

heated to boiling. The fat should then be added slowly to avoid frothing and when all has been added. the mixture should be boiled for three hours. The solution can be tested for complete saponification of the fat by treatment of a small quantity with water as no oily globules should separate. When saponification is complete, the soap solution can be poured into a suitable mold. Either individual molds for the bars can be employed or the soap can be poured into a trough about 3 inches deep. When cold the soap mass produced can be cut into suitable pieces. It will usually be found desirable to stack the soap manufactured in this way for a few weeks before use to enable the bars to dry out and harden. The character of the soap naturally will depend to some extent on the nature of the fat used. Soap produced in this way differs chemically from soap as produced commercially, in that it still contains the glycerin produced by the saponification of the fat.

### Saddle Soap

Daudic Doap	
Soap Powder	15
Water	72
Neatsfoot Oil	5
Beeswax	8

Dissolve the soap in hot water. Heat the neatsfoot oil and wax until melted and pour hot mixture into soap solution. Stir until it begins to thicken, pour into cans.

### Anti-Perspirant Soap French Patent 841,802

To 100 parts of soap are added 3-5 parts chromic anhydride, 1-2 parts hexamethylene tetramine and 1 part aluminum acetate.

### Fluorescent Soap

For catching thieves a small amount of fluorescein can be incorporated in ordinary soap and, when the thief washes his hands with the soap, they will be stained bright greenish which is more visible in ultraviolet light.

Although the above soap is visible, an invisible soap stain may be made by adding beta-methylumbelliferone to ordinary soap. This stain will not be seen in white light but under ultraviolet light a bright blue color will be noted.

Trick soap can be prepared by adding uranine and acriflavine to ordinary soap. The more a person washes his hands the more the staining.

### Soap Pad

Soap pads are composed of flannel pads impregnated with jelly cleanser and with ammonium-oleate and other soaps.

### Pumice Soap

A pumice soap is prepared by the cold process from 15 parts of cocoanut oil, 10 parts of tallow and 12.5 parts of 38° Bé caustic soda. After saponification, 10 parts of crystalline soda are dissolved in the soap and enough pumice crushed in to give a sufficiently firm product when cold.

### Soapless Soap German Patent 696,126

10 kilograms methyl cellulose are mixed with 100 kilograms of saponin extract. This is brought to the boil and then 150 kilograms of saponin extract added cold. The emulsion formed on standing is stated to be

excellent for washing fine fabrics and is also recommended for toilet use. By the addition of sodium lauryl sulphate, approximately 10%, the detergent properties of the mixture are still further improved.

Acid Cleaning Emulsions

A cleansing emulsion suitable for use on porcelain, metals, or cement is made of the following composition:

Polymerized Glycol Oleate	15
Oleic Acid	5
Mineral Oil	30
Hydrochloric Acid	6
Water, To make	100

Another cleaning emulsion that may be used is of the following composition:

Polymerized Glycol	
Distearate	10
Stearic Acid	5
Mineral Oil	15
Hydrochloric Acid	3
Water	67

Preventing	Gelling	of	Soap
So	olutions		_
Soap Flakes			10
Water			990

Ammonium Sulphamate 1
The above may be used hot and will not gel on cooling.

Cleaner and Polis	sher
$(For\ transparent\ s$	heet)
Diatomaceous Silica	
(Snowfloss)	100
Emulsifying Agent *	10
Water	600
Naphtha	300

\* Emulsone B. (Vegetable Gum.)

Non-Inflammable	Cleaning Fluid
U. S. Patent	2,245,052
Water	94 fl. oz.
Oxalic Acid	$5\frac{5}{8}$ oz.
Potassium Chrom	ate ¼ oz.
Glycerin	1/8 fl. oz.

Hand Cleaners	
(Mechanic's)	
Formula No. 1	
Soap, 90% (Titre: 30°)	15
Tetrasodium Pyrophos-	
phate	10
Silica Sand, Fine, Round	
$\mathbf{E}$ dged	40
Ash, Finest Volcanic	35
No. 2	
Borax	20
Sodium Silicate, "G" Type	•
Fine Mesh	15
Soap, 90% (Titre: 36°)	<b>2</b> 0
Sodium Metasilicate, Fine	
Mesh	5
Silica Sand, Fine, Round	
Edged No. 3	40
Sodium Carbonate	2 5
Borax	$\frac{3.5}{11.5}$
Sodium Metasilicate	5.0
Soap, 90% (Titre: 36°)	28.0
Wetting Agent (Sul-	20.0
fatate)	2.0
Silica Sand, Fine, Round	2.0
Edged	15.0
Ash, Fine Volcanic	35.0
, = =====	55.5
Tall TT 1 Cl	
Jelly Hand Cleanser	

Jelly Hand Clean	ser
Agar-Agar	0.2
Psyllium	0.3
Glycerin	5.0
Soda Ash	5.0
Soap	5.0
Ammonia	2.5
Javelle Water	0.5
Water	81.5

Hand Stain Rem	over	
Water	8	oz.
Soap Powder	4	oz.
Silica (150 Mesh)	$\frac{1}{2}$	
Pumice Flour	$\frac{1}{4}$	oz.
Chlorox (Chlorine		
Water)	1	$\mathrm{dr.}$
Glycerin	1	ΟZ.
Rubbing Alcohol	1	oz.

Heat the soap in the water until dissolved, and add the abrasives. When cool add the chlorox (or the like) the glycerin and alcohol.

Bottle and use in the same way as any liquid soap on well-wetted hands.

#### Abrasive Cleanser

Soap Flakes	12.5
Mineralite	28.5
Water	59.0
Sassafras Oil, Trace	

Waterless Hand Cleanser
Powdered White Soap
Potassium Carbonate
Tri-sodium Phosphate
Finely Powdered
Asbestos
1 lb.
Water
10 pt.
Perfume, To suit

Dissolve the soap and the chemical salts in hot water, allow to cool, stir in the asbestos, mix thoroughly, and cool for packing. This is used without water.

# Industrial Hand Cleaners Formula No. 1 Diethylene Glycol Oleate 97 Wetting Agent (Sulfatate) 2 Perfume 1

#### No. 2

Propylene Glycol Laurate	44
Water	43
Wetting Agent (Wetanol)	2
Perfume	1

These have excellent cleansing and skin-softening properties and do not abrade or de-fat delicate skin.

#### Denture Cleaner British Patent 506,451

A denture cleanser is made from 2 parts of sodium peroxide and 3 parts of sodium chloride. Sodium carbonate, calcined soda, phosphates and other agents may be added.

#### Laundry Washing

Though no one formula is suited to every washroom, the following proportions for "Stock Soap Solutions" have been found to give excellent results under many conditions. The exact formula to be used with these solutions should be worked out with the aid of pH and titration figures. For a 300 pound dirty load of nets (42 x 84 washer) it is advisable to add one pound sodium metasilicate (dry) to break, following with the stock soap solution as below until the desired suds are obtained.

#### Stock Soap Solution

Soap	3
or	
Soap	2
Sodium Sesquisilicate	1
Sodium Metasilicate	1

#### White Work Formula

Soap mixture used: 50 parts high titer soap and 50 parts sodium metasilicate. Extra metasilicate used on the break (pH 11.0). (For net washing use 2 more inches of water and one additional rinse.)

			Tempera-		
		Water,	ture,	Time,	
Op	eration	Inches	Degrees F.	Minutes	
1.	Break	6"	90°	10 min.	Good suds
2.	Suds	4	130-140	10	Good suds
3.	Suds .	4	160-170	10	Good suds
4.	Suds and bleach	5	160	15	Javelle water first;
5.	Hot rinse	10	160	5	after 5 min. add
6.	Hot rinse	10	160	5	enough soap to give
7.	Hot rinse	10	160	5	light suds *
8.	Warm rinse	10	140	5	
9.	Sour	5	140	5	Dump the water
10.	Blue	10	$\operatorname{Cold}$	5	

<sup>\*</sup>Probably preferable to add soap first, then add Javelle water after running 5 minutes.

#### Fast Colored Work Washing Formula

Soap mixture used: 70 parts soap and 30 parts sodium metasilicate (pH 10.5-10.8 in the break). (For net washing use 2 more inches water.)

Laundry Compounds	No. 5
Formula No. 1	Sodium Carbonate 40
Sodium Carbonate 50	Sodium Metasilicate 50
Sodium Bicarbonate 50	Soap 10
This compound can be used in the	No. 6
wash wheel and does not injure fiber	Sodium Carbonate 50
nor does it develop any heat.	Sodium Metasilicate 13
	Trisodium Phosphate 2
No. 2	Borax 5
Formula No. 1 plus any desired	Soap 30
amount of an alkali free soap.	No. 7
No. 3	Sodium Sesquicarbonate 50
Soap 65	Borax 50
Sodium Carbonate 15	No. 8
Sodium Bicarbonate 5	Sodium Carbonate 40
Trisodium Phosphate 10	Sodium Metasilicate 45
Sodium Metasilicate 5	Trisodium Phosphate 15
	No. 9
No. 4	Sodium Carbonate 10
Sodium Carbonate 50	Sodium Bicarbonate 35
Sodium Metasilicate 40	Trisodium Phosphate 40
Soap 10	Soap 15

No. 10		Trisodium Phosphate,	
Sodium Carbonate	75	Anhydrous	15
Sodium Metasilicate	22	No. 21	
Soap	3	Sodium Carbonate	50
No. 11		Sodium Metasilicate	15
Sodium Carbonate	70	Trisodium Phosphate	35
Sodium Bicarbonate	10	No. 22	00
Borax	5	Sodium Carbonate	65
	15	Sodium Bicarbonate	35
Soap No. 12	10	No. 23	99
Sodium Carbonate	55		05
G diama Matagiliante	45	Sodium Carbonate	$\frac{25}{50}$
Sodium Metasilicate	40	Sodium Metasilicate	50
No. 13	1.77	Trisodium Phosphate	25
Sodium Carbonate	17	No. 24	
Sodium Metasilicate	32	Sodium Carbonate	40
Pine Oil	1	Sodium Metasilicate	24
No. 14	(i)_	Trisodium Phosphate,	
Sodium Carbonate	40	Monohydrated	32
Sodium Metasilicate	44	Caustic Soda	5-7
Disodium Phosphate	16	Wetting Agent	1-2
No. 15		No. 25	
Soap (90%)	55	Sodium Carbonate	36
Sodium Metasilicate	20	Trisodium Phosphate	57
Sodium Carbonate	15	Caustic Soda	6
Sodium Pyrophosphate	10	Wetting Agent	1
No. 16		No. 26	
Sodium Carbonate	20	Soap Powder (95% Soap)	18
Sodium Metasilicate	30	Sodium Carbonate	82
Sodium Pyrophosphate	10		
Soap	40	Linen Alkali	
No. 17		Sodium Carbonate	75
Sodium Carbonate	50	Caustic Soda	25
Silicate, Liquid (40%)	50		
No. 18		Break Soap	
Sodium Carbonate	5	Sodium Carbonate	55
Sodium Metasilicate	35	Trisodium Phosphate	20
	60	Soap	25
Soap No. 10	00	Laundry Detergents	
No. 19	45	(Hand or Open Washing Ma	(ahima)
Sodium Carbonate		Sodium Sesquicarbonate	43
Sodium Metasilicate	20		$\frac{43}{17}$
Trisodium Phosphate,	90	Trisodium Phosphate	17
Anhydrous	30	Tetrasodium Pyrophos-	1 5
Caustic Soda	5	phate	15
No. 20		Soap, Neutral, 90% High	
Sodium Carbonate	55	Grade, (Titre: Approx.	0-
Sodium Metasilicate	30	32°)	25

Soap Builders		Sodium Metasilicate	47
Formula No. 1		Sodium Hydroxide	18
Sodium Carbonate	90	No. 3	
Tetrasodium Pyrophos-	4.0	Trisodium Phosphate	10
phate	10	Tetrasodium Pyrophos-	
No. 2		phate	40
Sodium Carbonate	95	Sodium Bicarbonate	5
Sodium Metasilicate	4	Wetting Agent (Sul-	
Sodium Hydroxide	1	fatate)	30
T 1 "D 1 "		Sodium Sulphate	15
Laundry "Breaks"		No. 4	
Formula No. 1	e E	Sodium Bicarbonate	5
Sodium Carbonate	65	Sodium Tetraborate	5
Sodium Metasilicate	$\frac{22}{3}$	Tetrasodium Pyrophos-	
Sodium Hydroxide	9	phate	40
No. 2	22	Sodium Sulphate	25
Sodium Carbonate		Wetting Agent (Sul-	
Sodium Metasilicate	13	fatate)	25
Trisodium Phosphate	40	No. 5	
Sodium Bicarbonate	15	Soap (Titre: 30°)	35
Tetrasodium Pyrophos-	10	Wetting Agent (Sul-	
phate	10	fatate	15
Textile Sodas		Tetrasodium Pyrophos-	
Formula No. 1		phate	40
Sodium Carbonate	53	Trisodium Phosphate	10
Sodium Bicarbonate	47	No. 6	
No. 2		Sodium Sulphate	50
(Super Strength)		Trisodium Phosphate	10
Sodium Carbonate	58	Tetrasodium Pyrophos-	10
Trisodium Phosphate	42	phate	20
		Wetting Agent (Sul-	20
Laundry Soap Builder	•	fatate)	20
Sodium Carbonate	28	No. 7	20
Sodium Metasilicate	35		0.5
Tetrasodium Pyrophos-		Soap, 90% (Titre: 30°)	25
phate	8	Wetting Agent (Sul- fatate)	4 P
Sodium Hydroxide	29	•	15
T. T. D.		Trisodium Phosphate	10
Laundry Detergents		Tetrasodium Pyrophos-	F 0
(Open or Wheel Washin	g)	phate No. 8	<b>5</b> 0
Formula No. 1	50		
Sodium Carbonate	52	Soap, 90% (Titre: 30°)	12
Sodium Metasilicate	38	Wetting Agent (Sul-	_
Soap (Titre: 30°)	10	fatate)	3
No. 2		Sodium Bicarbonate	30
Sodium Carbonate	45	Sodium Metasilicate	5

Trisodium Phosphate 10 Tetrasodium Pyrophosphate 40

#### Laundry Stain Removal

The fabric must stand up under the treatment proposed whether the stain is stripped or not. Chlorine bleach and strong alkalies, while applicable to cotton and linen with adequate control, should be kept away from wool and silk. Strong mineral acids, which can be used carefully and with short exposure time on wool and silk, should not he used on cotton and linen. Stains on wool and silk are in general more resistant to removal than those on cotton and linen. Mixed goods, of course, require that the specific precautions pertaining to each different type of fiber present be taken for successful, safe stain removal treatment.

Colored goods introduce the factor of dye behavior under the influence of the stain removal reagent in addition to that of effect on fiber. In this case, the reagent must be safe to color as well as to fiber. A preliminary test at some out of the way point on the fabric is always imperative to determine just what effect on color the proposed treatment will have. Some staining substances have in themselves the power of altering color and care should be taken not to extend any damage of this nature which has already taken place.

The age of a stain is perhaps the most important factor relating to its ease and completeness of removal. Old stains of any kind are always more difficult to remove than fresh similar ones. The fixative chemical

and physical reactions which take place in the fabric after the solvent or vehicle of the staining substance has dried or spread out through capillarity are progressive in practically every case. If simple "First Aid" could always be rendered soon after the staining contact was made, the later removal of the stain would be greatly simplified. Such simple treatments as a little cold water on spots of food products, body fluids and any other substances known to contain water or be soluble in it, or smallamount of kerosene. naphtha, turpentine or similar light oily solvent for paint, grease and oil spots are vastly worthwhile.

Regarding reappearance of stains decolorized by oxidizing or reducing methods, it may be said, in general, that stains removed completely but with difficulty, seldom reappear. This is particularly true of oxidizing bleaches which do their color stripping by forcing oxygen into the chemical makeup of the stain body to change its composition and destroy its chromatic or coloring power. The opposite or reducing conditions necessary to change back a stain once decolorized by oxidation is rarely met with in service.

On the other hand, stains decolorized by reducing agents, which bring about their decolorizing action by taking oxygen away from the stain body, do sometimes reappear, since the oxygen necessary to reproduce the chromatic or coloring matter is found everywhere in the air. To break this chain, it is sometimes efficacious to actively oxidize a stain after stripping with a reducer such as hydrosulphite, by the action of permanganate, and then re-reduce.

The chemical action of forced reversal seems to move the stain body so that the final reduction is more permanent than with a single reducing treatment.

With the above general considerations in mind, the specific procedure in spotting or stain removal is as fellows:

- 1. The first step may well be called "detective work," since the logical first move is to determine by inquiry, visual examination with or without the aid of magnification or by general deduction from the type of article and location of the stain, just what its nature is. A well thought out plan is as valuable as any of the reagents.
- 2. Try solvents such as naphtha or gasoline, carbon tetrachloride, trichlorethylene, acetone, etc.
  - 3. Try alcohol.
- 4. To the dry fabric apply Kerosene-Oleic-Benzol cleaner. Work in and wash out with a solution of a safe alkali.
- 5. Try the oxidizers such as chlorine bleach, hydrogen peroxide and permanganate. (Type of oxidizer contingent on type of fiber.)
- 6. Try the reducers such as hydrosulphite, bisulphite and titanous chloride. (The last is an acid solution. Rinse well after spotting.)

#### Acriflavin Stain Removal

The very resistant orange yellow stain from this dye is most frequently found on hospital work since it is in common hospital use. Its fastness makes three separate successive treatments necessary:

- 1. Soap and water wash.
- 2. Acetic acid—alcohol.
- 3. Permanganate—hydrosulphite.

Argyrol (Silver Antiseptic) Stain Removal

Like all other silver stains, argyrol is not removed in the regular washing process but requires separate treatment.

The best remover for silver stains resulting from any of the many silver compounds used in medicine, dentistry and photography is a mixed solution of bichloride of mercury and ammonium chloride. The reagent is made by dissolving 5 grams of bichloride of mercury and 5 grams of ammonium chloride in 100 cc. of water. Heat the solution to just below boiling, immerse the article and follow by thorough rinsing after the stain disappears.

Iodine in the form of ordinary tincture of iodine is recommended for silver stains in some cases. This converts the silver residue to silver iodide which is soluble in ammonia water.

Spot the stain with tincture of iodine, using a glass rod. Allow to stand a few moments for reaction to take place. Apply sodium thiosulphate solution to remove both excess iodine and the silver iodide formed. Follow by the regular wash.

Automobile Grease Stain Removal

This common source of oily stains produces some difficult ones that the ordinary laundering operation will not remove, especially the new long life high pressure greases featured for chassis lubrication. Local treatments with dry solvents such as carbon tetrachloride, trichlorethylene, gasoline, chloroform, etc., will sometimes suffice for removal. Frequently, however, a more efficient treatment is required and spotting

with Kerosene-Oleic-Benzol cleaner, followed by a hot 1 to 2% solution of sodium metasilicate. Follow by the regular wash.

Balsam of Peru Stain Removal The brown stain due to this resinous medicinal material responds to acetone, xylol, chloroform and alcohol.

Benzoin, Tincture of (Stain Removal)

Treatment with a sufficient quantity of alcohol will completely remove the brown stain due to this medicinal compound.

Bleaching Silk or Wool

It is frequently necessary to whiten silk or wool articles, which have become yellowed. The best method for the stain removal operator to use is a treatment with 1 volume hydrogen peroxide made alkaline with ammonia or Escolite.

Make up the 1 volume peroxide bath in a crock or non-metallic container by diluting one part of drugstore hydrogen peroxide (10 volume, 3%) with 9 parts of water or 1 part of the (100 volume, 30%) material with 99 parts of water. Add the ammonia water or Escolite to produce an alkaline bath and immerse the articles to be bleached. The time necessary for bleaching is a function of the depth of off-color to be taken care of.

Iron in any form should be absent and heat should not be applied.

Sulphites will also bleach silk and wool but the control necessary precludes their use in laundry practice for this purpose.

Never use a chlorine bleach on silk or wool.

Carbon Stains

The more finely divided the form in which the carbon in a stain occurs, the more difficult it is to remove. Some of the carbon blacks produced by burning natural gas or oil and used as pigments in polishes, paints, etc., are so fine that their removal from stain residues is difficult. The regular wash is usually not sufficient to take them out without assistance.

Saturate the dry goods containing the carbon stain with Kerosene-Oleic-Benzol cleaner and follow with the regular formula in the washwheel.

Cement Stains

Cement stains appear to be the result of chemical action between the cellulose of the fabric and the lime in portland cement and are formed when goods are allowed to lie on a wet concrete floor. This discoloration is extremely resistant. While part of the lime can be removed by an acetic acid treatment and the residual color lightened by treatment with chlorine bleach, the fabric never completely regains its original condition.

Chocolate and Cocoa Stains

The coloring matter of these stains is bound with fatty matter, sugar and milk solids. Spots remaining after the regular laundering can be stripped with one of the solvents for grease.

#### Coffee Stains

Ordinarily the brown stains caused by coffee respond completely to the regular washing process. Occasionally, however, the effect of

alkali changes them over to a bright yellow color in which form they are no more difficult to remove than before but show up more plainly. The Permanganate-Oxalic treatment will take care of any coffee stains, brown or converted by alkali to yellow, remaining after normal laundering.

Contact or Loose Dye Stains
The first step in attempting to
strip bled dye taken up by other
goods in the washwell from a loosely
dyed article such as a sock or cheap
print, accidentally included in a
load, is to give the stained articles a
thorough treatment with chlorine
bleach

If this treatment does not succeed, the contacted dye is usually of the type requiring the action of a reducing agent. Treatment with sodium hydrosulphite or sodium sulphoxalate formaldehyde is therefore recommended. Either of these strippers may be also used on silk or wool if carried at lower concentrations than that given for cotton or linen goods.

The intensity of the stain determines the amount of reducing stripper required, but a good average can be taken as 4 ounces of sodium hydrosulphite or sodium sulphoxalate formaldehyde for a load of clothes, added to 2 inches of cold water in the wheel and run for 10 minutes. The treatment may be repeated to keep the sulphite bath definitely alkaline since hydrogen sulphide is formed if the solution should become acid and will blacken the metal.

For local spotting of contacts, the same strength solution can be used

in a dish. Pyridine-sulphite is also effective on some types of dye contacts.

One of the most powerful reducing stripper treatments for dye stains known is the acid solution of either titanous chloride or titanous sulphate. These are violet colored liquids, always marketed in solution form (20%) and act by changing chemically from the trivalent or titanous salt to the more highly oxidized quadrivalent or titanic equivalent. In this change, the violet color is lost, indicating when the reducing power of the solution has been expended.

For contact dye stains, make up a 1 fluid ounce per gallon solution of titanous chloride (20%) or titanous sulphate (20%). Immerse the stained articles for 15 to 30 minutes, remove, wring out and rinse thoroughly with water.

Heavy contacts require the addition of about 1 tablespoonful of oxalic acid crystals to the above bath at the start.

The treatment with titanous reducers should not be carried out in a metal container. Crockery, glass, wood or vitreous enamel should be used to prevent attack by the acid present.

Blue vat dyes which have become green in the course of bleaching with white goods processed with an indanthrene blue in manufacture, are restored to their original shade by an acid titanous chloride or sulphate treatment.

Vat dyes are normally very fast to alkalies and bleaching since their colors are developed by oxidation in the dyeing process. When, however, they have been transferred by contact, strong alkali, heat and pressure to another article or to a white adjacent area in the same garment, they are very difficult to remove. Treatment with a reducer causes temporary decoloration but the stain returns on contact with the air, after rinsing, unless the dye is actually destroyed.

The following treatment (with care) is effective for vat dye contacts:

Spot the stained area with a 10% solution of potassium dichromate. Allow to stand for 5 minutes, then spot (without rinsing) with a mixed solution of 1% oxalic acid and 2% sulphuric acid. Follow with several thorough rinses. For complete safety from possible acid attack, add a little ammonia or put the article through the regular wash.

#### Fish Oil Stains

These stains produced by fish oils such as cod liver, haliver and others in present day use as vitamin sources in diet give rise to yellow or brown stains and an unpleasant, fishy odor in goods from which they have not been completely removed.

In instances where fish oil stains persist after washing or as a precautionary measure on badly stained unwashed goods, saturation with Turkey Red Oil (sulphonated castor oil) or Kerosene-Oleic-Benzol cleaner, followed by the regular wash, will bring about removal.

For the final traces of organic coloring matter left after the oily body of some of the dark, high vitamin fish oil concentrates used in infant feeding has been removed, the peroxide-soap soak is very effective.

#### Fruit Stains

Stains from fresh fruit have greater resistance to removal from fabric than those from cooked fruit since the cooking process coagulates some of the natural fixative substances present. Consequently the summer season brings more trouble from fruit stains than the balance of the year, both because fruit is more plentifully used at that time and because a great deal of it is used uncooked. In contrast to fresh fruit, cooked fruit contains added sugar from the preserving process which aids in keeping the spots soluble and more easily removed in washing.

With cotton and linen goods, no difficulties are usually encountered in the complete removal of fruit stains by normal laundering. Silk, wool and fugitive colors, however, require special treatment:

- 1. Warm water.
- 2. Hydrogen peroxide made alkaline with ammonia.
  - 3. Rinse.
  - 4. Permanganate-oxalic.
  - 5. Thorough rinsing.

Sodium hydrosulphite and sodium sulphoxalate formaldehyde are also useful when reducing conditions are required.

Faint, brownish tannin residues from fruit are effectively treated with Pyridine-Sulphite.

#### Gentian Violet

Violet stains from this medicinal dye are treated as follows:

- 1. Soak in alcohol-acetic for 5 minutes.
  - 2. Rinse.
  - 3. Light chlorine bleach.

Old stains may leave a yellow color after this treatment. These are

removed by drying the fabric and again applying the same reagents.

#### Glue

Ordinary animal or fish glue is usually removed by normal laundering. Heavy spots may require a period of soaking in hot water followed by bleach, before washing.

Rubber cement requires treatment with a dry solvent such as gasoline, carbon tetrachloride or tri-

chlorethylene.

Cellulose nitrate cements (airplane dope, collodion, etc.) are readily removed by acetone or amyl acetate. (Banana oil.)

#### Grass Stains

Except for those which are heavily ground in, grass stains usually require only normal laundering for removal from cotton and linen. Increased bleaching for heavy stains is called for since this phase of the formula is the most effective part of removal.

On silk, wool or fugitive colors where chlorine cannot be used, the green coloring matter (chlorophyll) is removed by the use of acidulated alcohol or gasoline in which it is soluble. Sponge the dry spot with alcohol-acetic mixture or with gasoline, using no water since the green natural dye body is not water soluble.

#### Grease and Oil Stains

Ordinary grease and oil stains are readily removed by treatment with solvents such as gasoline, ether, xylol, chloroform, etc. These reagents are also effective on chewing gum, paraffin, tar and various waxes.

A very common type of resistant

stain encountered in the laundry consists of unsaponifiable grease and oil carrying finely divided pigment. These stains originate in so many ways that it is impossible to enumerate all or describe the many greases, oils and pigments composing them. Typical of these are lubricants which have picked up finely divided metal, graphite, carbon, etc., in service, tar oil and stove polishes.

In contact with textiles the greases and oils of such stains are taken into the fiber by absorption and capillary action, carrying with them the finely divided pigments, which become so embedded in the fiber that ordinary washing and solvents are ineffective. In fact, the removal of the grease carrier in this way greatly lessens the chances for complete stain removal.

In recommending a method for removal, let us say at the start that aged stains and those which have previously been set or treated to remove all carrier are not likely to be removed completely by any

method safe to the fabric. They are often quite permanent.

For these stains use the Kerosene-Oleic-Benzol treatment in conjunction with one of the colloidal detergents. The Kerosene-Oleic mixture has previously been offered as a treatment for this type of stain, but the outstanding effectiveness of these colloidally active builders as after-treatment in place of ordinary alkali gives this method a decided advantage. The addition of the small amount of benzol increases penetration and greatly extends the scope of stain solvency.

When a dry stained article is

soaked in the Kerosene-Oleic-Benzol cleaner, penetration takes place and the oily matter of the stain is dissolved, diluted and homogeneously mixed with saponifiable oleic acid. This action brings about a loosening of the pigment particles, acts as a lubricant, and envelops the particle with a readily saponifiable film. When, after allowing sufficient time to react, the article is passed without rinsing into a hot solution of one of the colloidal detergents, the stain is subjected to both physical and chemical forces. Peptization, adsorption and colloidal action take place simultaneously with saponification, with the result that the pigment is caught in an active, live emulsion which is readily washed out of the goods.

# Ichthyol Stains (Black or Gray)

Its fresh stains are removed in the regular wash.

For old hardened stains a presoftening by dipping in cresol solution is effective, before laundering.

#### Indelible Pencil Stains

Such stains as do not come out in the washing process may be loosened with acetic acid and alcohol.

### Ink Stains (a) Writing Ink

There are so many different kinds of writing ink that it is impossible to prescribe a remover that will be effective on all ink spots. The following treatments should be tried in the order listed:

- 1. Dilute bleach solution.
- 2. Dilute hydrofluoric or oxalic.

3. Permanganate-oxalic.

4. Commercial ink removers.

Stains on wool and silk should be treated with hydrogen peroxide followed by dilute hydrofluoric acid.

#### (b) Marking Ink

Some marking inks contain silver nitrate or other silver compound.

Treat the stains with bichloride of mercury and ammonium chloride solution as described under Silver Stains.

Marking ink of the aniline black type cannot always be successfully removed. Carbolic acid containing a small amount of nitrobenzol and aniline oil is often effective on fresh stains.

#### (c) Waterproof India Ink (Drawing)

Spot or immerse the dry stained fabric in carbon disulphide. Follow with regular soap and water wash.

#### Iodine Stains

When iodine is dropped on unstarched material, it makes a brown or yellow stain, but on starched material a deep blue or black. For removal, spot with 5% solution of sodium thiosulphate (hypo).

#### Iron Rust Stains

An iron rust stain is often formed after only a momentary contact of the cloth with iron, particularly if the cloth is white. If, for instance, goods are washed at home and then laid to dry over a radiator, it is no uncommon thing to find a series of rust spots wherever the cloth came in contact with exposed metal on the radiator. Treatment with oxalic acid or hydrofluoric acid with care-

ful rinsing is the most effective means of removal.

#### Removal of Rust Spots from Fibrous Materials

Twenty-five parts 65% phosphoric acid in 75 parts glycerol of 28° Bé; glycerol added to a 15% aqueous citric acid solution until the specific gravity is 17–18° Bé, phosphoric acid added to specific gravity 30° Bé.

Lacquer and Nail Polish Stains

The use of lacquers in replacing paints and varnish not only in industry but also in the household is reflected in the frequent appearance of stains from this source upon linen

and wearing apparel.

The lacquers differ widely from paints and varnish in that they do not react chemically with alkaline washing solutions as do paint and varnish. The base of the lacquers and some of the popular nail polishes is nitrocellulose which is dissolved in such solvents as amvl. butyl and propyl acetates together with a suitable pigment. Upon application, the solvent evaporates leaving the insoluble, water resistant nitrocellulose. The very best solvents or stain removers for this type of composition are, therefore, amyl acetate or acetone.

Acetone is recommended because it has a more agreeable odor and can be applied readily without discomfort to the operator. However, both acetone and amyl acetate are excellent for this work and spotting the dry fabric will prove very satisfactory in the majority of cases. These solvents should not be used on cellulose acetate fibers (celanese, etc.).

#### Leather Stains

Good washing usually removes leather stains such as are most commonly caused by friction of shoe linings on light colored stockings. However, if any amount of tannin compound is present, it may leave a stain which can sometimes be removed by treatment with potassium permanganate. Treatment with pyridine-sulphite is also highly recommended where tannin is encountered.

Leather Grease Remover	
Carbon Tetrachloride	79
Petroleum Ether	15
Amyl Alcohol, Tertiary	4
Diglycol Laurate	1
Butyl "Cellosolve"	1

#### Lime Soap Stains

Treatment of the stained articles with strong, boiling hot solution of acetic acid followed, after a rinse, with a strong solution of one of the colloidal detergents will prove very effective in the removal of these stains.

For spotting, gasoline or carbon tetrachloride is recommended. Treatment with a strong solution of sodium metaphosphate is also effective. Oleo Calcaire (olive oil and lime water) and other insoluble soap ointments should also be treated as above.

#### Medicine Stains

In general treat with bleach or with potassium permanganate solution, followed by oxalic acid and thorough rinsing.

There are, of course, many staining substances which are classified

as medicines, e.g., Argyrol, Mercurochrome, iodine, etc. The treatment for each is given elsewhere in this discussion. Wherever medicines are in use the precaution of rinsing the goods in warm or cool water after staining is highly advisable.

#### Mercurochrome Stains

The red dye stain can be removed from cotton through oxidation. When the stain is fresh, bleach will usually bring about removal. When old and set, it is more resistant and the following method is recommended:

Work the stained articles in a 2% solution of potassium permanganate at 100°-130° F. for 5 minutes; rinse and then work in a 2% solution of oxalic acid at 120°-130° F. until all brown coloration is gone; rinse thoroughly.

This treatment will remove all ordinary Mercurochrome stains and can be repeated in special cases

where found necessary.

Mercurochrome stain on animal fibers is subject to reactions which make it permanent. Substantial lightening of stain, if not complete removal, can be obtained by the use of acidified alcohol (50:50 alcohol and acetic). For cleaning up stains on hospital equipment a mixture of 90% alcohol and 10% sulphuric acid is generally employed, but this, of course, should never be used on fabrics.

Methylene Blue Stains

Methylene Blue is a basic dyestuff used in commercial and pharmaceutical preparations. Alcohol is usually effective on fresh stains. Py-

ridine-sulphite treatment is recommended for old stains.

#### Mildew Stains

Mildew is due to micro-organisms commonly known as fungi, which have the property of attacking textile fibers and producing various colored stains. They grow rapidly when the goods are in a damp condition, and especially when the articles contain soil which serves as food. It has recently been discovered that improperly operated air conditioning in drygoods stores during summer months, resulting in excessive humidity, causes extensive amounts of mildew on new goods. Mildew stains respond to oxidizing agents, and for their practical removal there is no more efficient reagent than bleach. In the treatment of mildew stains in the laundry, a formula can be devised which will remove them in a regular wash, but to treat an entire load with bleach for the purpose of removing stains from a comparatively small percentage of the work would be very poor practice. It is recommended that the mildewed articles be culled out and given a special stain removing treatment, when a quantity sufficient to make a load is obtained. For treatment a short bleach suds or plain bleach, followed by sufficient rinses, will serve to remove the stains.

As mentioned above, there is no washing formula which can be used to remove mildew stains without the use of bleach, and from the standpoint of economy, as well as the life of the linens, we do not recommend that attempts be made to remove resistant deep-seated stains in the regular wash.

#### Mud Stains

Mud stains constitute a very difficult type of stain since, for the most part, the staining material is chemically inert and must be broken up and suspended by colloidal action. Plenty of mechanical washing action in the presence of soap and one of the colloidal detergents, plus ironremoving sour, is the best method of attack.

#### Oil Stains

For the removal of the common oil stains see the treatments described under Grease and Oil Stains.

The preparations used in hair treatment which contain an appreciable percentage of crude (mineral) oil give rise to a very conspicuous resistant brown stain. These stains are largely found on bed linen and especially pillow cases. The ordinary oil solvents such as gasoline and carbon tetrachloride are effective before washing, but the residual set stains after laundering are practically impossible to remove completely.

The previously mentioned Kerosene-Oleic-Benzol cleaner is usually successful, but not always positive.

#### Ointment Stains

Ointment is often water repellent, which accounts for the difficulty in removing stains in the ordinary washing process. To overcome this it is necessary to remove the greasy material as outlined under Grease and Oil Stains and then follow with the recommended treatment for the residual stain.

#### Paint Stains

Oil paint stains generally consist of a finely divided pigment held in the fiber by vegetable oil, varnish gums and turpentine. The hardening or drying of both paint and varnish is due to oxidation of the oil, which converts it to a solid state, thus holding the pigment of the paint or the gum of the varnish firmly within the fibers, and renders the removal of old stains a difficult job.

Light paint stains may be removed by the ordinary washing formula used for cotton and linen goods. Colloidal detergents highly effective on oxidized oil. When the stains are on delicate goods, the use of special solvents suggested for automobile grease and road tar stains is necessary. A special treatment may also be required if the paint stains are old and have been thoroughly hardened in the fiber. Castor oil containing a small amount of strong acetic acid is valuable in spotting. Oftentimes aniline followed by removal with alcohol is also excellent. (See Lacquer.)

#### Perspiration Stains

The composition of perspiration has never been definitely determined, one of the principal reasons being that it varies in different individuals and also under conditions of exercise and repose.

Its reaction from most parts of the body is acid, while as a rule it is alkaline in the armpits. Organic acids, inorganic salts such as sodium and potassium chloride, phosphates, small amounts of iron and albumin are invariably present.

It has a peculiar and destruc-

tive action on many dyes. If a perspiration stain is fresh it will largely be removed in the ordinary washing process. On white goods, a vellowish tinge sometimes remains (gilt edges on collars), which is removed by reducing in acid solution as in oxalic acid souring. The older a stain is the more fixed it becomes and consequently the more difficult to remove. It is next to impossible to restore color in a garment in which the dve has been loosened or changed chemically by perspiration. A salt solution acidified with formic acid is often useful in spotting delicate fabrics.

#### Picric Acid Stains

Picric acid dyes cotton a permanent yellow and produces stains which are exceptionally fast to washing. For removal, immerse the dry stained fabric in a 50:50 mixture of alcohol and ammonia water (regular household 5%).

#### Printing Ink Stains

These inks commonly consist of finely divided carbon suspended in oils with rosin, turpentine, etc. They virtually constitute a paint or varnish. An extra thorough washing will generally prove effective. For spotting, use a mixture of equal parts of alcohol, amyl acetate, benzol and acetone. This formula should not be used on celanese, etc. (See Carbon Stains.)

#### Prontosil Stains

This stain is a bright red dye commonly used in medicine. It is generally removed in the regular laundry process, but if a slight residual stain persists it can be entirely cleared up with a light hypochlorite bleach.

#### Red Clays Stains

Red clays produce a very intensive stain because of their high iron content. Treat as recommended under Mud Stains and follow with hydrofluoric or oxalic for iron removal.

#### Road Tar Stains

Unfortunately, road tar stains are not usually noticed before they have been wet with water, or in other words, before they have passed through the laundering process. An ordinary washing formula has but little effect upon them. The use of special solutions such as carbon tetrachloride, carbon bisulphide, gasoline, turpentine, or chloroform is required. (See Grease and Oil Stains.)

#### Tar Remover

For use in removing tar from clothes and autos.

Benzol	50
Carbon Bisulphide	10
Carbon Tetrachloride	40

Toluol can be used in place of benzol. Use methyl salicylate as perfume.

#### Rouge Stains

Rouge stains can be most readily overcome by removing the carrier (binder) with a suitable solvent before washing with soap and alkali. The carriers sometimes used in rouge compounds are oil and grease. Carbon tetrachloride is an excellent solvent for such carriers. In persistent cases acetone may be more effective. The coloring matter in rouge is usually iron oxide or dye

such as carmine. Washing directly with soap and alkali sets these in the fabric. There is one type of cosmetic color known as carmine red, which is very resistant, and for complete removal requires severe rubbing, after moistening, with amyl alcohol. The common lipstick stains do not offer difficulty unless set by age or previous treatment. The iron pigment yields to the common rust removing sours in concentrated form, and the basic dyes offer no difficulty to solution in alcohol after the binder is removed.

#### Scarlet Red Stains

This stain is a bright red medicinal dye and therefore frequently found on hospital work. The color is removed or considerably reduced in the regular wash. It readily responds to acetone when heavy stains are present.

#### Scorch Stains

It is easier to remove scorch from cotton and linen than from wool and silk. In a great many cases surface stains can be quickly removed, especially on white goods, by treatment with ammoniacal hydrogen peroxide, which procedure follows: Dampen a small cloth with commercial 3% hydrogen peroxide to which a few drops of ammonia have been added and place it over the scorch stain. Cover with a dry piece of bleached muslin and iron with a medium hot iron. Repeat if necessary. For heavy stains the only helpful treatment is repeated washing with adequate bleaching, as no procedure can be given which would remove heavy scorch stains successfully. To try to remove heavy scorch stains is usually a needless waste of time.

Shoe Polish Stains

Treat stain with gasoline and follow with alcohol-acetic mixture.

#### Silver Stains

Silver stains which usually show up brown or black do not respond to washing or the common stain removers. They usually develop from colorless silver salts, such as silver nitrate, which are not noticed until the damage is done.

For the removal of silver stains the bichloride of mercury and ammonium chloride treatment, which is described under Argyrol, is highly recommended.

#### Smoke Stains

Smoke stains are insoluble, consisting chiefly of carbon and generally accompanied by creosote, a substance which produces a yellow stain and has the characteristic odor of smoke. The carbon in most cases can be emulsified and washed away. In order to remove the yellow creosote stain, the material is treated for a reasonable length of time with cresol, the excess being saponified by the alkali detergent in the washing process.

#### Tannin Stains

Tannin stains are among the most resistant encountered in the laundry.

Leather, tobacco, tea, medicine, Coca-Cola, fruit juices, coffee, liquor, ginger ale and an innumerable quantity of common household preparations contain tannin in greater or lesser amounts. Articles coming in contact with tannin-bearing substances should be rinsed as soon as possible in order to avoid permanent stains.

Tannin reacts with metals producing insoluble compounds. Iron reacts to form black tannin ink, which at one time was a very common source of writing fluid.

Tannin is used extensively as a mordant for cotton in dyeing with basic dyestuffs. Because of its mordant properties, some laundry blues take to tannin stains producing blue spots and streaks which impair quality.

A peculiar characteristic of these stains is their invisibility when first formed, with a gradual development, depending upon atmospheric conditions and age.

Fresh and moderately aged stains are most readily removed by the pyridine-sulphite treatment. Pass the stained article into a hot 5% solution of pyridine; remove and pass directly into a hot 5% solution of sodium hydrosulphite. Alternate from one solution to the other until the stains are completely removed.

Old set tannin stains are very apt to prove permanent.

#### Tea Stains

The brown coloring matter in tea is not difficult to remove when fresh, but becomes very persistent on standing. Stains from tea to which milk or cream has been added are usually more easily removed than those from clear tea. Potassium permanganate and ordinary chlorine bleach are effective on tea stains that have resisted ordinary washing. Residual tannin stains should be given the pyridine-sulphite treatment.

#### Verdigris Stains

The blue-green tarnish on copper, brass, and bronze, consisting of ba-

sic copper carbonate, is commonly known as verdigris. Stains that are not removed by the ordinary washing process can be dissolved by using a dilute acid such as acetic.

The green deposit which develops on brass and bronze washwheels is not, chemically speaking, verdigris, but a complex conglomeration of metallic soaps and salts. Nevertheless, all green-colored deposits on copper-bearing metals are commonly referred to as verdigris, and the term as used is generally so understood.

Soap, or more accurately soap fatty acids, give green, insoluble copper soaps, which adhere firmly to metal parts.

Regardless of the care exercised, some insoluble lime, magnesium or other metallic soaps are formed in washing. Being insoluble and sticky, they have a tendency to cling to surfaces. When goods are soured, fatty acid is liberated from these soaps, which, in turn, is set free to react with copper on neutralization.

Sours, especially acetic and oxalic, rapidly form verdigris, and most of the alkalies, such as silicates, carbonates and phosphates, yield salts which are green in color.

To prevent staining by contact with verdigris in washing, the machine should be periodically cleaned. An acid bath of sulphuric acid, or less preferably hydrochloric, is highly recommended. In cleaning, run two or three inches of water in the machine; add about one quart of sulphuric acid, depending upon the wheel size; start the machine and allow to run until all deposit is removed. An old broom held against the revolving cylinder greatly facili-

tates removal. After cleaning, the machine should be rinsed; given an alkali bath and rinsed again.

The usual precautions should be taken in adding concentrated sulphuric acid, i.e., run the acid very slowly into the water.

#### Water Spots

In sponging some goods, notably silk and wool, an irregular ring or spot usually remains. Under such circumstances it may be necessary to dampen the entire material evenly and press while still damp. Sponging the surface with alcohol is also an effective treatment. A moist chamois is useful in drying the dampened goods.

#### Yellow Stains

The term "yellow stain" is often used too broadly. The "yellow" may be due to unrinsed alkali or soap; it may be rust, it may be oxycellulose, it may be a contact stain from a loose dye.

In general, such of these stains as do not identify themselves readily as rust, alkali or soap, will usually respond to a strong reducing bleach. Unless the reducing action is quite intensive, however, there is a possibility of the stain reappearing through atmospheric oxidation. Potassium permanganate followed by oxalic acid is usually very effective.

Spot Remover	
Carbon Tetrachloride	25
White Gasoline	25
Solvent Soap (Diglycol	
Laurate)	50

#### Cleaners' Spotting Mixture Formula No. 1

Aerosol MA	1	lb.
Toluol	3	qt.
Perchlorethylene or		
Toluol	1	qt.
Water	$\frac{1}{2}$	pt.
No. 2		_
Aerosol OT (100%)	1	lb.
Stoddard Solvent	2	gal.
Water	3	pt.

#### Grease Spot Remover

A paste of benzinized magnesia is suitable for this purpose, and is prepared by mixing calcined magnesia with just sufficient pure benzine so as to moisten it without being pasty. It should be just wet enough so that when the mass is pressed between the fingers, a small quantity of liquid benzine is squeezed out. In this state, it forms a crumbly mass which is kept for use in a well-corked, somewhat wide-mouthed, glass bottle. Apply by spreading the paste quite thickly over the stains and rub it thoroughly to and fro with the tip of the finger. Brush off the small lumps of earthy matter thus formed, lay on more of the paste, allowing it to remain until the benzine has entirely evaporated, and then brush off the adhering particles of magnesia.

#### Laundry Bluing Tablets

Make a thick paste with 6 ounces of ultramarine, 4 ounces of sodium carbonate, and 1 ounce of glucose. Roll into sheets and cut into tablets.

# Laundry Bleaching Cotton, Linen and Other Vegetable Fibers

Bath 1. Permanganate (2 oz. potassium permanganate per gallon of water).

Bath 2. Oxalic Acid (2 oz. oxalic acid crystals per gallon of water).

Immerse the stained articles in Bath 1 at a temperature of 120° F. until thoroughly saturated (1 to 2 minutes). Remove and rinse well.

Transfer to Bath 2 at 140–150° F. and work until all traces of brown coloration are removed. Add more oxalic acid to Bath 2 if the goods do not clear in 2 minutes or so. Rinse thoroughly with hot water to insure removal of all traces of oxalic acid.

## Wool, Silk and Other Animal Fibers

Wool, silk and other animal fibers respond better to acid permanganate and in their case, the procedure above is modified only by the addition of a small amount of sulphuric acid to Bath 1. Otherwise the treatment is exactly the same.

Colored goods should not receive the permanganate-oxalic treatment without a preliminary test with it at an inconspicuous point to determine whether or not the dye is fast to the reagents.

Many contact types of dye stains and other organic color residues which respond to oxidizing measures are very effectively stripped by the permanganate-oxalic treatment.

In working with hydrogen peroxide for spotting or small scale bleaching where an alkaline builder is not required, the drugstore material (3% or 10 volume) which may have been made slightly acid in

manufacture to hold its strength on the shelf, should be rendered alkaline with ammonia water. This neutralizes the acid, removing a source of later danger to the fabric by acid attack and liberates the nascent oxygen more rapidly for bleaching.

Concentrated hydrogen peroxide (30% or 100 volume) should be diluted with water to 3% strength before use on fabric and should be neutralized as above if acid is present.

Permanganate-hydrosulphite interchangeable with permanganate-oxalic, the oxidizing stripper. The replacement of the oxalic acid by sodium hydrosulphite results in a quicker discharge of the brown manganese hydrate formed and this feature is of advantage in spotting work. A further advantage of this method over permanganate-oxalic in some instances, is that sodium hydrosulphite itself is an active reducing stripper and the swing from active oxidizing conditions in the presence of permanganate to active sulphurous reducing conditions in the presence of the hydrosulphite, often results in better stripping of a mixed organic stain.

Quantities and procedure are the same as for permanganate-oxalic except that the sodium hydrosulphite bath must be made with cold water.

#### Kerosene-Oleic Acid-Benzol Cleaner

This mixture is composed of:
Kerosene 1 gal.
Oleic Acid (Red Oil) 4 oz.
Benzol 4 oz.
Its use is in removing deep seated

grease stains and others of similar type as described under the heading Grease and Oil Stains.

Dye Stain Solvent

A mixture of 9 parts alcohol and 1 part glacial acetic acid. Useful for some types of dye stains. Example: methyl violet.

Laundry Starch	
Wheat Starch	1
Corn Starch	<b>2</b>

Laundry Gloss

Gloss preparations to be used with starch are widely employed in the laundry, not only to lend a fine smooth finish, but also to prevent scorching and sticking of the iron. The following is a typical formula:

Acacia, Gum	1 oz.
Borax	2 oz.
Glycerin	1 oz.
Water	32 oz.

Soak the acacia in the water for six hours, add the borax, then heat to a boil and add the glycerin, let cool and strain. To use, add two ounces of this preparation to 3 quarts of the usual starch solution.

	Textile Soap	
<b>(1)</b>	Olive Oil Foots	600
	Potash Lye (20° Bé)	660
(2)	Corn Oil	800
	Rosin	200
	Potash Lye (27° Bé)	790
	Water	340
T	ha aila ara hastad to 1000	T73

The oils are heated to 190° F. and then the potash lye is added in the crutcher and the mixing is continued until the soap begins to bunch. When this occurs the soap is run directly into barrels, which should be kept in a warm place for a day or two.

The saponification process proceeds in the barrels.

	-
Wool Thrower's	Soap
Olive Oil Foots	12
Corn Oil	46
House Grease	20
Soda Lye (36° Bé)	3
Potassium Carbonate	
(Dry)	$5\frac{3}{4}$
Potassium Hydrate	, ,
(Solid)	23

Rayon Scourings Formula No. 1 Box Scouring

Sodium Metasilicate 20 lb. Soap, Low Titer 10 lb. Water 1000 gal.

No. 2

Continuous Scouring

The scouring section is charged at the rate of 2 lb. of sodium metasilicate and 1 lb. of low titer soap per 100 gallons of water. Additions are made so that the total alkalinity never drops below 0.04% as Na<sub>2</sub>O. The pH (alkali pressure) is maintained above 10.2 at all times; with regenerated cellulose rayons, a pH above 11 is economical and gives rapid scouring.

No. 3		
Jig Scouring		
Sodium Metasilicate	4	lb.
Soap, Low Titer	2	lb.
Water	50	gal.
No. 4		
Sodium Metasilicate	1	lb.
Soan, Low Titer	. 2	lh

Sodium Pyrophosphate 1 lb. Water 100 gal.

Textile Mill Stain Removal Oil and grease stains are perhaps the most prolific, due in some cases to careless or over-liberal use of the oil can, with consequent dropping upon goods in course of processing; and in others to inefficient machinery. Dye stains are another fruitful source of trouble, as, indeed, are also many of the chemicals employed in modern practice.

The labor element is responsible for introducing certain of the stains with which the technician has to contend; tobacco, gum and foodstuffs can cause a great deal of worry.

Then, again, most mills have their own constructional departments or, at any rate, carry stocks of such raw materials as paint, tar, asphalt and creosote, thus introducing a further stain hazard.

As these stains frequently occur on delicate fabrics, which require very careful treatment, it is disastrous to try various methods haphazardly in the hope that one will prove successful. The best method of treatment is to have a clear jar, basin or other receptacle ready, and to stretch the fabric tightly over it, and then to pour the solutions made up as directed through the material into the basin.

In the case, however, of such stains as oil, tar, grease and asphalt, it is more efficacious to place a pad of blotting paper or other absorbent material beneath the stain and to apply the cleaning fluid recommended by means of a small tuft of cotton wool or a pad of fabric.

The successful removal of stains is largely dependent on the correct method of working. The aim should be to work from the outer edge of the stain towards the center, as this lessens the risk of leaving a ring.

It is better to dab the solution on, so as to carry the stain through into the blotting paper, and not to rub, as any friction, especially on delicate fabrics, is liable to leave a slight roughening of the surface after the discoloration has been removed.

Grass stains may be treated with hot methylated spirits or with hot glycerin followed by methylated spirits. Coffee stains can be removed by a treatment with a solution of potassium permanganate, followed by a slightly acidulated solution of hydrogen peroxide. Glycerin is also a useful reagent for coffee spots, and is best applied with a small sponge or a pad of cotton wool. The glycerin is more effective when used hot, and the fabric should be left for a few minutes saturated with the liquid, and then washed out with either methylated spirits or water. This method is also useful in the case of chocolate and cocoa stains.

Perspiration stains are best removed with warm water and ammonia when the fabric is wool or silk. For cotton or rayon a treatment with a solution of one part of sodium hypochlorite to four parts of warm water is better. This latter process must be followed by a thorough rinsing, first in clear water and then in acidulated water, and must not be used for any materials made of wool or real silk.

Scorch marks may be treated by damping the place and then exposing it to the sun. Two other methods recommended are:

(1) Treat with hydrogen peroxide acidified with an addition of sulphuric acid.

(2) Bleach with potassium permanganate, and then rinse in weak

sodium bisulphate.

Stains caused by soot or lampblack will be found to yield to a treatment with some organic solvent such as ether, chloroform acetone or carbon tetrachloride, followed by washing with paraffin oil and then again in soapy water. Glue stains can be dealt with by means of hot methylated spirits or by a weak solution of soap and ammonia.

Stains caused by pitch, tar and asphalt should be treated with organic solvents as listed under soot stains. Turpentine and lard are also effective. Another method which has been recommended especially for the removal of tar stains from silk is to rub butter on the marks, and allow to remain some time, and then to go over them again with benzene.

The removal of paint marks is generally attended with considerable difficulty, especially in the case of marks of long standing. Here again the organic solvents are of great value. If the stains are not dry they may be removed with turpentine and benzene; a strong solution of ammonia is sometimes effective: while an emulsion of turpentine and ammonia is often advocated for this purpose, although this should not be employed for silk. Varnish stains may be treated in the same manner, although the presence of gums and resins makes their eradication even more difficult.

Ink stains frequently prove difficult, if not impossible, to remove by ordinary laundering methods; yet they yield fairly easily to proper treatment. The most common ink stains are, of course, those caused by ordinary writing inks. A dilute warm solution of oxalic acid is generally successful with blue-black inks, but care must be taken not to leave this reagent in the material; it is also liable to remove the color from dyed fabrics. Another method is to treat with a dilute solution of potassium permanganate, and to follow this with a slightly acidified solution of peroxide of hydrogen, as was employed for coffee stains.

A third method is to lay the stained portion on a saucer, moisten with hot water, then to rub in salts of lemon until the stains disappear and finally rinse thoroughly.

Red inks can sometimes be removed by the use of methylated spirits slightly acidified with acetic acid. If this method fails, a warm solution of sodium hydrosulphite will remove the stain. This reagent, however, will decolorize most dyed goods, and should therefore be applied with caution.

Printers' ink stains are less commonly met with, which is fortunate, as they frequently prove troublesome. One course is to rub them with lard, and a second to soak in turpentine, and then to wash them out with methylated spirits. Such organic solvents as chloroform, acetone and carbon tetrachloride are also useful.

Stains due to Indian inks are often impossible to remove completely. Three solvents which are sometimes successful are:

- (1) Hot methylated spirits.
- (2) Glacial acetic acid.
- (3) Chloroform or carbon tetrachloride.

Marking inks are of two types: One is made from an organic dye. (Goods marked with this type have to be washed before ironing, to fix the color.) These are practically impossible to remove when fixed.

The second is the silver nitrate type, where the goods have to be ironed before washing to fix. A repeated treatment with a weak solution of chloride of lime, followed by washing in ammonia water, will often remove these stains. Corrosive sublimate and nitrobenzene are two further reagents which have been recommended.

Blood stains may be removed from silk by the use of strong borax water or by soaking repeatedly with chloroform or hydrogen peroxide. Many medicine stains can be dissolved out in alcohol or methylated spirits. Iodine marks are best treated with ammoniated alcohol or ammonia or by sodium hydrosulphite. Picric acid leaves yellow stains on silk, wool and acetate silk, which can best be removed with a paste of magnesium or lithium carbonate. Ordinary laundering methods will remove these stains from cotton and rayons other than acetate.

A mixture of	
Aniline Oil	1
Powdered Soap	1
Water	10

is advised for the removal of vaseline marks from fabrics. The stained portion of the goods should be allowed to remain in the solution for some time, and then be well washed with water.

Acid stains should be well washed and then neutralized with an alkali, a warm solution of soap and ammonia being particularly effective. Alkali stains, after a preliminary wash, should be immersed in dilute acid, such as acetic or formic.

Rust stains are of frequent occurrence, and can be dealt with by means of a mixture of one part of potassium bioxalate added to forty-five parts of water and one part of glycerine. A well-known remedy is to moisten the spot with lemon juice and salt and expose it to the sun. One or two applications are most successful. This method is often advocated for ink stains.

Grease stains can be dealt with by the use of organic solvents, such as petrol, benzene or carbon tetrachloride, or by covering with blotting paper and ironing with a hot iron. Black grease, however, such as is formed on axles and machinery, is more difficult to remove, as it contains minute particles of iron, removed by friction, and when the grease itself has been removed these iron particles leave a vellowishbrown stain. It is best in these cases to remove the grease as above, and then to treat as for rust stains or by the use of a warm solution of weak oxalic acid.

Color stains caused by dyestuffs generally require bleaching with one of the usual agents—hypochlorites, hydrogen peroxide or a permanganate—for their removal, although many basic dyes will yield to a treatment with ammonia and methylated alcohol.

Before applying these cleaning methods it is safer to try them on a spare scrap of material, if one is available; failing this, use some corner of the fabric which will not show. In this way one can see if the reagent is going to decolorize the fabric or have any other harmful action, as it is not possible to foretell in all cases what effect a given reagent will have on the dyestuffs which have been used.

Removal of Stains from Fabrics

Fabrics used in our daily life are made from materials such as cotton, silk, wool and artificial silk. These fabrics often get stained with substances such as butter, vegetable or animal oil, ghee, fats, tea, coffee, fruit juice, wine, beer, ink, iron, rust, iodine, paint, varnish, tar, blood, mildew, perfume, etc. These stains can be removed without damaging the fabric. But there are some stains which cannot be removed and are, therefore, better left alone. Ordinary stains such as those stated above can be removed by the application of the correct reagent, and this in its turn depends upon ascertaining the substance causing the stain and the material from which the fabric is made. If the fabric is dved it is also necessary to know, in order to remove the stain without removing the color of the dyed fabric, whether the dye used is fast or fugitive. Certain reagents which can be safely used for removing a particular stain from a cotton fabric, if applied on silk or wool, will damage the cloth. Then again it must be borne in mind that fresh stains can be more easily removed than old stains and, therefore, efforts to remove the stain should be made as early as possible. In any case, the cloth should be washed with hot soap solution immediately on discovering the stain. Several stains can be removed easily by the mere application of warm soap solution, or by holding the cloth tight on an empty vessel and pouring boiling hot water from a kettle on the stained spot.

If the cause of the stain is not known and cannot be identified. then much difficulty will be experienced in selecting the suitable reagent for removing the stain. In such cases, it is necessary to carry out several trials with different reagents which are suitable for the nature of the fabric. If the material from which the fabric is made is not known, it is necessary to conduct a simple test. Some fibers may be taken out from the fabric and held in the hand and the gentle flame of a match applied to them. Cotton and artificial silk will burn rapidly, giving a smell of burning paper and leaving a little ash. Wool and silk will, on the other hand, burn rather slowly, emitting a disagreeable smell of burning feather, and leave a black bead at the end. If the fabric is dyed, trials will have to be carried out with different reagents or hot soap solution on a corner of the fabric to ascertain whether the color is fast or fugitive. In some cases, it will be found that the stain cannot be removed without removing the color of the cloth at the same time.

Stains are removed by different methods of treatment such as solvent, chemical and absorption.

#### Solvent Method

In this method the stain is dissolved so that it may pass from the fabric on to a blotting paper pad placed underneath the fabric. The stain is absorbed by the blotting paper and the solvent in the fabric evaporates. Before proceeding to remove the stain, the portion of the fabric which is stained should be

washed with hot Sunlight soap solution in preferably a solution of Igepon T. Soap. The fabric should then be dried.

Now a pad, consisting of a few sheets of blotting paper, is placed on the table and the cloth containing the stain laid on the top of the blotting paper. A small quantity of the reagent is poured in a small cup. A clean cotton muslin rag is then dipped in the reagent, the excess quantity squeezed and the rag pressed gently on the stain from the outer side of the stain to the center. The solvent will carry the stain into the blotting paper. At every application of the solvent, a clean rag and a fresh blotting paper should be used. The excessive use of reagent at every application should be avoided, in order to prevent the formation of a ring around the stain. The portion of the cloth stained may finally be washed in cold water. In removing stains, the rag dipped in the reagent should be pressed gently but not rubbed on the fabric, as it will cause the dissolved stain to spread out on the fabric. In some cases more than one solvent will have to be applied in succession in order to remove the stain. As many of the solvents are inflammable, they should be kept at a safe distance from any flame.

#### Chemical Method

In this method, the stain is decomposed or bleached and the chemical that remains in the fabric is removed by washing. Before proceeding to remove the stain, the portion of the fabric which is stained should be washed with hot Sunlight soap solution or preferably a solution of Igepon T. Soap. The solution

of the chemicals is first poured in a small cup. A white cloth is placed on a table, and the fabric containing the stain laid on the cloth. A clean cotton muslin rag is then dipped in the solution and the rag pressed gently on the stain. After the stain has been removed, the fabric is washed in cold water to remove the chemical.

Absorption Method

This method is applicable only in the case of grease and lubricating oil stains. As magnesium carbonate has the property of absorbing oil and grease, it is rubbed on the stain and left until the oil is absorbed, and then brushed off. For removing old stains, powdered magnesium carbonate is mixed with benzol (not petrol) and then the paste is rubbed on the spot and allowed to dry and brushed off. This is useful on heavy garments such as coats.

Hot Application

This method is applicable in the case of stain produced by rain-water on silk fabrics. A white cloth is laid on the table, and the stained fabric is placed over it. A wet cloth is then placed on the stained cloth, and a dry cloth is placed over it. A hot iron is pressed on the cloth in order to remove the stain.

I. Nature of stain.—Milk, butter, ghee, vegetable and animal oils, fats.

Class of fabric—Cotton, silk, wool and artificial silk.

Reagent to be used—Carbon tetrachloride.

Method to be adopted—Solvent.

II. Nature of stain.—Tea, coffee, cocoa, chocolate, fruit juice, wine and beer. (a) Class of fabrie—White cotton and artificial silk.

Reagent to be used—Sodium hypochlorite solution (1 oz. of sodium hypochlorite in 10 oz. cold water).

Method adopted—Chemical.

(b) Class of fabric—White silk, wool and colored cotton and colored artificial silk.

Reagents to be used—Ammonia solution (1 oz. ammonia in 5 oz. water) followed by hydrogen peroxide (12 volumes strength).

(c) Class of fabric—Colored silk and wool.

Reagents to be used—Ammonia solution (1 oz. ammonia in 5 oz. water).

Method adopted—Chemical.

III. Nature of stain.—Ink and iron rust.

(a) Class of fabric—White cotton and artificial silk.

Reagents to be used—Hot oxalic acid solution (½ oz. oxalic acid in 16 oz. water) followed by sodium hypochlorite solution (1 oz. in 10 oz. water).

Method to be adopted—Chemical.

(b) Class of fabric—Colored cotton and artificial silk.

Reagent to be used—Hydrochloric acid (1 oz. acid in 15 oz. water) followed by washing and then treatment with ammonia (1 oz. ammonia in 5 oz. water).

Method adopted—Chemical.

(c) Class of fabric—White silk and wool.

Reagent to be used.—Warm oxalic acid solution (½ oz. oxalic acid in 16 oz. water) followed by washing and then treatment with ammonia (1 oz. ammonia in 5 oz. water).

Method adopted—Chemical.

IV. Nature of stain.—Iodine.

Class of fabric—Cotton, silk, wool and artificial silk.

Reagent to be used—Sodium thisulphate solution (1 oz. thisulphate in 5 oz. water).

Method adopted—Chemical.

V. Nature of stain.—Grease, tar and wax.

Class of fabric—Cotton, silk, wool and artificial silk.

Reagent to be used—Cocoanut oil followed by hot soap washing and then treatment with carbon tetrachloride.

Method adopted—Solvent.

VI. Nature of stain.—Paint and varnish.

Class of fabric—Cotton, silk, wool and artificial silk.

Reagent to be used—(1) Methylated spirit followed by turpentine and soap washing finally after drying.

(2) Carbon tetrachloride.

(3) Mixture of acetone and amyl acetate (1 oz. of acetone and 1 oz. of amyl acetate).

VII. Nature of stain.—Blood.

(a) Class of fabric—White cotton and artificial silk.

Reagent to be used—Sodium hypochlorite solution (1 oz. in 10 oz. water).

Method adopted—Chemical.

(b) Class of fabric—Wool and silk and colored cotton and artificial silk.

Reagents to be used—Acetic acid (2 oz. concentrated acetic acid ½ oz. common salt in 19 oz. water) followed by washing and treatment with ammonia (1 oz. ammonia in 5 oz. water).

Method adopted—Chemical.

VIII. Nature of stain.—Mildew. Class of fabric—Cotton, silk, wool and artificial silk.

Reagent to be used—Hydrochloric acid (1 oz. in 15 oz. water) followed by wash and treatment with hydrogen peroxide (12 volumes strength).

Method adopted—Chemical.

IX. Nature of stain.—Perfume.

Class of fabric—Cotton, silk, wool and artificial silk.

Reagents to be used—Ammonia (1 oz. in 5 oz. water) and oxalic acid solution (½ oz. oxalic acid in 16 oz. water) alternately.

Method adopted—Chemical.

X. Nature of stain.—Perspiration.
Class of fabric—Cotton, silk,
wool and artificial silk.

Reagent to be used—Hydrogen peroxide (12 volumes strength).

Method adopted—Chemical.

Method of preparing hypochlorite solution:

Take 1½ oz. of soda ash and dissolve it in 5 oz. of cold water. Then take 2 oz. of bleaching powder (containing 35% available chlorine) and dissolve it in 15 oz. of cold water. Mix the two solutions, stir and leave it undisturbed for 20 minutes. The clear solution is sodium hypochlorite and this should be poured into another vessel without disturbing the sediment. As the sodium hypochlorite solution is not stable, it should be prepared fresh every time.

The following materials may be stocked for removal of stains: Methylated spirit, acetone, amyl acetate, carbon tetrachloride, turpentine, cocoanut oil, soap, soda ash, liquor ammonia, hydrogen peroxide (12 volumes), bleaching powder, acetic acid (strong), oxalic acid

crystals, hydrochloric acid (strong), sodium thiosulphate.

Textile Rust Remover Dutch Patent 50,110	•
Phosphorie Acid (65%)	25
Glycerin (28° Bé)	75
Rug Cleaner	
Cocoanut Oil Soap	12.0
Ammonia (28%)	2.8
Glycerin	7.9
Water	77.3

	_	
Cloth Top Shoe Cl	ean	er
Trisodium Phosphate	$^2$	oz.
Borax	2	oz.
Diglycol Stearate	1	oz.
Sulfatate (Wetting		
Agent)	1	∕2 oz.
~~~		_

Water, To make 1 gal.
Warm and mix to dissolve. Apply with a sponge or medium-stiff brush.

Dry Cleaning Leather Gloves The best, i.e., cleanest, gloves are treated with dry cleaning solvent only and the badly soiled goods in solvent plus dry soap. For lightly soiled gloves the following compound is used:

Stock Solution
Cocoanut Oil 40
Castor Oil 20
Neatsfoot Oil 20
Olive Oil 20

Three parts of Stoddard's solvent is added to one part of the above stock solution and 70 to 80 pairs are processed in 10 gallons in an ordinary brushing machine for 35 to 40 minutes. After machining the gloves are hydro-extracted and then dried at 100° F.

In the case of badly soiled gloves

1½ gallons of dry soap are added to
40 gallons of solvent, usually white
spirit or Stoddard's solvent. The fin-
gers of particularly badly soiled
gloves, usually due to sweat marks,
are first soaked for 1/2 hour in a neat
wet soap made up as follows:

To 1 gallon of strong oil bath (compound) is added ½ gallon wet soap, ½ pint water and 1½ pints

butyl "cellosolve."

They are then cleaned in the usual way in the compound. These soiled grades, after cleaning, are reworked in white spirit for 30 minutes, extracted and then further reworked for five minutes in a solution containing:

Castor Oil 12½ oz.

Neatsfoot Oil 3½ lb.

made up with 5 gallons white spirit.

In summer an addition of 12½ oz.

beeswax is added to the above.

They are then extracted, "knocked out" and dried, paired and sorted.

Dishwashing Compounds (Hand Washing)	
Formula No. 1	
Trisodium Phosphate	30
Tetrasodium Pyrophosphate	60
Borax	10
No. 2	
Trisodium Phosphate	88
Soap, 92% Anhydrous	2
Borax	10
No. 3	
Sodium Carbonate	25
Sodium Bicarbonate	35
Tetrasodium Pyrophosphate	20
Trisodium Phosphate	
(Monohydrated)	20
Trisodium Phosphate	10
Borax	8
Soap, Anhydrous	2

No. 4	
Sodium Hydroxide	3
Sodium Carbonate	27
Sodium Bicarbonate	20
Trisodium Phosphate	40
Soap	8
Wetting Agent (Sulfatate)	2
(Machine Washing)	
Formula No. 5	
Sodium Carbonate	40
Sodium Metasilicate	15
Tetrasodium Pyrophosphate	
No. 6	
Sodium Metasilicate	20
Trisodium Phosphate	15
Tetrasodium Pyrophosphate	,
Crystalline	65
No. 7	
Sodium Carbonate	20
Sodium Metasilicate	80
No. 8	
Sodium Carbonate	10
Trisodium Phosphate	20
Sodium Metasilicate	30
Tetrasodium Pyrophosphate	40
No. 9	
Sodium Carbonate	10
Sodium Hydroxide	5
Sodium Metasilicate	45
Tetrasodium Pyrophosphate	40
No. 10	
Sodium Carbonate	15
Sodium Metasilicate	40
Tetrasodium Pyrophosphate	30
Trisodium Phosphate	15
No. 11	
Sodium Carbonate	25
Sodium Metasilicate	<b>54</b>
Trisodium Phosphate	<b>2</b> 0
Wetting Agent, Low Foam	
(Sulfatate)	1
No. 12	
Sodium Carbonate	30
Trisodium Phosphate	55
Sodium Metasilicate	5
Tetrasodium Pyrophosphate	10

_		
	No. 13	Alcol
	Trisodium Phosphate 85	Wate
	Tetrasodium Pyrophosphate 15	
	No. 14	
	Sodium Carbonate 25	I
	Trisodium Phosphate 60	Hyd
	Sodium Metasilicate 3	Hyd
	Tetrasodium Pyrophosphate 12	Wate
	No. 15	Glue
	Sodium Metasilicate 40	Glyc
	Trisodium Phosphate 20	Clean
	Tetrasodium Pyrophosphate 40	
	No. 16	Put ·
	Sodium Hexametaphosphate 40	distilli
	Sodium Metasilicate	evapor
	(Pentahydrate) 40	trated
	Trisodium Phosphate	heated
	(Monohydrate) 14	F.). Sr
	Sodium Hydroxide 5	should
	Sulfatate (Wetting Agent) 1	heated
	CANADA CONTRACTOR CONT	Large !
	Dish Washing Powder	sufficie
	British Patent 528,964	the ho
	Trisodium Phosphate 40	is clear
	Soda Ash 26	and all
	Sodium Silicate 25	rinsing
	Sodium Sulphite 5	tion is
	Sodium Hexametaphosphate 2	leum p
	Soap, Powdered 2	more e
		solutio
	Glass Cleaner	used n
	Formula No. 1	Cau
	Glycerin 1.25	tubes,
	Oxalic Acid 56.25	operate
	Potassium Chromate 2.50	into th
	Water 940.00	tion wi
	No. 2	causes
	Aerosol O. T. (Wetting	open e
	Agent)	should
	Methanol 2	bottle
	Ethylene Glycol 1	Cleani
	Water 96	from
	No. 3	Put
	Isopropyl Alcohol 9	chlorat
	Diglycol Laurate 1	flask g
	Ethylene Glycol 3	flame
		17

Alcohol, Denatured	28
Water	59
Glass Cleaning Jell	У
British Patent 532,8	16
Hydrofluoric Acid 9	gal.
Hydrochloric Acid 33	1/3 gal.
Water 13	1/3 gal.
Glue 91	½ lb.
Glycerin 12	½ lb.

ing Organic Smears—Tars, Etc.—from Apparatus

the dirty beakers, test tubes. ng flasks, etc., into a large ating dish containing concencommercial sulphuric acid to 200-225° C. (400-435° mall quantities of nitric acid be added whenever the acid becomes black in color. beakers can be turned around ently to bring all parts into t acid. When the apparatus n, remove (use a glass rod) low the articles to cool before g in water. This cleaning solus not satisfactory for petroroducts. This solution is much economical than chromic acid ns—the same acid can be nany times.

tion: Have beakers, flasks, etc., pointed away from the or while they are being put ne acid. Sometimes the reacith wet, very dirty apparatus a spattering of acid from the end of the vessel. The acid be kept in a glass-stoppered when stored.

ing Flasks or Other Apparatus Baked-In Carbon Deposits

a small quantity of potassium te in the dry flask; heat the gently in a Bunsen burner flame until the chlorate is barely melted; rotate the flask so that the molten chlorate comes in contact with the carbon. The quantity of chlorate to contact the carbon residue is surprisingly small. After cooling, dissolve the remaining mixture in water.

Caution: Use this only on the solid carbon stain that will not wash out or that cannot be removed by ordinary mechanical means.

Chromic Acid Cleaning Mixture
This is needed for apparatus such
as burettes, etc., which cannot be

immersed conveniently in a vessel

of hot sulphuric acid.

Add 1 l. of conc. commercial sulphuric acid to 50 g. chromic acid dissolved in 25 cc. of warm water. There will be no trouble from crystallization of salts from this mixture. This mixture, without heating, removes organic material after a few hours of contact. More chromic acid can be added whenever the solution loses its red color.

Caution: Keep in a glass-stoppered bottle. The reason: absorption of water from the air reduces the activities.

Cleaning Laboratory Glassware
Iodoform stains and odor may be
removed by washing glassware with
a solution of potassium or sodium
hydroxide and rinsing it with a
small amount of alcohol. Of course,
the final step in this cleaning operation, as well as in all others to be
described, is thorough washing with
soap and water.

Ferrocyanide or iron stains are easily and rapidly removed with a solution of potassium hydroxide.

Lime deposited by lime water or similar preparations can be removed from glassware with diluted solutions of acetic acid or nitric acid. Deposits from lead subacetate solution can also be removed with these cleansing agents.

Deposits of soluble metallic salts are usually readily removed by thorough rinsing with water; however, in some cases, a small amount of hydrochloric acid may facilitate the cleansing. Insoluble or practically insoluble salts may be removed from glassware by dissolving them with the appropriate solvent which differs for each salt.

Metallic soaps, such as oleates and lead plaster, may be removed

by oil of turpentine.

Oils, resins, balsams, and similar resinous bodies can usually be removed with soap, but in some cases a solution of potassium hydroxide may be required.

Collodion may be removed by peeling it off the glassware. If, however, the film adheres firmly, a mixture of ether and alcohol will remove it. In the case of adherent guttapercha film, chloroform should be used as the solvent.

Sawdust is one of the best materials for removing petrolatum, lard, or other greasy substances from mortars and ointment tiles. Paper cleansing tissues are also excellent for this purpose. After the greater part of the grease has been removed with the sawdust or paper, the glassware should be washed with soap and water.

Bottle Cleaner
U. S. Patent 2,241,984
Caustic Soda 2½-6%
Sodium Aluminate ¼-1%
Water 93 -97%

Wi	indow	W	ash	ing
had	coluti	Oη	001	2010

The best solution consists of one part alcohol to two parts water. In freezing weather the alcoholic content should be increased to 50%. The same solution can be used until the water is almost thick with dirt, since its efficiency is not materially reduced until it has assumed the approximate consistency of cream. If a chamois is used it should be merely dampened with the solution, not soaked in it. After the window is dry it should be wiped with a silk rag.

Stain Remover for Polished Glass
Hydrofluoric Acid 0.25
Water 99.75

To Remove Scratches on Glass Scratches on glass may be eradicated by using a paste made of glycerin, water and rouge (iron oxide) mixed to the desired consistency. A hard felt pad is dipped in this paste and rubbed briskly back and forth over the scratched surface until the markings disappear. The paste can be washed away by simply flushing with water. This paste is particularly suitable for removing shallow scratches. Deeper gougings require more specialized treatment and coarser abrasives to start with. For this latter purpose emery powder will often serve, and glycerin makes a satisfactory medium in which to suspend the powdered abrasive.

Dairy Utensil Cleaners

General Work

Formula No. 1

Sodium Carbonate 46

Sodium Metasilicate 46

Trisodium Phosphate,

Monohydrated 8

No. 2	
Sodium Carbonate	58
Sodium Bicarbonate	42
No. 3	
Sodium Carbonate	60
Sodium Bicarbonate	40
No. 4	
Sodium Carbonate	60
Trisodium Phosphate	40
No. 5	
Sodium Carbonate	60
Trisodium Phosphate	30
Sodium Hydroxide	10
No. 6	
Sodium Carbonate	66.6
Trisodium Phosphate	14.0
Sodium Metasilicate	19.4
No. 7	
Sodium Carbonate	5
Trisodium Phosphate	20
Sodium Metasilicate	65
Sodium Hydroxide Sodium Aluminate	5 5
	Ð
No. 8	20
Trisodium Phosphate Sodium Tetraborate	90 10
	10
No. 9 Sodium Carbonate	55
Sodium Hydroxide	10
Soap	35
No. 10	90
Trisodium Phosphate	75
Sodium Sesquicarbonate	25
No. 11	
Sodium Carbonate	30
Sodium Metasilicate	50
Sodium Hydroxide	6
Soap	14
TO 1 TO 11 TO 1	
Dairy Bottle and Glassy	vare
Cleaners	

Formula No. 1

55

45

Sodium Carbonate

Sodium Hydroxide

No. 2 Sodium Carbonate 40 Sodium Hydroxide 60 No. 3 Sodium Carbonate 30	Sodiuı Sodiuı
Sodium Carbonate 40 Sodium Hydroxide 60 No. 3 Sodium Carbonate 30	
Sodium Hydroxide 60 No. 3 Sodium Carbonate 30	
No. 3 Sodium Carbonate 30	
Sodium Carbonate 30	
	Dair
Sodium Hydroxide 70	Trisod
No. 4	Tetras
Sodium Carbonate 20	2000
Sodium Hydroxide 80	Sodiu
No. 5	Sodiui
Sodium Carbonate 25	Trisod
Sodium Metasilicate 10	11100
Sodium Hydroxide 65	Phosp
No. 6	Monos
Sodium Carbonate 3	Water
	Sulfat
Anhydrous 4	Bullat
Trisodium Phosphate,	Taller
	Jelly
	B
	Hydro
Melt together. Especially suited	Hydro
for washing machine.	Water
	Glue
,	Flour
	Glycei
Caustic Soda 92	Use w
Melt together.	ly.
For Use in Soaker-Washing	
Machine	$\operatorname{Remov}$
Formula No. 8	]
	Place
Sodium Carbonate 5 siu	ım bist
Trisodium Phosphate, is	melte
Anhydrous 7 mi	nutes,
Sodium Metasilicate,	t wate
Anhydrous 5	
Sodium Hydroxide 83	Remov
No. 9	
Sodium Carbonate 20	An ex
	oving t
Caliana III.alianaida	made
37 40	unds
~ " ~ .	
	stals x 12 c
Dodium Messelliere 9 10	a pas

No. 11	
Sodium Metasilicate	15
Sodium Hydroxide	85
Dairy Milk Stone Remove	$\mathbf{r}\mathbf{s}$
Formula No. 1	
Trisodium Phosphate	45
Tetrasodium Pyrophosphate	55
No. 2	
Sodium Carbonate	20
Sodium Metasilicate	15
Trisodium Phosphate	65
No. 3	
Phosphoric Acid 50%	30
Monosodium Phosphate	45
Water	20
Sulfatate (Wetting Agent)	5
Personal Personal Control Cont	

Jelly Detergent for Porcelain
British Patent 532,816
Hydrofluoric Acid 8 lb.
Hydrochloric Acid 3 lb.
Water 10 gal.
Glue 434 lb.
Flour 371/8 lb.
Glycerol 61/8 lb.

Use with rubber gloves or swab only.

#### Removing Carbon Grime from Porcelain Crucibles

Place crucible in a dish of potassium bisulphate and heat until latter is melted. Allow to remain for 5 minutes, cool slowly and wash with hot water.

#### Removing Tobacco Stains from Marble

An excellent preparation for removing tobacco stains from marble is made as follows: Dissolve 2 pounds of trisodium phosphate crystals in 1 gallon of hot water. Mix 12 ounces of chlorinated lime to a paste in an enameled pan by

adding water slowly and stirring. Pour the two solutions into a stoneware jar and add water until about 2 gallons are obtained. Stir thoroughly, cover the jar and permit the lime to settle. Add some of the liquid to powdered tale until a thick paste is formed and apply a layer 1/4 inch thick with a trowel. To apply with a brush instead, add about one teaspoonful of sugar to each pound of powdered talc. If working on polished marble, scrape off with a wooden paddle; if dull marble, scrape off with a trowel. This mixture is a strong bleaching agent and corrodes metals, hence care must be exercised to prevent its dropping on metal fixtures or colored fabrics.

Removing Ink Stains from Marble
Ink marks on marble may be removed with a paste made by dissolving an ounce of oxalic acid and half an ounce of butter of antimony in a pint of rain water, and adding sufficient flour to form a thin paste. Apply this to the stains with a brush; allow it to remain on 3 or 4 days and then wash it off. Make a second application, if necessary.

Stripping Compounds (For removing paints, lacquers, enamels, etc., from metals, without corrosion.)

`	7110010111)		
	Formula No. 1		
	Sodium Hydroxide	6	0
	Potassium Hydroxide	3	0
	Wetting Agent (Sulfatate)		5
	Rosin		5
	No. 2		
	Caustic Soda	75	
	Caustic Potash	15	
	Trisodium Phosphate,		
	Monohydrated	5	
	-		

Wetting Agent (Sul-	
fatate)	$2\frac{1}{2}$
Rosin	$\frac{21}{2}$
No. 3	- /2
Caustic Soda	70
Trisodium Phosphate,	• •
Monohydrated	25
Rosin	5
No. 4	
Caustic Soda	50
Sodium Carbonate	35
Trisodium Phosphate,	
Monohydrated	10
Rosin	5
No. 5	
Caustic Soda	50
Sodium Carbonate	35
Trisodium Phosphate,	
Monohydrated	10
Sodium Abietate	5
No. 6	
Sodium Carbonate	25
Caustic Soda	67
Trisodium Phosphate,	-
Monohydrated	5 3
Wetting Agent (Sulfatate)	3
No. 7	~0
Caustic Soda Sodium Carbonate	50 15
Trisodium Phosphate,	15
Monohydrated	25
Soap (20° C. Titre)	5
Wetting Agent (Sulfatate)	2
Rosin	3
No. 8	
Caustic Soda	70
Sodium Carbonate	22
Trisodium Phosphate,	
Monohydrated	5
Wetting Agent (Sulfatate)	3
All above mentioned con	
tions, when used for the stripp	
paint, lacquer or enamel from	n iron

and steel (only) are employed by making a hot, nearly boiling, solution of a concentration of from 6 to 8 oz. per gallon of water. The painted articles are either suspended in the solution until the paint is loosened sufficiently so that it can be rinsed off. The "milder ones," that is the compositions with a lower caustic content, can be sprayed on with a steam gun (not of aluminum), or a poultice can be made from a paste of these compounds and placed on painted surfaces to remove the paint. In the latter case, care must be employed not to get the paste in contact with the bare skin.

Daint Stainne

Paint Stripper	
$(From\ Aluminum)$	
Formula No. 1	
Sodium Metasilicate	47.5
Sodium Silicate, "G"	
Brand	47.5
Rosin	5.0
No. 2	
Sodium Carbonate	8.0
Trisodium Phosphate	35.0
Sodium Metasilicate	40.0
Sodium Silicate, "G"	
Brand	10.0
Sodium Sulphite	1.5
Soap, Neutral (30° C.	
Titer)	5.0
Wetting Agent (Wetanol)	0.5
No. 3	
Oleic Acid	20.0
Cresol	67.2
Water	8.0
Potassium Hydroxide	4.8
Dilute 1 part of the cor	מנים

Dilute 1 part of the compound with 4 parts of water; heat to not more than 140° F. and submerge articles until paint, enamel or lacquer is completely loosened, when it will come off in coherent large films.

This material can be used suc-

cessfully for the removal of lithographic inks from tinned sheets without attacking the tin.

Paint Stripper	
$(From\ Steel)$	
Formula No. 1	
Caustic Soda	80
Sodium Carbonate	15
Trisodium Phosphate,	
Monohydrated	5
No. 2	Ū
Sodium Silicate, Anhy-	
drous	50
Supersilicate	20
Sodium Carbonate	10
Trisodium Phosphate	20
	0
Enamel Stripper	
$(From\ Steel)$	
Formula No. 1	
Caustic Soda	86
Soda Ash	14
No. 2	11
Potassium Hydroxide	75
Sodium Fluoride	25
No. 3	20
Potassium Hydroxide	20
Sodium Hydroxide	35
Sodium Fluoride	20
Alum	25
Removing Metallic Stains fr	nm
Transfer and a committee of the committe	

Painted Surfaces
Formula No. 1
Sodium Metasilicate 2 oz.
Water 1 gal.

Stained areas on weathered surfaces should be thoroughly wetted with water before using this solution. Gentle rubbing with a cloth wetted with the solutions will generally remove the stains. In severe cases, two applications may be required. After the stains have been removed steps should be taken to

remove the cause of staining by painting the exposed metal surfaces.

No. 2

These unsightly brown stains will usually be found beneath copper screening, but they may be caused by rusted leaders and gutters, or by exposed or improperly puttied nail heads, hinges, etc. Rain water, passing over these parts, takes a small amount of metal into solution and deposits it on the painted surface below. Staining takes place as a result of these metal salts reacting with or being adsorbed by the paint film.

An inexpensive, easily prepared solution which removes metal stains, particularly copper, without damage to the paint film is obtained by dissolving 1½ to 2½ ounces of sodium metasilicate in a gallon of water. The surface to be cleaned is first wet with plain water, using a soft sponge or cloth. The solution is then applied with another sponge, rubbing lightly until the stain disappears. This is followed by a thorough washing of the cleaned surface with plain water.

Ordinary rust stains may also be cleaned with a 2% solution of oxalic and/or a 5% solution of phosphoric acid, rinsing with clean water after application.

The best practice to avoid metal staining is to apply a coat of zinc dust-zinc oxide paint to all exposed metal parts, particularly copper screens, and thus protect them from the weather.

#### Removing Mildew from Painted Surfaces

Mildewed exterior surfaces should be washed prior to repainting. Abrasive soaps and water or alkali cleaning soap solutions containing trisodium phosphate or sodium metaphosphate may be used to advantage. After thorough scrubbing, the siding should be flushed with clean water and allowed to dry. Laps and seams or portions which have shown badly mildewed areas may be treated with a solution of one part of bichloride of mercury in 300 parts of water. Precaution should be taken to prevent this solution from coming in contact with the skin. Rubber gloves could be employed. After drying, the finishing coats of house paint may then be applied.

Removing Varnish from Furniture Some varnish removers contain wax. This type of remover works best on pieces of furniture that have been finished for months or years, as the wax slows up the evaporation of the remover, making it stay wet longer, hence its softening action is quicker on the film to be removed. Much care must be exercised when using this wax-type remover to avoid leaving any of the wax on the surfaces to be refinished. If wax were left on such surfaces it would cause the finish to remain soft and not dry as it should—and probably the finish would peel off or scale off later.

After removing the finish with a wax-type remover, all cleaned parts should be washed clean with denatured alcohol. This will remove all of the wax residue.

Perhaps the best method of removing the old finish is to use a vat in which to put the articles to be washed. Put the pieces to be washed

in the vat and let them soak a few minutes; then use a rag or pad of steelwool, dipping this in the remover and then washing with the grain of the wood while the piece remains in the vat. After all of the old finish is off, remove the piece of furniture from the vat and wipe it clean with a soft cloth, being sure that all remover is wiped from the piece washed. Then allow the washed piece of furniture to dry for about two hours. It is now ready to refinish.

Where the piece of furniture is too large to be put into a vat, use a bench the same height as the sides of the vat. The piece of furniture can be put partly over the vat, to as to wash it and allow the unused "rundown" to drain back into the vat.

Whenever or wherever a vat is used, a cover should be kept on the vat when it is not in service, so as to avoid any evaporation of the remover material in the vat.

Another method is to brush the remover on the finish to be removed. Keep brushing it on so as to keep the surface wet until the old film gets soft; then use a putty knife or cabinet scraper to lift the film to be removed. This should be followed by a sponging of all the surface with some of the remover on a soft rag. This will remove all streaks left when scraping.

Still another method of removing the old finish from furniture is to spread several layers of old cloth or burlap on the surfaces to be cleaned and then pour the remover on this covering. This will keep the surface wet until the old film becomes soft. Then follow by scraping and sponging the surfaces. Painted Woodwork Cleaner

Kerosene (about 15%) emulsified in a mixture of soap (6%), colloidal clay (7%), and water (72%). The kerosene dissolves grease while the clay adsorbs dirt and keeps it dispersed. The soap exerts its usual powerful detergent action.

## Painted Woodwork and Wall Cleaner

Starch	69
Trisodium Phosphate	15
Soda Ash	7
Sulfatate	1
Water	8

Preservative, As needed
The above is made into a slurry
with water before use.

## Paint Brush Cleaner

rame Drush Cleaner	
Kerosene	2
Diglycol Oleate	1
Ammonia	1/4
Alcohol	1/4

Place brush in above over-night and then wash well with water.

## Cleaning and Conserving Paint Brushes

Strong alkalies should never be used to clean paint brushes. Hardened paint (oil-base) can be softened by soaking the brush over night in any good grade lacquer thinner or (if not too hard) in gasoline or turpentine. Softened paint can be removed with a putty knife or steel painter's comb—a step which, properly done, should clean out all of the paint pigment right down to the rubber setting.

In the washing operation thorough scrubbing to remove remaining paint particles is important. A good grade of white floating soap,

or any other neutral soap may be used. When the brush is cleaned, rinse first in hot water, then in cold water. Repeat until all trace of soap is removed. Shake out excess water.

Combing the bristles immediately after, removes all twists and curls; wrapping in paper keeps the bristles straight. Thorough drying is especially important, for if the brush is used before the bristles are completely dry, paint will seal the moisture inside of the porous bristles, causing them to lose their inherent resiliency that is so important to quality painting.

Sweeping Compound	
Sand (Clean)	44
Paraffin Oil	20
Sawdust, Kiln Dried	36

Garage Concrete Floor	Cleaner
Water	132
Copper Sulphate	16
Cotton Seed Oil	$1\frac{1}{2}$
Muriatic Acid	100
Powdered Pumice	9
Water, To make	400

Degreasing Detergents
Formula No. 1
Sulphated Higher Alcohol or "Sulfatate" 30–35
Trichloroethylene 65–70

Pour the trichloroethylene into the sulphated higher alcohol under constant stirring. Stir again before use.

No. 2	
Sulphated Higher Al-	
cohol	30-35
Turpentine	10-15
Tetrahydronaphthalene	20

Wate	r		30
	methylhexalin	until	dis-
solved.	37 0		

nveu.	
No. 3	
Soda Ash	8 oz.
Trisodium Phosphate	2 oz.
Caustic Soda	2 oz.
Water	1 gal.
No. 4	
Sodium Metasilicate	95
Nacconol NR (Wetting	
Agent)	5
Water	3300
Use at 140° F.	

## Organic, Emulsifiable Grease and Dirt Solvents

For use on metals, metallic articles, on automotive equipment (chassis, wheels, engines), in aviation industry, and anywhere, where large amounts of old grease (mineral, etc.) have to be removed:

# Metal Degreasers Formula No. 1

Cocoanut Fatty		
Acid	15	fl. oz.
Oleic Acid	28	fl. oz.
Water	34	fl. oz.
Potassium Hy-		
droxide	9.8	oz.
Diethylene Glycol		
Monobutyl		
Ether	20	fl. oz.
Naphtha, Hydro-		
genated	26	fl. oz.
"Chlorasol"	<b>2</b>	gal.
Cresol	2	gal.
Kerosene	16	gal.

This formula can also be changed to a jelly-like paste and then used in a water solution (emulsion) by stirring into the formula a low titer, highly hydrated jelly soap, made from low titer vegetable oils.

488 THE CI	DEMICA	TE FORMULARI	1
No. 2		Caustic Soda	10
Sodium Carbonate	18	Sodium Abietate	5
Trisodium Phosphate	20	(From 1-2% wetting ager	
Sodium Hydroxide	55	anol) can be added to abov	
Sodium Abietate	7	No. 7	c. <i>)</i>
No. 3	•	Another milder, but very	officien
Sodium Carbonate	20	metal cleaner is composed of	
Sodium Silicate (40° Bé)	30		31:
		Tetrasodium Pyrophos-	10
Caustic Soda	40	phate, Anhydrous	10
Sodium Abietate	10	Trisodium Phosphate,	
Above two compounds are e		Monohydrated	15
metal cleaners, which can b		Trisodium Phosphate	10
for many metals, but are esp		Sodium Carbonate	38
suitable for the removal of		Sodium Hydroxide	15
oils and greases from ferrous	metals	Potassium Hydroxide	10
prior to plating such as zincking	ng, tin-	Sodium Abietate	<b>2</b>
ning, etc., or prior to enameli	ng and		
lacquering.		Iron and Steel Wire Cle	aner
But buffing compounds and	lighter	Formula No. 1	
oils and greases can also be re		Sodium Carbonate	30
T	buffed	Trisodium Phosphate,	•
brasses, bronzes, copper articl		Monohydrated	5
No. 4	,	Trisodium Phosphate	10
Sodium Carbonate	25	Sodium Hydroxide	45
Trisodium Phosphate,	20	Sodium Abietate	10
	25	1	
Monohydrated	-	1% of Wetanol (wetting	agent
Caustic Soda	37	may be added.	
Sodium Abietate	3	No. 2	
Caustic Potash	10	Trisodium Phosphate,	-
No. 5		Monohydrated	20
Sodium Metasilicate	<b>2</b> 0	Trisodium Phosphate	15
Trisodium Phosphate,		Sodium Carbonate	35
Monohydrated	20	Caustic Soda	30
Sodium Carbonate	10	No. 3	
Caustic Soda	58	Trisodium Phosphate,	
Cresol	2	Monohydrated	20
The cresylated cleaner show	ıld not	Trisodium Phosphate	25
be used as an electric cleane	er, be-	Sodium Carbonate	40
cause it produces stains later.		Caustic Soda	15
No. 6		No. 4	
Sodium Carbonate	25	Above Cleaner	95
Sodium Metasilicate	25	Dextrose	5
Sodium Silicate (G Brand)	5		U
Trisodium Phosphate,	. J	Soak Cleaner	
	15		
Monohydrated	15	Formula No. 1	40
Trisodium Phosphate	15	Sodium Carbonate	40

		1
Tetrasodium Pyrophos-		No. 7
phate, Anhydrous	4	Sodium Orthosilicate 80
Trisodium Phosphate,		Trisodium Phosphate,
Monohydrated	10	Monohydrated 20
Trisodium Phosphate	5	No. 8
Sodium Abietate	5	Sodium Carbonate 55
Rosin, Powdered	4 30	Sodium Metasilicate 20
Caustic Soda Wetting Agent (Wetanol)	$\frac{50}{2}$	Caustic Soda 15
No. 2	4	Sodium Abietate 10
Sodium Metasilicate	50	Light Metal Alloy Degreaser
Sodium Orthosilicate	25	Trisodium Phosphate 5
Sodium Aluminate	5	Sodium Silicate 3
Caustic Soda	20	Caustic Soda 1–2
No. 3		Water, To make 100
Sodium Carbonate	15	Treat at 50–60° C. for 5 minutes.
Sodium Metasilicate	40	Boiler Tube Grease Remover
Sodium Orthosilicate	30	U. S. Patent 2,248,656
Trisodium Phosphate,		Tetrasodium Pyrophos-
Monohydrated	10	phate 30
Aluminum Phosphate	5	Sodium Sulphate 40
No. 4		Sulphite Liquor (Solids) 30
Sodium Carbonate	35	25.1.0
Sodium Metasilicate	30	Metal Cleaner
Sodium Orthosilicate	25	Sodium Silicate 42.7%
Sodium Abietate	10	Sodium Metasilicate 8.0%
No. 5		Sulfatate (Wetting Agent) 2.0%
Sodium Carbonate	20	Water, To make 100 %
Sodium Metasilicate	10	Water, To make 100 //
Sodium Orthosilicate	5	Metal Cleaning Emulsion
Trisodium Phosphate,	0	Kerosene 70
Monohydrated	8 10	Pine Oil 6
Trisodium Phosphate Sodium Abietate	5	Wetanol (Sulphated Fatty
Sodium Oleate	5	Alcohol) 12
Wetting Agent (Wetanol)	$^{\circ}_{2}$	Water 12
Caustic Soda	35	The above is diluted with
No. 6		Water 100
Sodium Carbonate	10	Metal Cleaner and Sterilizer
Sodium Orthosilicate	15	British Patent 533,265
Sodium Metasilicate	50	Sodium Hypochlorite 10.0%
Trisodium Phosphate,		Sodium Hexameta-
Monohydrated	10	phosphate 15.0%
Sodium Aluminate	5	Caustic Soda 2.4%
Caustic Soda	10	Water 72.6%

Metal Test Panel Cleaner	
Phosphoric Acid	3
Tergitol Penetrant No. 4	1
Water, To make 100	0

## Metal Utensil and Appliance Cleaner

Cleaner	
Australian Patent 1	11,451
Soft Soap	<b>2</b>
Soda Ash	1
Crude Sugar	1.5
Magnesium Carbonate	3
Diatomaceous Earth	18
Water	30 %

Dissolve the soap in half the water, the soda ash and the sugar in the other half. Mix the earth and magnesium carbonate and knead well with the strained solutions.

Magnesium Alloy	Clean	ers
Formula No	. 1	
Soda Ash	3	oz.
Caustic Soda	2	oz.
Diglycol Stearate	1	oz.
Water	1	gal.
No. 2		
Sodium Bichromate	$1\frac{1}{2}$	lb.
Nitric Acid	$1\frac{1}{2}$	lb.
Water	1	gal.
Use at 70-90° F.		

## Metal Cleaners

Mild metal cleaners are such without added caustic soda or potash, or with caustic constituents not higher than 10% and, at the same time, low in sodium carbonate and orthosilicates.

Medium strong metal cleaners may contain caustic alkalies up to 25–30% depending upon the percentage content of other strong alkalies such as sodium carbonate and orthosilicates.

Strong metal cleaners contain,

generally, high concentrations of caustic substances, and also sodium carbonate, orthosilicates.

The higher the percentage concentration of abietates, soaps, etc., or silicates plus these organics, mentioned in cleaning compounds, the more are such cleaners suited as soak cleaners or still cleaners. Cleaning solutions are used to surround or penetrate oils, greases, emulsify and loosen them and dirt from the metal surfaces. Then their removal by rinses and their subsequent complete cleaning to a chemically pure surface is easily and quickly attainable in an electric cleaner.

Wetting agents, soaps, abietates, solvents, etc., are generally to be avoided in electric cleaners, while their presence in larger amounts is preferable in many instances in still cleaning solutions (soak cleaners), especially, where this preliminary cleaning operation is followed up and completed in a second and preferably electric cleaner.

None of the alkaline cleaning compositions is particularly or at all suitable for the cleaning of aluminum or of tin articles. Specially buffered and composed cleaners are used for these two metals and for their alloys.

# Mild Plater's Cleaner Sodium Carbonate

Sodium Carbonate 40 Trisodium Phosphate 45 Caustic Soda 13½

Sodium or Potassium Abietate

Sometimes, coloring gums (e.g. gum guaiac) are used instead of abietates whenever the presence of

11/2

abietates is objectionable. The above is used for copper, brasses, white metals and diecast metals, and also for the cleaning of stamped steel articles (but not for tin). It is also quite efficient in removing buffing compounds, light oils, etc., from such metals where a pure surface is required prior to enameling or lacquering.

# Concentrations of Cleaning Solutions

For brass, copper, die-castings, etc.: (still tank) 4-6 oz./gal. Temperature of operation: 180-200° F.

For iron and steel cleaning: (still) 6-8 oz./gal. Temperature: 190-212° F.

For electric cleaning of iron and steel: 4-6 oz./gal. Temperature: 212° F.

For electric cleaning of brasses, copper, die-castings: 2-4 oz./gal. Temperature: 180-200° F.

When used as electric cleaner, use as counter electrodes: iron or steel sheets about 1/8 to 1/4 inch thickness, or connect the tank to the positive electrode. The articles to be cleaned are connected cathodically. The cleaning time is from 1/2 minute to 3 minutes or sometimes more, depending upon the amount and type of grease and dirt to be removed. Following this cleaning operation, the work can be made the anode for from 5-10 seconds. To make this change instantly and without removing the articles from one pole and switching them with the steel plates, a double-throw switch should be installed. A voltage of from 3-5 volts is required for soft metals and of 4-6 volts can be used for steel and iron.

After cleaning, the articles are removed and immediately rinsed in a good warm and clean rinse water or spray, followed immediately by a second rinsing in running cold water. Thereafter, the articles are dipped in a hydrochloric acid dip (concentration from 5-15% volume for brasses, etc.; of 40-60% volume for iron and steels) for from 2-10 seconds, rinsed in cold water, thoroughly, and plated in the desired solution. If in copper cyanide, brass cyanide or silver or other cyanide, both, the articles can be dipped momentarily in a sodium cyanide dip (2-4 oz./gal. or more) and then introduced into the plating solution.

When making up the cleaning solution, fill the tank with about  $\frac{2}{3}$  of the total desired volume of cleaning solution, heat the water to about  $160^{\circ}$  F., dissolve the measured quantity of cleaner in it and bring the solution to the boiling point and keep it there for about 15 minutes with intermittent stirring. Now, add water to bring the volume of the cleaning solution to the proper measure and the solution is ready for use.

Above outlined procedure is, generally, the same for all inorganic metal or plater's cleaners, except for concentrations, temperatures, time of cleaning and intensity and quantity of electric current used.

## Brass, Copper and Soft Metal Cleaners

Formula No. 1	
Sodium Carbonate	40
Trisodium Phosphate	35
Caustic Soda	15
Sodium Abietate	10

No. 2	
Sodium Carbonate	30
Sodium Silicate (60%)	25
Borax	5
Caustic Soda	35
Sodium Abietate	5
No. 3	
Sodium Carbonate	20
Sodium Silicate (40%)	35
Caustic Soda	35
Sodium Abietate	10
No. 4	
Sodium Carbonate	25
Sodium Metasilicate	50
Trisodium Phosphate	25
No. 5	
Sodium Carbonate	24
Sodium Metasilicate	48
Trisodium Phosphate	24
Sodium Abietate	4
No. 6	

Formula No. 4 or No. 5 with 5-10% caustic soda.

Soak Cleaner for Removal of Tripoli and Buffing Compounds from Brass. etc.

Cocoanut Oil	18.5
Tallow Fatty Acids	30.0
Potassium Hydroxide	8.3
Water	23.5
Sodium Hydroxide	2.7
Water	4.5
Pine Oil	1.0
Boric Acid	1.5
Water	1.0
Cane Sugar	9.0

Melt fatty matter; add all of the lyes as usual at a temperature of about 60°-70° C. and saponify. After complete saponification, add pine oil; thereafter, add the sugar and the boric acid in paste form, and finally stir thoroughly.

If desired, from 1-5% of wetting agent (Wetanol) can be successfully

added to the total compound. It may also be beneficial to use other combinations of fatty matter but the titer of the total fatty matter should be kept at around 30–35° C.; for example:

Corn Oil

Cottonseed Fatty Acids

Red Oil (small amount that can be substituted for part of the tallow fatty)

Cocoanut Oil

In any such case, the total amount of hydroxides must be adjusted to the mean saponification number of the combined fatty acids and oils, to obtain a neutral soap.

From 2-6 oz./gal. of the above compound are dissolved at a temperature of from 140-160° F. The articles are now suspended, either in baskets, on hooks, or on wires, in the solution, until the polishing and buffing materials are at least completely penetrated. They may now be removed and either rinsed in hot water, or they may be dipped in a second cleaner solution of mild alkalinity, similar to previously mentioned brass cleaners, and then rinsed in hot and cold water.

Tin Cleaners	
Formula No. 1	
Sodium Carbonate	30
Tetrasodium Pyrophos-	
phate, Anhydrous	30
Trisodium Phosphate,	
Monohydrated	25
Sodium Metasilicate	10
Bichromate of Soda	5
No. 2	
Sodium Carbonate	5
Tetrasodium Pyrophos-	
phate, Anhydrous	50

Trisodium Phosphate,	
Monohydrated.	30
Sodium Silicate (40° Bé)	10
Bichromate of Soda	5
No. 3	
Sodium Carbonate	35
Sodium Silicate (40° Bé)	25
Sodium Metasilicate	25
Disodium Phosphate	15
Similar alkaline composition	ons as

Similar alkaline compositions as above plus lasting reducing substances, which are without physiological or toxic or poisonous characteristics may also be used.

No. 4	
British Patent 537,136	
Sawdust (1/32")	14
Wood Flour	85
Whiting	1

How to Clean Stainless Steel The necessity for cleaning stainless steel is not usually due to the formation of any rust or corrosion products from the metal itself, but to surface contamination and deposits. The equipment may be set up adjacent to sewers where vapors may develop an iridescent film that is difficult to remove. Stainless decorative trim is frequently exposed to corrosion products from less corrosion resistant metals and washings from acid-treated insulating materials, which stain the surface or form hard deposits. Heat exchanger tubes often become coated with mineral deposits from cooling water. Such deposits, unless uniform over the entire surface, are a source of localized pitting or corrosion.

Because stainless steel is a solid metal and not a plating, frequent cleaning is more beneficial than harmful. If proper cleaning methods and materials are employed, the original luster remains unaffected indefinitely. Probably the simplest procedure for removing ordinary deposits is frequent washing with soap and water. This prevents the deposits from becoming hard and tightly adherent, and subsequent cleanings are less difficult.

The luster of the polished finish can usually be restored with any of the stainless polishing pastes or powders available. In some cases, the use of vinegar or dilute acetic acid instead of water increases the effectiveness of the dry powders. When vinegar or acetic acid is used, thorough washing with water should follow.

Iron-free emery, of 180 grit or its equivalent, with kerosene as a lubricant, should be used when any abrasive is necessary.

More caution is required in sterilizing stainless steel equipment than in cleaning it. Most sterilizing compounds consist of, or contain, sodium or calcium hypochlorites. These hypochlorites should never be permitted to remain in contact with stainless steel for more than six continuous hours, and a thorough washing with water should follow each period of exposure. The type of corrosion usually encountered with the hypochlorites is entirely confined to small localized areas.

The cleaning of condenser or heat exchanger tubing or brine coils presents quite a difficult problem. In cases where construction permits, solutions of nitric, sulphuric or muriatic acid can be used for removing water scale or other deposits that may form on the walls of the tubing. The most desirable acid solution for cleaning such stainless

steel equipment is 10 to 20% nitric acid. Stainless steel is not attacked by solutions of nitric acid. Consequently, the acid solution can remain in the equipment for long periods of time without any harmful effects. Nitric acid cannot be used, however, if ordinary steel, brass, bronze, nickel or any material that is soluble in this acid is present in the system.

Steel Plate Cleaner Phosphoric Acid (Sp. Gr. 1.557) 840 cc. Ethylene Glycol Menomethyl Ether 150 ec. Sodium Chromate Solution (200 g. per l.) 10 cc. Isopropyl Naphthalene Sodium Succinate (Aerosol OS) 15 g. 2000 cc. Water

Dissolve 15 g. of the solid wetting agent in the glycol, add the chromate solution, and pour slowly with constant agitation into the phosphoric acid. Final gravity should be 1.48.

Cannon Sponging Fluid
Castile Soap 2 lb.
Sulfatate 3 g.
Water 8 gal.

Rifle Fouling Cleaner

Ammonia 3% pt.

Ammonium Persulphate 1 oz.

Ammonium Carbonate 5 dr.

Water 1/4 pt.

Sulfatate (Wetting Agent) 1 dr.

Rifle Swabbing Solution	n
Ammonia	300
Water	200
Sulfatate (Wetting	
Agent)	2

Aircraft Cleaning Compound

Formula No. 1
Alcohol 1 gal.
Pine Oil 1 qt.
Naphtha 5 pt.
Soap 4 lb.
Sulphonated Castor Oil 1 lb.

No. 2 Fusel Oil lb. Naphtha  $4\frac{1}{2}$  lb. Pine Oil lb. 4-5 lb. Soap Castor Oil, Sulphonated 1 lb. Kerosene 76 lb.

Automobile Soap Corn Oil, Crude 54.7 lb. Caustic Potash, Flaked 9.2 lb.

Dissolve caustic in 30 lb. water and add it to the oil slowly with stirring. Bring to a boil and then add water to bring to strength desired.

To color green add 5 g. alizarine green per 100 lb. soap.

Windshield Cleaner
U. S. Patent 2,296,097
Feldspar 12
Calcium Carbonate 8
Sodium Bicarbonate 34
Bentonite 3
Water, To make a paste.

Engine Carbon Remover
Formula No. 1
Neutral Coal Tar

Oil 39.5 cc.
O-Toluidine 15.0 cc.
Diethanolamine 15.0 cc.
Oleic Acid 15.0 cc.

Ethylene Glycol Phosphoric Acid	15.0	cc.
Ethyl Silicate	$\frac{1}{2}$	cc.
No. 2		
Neutral Coal Tar Oil	l	
(Cresol Free)	40	cc.
O-Toluidine	15	cc.
Diglycol Oleate	28	cc.
Ammonia	2	cc.
Ethylene Glycol	15	cc.
Phosphoric Acid	$\frac{1}{2}$	cc.
Ethyl Silicate	$\frac{1}{2}$	cc.
No. 3		
Neutral Coal Tar Oi	1 40	cc.
O-Toluidine	15	cc.
Ethylene Glycol	15	cc.
Emulsifier A 3076A	30	cc.

# Rust Remover U. S. Patent 2,209,291

Metal rust may be removed by a composition of 36 parts phosphoric acid, 3 parts zinc phosphate, 2 parts gum arabic, 1 part manganese chloride, 30 parts butyl propionate and 28 parts water.

Watch Cleaning Pre	parat	ion
Formula No.	1	
Ammonia (10%)		12.0
Castor Oil		1.2
Glycerin		0.2
Water, To make	1	0.00
No. 2		
White Oleic Acid	800	
Potassium Hydroxide		
(35° Bé)	300	
Saponin	16	
Water, To make	1	gal.
Mix the potassium hy	drox	ide so-
lution with most of the	wate	r, heat
to 80° C. Add the oleic	acid	slowly
with agitation. Dissolve	the s	aponin
in the remaining water,	add	to the
above, making to 1 gall	lon, a	and let

No. 3
Sulfatate (Wetting Agent) 90
Trisodium Phosphate 5
Tetrasodium Pyrophosphate 5
Mix intimately. To use, add 1–2
tablespoons to 1 pint of water.

cool. To use, mix 1 tablespoon of

the above with 1 pint water.

## CHAPTER TWENTY

## TEXTILES AND FIBERS

# Rotproofing Sandbags Formula No. 1

copper/ammonium solution containing approximately 4% of metallic copper can be prepared by dissolving 20 pounds of copper sulphate in water and making up the liquor to 10 gallons. To the solution so prepared is now added 2.1 gallons of strong ammonia (Sp. Gr. 0.88), care being taken to protect the eyes and respiration from the ammonia fumes. The resulting cuprammonium solution contains approximately 4% of copper and can be used for purposes of immersion when correctly diluted with water to give the required copper content.

An exceedingly useful water emulsion can be prepared from this liquor in combination with creosote:

(a) Prepare a cuprammonium solution as described above. (Solution A.)

- (b) Prepare a 14% solution of carpenter's glue by soaking the glue in water overnight and then warming the mixture until a clear solution is obtained ready for use. (Solution B.)
- (c) Neutralize the acids in the creosote with a trace of caustic alkali, to ensure stability of the ensuing emulsion. This is done by mixing 5 gallons of creosote with 0.5 gallon of caustic soda solution of

10% concentration. (Solution C.)

To make 10 gallons copper/creosote emulsion containing 50% creosote and 1.5% metallic copper we proceed in the following manner. The creosote caustic soda mix is first taken and 5 gallons (Solution C) measured out. To 3.8 gallons of Solution A add 0.7 gallon of Solution B. Now add the latter mixture (copper/ammonia/glue) gradually to the former liquor Solution C with continuous stirring. Warm the whole mixture to about 50°, stir vigorously, or better still, put through an emulsifier machine, and the composition readily becomes an aqueous emulsion. Sandbags treated with this by immersion or spraying are not sticky and quite dry to the touch.

No.	2

Soda Ash 4½ lb.
Soda Crystals 11½ lb.
Water 6 gal.

Stir the above solution, slowly, into a solution of:

Copper Sulphate 10 lb. Water 36 gal.

When well mixed, add water to make up to 48 gal. and

Wetting Agent (Sulfatate)

atate) 2 oz.

Immerse bags in above until saturated and wring out excess solution. Dry at low temperature.

Mothproofing Cloth
U. S. Patent 2,127,252

Cloth is immersed in an emulsion of

Magnesium Silicofluo-

ride 4–10%
Water 96–80%
Liquid Hydrocarbon 10–20%
Sulphonated Fatty
Alcohol 1%

After saturation of cloth, it is squeezed and dried.

Destroying Moths in Garments
Expose to
Ethylene Dichloride 10
Carbon Tetrachloride 10
Use 20–25 lb. of above per 1000
cu. ft. of air for 24 hr. at 65–75° F.

Detecting Beginning of Mildew
The following fluorescence test is
valuable for the detection of the
start of mildew formation on wool,
cotton, and rayon. Usually it is very
difficult to detect the start of mildew
formation, but this test solves this
problem. When examined under
ultra-violet light, the fiber shows a
brilliant blue to greenish fluorescence at the point where mildew is
starting.

Mildew Proofing
Copper Naphthenate 9 lb.

Zinc Bromide 5 lb. Amyl Acetate 1 lb.

Water 20 gal. (1) Mix and dissolve thoroughly.

(2) Filter.

(3) Make working solution with 1 part of above and 200 parts of water.

(4) Soak for 5 minutes.

(5) Dry.

Mildewproofing Spray U. S. Patent 2,292,423

Mineral Oil, Light 95 p-Chlorophenol 5

Spray until textile has absorbed about 0.2% by weight.

Fireproofing for Textiles and Paper
II S. Patent 2,097,509

U. S. Patent 2,097,509

Zinc Chloride 2.5%

Sodium Dichromate 0.5%

Sodium Silicofluoride 0.5%

Ammonium Dihydrogen
Phosphate 9.6%

Urea 1.9%

Flameproofing Wadding (Cellulose) U. S. Patent 2,132,016

The pulpweb is impregnated on forming cylinder with 0.7–1.1 lb. per gal. of water of following mixture:

Ammonium Sulphate 80 Ammonium Phosphate 10 Borax 10

> Flameproofing Kapok British Patent 535,058

Kapok is sprayed with or immersed in

Casein 1
Borax 5
Polyvinyl Acetate in Benzol (10%) 10
Triphenyl Phosphate 5
Water 85

Then squeeze through rollers; pass through 5% aluminum sulphate solution and dry.

Water and Alkali Resistant Textile
Finish

Ceresin Wax 90
Bitumen (m.p. above 100°) 45
Tricresyl Phosphate 45
Turpentine 820

Water-Repellent for Textiles Paraffin Wax (130° F.) 140

Stearic Acid	60
Naphthenic Acids	10
Gelatin	20
Aluminum Formate (30%	
Solution)	200
Water	570

Melt the wax and stearic acid and add the naphthenic acids, following with 150 g. of boiling water. Stir until an emulsion is produced. Dissolve the gelatin in 180 g. of water. Add the wax mixture to the gelatin solution at 60° C. Run through a colloid mill if desired. Finally add the aluminum formate solution very slowly and with much stirring. Now add the remaining water and filter if necessary.

Water Repellent for Cotton or Rayon Textiles British Patent 474,403

A 0.5% solution of decyl isocyanate, hexadecyl isocyanate, or octadecyl isocyanate, is made in benzol. The rayon or cotton fabric is dipped and dried. It is then heated to 100° C. for one minute, followed by two minutes at 140° C. The result is a water repellent material which can be dry cleaned.

Water-Repellent for Felts, Etc. Vistanex (Medium) 2.0 Toluene 60.0 Paraffin Wax (130° F.) 2.0 Aluminum Distearate 6.0 Aluminum Monostearate 4.0 Amyl Alcohol 10.0 Trichlorethylene 15.9 Triethanolamine 0.1

Dissolve the Vistanex in the toluene, add all the ingredients except the triethanolamine and disperse by stirring and heating to 60° C. Cool and work in the triethanolamine.

To use, dissolve in trichlorethyl-

ene and immerse the material; wring or centrifuge dry. Use a 10% solution. This may also be sprayed on.

Waterproofing Duck or Canvas

Waterproofing is of two general kinds, one, when chemical treatment of the fabric results in the deposit of chemical substance that is water repellent, and the other is when a water-repellent is applied directly. The first named process is as follows: Prepare a solution of acetate of alumina standing at 9° Tw., and heated to 100° F. Prepare a second solution of 25 gallons of water in which is dissolved about 25 pounds of soap, heated 100° F. Pass the goods first through the acetate solution, squeeze, and then pass through the soap solution, and dry. This causes an insoluble deposit of an alumina soap on the goods, and fabric is absolutely water-repellent.

The other process consists of impregnating the duck with a solution of paraffin wax and stearic acid in benzene (petroleum benzene-naphtha). About two or three ounces of equal parts of paraffin and stearic acid for gallon of benzene makes a most satisfactory proportion. After impregnating the goods, the fabric is dried in a machine provided with a condenser, so as to recover the benzene for re-use. Fabrics so waterproofed are practically impervious to water and the "proofing" lasts even longer than the utility of the duck.

Waterproofing Umbrellas
Tannic Acid 10
Sulphonated Oil 200
Lead Acetate 5
Aluminum Sulphate 10

Olive Oil	20
Pyridine	4
Water	1000

Pass fabric rapidly through the above solution at 50-60° C. and immediately centrifuge. Repeat until required degree of waterproofness is attained.

Flameproof, Waterproof and Mildewproof Coating for Textiles Pigment Composition Formula No. 1

Antimony Oxide	12.0
Zinc Oxide	1.5
Black Iron Oxide	1.2
Olive Drab Composite	15.3
Non-Volatile Vehicle	
Formula No. 1	No. 2
Cl l I D	

Chlorinated Paraffin  $16.2 \cdot 16.2$ Wax Polychlorphenol 1.8 1.8 Nevtex 10 Resin 10.2 Acrawax C 1.8 Nevtex 90 Resin 11.1 Volatile Solvent Formula No. 1 No. 2

Neville Hi-Flash Solvent 40.0 Xylol 32.0Isopropanol 8.0 Resin

Polyvinylbutyral Resin 10.0 Xylol 90.0

The Acrawax C is melted into the chlorinated paraffin wax or Nevtex 10 Resin. All the ingredients except the solvents are combined at room temperature and ground on a 3 roll differential speed paint mill. When a uniform grind is obtained, thin with the solvent. Grinding the thinned pigment dispersion is not recommended—stirring is sufficient.

Vinyl Butyral Resin is prepared by wetting it with xylol, stirring to a slurry, and then adding the alcohol. About 4 hours agitation is required to dissolve it. A tumbling drum or other closed means of agitation is preferred.

The pigments, chlorinated paraffin wax, Nevtex 90 Resin, and polychlorphenol are mixed together and ground on a 3 roll paint mill. This ground mixture is then thinned with the remainder of the solvent not used in preparing the Vinyl Butyral Solution. After the thinned pigmented composition is made uniform by stirring, it is added slowly to the requisite Vinyl Butyral Resin Solution or vice versa. The whole is stirred together until uniform. Grinding the final solution is not recommended.

## Identification of Naphthol Dyes on Fibers

Reds produced on yarn or pieces with Naphthol AS may be detected in most cases by treating the dyeings with chlorine at 3° Tw., the solution weakly acidulated with hydrochloric acid. Direct, developed and sulphur dyestuffs, also Alizarine Red, are destroyed within a short time. If the color withstands this test, it is reduced by heating with hydrosulphite (conc.) and caustic soda. If the color disappears and then returns on exposure to air it may be assumed to be a vat color. If the color does not return and the material remains white it most likely is Para Red but if the material retains a slight yellowish coloration, the dyeing may be assumed to have been produced with Naphthol A 10% by weight solution of AS. To verify, it is advisable to

make a sublimation test. Para Red sublimes, Naphthol Reds do not.

Glycerin Aid in Micro-identification of Textiles

In the microscopic analysis of textile fibers glycerin is a most useful temporary mountant. Glycerin is the best all-around mounting medium; it is easily removed from the used slides with either warm water or soap, and is in addition without odor. However, since the index of refraction of acetate fibers is almost the same as that of glycerin, bromonaphthalene alpha is advocated as the mountant when such textiles are being studied.

In the identification process, a drop of glycerin is placed upon the slide, and the fiber sample (about 3/16 inches long) is brought on the drop and teased apart with mounted (dissecting) needles, and finally covered with a cover glass. Practice will soon enable one to determine the correct size of the drop of glycerin so as to avoid smearing and waste.

If desired, it is easy for a technician to convert these temporary mounts into permanent slides for filing for future reference and comparison. All that is necessary is to seal around the cover glass with hot paraffin which is applied with a soft camel's hair brush such as is used for water colors. Properly labeled, in time such a collection will form an invaluable textile fiber slide library.

Fiber Identification Stain Acid Fuchsin (Color Index

No. 692) 6 g. Picric Acid 10 g. Tannic Acid 10 g.

National Soluble Blue 2B Extra (Color Index No.

707)

The dyes may be ground together and dissolved together, or dissolved separately in any order and diluted to 1 liter, with water. While the over-all concentration may not be very critical, these ratios of components appear to give the best differentiation. The dye mixture can be dissolved readily only in hot water, but the solution may be used hot or cold. Momentary immersion in the hot solution is sufficient, but commonly something over 2 minutes is allowed for cold dyeing. A thorough rinsing in water completes the test. Some dyed textiles may be identified without previous bleaching. The fibers are treated as usual, and then rinsed. When pressed wet (after rinsing) between white absorbent papers, a dye mixture characteristic of the color which would have been shown by the undyed fibers is transferred to the papers.

The colors shown by common fibers are:

Vegetable fibers Synthetic fibers

Cotton or Linen Acetate or Nylon Cuprammonium Viscose Vinyon Wool Silk (Raw)

Light blue Pale greenish yellow Dark blue Lavender Very pale blue Yellow Black

Animal fibers

Silk (Degummed) Brown

# IDENTIFICATION OF RAYONS AND NATURAL SILK

		CHARDONNET	GLANZSTOFF COLLODIUM	XANTHOGENATE LUNA	
REAGENT	ACETATE	NITRO	CUPRAMMONIUM (BEMBERG)	VISCOSE	TRUE SILK
Burning  Water Acetone Acetic Acid (Conc.) Chloroform Ammoniacal Copper Oxide Chromic Acid Million's Reagent Decolorized Magenta Ammoniacal Nickel Oxide Alkaline Glycrol Copper P-Nitraniline Diphenylamine Brucine Sulphate Fehling's solution Relling's solution Alkaline Silver Nitrate Sulphuric Acid Ruthenium Red Iodine Zinc Chloride Iodine Zinc Chloride	Melts hard, black beady residue No swelling Soluble Soluble Soluble Soluble Soluble Swells but not dissolved Unstained Swells, not dissolved No color No color Blue Dissolves slowly Colorless Yellow Yellow	No odor, burns slower than viscose All swell All insoluble All insoluble All insoluble All insoluble Swells quickly, dissolves slowly Dissolves cold Unstained Unstained Swells, not dissolved No change Unstained Swells, not dissolved Red Green Quickly dissolves yellowish solution Violet Reddish violet Violet	Easiest to ignite, no odor, slight ash All swell All insoluble All insoluble All insoluble All insoluble Swells slowly, dissolves slowly Dissolves cold Unstained Unstained Swells, not dissolved No change No color No color No color Blue Dissolves slowly, yellowish brown solution solution slight plue Light blue	No odor, burns slower than Cupra. All swell All insoluble All insoluble All insoluble dissolves bissolves bissolves cold Unstained Swells, not dissolved No change Uncolored No color No color Blue Brown Guickly dissolves, rusty brown solution Pink Blue Brown Solution Pink Blue Brown Solution Blue Brown solution Shue Shue Brown solution Blue Brown solution Blue Brown Solution Blue	Odor of burning feathers, black ash All insoluble Dissolves on boiling Insoluble Fibroin dissolves Dissolves slowly Colored red Colored pink Dissolves quickly Dissolves quickly Red Quickly dissolves Fale
•					

The presence of this new synthetic among acetate and other fibers is indicated by a treatment with potassium permanganate followed by the usual stripping of the brown coloration in a bath of sodium bisulphite. Nylon retains some of the brown stain while other fibers are bleached.—Nylon shows affinity for many classes of color but best results so far are obtained with the SRA types. Nylon is difficultly soluble in most reagents. Phenols and Formic Acid are active solvents. Nylon materials are practically non-inflammable.

The stain is also useful in the identification of films of cellulose acetate or viscose (cellophane), giving the above colors. The colors realized with any such dye mixture will depend somewhat on the history of the sample tested, and increased confidence follows a check by other dye mixtures.

Distinguishing Linen and Cotton

The unknown fiber and one each of cotton and linen are soaked in a 5% solution of ortho hydroxy quinoline sulphate for ten minutes. Wash well and place in a 5% soda ash solution. Examine the samples under ultra-violet light. Linen fluoresces a brilliant canary yellow while cotton does not fluoresce and appears dark violet.

Sizing	
Starch	14.0
Wheat Flour	48.5
Mineralite	64.0
Water	350.0
Oil and Drier (Linseed)	55.0
Paraffin Wax, Amorphous	33.0
Annual Control of the	

Adhesive Sizing for Rayon Warps
U. S. Patent 2,231,050
Starch
Lactic Acid
Sodium Chlorate
Heat to 110° C. to solubilize starch.

Nylon Yarn Size	3
Polyvinyl Alcohol	6%
Boric Acid	2%
Water	92%

Textile Sizing, Thermoplastic U. S. Patent 2,230,792 Five hundred grams of (eth)

Five hundred grams of (ethylcellulose 16.6 plus hydrogenated

methyl abietate 3.4 plus toluene 56.0 plus butyl alcohol 16.0 plus "highflash" naphtha 8.0 g.) is emulsified in a colloid mill with 300 g. of water containing sodium lauryl sulphate 1.5 and (if the m.p. of the size is not more than approximately 205°) sulphonated castor oil 3 g. The fabric is immersed in 1% aqueous aluminum chloride and squeezed, and the emulsion applied from paddle rolls; excess is squeezed out, and the ethylcellulose dried at approximately 138° and pressed at a temperature which incipiently fuses the size (e.g., approximately 171°).

Logwood Textile Sizing

For black shirtings, glaces and similar materials with a hard finish, the finishing size is frequently stained with logwood. For 100 gallons size, the usual quantities are:

Sizing Awning Duck

When sizing 10s skein mineral dyed duck yarn the fact that the dye deposits a stiffening mineral matter in the fiber should be considered in selecting a suitable size that will have a tendency to make a boardy finished product. A suitable formula which should give an efficient weaving quality to the yarn is as follows:

ab Idilows.			
Water	100	gal.	
Corn Starch	80	lb.	
Potato Starch	40	lb.	
Beef Tallow	15	lb.	

Stir thoroughly in cooker for 8

to 10 minutes before applying heat, then bring to a boil as quickly as possible. Then shut off steam and reduce the mixture to 175° F. and maintain same for use. If the finish is too harsh, decrease the corn and potato starch in equal proportions and increase temperature to 185° F.

This procedure carefully adhered to should give a satisfactory sizing to the yarn, and the dye in question should not be affected with regard to brilliancy in the finish.

Rayon Fabric Desizer
German Patent 703,497

Soda Ash 1–5 g.
Sodium Bicarbonate 1–5 g.
Hydrogen Peroxide
(40%) ½–1 g.
Water 1 l.

Lusterizing Finish for Rugs
Diglycol Laurate 1 pt.
Dry Cleaners' Solvent 5 gal.
Apply to pile of rug or carpet with
a clean, soft cloth.

Increased Flexibility and Luster for Cotton and Rayon Braid

A mixture of Glyceryl tristearate and Flexo Wax C gives high luster and flexibility to cotton and rayon braids, shoe laces, etc. The blended waxes are melted and the braid is run through in continuous lengths and then over brushes on polishing rollers. The addition of oil soluble colors to the wax mixture will enable the coating to be used for different colored braids.

Lusterizing Delustered Rayon
Ammonium Adipate 10
Gum Tragacanth Solution
(8%) 51
Water 39

This is printed on the delustered acetate rayon fabric and then dried. Afterwards the fabric is steamed for about one-half hour at 100° C. and then rinsed. A clearly defined lustrous pattern is thus produced on a matt ground.

Textile Duller (Delusterant) for
Hosiery
Formula No. 1
Barium Chloride 40
Anhydrous Zinc Sulphate 26
Dextrin 22
Starch 12

All ingredients should be finely powdered and intimately mixed.

No. 2
Barium Chloride 48.0
Corn Starch 8.5
Hydrous Aluminum Sulphate 43.5

Bleaching Textiles

For fabrics made of rayon taffeta and cotton yarn the following bleaching procedure is recommended: (1) washing at 95-100° for 80 minutes in a solution containing 20 g. of sodium hydroxide and 5 g. of sodium ricinoleate per liter of water, (2) washing with hot and cold water, (3) treatment with alcohol for 2-5 minutes at 40-50° in a solution containing 3 g. of active chlorine and 2 g. of sodium silicate per liter, (4) washing with cold water, (5) acidification with sulphuric acid (5 g. per liter) and washing with cold water.

Bleaching Cotton with Perborate For yarn the process is as follows: 2000 lb. cotton yarn is soaked in boiling water for about half an hour, rinsed, centrifuged, and packed in a boiler provided with a circulating

pump. The goods are then heated in the bleach lve for four hours at a pressure of about 22 lb. with constant circulation. The goods are then rinsed in the boiler, taken out. soured with 1/2% of sulphuric acid, rinsed again, blued if necessary, and dried. The bleach lye is made up as follows: 100 lb. caustic soda and 50 lb. soap or 25 lb. Turkey-red oil are dissolved in 2000 gal. of water. In the meantime another solution is prepared of 15 lb. sodium perborate and 12 lb. aluminum sulphate in a convenient but not excessive quantity of water. The caustic soda and soap solution is then mixed with the perborate solution.

Piece goods are freed from dressing the first place, and then well rinsed. Scouring is unnecessary except in the case of very dirty goods. The pieces are then steeped in the bleach liquor and heated in the caustic soda lye for four to five hours while the whole liquid circulates under a pressure of 22 to 30 lb. The subsequent processes are as

for yarn.

Bleaching Textiles with Textone Cloth—1200 yards cotton and acetate collar interlining.

cetate conai intermin	ıg.	
Water	1000	gal.
Textone	8	lb.
Wetting Agent	8	lb.
Acetic Acid (56%)	12	q.
Phosphoric Acid		
(85%)	1/2	p.
Tetra Sodium Pyro-		-
phosphate	1	lb.

The temperature is maintained at 185° F. or higher for a period of two hours. It is possible that a satisfactory bleach may be obtained in a shorter period of time. When the

desired bleach is obtained, the cloth is given one hot water and one cold water wash and then dried.

Textone is also being successfully used on the acid side for bleaching and preparing spun rayons, rayon taffeta crepe and other rayon fabrics.

Another use of acid Textone is for pre-treating "Nylon" or rayon hosiery. The following is a typical procedure:

## Solution

Cloth Ratio	35:1
Textone	0.1%
Wetting Agent	0.1%
Acetic Acid (56%)	0.3%

The solution is made up at a temperature of 135° F. The hosiery is immersed and during a period of 20 minutes the temperature is raised to 155–160° F. The hose are then washed and dyed in accordance with customary practice. Besides giving the hose a greater dye amenability, fewer tiger stripes are encountered.

In practically all cases where acid Textone is employed the equipment must be made of acid resistant material. The process can be used safely in vessels made of wood, stainless steel or nickel. The presence of copper, bronze, brass, or Monel metal may cause greenish or yellowish stains on the goods. In many cases stainless steel clad equipment will show apparent excessive corrosion. Investigations generally reveal, however, that this is caused by the liquor penetrating a pin hole in the stainless steel lining and corroding the underlying metal. The addition of small quantities of tetra sodium pyrophosphate is effective in minimizing such corrosion.

## Scouring Rayon Circular Knit Fabric

- 1. Run water in kettle (80° to 120° F.) using minimum amount that will enable the fabric to run freely over the reels. A properly loaded kettle of the correct type requires approximately a 20 to 1 bath.
  - 2. Load kettle with fabric.
  - 3. Add 2 lb. soda ash or trisodium-phosphate (depending upon water conditions).
  - 4. Turn on steam and run goods for 10 minutes.
  - 5. Add 3 lb. high grade neutral soap—olive or red oil base.
  - 6. Add 2 lb. "soluble pine oil" or a similar solvent containing material. If desired this solvent material and soap can be added simultaneously in order to aid solvent dispersion.
- 7. Raise bath to boil. Observe condition of bath at all times. If bath does not show a good, clean, sudsy condition, add more soda soap and pine oil. It is impossible to accurately predict the amount of soda soap and solvent or the exact proportions of the same that will be required under an unknown set of conditions.
- 8. Run the kettle at or near the boil for one hour.
- 9. Drop bath and proceed with bleaching or dyeing operation.

Dyeing "Black-Out" Cloth

Pad Liquor

Aniline Hydrochloride (16° Tw.) 20 gal.

Prussiate Liquor 44 gal.

Acetic Acid (56%) ½ gal.

1

gal.

Aniline Oil

Gum Tragacanth		
(6 oz.)	$2\frac{1}{2}$	gal.
Water	32	gal.

Prussiate Liquor

Sodium Chlorate 80 lb.

Sodium Yellow Prussiate 140 lb.

Water 50 gal.

Bulk to 100 gal.

Prepare in adequately cooled apparatus a mixture of the following proportions:

Aniline Oil	275	lh
Muriatic Acid	210	10.
(32° Tw.)	300	lh.
Water	355	

Run the cloth through the pad liquor, then through the squeeze rolls, and directly on to the dry cans.

After padding, the goods are dried on dry cans and should come off slightly greenish in shade, and after running in the rapid aniline ager for one minute they should come out a green black. Passage through hot soda ash solution to neutralize the acidity, together with hot sodium dichromate to develop the oxidation to the ungreenable black, and a good soaping completes the process.

Common practice is to utilize the open range, but a rope soaper is more thorough in washing effectively.

Brown (Vegetable) Dyeing of Cotton

Cutch 35 lb. Hypernic Extract 16 lb. Logwood Extract 3½ lb.

Add to dye bath and boil until dissolved, then add 3 lb. copper sulphate, add cold water, rake well and enter yarn. Give 6 turns and put

down over night. Take up, give 6 turns, introduce into a solution of 4 lb. Chrome at 160° F. and give 6 hours. Remove, wash well in cold water, put back in cutch liquor, 6 turns; into chrome, 4 turns; into cutch, 4 turns; into chrome, 4 turns. Wash off each time after chrome. Start new kettle with

Fustic Extract 7 lb.
Logwood Extract 3½ lb.
Boil well for 2 hours.

## Dyeing Cotton with Chrome Logwood

Dissolve 3.3 lb. of bichromate of potash in a small quantity of water, mix the solution with 100 gal. of logwood decoction at 3° Tw., and add 7.7 lb. hydrochloric acid, 34° Tw. The cotton is introduced into the cold solution, and the temperature is very gradually raised to boiling point. The cotton acquires at first a deep indigo-blue shade, which changes to a blue-black on washing with a calcareous water.

A slight modification of this process consists in working the cotton in a solution containing at first only the bichromate of potash and hydrochloric acid, and adding the decoction of logwood to the dye-bath in small portions from time to time, gradually raising the temperature as before.

Logwood Speck Dye

Logwood Extract
(51° Tw.)

Soda Ash
Copper Sulphate

12 lb.

This should be diluted to about 2°-3° Tw.

Dyeing Vat Colors on Thread and Yarn

Package Dyeing Procedure
Shade: Khaki. Pigment Method
Soap Flakes—2%
Dye—X%

Circulate the above liquor at 180° F. on the dry packages for ten minutes, or until the entrapped air has been displaced.

Add.

Caustic Soda—¼ oz. per gal.

Sodium Hydrosulphite—¼
oz. per gal.

Circulate 20 min. at 180° F. Rinse inside out with running cold water, overflowing to sewer, until neutral to Clayton Yellow Paper.

Add:

(100 vol.) Hydrogen Peroxide—1%

Circulate 10 min. at 140° F. Add:

Soap Flakes—1½% Circulate 20 min. at 200° F. Rinse twice at 200° F., 10 minutes each.

Cascade Machine Procedure
Shade: Khaki. Reduced Method
Soap Flakes—¼ oz. per gal.

Dye—X%

Caustic Soda—1 oz. per gal. Sodium Hydrosulphite—1 oz. per gal.

The dye is reduced for five minutes at 200° F. The liquor is then circulated on the dry yarn and dyeing proceeds for six minutes. Cold water is then circulated until oxidation is complete.

The dyeing is oxidized at 140° F. with 1/16 oz. of hydrogen peroxide per gallon, and soaped ten minutes at 200° F. with ½ oz. of soap per gallon. Rinsing completes the operation.

## Hand Tub Procedure

Shade: Khaki. Reduced Method

Dyebath: 120° F.

Caustic Soda—½ oz. per gal.

Deceresol AS—1/5 oz. per gal.

Stock vat: 140° F.

Dye-X%

Caustic Soda—4 oz. per gal. Sodium Hydrosulphite—4 oz. per gal.

Soft Water—1 gal, per 4 oz. of double strength dye Reduce ten minutes at 140°

F.

The scoured thread is worked in the dye bath and then laid up while the reduced dye is added. The thread is worked in the dye until the desired shade is attained.

The dye bath is drained, and the thread is rinsed in cold water, oxidized with 1/16 oz. of hydrogen peroxide per gallon, and soaped at a boil with ½ oz. of soap per gallon.

## Buhlman Machine Procedure

Shade: Khaki. Pigment Method Deceresol OS-1/10 per gal.

Dye-X%

Caustic Soda—¾ oz. per gal. Temperature—140° F.

Enter dry thread and run five minutes. Add:

Sodium Hydrosulphite — ¾ oz. per gal.

Run until shade is correct, adding salt if necessary.

Drain, oxidize at 140° F. with 1/16 oz. of hydrogen peroxide per gallon, and soap ten minutes at 200° F. with ½ oz. of soap per gallon.

## Klauder Weldon Machine Procedure

Shade: Khaki. Pigment Method Deceresol OS—1/10 oz. per gal.

Dye—X%

Temperature-140° F.

Run for ten minutes at 140° F. Add:

Caustic Soda—¾ oz. per gal. Sodium Hydrosulphite—¼ oz. per gal.

Run five minutes. Add:

Sodium Hydrosulphite — 1/4 oz. per gal.

Run five minutes. Add:

Sodium Hydrosulphite — 1/4 oz. per gal.

Common Salt—2 oz. per gal. Run ten minutes. Run in cold water and rinse ten minutes. Drain. Refill machine with cold water and rinse ten minutes. Drain.

Oxidize ten minutes at 140° F. with 1/16 oz. of hydrogen peroxide per gallon. Add ½ oz. of soap per gallon and run ten minutes at a boil. Drain and rinse.

Vat Dye Reducing Bath
Caustic Soda 5 lb.
Sodium Hydrosulphite 5 lb.
Deceresol AS 1 lb.
Water (140° F.) 80 gal,

Vat Dye Oxidizing Bath Formula No. 1

Sodium Bichromate 2 lb.
Acetic Acid (56%) 3 qt.
Water (140° F. or
212° F.) 40 gal.

No. 2

(100 vol.) Hydrogen Peroxide

Acetic Acid (56%) Water (140° F.) 2 lb.

3 qt. 40 gal

## No. 3

Ammonium Persulphate 2 lb. Acetic Acid (56%) 3 qt. Water (80° F.) 40 gal.

The cloth is then rinsed several ends at a boil after which it is aftertreated in a soaping bath prepared as follows:

Soap Flakes 2 lb.
Soda Ash 2 lb.
Water (212° F.) 80 gal.

After two to four ends in the boiling soap bath, the cloth is rinsed several ends at a boil and is shelled up, dried, and finished.

## Mineral Khaki Color

This form of dyeing is used on army field equipment such as heavy duck, canvas, etc., for tents and army cots. It is not permitted for clothing or anything coming into close bodily contact.

This dyeing method is simple and productive and consists, actually, of producing a mixture of iron and chrome oxides within and upon the fabric fibers from a bath of black iron liquor and acetate of chrome to which is added an agent for leveling and penetration. A standing bath is used and replenished as needed.

A red shade of khaki is produced with:

Black Iron Liquor
Acetate of Chrome
(8%)

5 gal.

Levelene 1 gal. which is brought to a volume of 50 gallons with cold water.

The material is simply padded cold in this solution, then dried at

about 200° F. to drive off the acetic acid formed. Following this the material is soaped at an elevated temperature to develop the shade. About 1 oz. soap and 2 oz. of soda ash is used per each gallon of bath.

Greener shades of khaki or olive drab can be made by increasing the chrome acetate and decreasing the quantity of iron liquor.

Dyeing of Synthetic Wool Fibers

Aralac, a casein product, one of the new synthetic wool fibers, may be successfully dyed with many acid colors.

Some of those colors applied and found satisfactory are:

Brilliant Milling Yellow 5G Amacid Yellow R Supra Amacid Fast Yellow RS Amacid Milling Yellow O Amacid Neutral Orange G Amacid Neutral Orange SGS Polar Orange GS Polar Orange R Amacid Milling Scarlet G Amacid Red 3B Amacid Milling Scarlet 3R Amacid Azo Phloxine G Formvl Violet 3B Amacid Blue A Sulphon Cyanine 5R Alizarine Green CE Ex. Brilliant Milling Green B Ex. Amacid Black 10BR Conc. Sulphon Cyanine Blacks

These may be dyed at the boil with 10-15% Glauber salt and 3-5% acetic acid.

In mixtures with real wool and synthetic fibers, the latter draws the color faster.

## Fugitive Wool Colors

(For tinting wool for identification purposes, to be later cleared by soaping.)

Indigotine Conc. Ultramarine Blue

Amacid Chinoline Yellow Ex.

Kiton Fast Violet 10B

Amacid Fuchsine 10B Conc.

Orange II Guinea Green B

Carmoisine B

Amacid Blue A

Amacid Black 10BR Conc.

The tints are applied for 10 minutes at 100° F., extracted and dried. When required the tint is removed by soaping at 140° F. with a clear, hot rinse.

## Dyeing Brush Bristles

When dyeing fiber materials to be used for the manufacture of brushes, etc., and necessitating the material being dyed through well, it is best to use a combination of about 2–3% of a Direct Black and 2–4% logwood extract.

Charge the starting bath with 2% ammonia and \(\frac{1}{4}\)-\frac{1}{2}\% soda ash, add 2-3% dve previously well dissolved in condensed water, and then about 5% cryst. Glauber's salt; boil up well, enter the material, work for 5-10 minutes, cover with a lattice frame weighted with stones, boil for 2-3 hours, and allow to feed for  $\frac{1}{2}$ -1 hour in the cooling bath. Then lift the material, allow it to lie exposed to the air for several hours, and enter into a fresh bath heated to 30°-40° C. (85°-105 F°.) containing pyrolignite of iron of 4°-7° Tw.; leave in this bath for ½-1 hour, throw out and leave exposed to the air for several hours, rinse well and dry.

If so-called patent or luster-fiber is to be produced, the method of working is exactly as described above; only the fiber is finally taken through a bath of 40°-50° C. (105°-120° F.) charged as follows:

Liquor , 10 gal. Gelatin Glue 2 lb. Soft Soap 2 lb. Logwood Extract 2 lb. Fustic Extract ½ lb.

Pyrolignite of Iron ½ lb.
Treat the goods in this bath for thirty minutes, allow to drain, and brush dry with suitable brushing machines. If the fiber is not lustered, 8 oz. of whitening per 10 gallons liquor are added to the bath of pyrolignite of iron.

The dye liquors may be used repeatedly; dyeing in the standing bath requires about ½-⅔3 of the stated quantities of dye and logwood extract, equal quantities of soda and ammonia, and about 3% salt calculated on the weight of the goods.

## Lubrication for Nylon, Vinyon and Other Textiles

In many cases, expensive olive oil can be replaced by a soluble oil consisting of the following:

Diglycol Laurate 12.0 lb. White Mineral Oil 87.9 lb. Tergitol 0.1 lb.

This solution is easily made in the cold. The color is almost water-white, the emulsions in water are stable and easily removed. This preparation is suggested as a worsted lubricant, rayon coning oil, spun rayon stock lubricant, Nylon

and Vinyon lubricant, mercerizers lubricant, finishing and luster oil for cotton, rayon and other natural and synthetic materials. It is also recommended for silk-soaking and for lubrigation of needles and sinkers. When used as a worsted stock lubricant, it is applied in combing, carding or spinning operations as an oil, or in the emulsified condition. The amount of oil required in the finishing varn determines the proportions used. In rayon stock lubrication, the straight soluble oil is sprayed. A water emulsion should not be used unless other fibers in addition to rayon are present. In such a case, the emulsion must be sprayed on a aver of the non-rayon fiber, then ay down a layer of rayon, then another layer of compounding fiber, etc. In mercerizing, an emulsion of the proper proportions is used in the finishing bath. The 100% oil is applied on the coning machines. For finish and luster the emulsion is used in the last rinse or finishing bath.

For needle and sinker lubrication, the straight oil can be applied by spraying or brushing on needles and sinkers. Metal parts are not discolored or corroded by this preparation.

The unusually high dye solvency of Diglycol laurate permits incorporation of tints in the soluble oil, so that the tinting operation may be carried on simultaneously with any one of the above operations. In addition to the fact that this oil is very much cheaper than olive oil, it has the advantage of being non-oxidizing, stainless and will not carbonize or become rancid. It is anhydrous and free of acids, completely self-emulsifying and easy scouring.

British Patent 539,3	33
Mineral Oil (Colorless)	64.3
Tricresyl Phosphate	11.6
Oleic Acid	10.9
Triethanolamine	5.7
Sulphonated Olive Oil	5.0
Sperm Oil	2.5
Dye Printing Past	e
Induline B Powder	1.5
Ethyl Tartaric Acid	
(20° Tw.)	6.0
Acetin	4.2
Water	5.3
Acid Starch Paste	60.0
Acetic Acid (9° Tw.)	8.0
Tannic-Acetic Acid Solu	
tion (50%)	15.0
	10.0
Printing on Plush	
(Block Printing Dy	e)
Acid Dye	310 g.
British Gum,	
Powdered 3	325 g.
Glycerin	75 g.
Potassium Chlorate	25 g.
	30 g.
Ammonium Hydroxide 1	30 cc.
Water	5 l.
Direct colors (for cotton)	
printed similarly on wool	nile by
means of this recipe.	pire, by
But when direct colors a	no to ha
printed on mixed fabrics, p	hoophoto
of gods is added and the se	nospnace
of soda is added, and the sa	in which
frees the acid (oxalate of an	imonia),
is suppressed.	C1
For printing on mixed	
wool, cotton and silk, the	color 18
prepared with, for example	
Substantive Dye	6
Phosphate of Soda	3
Brown Glycerin, Thick-	
7 4 7 1	

ened According to the

1 (to 1.5)

Quality of the

Fabric

Synthetic Textile Fiber Lubricant

British Patent 539 333

Chrome colors may be used also for printing plush, for example, according to the following recipe:

Chrome Dve in Paste

Form (20%)	454 g.
Acetate of Chromium	283 g.
Oxalate of Ammonia	273 g.

Designs of large area, of brown or taupe, are enriched by printing their center with campeche black. The color (to be printed), is applied with an ordinary stenciling brush, and the borders of the central design are rubbed, in order to blend them more or less imperceptibly with the rest of the original design. Campeche is used for super-printing fabrics of great value, which have been printed, steamed and washed. The campeche black is prepared in the following manner:

Campeche Black

А	

$\mathbf{A}$		
Pyrelignite of Iron		
(20° Bé)	4.5	1.
Tapioca	1.350	kg.
Wheat Starch	680	g.
Water, To make	20	1.
В		
Hematine (Paste)	9	1.
Acetic Acid		
(6° Bé)	1.5	1.
Iron Sulphate	2.040	g.
Nitrite of Soda	425	g.
Bisulphite of Soda		
(35° Bé)	125	cc.
Water, To make	16	1.

equal parts of B. After printing, the fabric must be lightly dried and steamed as in the printing of ordinary wools.

Equal parts of A are mixed with

To prepare printing colors for mixed plushes, composed of silk and mohair, or cotton and mohair, it is often necessary, in the desire to obtain a solid color on all the fibers, to use, with substantive dve, an acid color which is fixed with medium neutral fixing, excluding, however, the dves which reduce very easily, such as marine blue and sulphocyanine blacks. In the presence of oxalate of ammonia, acid dyes of combination resist washing better which follows the steaming. To the contrary, few of the substantive dyes color vegetable fibers with dark shades, when the dve contains acid. It is necessary, therefore, to try the colors before combining them.

Brown pigment of manganese is used to produce certain effects, as much on mohair plush as on alpaca plush. The printing composition is prepared as follows:

Permanganate of

Potash	267	g.
Magnesium Sulphate	200	g.
Gray China Clay	133	g.
Boiling Water	400	cc.

The mixtures may be used after recooling.

To fix and develop this color, it is not necessary to steam it; it is sufficient to rinse the printed fabrics in cold water. To raise the points of white nap, the nap points are brushed with a cutting solution made of:

Hydrogen Peroxide

(12 Vol.)	9 1.	
Acetic Acid (30%)	850 cc.	
Oxalic Acid (20%)	850 cc.	

If black effects are to be produced on the brown pigment of manganese, it is sufficient to treat the fabric for some minutes in a bath containing aniline salt and sharpened with sulphuric acid. The development of the aniline black which is thus formed, is completed by finally soaping the pieces in a hot bath containing ammonia.

For other kinds of lifting, acid colors are used in place of brown pigment of manganese. The necessary acid color is printed, and, after being steamed and washed, the fabric is extended on a table and then the points of the nap are brushed with a discharge, such as:

Rongol NC 285 Oxide of Zine 140 British Gum Thickening 575

After having been lightly dried, the fabric is steamed for three minutes, without pressure, then washed

and allowed to dry.

Ordinarily, mohair plushes are made brilliant or glazed before printing. For this effect, the down is coated with a heavy sizing of white flour or British gum boiled in water. The sizing is allowed to dry, and the pieces are then steamed for an hour in 3–4.5 kg. per cc. of goods, then washed with lukewarm water. The brilliancy of finish is added to by repeating this treatment several times.

To obtain "uniformity" on mohair plush, the pieces are treated in a bath of carbonate at 6° Bé, for nearly one hour at 75–80° C., then rinsed freely with cold water. Good imitations of young animals and others of the same kind are obtained.

Further, these unions are used to produce waves, by setting the nap by means of rotating brushes, kept constantly humid by a spray of water across their width. The water is sometimes replaced by a fluid paste of flour or British gum, serving to lubricate and adhere on the nap. In this case, the waves obtained by the brushing are fixed by steaming.

The action of the water, in the presence of diastases, adds further to the luster of the waved nap.

On imitation fur plushes of short hair, special effects may be produced by printing with metallic powders. To do this, the plush pieces are first steamed on a rotating cylinder, in order to get the best possible uniformity of the nap.

Here is a recipe for a metallic printing composition, capable of being applied by block as well as by steneil:

Phenol 2
Acetone 4
Cellulose Acetate 3
Metallic Powder 1

Printing effects (mechanical), or embossing, may be obtained on certain qualities of plush. The best effects of this kind are obtained by passing the pieces between engraved and heated rollers.

The hair may also be curled and shrunk in places, by printing a strong solution of sulphocyanide of calcium, thickened with tragacanth, on the plush; afterwards, the pieces are steamed, washed and dried. The hairs are also curled and relooped, to contrast with the rest of the cover of the plush.

To imitate the pelt of a leopard, tiger and other savage animals, printing is carried out by means of a block, of which the engraving is very hard and also deeper than that of the other blocks of the print. Notice that dull rayon possesses ideal properties for producing this article, thanks to its appearance, to the subduing of its luster, to its soft, impressive feel, resembling that of fur, and also because this fiber permits the production of the particular

colors of the fur. Further, dull rayon is especially well adapted to the operations of manufacture.

The skin of the ocelot is imitated. for example, with a plush of two wefts, with a mercerized raw cotton back (102/2) for the warp, and 40/1for the west). Dull Celta (woven 120/1), unbleached, is used to form the hair. As a height for the nap, a height of 4 to 6 mm. is the one which is most adaptable, with a count of 50 to 60 hairs per square cm., the tuft being formed with W. (tungsten). The pieces are 120 cm. wide and to 35 meters long; in sorting and inspecting the weave, they are uniformly dampened with lukewarm water on a squeezing spray (moistening machine), then they are brushed on a machine of a single cylinder, with the cylinder cold, to smooth and straighten the curls. The pieces enter the machine through their leader. Care must be taken to preserve the same direction of the nap during the process of printing; for if the direction of the nap is reversed, the outlines of the printed design will become waved to the detriment of the colored effect.

The pieces are then dried in a hot chamber, then pressed on the cylinder. The object of the last treatment is to compress the nap strongly on the foundation of the fabric, a condition indispensable to the success of the printing. Thus prepared, the pieces are ready for printing. If a good oily sulphonate is added to the moistening water, the printings will be more uniform.

In printing on plush, in particular, in the printing of several colors, the screen method has given the very best results, even in those which con-

cern the cost of operation. Small lots of pieces, more frequently, as brought out in the beginning, are printed preferably by hand. There exists, for large production and for very large designs which are in demand, apparatus for screen printing.

Take, for example, a print of three colors. The piece is put on the printing table, stretched in the direction of the warp by means of gripping rollers, governed by a hand wheel; in the direction of the length, the pieces are extended by nailing first a narrow strip on the table at intervals of 30 to 50 cm., then stretching the piece strongly in the direction of the weft and fixing solidly the other strip in the same manner (with nails), on the table. It is essential that the pieces remain firmly stretched, especially if they are to be printed with several colors, in order that each application of the screen will not disarrange the surface to be reprinted, and not interfere with the superplacement of the following color. It is necessary that the table should be sufficiently long in order to permit the stretching of each piece to its full length.

When the table is too small, screen printing becomes difficult and does not have the desirable continuity, because of the dislocation of the design at the part of the piece that is resting on the extremity of the table. The printing is carried out by means of frames enclosing the design, on which the color is poured, and which two men on each side of the table spread equally with the aid of a wooden blade. The imitation of ocelot is composed of two colors, and therefore, it is necessary for two pairs of printers to execute the

application, the first pair impressing the clear color and the second the deep color when the first pair has raised the frame (screen), to carry it back to its new position. Mordant colors are used for this kind of printing.

The preparation of the colors is

as follows:

Beige		
Anthracene Brown R	D	
Paste	20	g.
Alizarine Yellow R		
Paste	2.5	g.
Water	300	cc.
Starch-Tragacanth		
Thickening	600	g.
Acetic Acid (6° Bé)	30	g.
Chrome Green Acetat	e	
(20° Bé)	40	g.
Deep Brown		
Anthracene Brown R	D	
Paste	150	) g.
Alizarine Yellow R		
Paste	70	) g.
Alizarine Black S		
Paste		) g.
Water	70	) g.
Starch-Tragacanth		
Thickening		) g.
Acetic Acid (6° Bé)		) g.
Chrome Green Acetat		
(20° Bé)	150	) g.
In proporting these col	ore it i	e nac

In preparing these colors, it is necessary to watch that they always have the same consistency, in order that the tones may vary in intensity, much as when one carefully weighs the quantity of color. The proportion of starch must be more or less large, according to whether the prints are large or small in size. For the ocelot article, it is preferable not to print the hair as far as the base, in order to better imitate the fur. It is necessary, therefore, to

regulate the quantity of thickening. The number of displacements to be given to the scraper to spread out the dve on the plush depends on the quantity of color to be printed. Four displacements are calculated for the clear color, and six for the deep color. It is necessary that the pressure which the two operators exert on the blade is uniform so that the impression will not become deeper or lighter on one part of the fabric than on the other. The designs to be effected must be of such kind that the dves will not encroach one on the other, or not mutually color themselves. In order that the colored designs may retain all their clarity, it is necessary that the outlines of the different motives be separated by at least a millimeter.

The printed pieces, as is customary, are either transported in an ordinary drier, or extended on poles fixed to a movable frame and dried in an ordinary warm room at a temperature of between 40–50° C.

The pelts of the ocelot and leopard present a gradation of color, going from beige, nearly white, from the middle of the back to the sides. Naturally, if this diminution of shade is to be reproduced by screen printing, one has, of course, recourse to a spraying pistol. The third color to be applied for diminishing of the shade, is sprayed on the table. It is composed of:

Anthracene Brown RD	)	
Paste	5	g.
Alizarine Yellow R		
Paste	0.5	g.
Water	950	g.
Acetic Acid (6° Bé)	25	g.
Chrome Green Acetate		
(6° Bé)	20	g.
		-

This diminishing color must also be well pulverized before printing. But, in this case, care must be taken that, at the moment of stretching and fixation of the pieces on the printing table, the parts where the colored effect is deepest must be placed to correspond with the corresponding parts of the design.

After spraying the color, the piece is dried again on the frame, and if possible, left during the night.

following operation, The steaming, to fix the dyes on the rayon fiber, deserves the most careful attention. Chrome colors must be steamed with humid steam, for one hour at 0.1 kilo. It is carried out in a circular steamer of which the bottom is filled with water. The steam is introduced by means of a system of perforated tubes which boil and vaporize the water. Constantly humid steam is thus produced, which is a very important factor in obtaining uniform printings. The pieces are deposited on a frame, rolled up under tension in order that the different layers of the fabric will not come in contact with one another and so that the steam will pass freely between them.

If some parts of the nap of one fold touch on the back of the neighboring fold, the steam will not produce its effect here, and the color, insufficiently fixed or not fixed, will more or less totally fade when washed. The steaming must be well clear of air before the introduction of the frame loaded with the pieces. During the steaming, the steam must circulate perfectly; it is necessary that it enters in a continuous manner when it is ejected through the outlet valve. This is evidently

not a means of steaming cheaply; the procedure must seem crude, but, at least, it assures the success of the printing. Once steamed, the pieces are left suspended in the stretching frame for about an hour, until completely cooled, then they are removed and suspended again on movable frames and left there for 6 to 8 hours before rinsing.

It remains to eliminate the thickening and the excess of color which has not been fixed. This is accomplished best at width in a washer provided with pressing rolls operated on top of a trough situated in the middle of the tank, 60 cm. from the bottom, in order to directly throw off the water that is squeezed out. At the farthest part, the vessel contains an obstruction, on top of which is found a winding roll, the action of which is completed by another roll placed at a lower level and in the squeezing trough. In this latter, two faucets sprinkle water copiously on the two sides of the piece. Naturally, the fabric circulates in the direction that is not against the direction of the nap.

For washing, simply cold water is used which is renewed constantly in order that the parts not printed will not become tinted. The washing machine is particularly suited for cleansing printed plushes drawn at width. The system of sprays of water under pressure, in combination with the pressing rollers, free the fabric of the thickener and unfixed dve. The soiled water is collected in the central trough where it is thrown off through a pipe. In this manner, the rinsing water of the large rinsing vessel is not worthlessly polluted and does not color the base of the fabric. Washing at width for half an hour to an hour, follows the deepening of the color; the speed of the passage of the fabric in the spraying and rinsing trough is about 10 meters a minute. Then the pieces are squeezed at the end and dried.

It is then that the foundation of the surface of the fabric shows clearly the gradations of color characteristic of the natural fur, from yellowish white of the stomach to beige of the back, as well as the light and dark spots.

It remains to bring about the completion of the fabric, and the first precaution to take is to be assured that the pieces are completely dried, in which case the colors are stained or become soiled in the brushing machine.

The pieces are placed again in a moistening machine, and pressed out with cold water sharpened with acetic acid, then passed through a brushing machine of one cylinder, consisting essentially of a rotating cylinder carrying the piece off on its back, on top of which cylinder is situated a brushing roller, also rotating, which sets and smooths the fur. The guiding rolls and an obstruction complete the depositing brush. The pieces pass once in the direction of the fur, once against the direction of the fur, and again in the first direction. They must be subjected to a large number of passages, according to the density of the fabric, but the number of these passages is always odd, since the direction finally to be given to the fur must be the same as the first passage.

Notice that the damp fabric,

when removed from the machine after its first passage, is suspended on the frame to be dried in a warm room. Once dried, it is repassed three or four times in the same brushing machine, and finally it is clipped on an ordinary clipping cylinder.

After stretching and mangling on the back, the pieces are examined, measured and folded before being sent out.

Cotton Piece Goods Printing Preliminary preparation of cotton piece material for printing consists of:

- (1) Singeing, to remove the nap and produce a smooth surface. This operation is necessary to insure a uniform application of color in the intended design. Gas singeing is still in use for plain cotton goods which is passed quickly, full width, over a series of open gas flames.
- (2) De-sizing. This is accomplished by saturating the cloth in a dilute but hot caustic soda solution, or liquor from a previous kier-boil and allowed to lie in this state for several hours. Malt extracts are more efficient and faster. A thorough washing follows.
- (3) Kier Boiling comes next which is usually given under a mild pressure for 5–7 hours in a 5° Tw. caustic soda liquor. Natural waxes and seed motes are thus removed. A thorough rinse and scouring in 0.3° Tw. sulphuric acid follows and then a further rinse.
- (4) Bleaching is carried out by passing the goods through a cold solution of sodium hypochlorite of 2 grams available chlorine per liter and then piled for 1-3 hours. A

thorough rinse and, if necessary, an anti-chlore plus a rinse completes the bleach.

Hydrogen peroxide is sometimes used in place of chlorine and when conditions require it both bleaches

are applied, separately.

Cotton and materials of allied fibers are printed with selected groups from among the acid, chrome, and basic colors, as well as the directs, vats and those colors regularly used on cotton.

Basic Colors—Direct Printing

The printing paste is prepared with the requisite basic color, thickening gums, tannic acid for fixing the color and an agent for retarding lake formations. Acetic acid serves well as a retardant.

Victoria Blue B	15 g.
Acetic Acid (30%)	75 g.
Kromfax Solvent	40 g.
Hot Water	170 g.
Gum Tragacanth—	
Starch Thickener	600 g.
Tannic Acid Fixer	
(50:50 Tannic and	
Acetic Acid)	100 g.

After printing and drying, the material is steamed for one hour without pressure and then treated with tartar emetic—10 g. per l. at about 100–120° F.

Direct Printing with Ch	rome or
Mordant Colors	
Alizarine Yellow 2G	
Cone.	40 g.
Kromfax Solvent	40 g.
Hot Water	140 g.
Starch-Tragacanth	
Thickener	500 g.
Acetic Acid	50 g.

Olive Oil	30 g.
Acetate of Chrome	
(32° Tw.)	200 g.
The acetate of chrome	should be

The acetate of chrome should be added only after cooling the paste.

Print, dry and steam one hour, no pressure. Then rinse warm and soap hot.

A few typical items applicable by

this method are:

Alizarine Yellow 2G Conc.
Alizarine Yellow 4G Conc.
Mordant Yellow R
Alizarine Red S Conc.
Alizarine Brown HD
Chromogene Violet B
Chromaven Green G
Alizarine Blue Black B

Acid Colors (	Direct Printing)
Orange II	40 g.
Hot Water	200 g.
Gum Tragaca	nth
Thickener	430 g.
British Gum	100 g.
Acetic Acid	50 g.
Aluminum Ac	etate
(15° Tw.)	180 g.

Print, steam for 30 minutes, no pressure and treat warm to remove gum. No further washing.

Colors suitable are:
Chinoline Yellow N
Naphthol Yellow S
Amacid Yellow T Ex.
Crystal Orange
Orange II—RO
Amacid Fast Orange LW
Brilliant Croceines
Scarlet 2R
Brilliant Indocyanines
Soluble Blues
Amacid Fast Green 3G
Brilliant Milling Green B

Printing of Direct Colors

Practically all of the substantive colors may be printed but only a selected few have sufficient resistance to steaming, wash fastness and solubility to make them suitable for satisfactory direct printing.

Direct Color	20	g.
Hot Water	310	g.
Glycerin	50	g.
Sodium Phosphate	20	g.
Starch-Tragacanth		_
mi: I	500	

Thickener 500 g. Egg Albumen 100 g.

Print, dry, steam one hour without pressure then rinse in water containing salt. Aftertreating with ½ oz. Fastogene per one gallon of water at 100° F. for 15 minutes increases water fastness.

A few suitable colors are: Chrysophenine G Direct Orange WS Benzo Orange R Amanil Toluvlene Orange R Pluto Brown GG Amanil Brown MR. Amanil Brown D3G Amanil Fast Brown RLH Benzo Fast Scarlet 8BA Amanil Fast Scarlet 4BA Amanil Fast Scarlet 4BS Benzo Purpurine Amanil Fast Violet RRL Amanil Fast Violet 4B Benzo Azurine 3R Benzo Chrome Black Blue B Amanil Sky Blue FF Conc. Benzo Green FFG Amanil Green B Conc. Direct Deep Black E

Vat Color—Direct Printing
A great many of the vat colors
when satisfactorily prepared in smooth paste form or very finely

suspension consisting of 20 grams of freshly precipitated copper phthalocyanine and 80 grams of water. In this manner there is obtained a pig-

ground (micropulverized) powders are suitable for direct printing. The dyestuffs are thoroughly mixed into a thickener of "Vat Gum" prepared with the necessary reducing and fixing agents, i.e. Hydrosulphite AWC and a carbonate, usually potassium carbonate also accelerating materials such as glycerin and Kromfax Solvent.

So called Suprafix colors may be printed immediately upon mixing with the thickener. Others require a few hours in a warm temperature to effect a partial-reduction. In any case, a pre-reduced color fixes more readily.

Vat Color	40	g.
Glycerin	40	g.
Kromfax Solvent	40	g.
Starch—Tragacanth		•
Thickener	480	g.
Potassium Carbonate	80	g.
Hydrosulphite AWC	60	g.
Water	200	g.

After printing and drying, the material is steamed without pressure for 7-10 minutes in moist steam. Then, soaped at boil and finished.

Textile Printing La	cquer	
Nitrocellulose (Wet	_	
with 30% Butanol)	200	g.
Castor Oil	200	g.
Glyceryl Sebacate	170	g.
Secondary Hexyl		
Acetate	210	g.
Octyl Acetate	220	g.
Xylol	100	g.
Butanol	100	g.
and into this is then stir	red a	blue
suspension consisting of 2	0 gran	ns of
freshly precipitated coppe	er phtl	alo-
cyanine and 80 grams of		
		-

mented water-in-lacquer emulsion. By the further addition of 770 grams of water containing 6 grams of a wetting agent (for example, sodium lauryl sulphate) and 12 grams of Turkey Red oil, and passing the mixture through a colloid mill to disperse the ingredients more completely there results a stable blue lacquer-in-water emulsion (the reversion of the two phases should be noted) at once suitable for printing on fabric.

Textile Printing Resist
Formula No. 1

Precipitated Chalk
Potassium Sulphite
(90° Tw.)
Acetate of Soda
Water
365
Dark British Gum
325
Beat the whole into a smooth

Beat the whole into a smooth paste, heat until the gum is dissolved, and cool.

No. 2	
Zinc Oxide	200
Water	170
Glycerin	25
Beat into a paste, and add:	:
Dark British Gum	200
Gum Senegal (50% Solu-	
tion)	150
Turpentine	30

	•	
Starch-Tragacanth 7	hicke	ner
(Textile Printing Th	ickene	r)
Wheat Starch	15	lb.
Water (Cold)	15	lb.
Gum Tragacanth		
(60% Paste)	25	lb.
Olive Oil or Glaurin	3	lb.
Water	42	lb

Starch is pasted with 15 lb. water then gum tragacanth paste added plus olive oil followed by balance of water to make 100 lb. Then the whole is gradually heated while continually stirring; boil for 20 minutes and stir until cold.

Commence of the commence of th	-	
Textile Printing Paste	Thick	ener
Formula No.	1	
British Gum	5	OZ.
Wheat Starch	14	OZ.
Potassium Carbonate	$1\frac{3}{4}$	lb.
Glycerin		pt.
Olive Oil	1/4	pt.
Formosul (Sodium		
Formaldehyde		

Sulphoxylate) 1¼ lb. Water, Sufficient to make 1 gallon of thickening.

The above is for thickening a strong printing paste; one suitable for a weak paste has the following composition:

No.	2	
British Gum	5	oz.
Wheat Starch	12	oz.
Potassium Car-		
bonate	8	OZ.
Glycerin	3/16	
Olive Oil	3/16	pt.
Formosul	6	OZ.
Water, Sufficient	to make 1 į	gallor
of thickening.		

In making the printing paste itself, a mixture is made (for a strong color) of 3 parts of the thickening and 1 part of the vat dye paste, or (for a weak color) the strong color paste is suitably diluted with the thickening.

## Artificial Velvet

Of the several methods of production the simplest is the use of a concentrated rubber latex dispersion. Practically any cloth is suitable for the fabric base, but, of course, certain weaves are better than others. It is not unusual to give

the fabric a preliminary light dressing of latex on one side. This promotes a smooth surface in the case of cloths which lack the required smoothness, and also prevents excessive shrinkage. Where a light weight fabric forms the base, or a waterproof product is required, a thorough initial coating is required. A representative formula for a suitable compound is as follows:

Concentrated Latex	100
Sulphur	3
Zinc Oxide	5
Casein Solution (10%)	5
Antioxidant	$\frac{1}{2}$
Accelerator	$\frac{1}{2}$

Modifications of above may be necessary to suit particular cases. The initial coating is effected by a spreading machine, during which penetration of light weight fabrics is avoided by stretching and not exerting counter pressure. The spreading knife should always be fairly sharp, and set in the opposite direction to that in which the cloth is running.

The mix is then diluted with water, and poured into the trough through which the fabric is running on a rubber roller. The level of the mix is adjusted so that it just reaches the surface of the fabric. The artificial velvet base then goes forward to the machine which applies the dust on the still moist surface. Rotating sieves, preferably hexagonal in shape and of 1 millimeter gauge. carry the dusting media. They should cover the same area. As the amount of dust they release varies with the amount they contain, both sieves should be in operation. When they are full or nearly empty, and only one operating when they are half empty, and, therefore releasing most dust. About 5/6 times as much dust is shaken on the base as is finally required. Meanwhile the fabric is beaten quickly and regularly from underneath with flat instruments to insure that each individual hair assumes as perpendicular a position on the cloth as possible. The material is then left for about 10 minutes on a hot plate, or pressed over drums heated by approximately 15 lb. of steam to dry it.

Brushing with soft cylindrical brushes takes place when the artificial velvet is quite cold. The superfluous dust removed by this process may be recovered and used again. Vulcanization, the final stage, is best carried out in a hanging position and heating for 10–30 minutes at a temperature of 140° C. to 150° C.

Different effects may be obtained by varying the dusting media, silk, artificial silk, wool, and cotton dust are all used. The depth of pile may also be varied, and it is possible to emboss these artificial velvets. A similar process is used to produce cloths hardly distinguishable from moguettes and suede.

Crush Proof Finish for Silk Velvet
The material after dyeing is
treated cold for 15 seconds with
0.13% formaldehyde and 0.3% ammonium chloride and then, without
rinsing, is baked at 310° F. for 5
minutes or until dry. Next wash five
minutes at 150° F: with a little ammonia in the bath, follow with a
hot, then a cold rinse in clear water.

Of a number of colors checked, the following were found to withstand the treatment:

gal.

Brilliant Milling Yellow 5G
Milling Yellow O
Amacid Neutral Yellow GNS
Amacid Fast Yellow RS
Polar Orange GS
Amacid Neutral Orange SGS
Amacid Milling Scarlet G
Amacid Milling Scarlet 3R Conc.
Supramine Red 2G
Polar Red RS
Amacid Fast Red A Conc.
Brilliant Croceine 3BA Conc.
Amacid Green G
Alizarine Green CE Ex.
Brilliant Milling Green B
Amacid Silk Brown R
Amacid Fast Blue BL
Amacid Fast Blue GL
Amacid Silk Black RW

Scrooping Compoun	ds
Formula No. 1	
Casein	$4\frac{1}{2}$
Formic Acid	1
Boric Acid	1
Ocenol KD	17
Odorant (Coverene),	
To suit	
Use up to 2% in water.	
No. 2	
Ocenol	9
Gelatin	6
Aluminum Formate	
(Basic)	24
Odorant (Coverene),	
To suit	
Water	2000
No. 3	
Viscose	
Lactic Acid	5-6%
Malt Extract	4%
Oil Emulsion (1%),	-
To make	100%
No. 4	

Mercerized Poplin

Lactic Acid

Paraffin Wax Emul-	
sion (1%)	5
Gelatin	5
Water	1000
Weighting for Text	iles
Glycerin	6.0
Urea	2.0
Potato Starch	2.0
Sodium Benzoate	0.2
Water	27.8
Cook the starch in the w	ater until

ents and cool with stirring.

Textile Back-Filling Stiffener
Starch 1 lb.
Talc 1½ lb.
Tallow Softener 1 lb.

swollen. Add the remaining ingredi-

Textile Fiber Preservative U. S. Patent 2,119,525

Water

Vegetable fibers, cordage, thread, or nets are soaked in an aqueous solution of a tanning agent (approximately 6% solution of catechu extract) at about 100° for about 12 hours, boiled for about 15 minutes in an aqueous solution of an oxidizing agent (0.5% solution of potassium dichromate), rinsed in water, dried and immersed for about 3 minutes in coal tar at about 95°.

Preventing Sticking of Resin Coated Textiles Formula No. 1

The addition of 34% Duponol ME or solids in synthetic resin finished on textiles prevents sticking together of cloth.

No. 2

The incorporation of ½% of Acrawax C in polyvinyl butyral resin compounds, used in rainproofing textiles, prevents sticking, even under tropical conditions.

# Textile Fibers from Maize Straw U. S. Patent 2,271,218

A method of producing spinnable textile fibers from corn straw, comprises the steps of boiling the straw with 1-5% soda solution, washing and squeezing the material to remove the leafy parts, then boiling for a short time with a 1-3% urea solution, leaving the material in said urea solution for about 3 to 4 hours. adding to the urea solution a solution of 1-3% alkali, boiling once more for 1 to 3 hours, thereby evolving free ammonia, and washing, drying and disintegrating so as to form fibers.

C	lasein	F	ìŀ	oers	
S.	Paten	t	2	225	198

TT

C. D. 1 diccirc m, mmo, 100		
Casein	24	
Water	198	
Ethyl Glycolate	5	
Triethanolamine	6	
Calcium Chloride		
(10% Solution)	7	

The above is extruded, dried and finished.

# Glazed Thread

Bring 50 gallons of soft water to 80° F. Then add 15 pounds potato starch which has previously been dissolved in cold water. After thoroughly mixing, add 1 pound paraffin wax and 2 pounds cocoanut oil. After all is dissolved, empty into clean pails and use when cold. Keep the tension off the yarn on the machine as much as possible. This will help to get a good, soft, brilliant luster. With too much tension the thread will be wiry.

Cotto	n Cord	Glaze	Finish	
Water	1 April 22/103	remark.	50 ga	al.
Potato 8	Starch		15 Îk	

Castile Soap	1/2	lb.
Paraffin Wax	4	lb.
Beeswax	1	lb.
Lard Oil	21/2	nt.

Mix the starch in cold water and add to the boiler when the water is at the boiling point. Add the other ingredients and boil 15 minutes. Use when cold.

# Giving Natural Finish to Smooth

	Calico	
	Potato Starch	5
	Wheat Flour	$7\frac{1}{2}$
	Boiled with Water	250
	Then add	
	China Clay Paste	10
	French Mineral White	10
	Boil and add	
	Cocoanut Oil	3/4
	White Soap	$\frac{1}{2}$
	Carbonate of Soda	$1\sqrt{4}$
	Water	3
	Add to a vat containing	
	Potato Starch	15
	Water	75
	Stir thoroughly and then	n slowly
ac	dd	•
	Potato Starch	5
	Water, With a Trace of	
	Ultramarine	5

Refinishing Fiber or Grass Rugs Spread a thick mat of newspapers on the floor and lay the rug out flat.

For the stain simply use flatting oil to which the necessary colors-in-oil

have been added.

The amount of color required will depend on how deep a tone is wanted -ordinarily a pint of the color to each gallon of flatting oil is sufficiently strong to freshen up the faded colors of the rug. The stain should be applied freely, with a wide brush, so that it penetrates the fibers and imparts a uniform appearance to the rug. If something more decorative than an over-all single-tone is wanted, stencils or masks may be used for certain patterns in various colors. Give the rug time to dry through before putting in service.

Immunized	Wool	
Wool	1000	lb.
Tannic Acid	200	lb.
Color (Direct) to		
Tint	$2\frac{1}{2}$	oz.
Acetic Acid (28%)	150	lb.
Tin Crystals	40	lb.
Formic Acid	60	lb.

Prepare bath with color, enough water to work wool in easily. Add 5% acetic plus 20% of tannic acid; dye at 120° F. Bring slowly to boil and boil ¾ hr. Add 5% acetic, boil ½ hr. longer and add 5% acetic. Boil ½ hr. longer.

Without washing off treat in a fresh liquor for 1 hr. at 195° F. made up of 4% tin crystals and 6% formic acid. Wash off, do not pole too much as wool will be felted.

Chlorine Treatment of Wool Scoured goods are worked ½ hour in a cold bath containing 10 lb. hydrochloric acid.

After allowing to drain, the goods are laid upon the reel and carried to a second cask and worked cold for ½ hour in a bath of chlorinated lime ¾° Tw. The lime (bleaching powder) should contain about 35% active chlorine. Meanwhile the first cask is drained and a bath of 8 lb. sulphuric acid (66° Bé) made up. The goods are worked for ½ hour cold, rinsed well and dried for printing.

Chlorinating leaves a yellowish

tint which can be removed by stoving. The machinery used for production is a 16 line dye kettle with studded reel.

# Non-Shrinking Wool Formula No. 1 British Patent 541.965

Woolen fabric is immersed for 2½ hr. at 70° C, in

Stannous Chloride 10 g. Hydrochloric Acid (2N) 100 cc.

It is then squeezed, washed and dried.

# No. 2

# British Patent 540,052

An 18:82 wool-spun viscose fabric is dried, treated for 1 hr. at 20° in beta propyl alcohol (100 cc.) containing potassium hydroxide (5 g.), centrifuged, rinsed in dilute alcoholic potash, washed, and dried.

# Non-Felting Wool British Patent 540,613

Woolen yarn (15) is immersed for 1 hr. at 30° in n-sterocarbamide (1 part) and sulphuryl chloride (6 vol.) in carbon tetrachloride (200 vol.), rinsed in cold water, immersed in 0.2% aqueous ammonia, washed, and dried. It is then non-felting and softer to handle than the untreated yarn.

Glass Wool Coating	Emulsion
Hydrocarbon Oil	24.5
Stearic Acid	18.5
Ammonia	4.0
Water	43.2

Preparing Metal-Coated Fabrics Impregnate the cloth surface with a prepared graphite-in-oil, which provides uniform distribution of the fine carbon particles. Then run the cloth through rollers, allow to dry and place in the plating bath. The cloth must be properly stretched to obtain uniform deposition. For nickel plating the cloth use 37 ounces nickel sulphate, 8 ounces nickel chloride, and 5 ounces boric acid per gallon of electrolyte. In addition use brightening agents. Bath temperature should be 43–48 degrees; current density, 40 amperes per square foot; then wash and dry the cloth.

# Metal Coated Fabric U. S. Patent 2,125,341

The fabric is coated with a film of cellulose nitrate 26-23%, a plasticizer (castor oil or ortho dibutyl phthalate) 46-52%, and a pigment 28-25%, then with an adhesive coating of cellulose nitrate not greater than 10%, ethyl acetate 40-20%, ethyl alcohol 60-40%, and dibutyl tartrate not more than 30%, and finally, when the adhesive is tacky, with a dusted-on coating of metal (aluminum) powder. The metal particles are brushed on so as to orient the flakes and produce a mirror-like luster, which is preserved by applying a thin coating of a clear lacquer.

Paraffin Coating for Balloons and Airships

From one to two pounds of paraffin wax, depending upon the weight of coating, and the condition of the surface to which it is to be applied, is melted over a steam bath or upon a large electric plate to prevent overheating.

The melted paraffin is allowed to come to a temperature 5 to 10° C.

above its melting point, when it is mixed with one gallon of solvent which has been previously heated to the same temperature. Care should be taken that the paraffin and solvent are the same temperature, as the addition of hot paraffin will cause the solvent to boil violently.

The solvent should never be heated over an open flame due to the fire risk.

The air shall be between 50% and 75% relative humidity at approximately 70° F. as there is danger of fire due to the building up of static charges from the evaporation of the solvent which will be dissipated if the humidity is in excess of 50%, while if the humidity is over 75% there is a tendency to precipitate moisture. The application of paraffin should not be accomplished on days when there is an approaching thunderstorm or the surrounding temperature is under high electrical tension.

The envelope shall not be inflated and coated from the inside.

The envelope shall be opened at the mid-section above 1/3 of the circumference when about 20% inflated, and reversed by rolling the envelope on the air in the interior of the envelope. After removing the original tape, a tape approximately four inches wide shall be applied at the opened seam on both sides. This will prevent the application of paraffin at this point, which would cause a poor union when the envelope is reassembled. The tape should not be removed after paraffining until the envelope is turned and ready to be reassembled.

The paraffin shall be applied with a standard sweeping broom in a

uniform coating so that it flows smoothly over the fabric, leaving no broom marks on the surface. Insofar as practicable, the surface to which the solution is to be applied should be flat in order that a uniform coating may be applied.

The increase in weight due to the application of the solution shall be approximately 0.5 ounce per square

yard.

The envelope shall be required to dry for at least 48 hours to permit complete evaporation of the solvent from the paraffined surface before

being rolled up.

It is very necessary to thoroughly ventilate the room in which the operation is being performed. Care should be exercised to prevent the formation of pockets of gas from the solvent, especially around the ballonet. When a section of the envelope has been doped it should be allowed to dry thoroughly before being turned over.

After the paraffin solution has been applied to the inside surface, the envelope should be inflated about 20% and returned to its original position. The tape shall then be removed from the seams and a careful inspection made to determine if paraffin is on the cemented surface. If there is any paraffin on the cemented surface, it shall be removed by scraping, buffing and washing with the solvent before any cement is applied. The seams shall then be cemented, sewed and re-taped in accordance with standard practice.

Retting of Istle and Sisal Fibers In order to remove the gum from sisal and istle fibers, it is necessary, at first, to consider the chemical structure of this gum. Upon analysis it will be readily found that the gum consists of bastose, a form of sugar, and tannin matter.

It is necessary that, in order to decompose the gum, the bastose be attacked.

The bastose can be successfully attacked by dissolving, in boiling water, 4 oz. by weight of the material of tri-sodium phosphate for every 5 lb. of raw fiber. The fiber should be kept in the boiling solution for about 10 minutes, after which it should be thoroughly rinsed with cold water, to remove any phosphate from the fiber.

# Softening Sisal Fibers British Patent 541,383

The fibers are boiled for 2 hours in 5% soft soap, washed in hot water, immersed for 5 minutes in aqueous calcium hypochlorite (pH 4.5 and containing not less than 1% available chlorine), washed with dilute aqueous alcoholic potash, then with water, lubricated, and dried.

Sisal, Aloe and Other Plant Fibers, Separating

British Patent 542,017

The leaves are crushed and the juice is removed. Then boil in 1% soda ash solution for 30 min. and scrape off fleshy covering of fibers. If desired the fibers may be boiled with 2% sodium sulphite solution for 1 hr. and then dipped in 1% cold hydrochloric acid. Finally they are washed with water and dried.

Kier Boiling of Cotton Goods

1. Type of Goods: Single and ply yarn and cables.

Water: 90 ppm. hardness.

C 214°	onditions:	Boil	3	hours	at
21T	J			%	
				,	
C	austic Soda	,		1.6	
S	odium Silica	ate		3.84	
$\mathbf{T}$	S.P.P.*			0.8	
W	etting Age	$\operatorname{nt}$		1.6	
	Type of (		W	oven pi	ece
	ls—flannels				
	ater: 80 p				
	onditions:				25

lb. pressure.

	%
Caustic Soda	4.0
Sodium Silicate	1.5
T.S.P.P.*	1.0
Wetting Agent	0.075
3. Type of Goods	Turkish towel-

ing.

Water: 18 ppm. hardness.

	. %
Caustic Soda	3.0
Sodium Silicate	1.0
T.S.P.P.*	1.0
Wetting Agent	small amt.

4. Type of Goods: Light weight woven goods.

Water: 100 ppm. hardness.

	%
Caustic Soda	3.0
Sodium Silicate	0.25
T.S.P.P.*	0.5

Gets cleaner kier and eliminates resist spots in dyeing, which are due to insoluble calcium soaps formed in the kier.

# Doubled Fabrics

Fabrics doubled with latex have many additional properties. It is not surprising, therefore, that such cloths are finding an increasing use in the production of shoe linings, boot tops, wind jackets, printers'

\*TS.P.P. = tetrasodium pyrophosphate. blankets, motor car hoods, miners' clothing and balloon fabrics. In this case a standard doubling mix consists of:

Concentrated Latex	100
Whiting	50
Zinc Oxide	3
Sulphur	2
Du Pont Accelerator	0.2
Casein Solution (10%)	5
Water	15

French chalk or barytes may be substituted for whiting, which serves to promote permeability to air as well as to cheapen the spreading mix. If more weight or a better handle is required the quantity can be increased, in which case it may be advisable to increase the quantities of water and casein solution. Curing is effected by the addition of zinc oxide, sulphur, and accelerators under heat. If Du Pont accelerator is taken, it is sufficient to run the fabric over a heating plate or cylinder heated to about 100-120° C. Vulcanization of the mix sets in and continues at ordinary room temperatures.

The quality of the material and the degree of waterproofness determine the amount of mix to be spread. The doubling mix will adhere to untreated material better than to a smooth dressed cloth. Too pronounced penetration of the mass into the fabric may be prevented by using a sharp spreading knife, set at an acute angle to the direction in which the fabric is traveling. The fabric should also pass under the knife as quickly as possible and without friction.

With light weight fabrics it frequently happens that a light colored mix is visible through the new ma-

terial. This has the effect of causing an apparent change in the shade. In such cases suitable coloring agents should be added to the mix. When dealing with pure white cloths, it is possible to avoid discoloration by displacing 10 parts of whiting in the above mentioned mix, and substituting 20 parts of titanium dioxide along with a further 5 parts of 10% casein solution. Here the addition of a water soluble blue is also helpful to tint the mix slightly.

Where good adhesion only is required, as in shoe fabrics, the cloths may be doubled in one operation by the aid of a combined spreading and doubling machine. It is also possible to use a calender having a spreading knife in front and drying apparatus behind. One fabric, after passing under a pulley, passes a spreading knife without counter pressure, and joins the second length at the doubling roller. The doubled fabric is then dried and rolled up. Speaking generally, when about 1 ounce of the mix is used for 1 square yard the material is sufficiently permeable to air. Penetration during calendering must be avoided, and the mix must not have time to dry out before doubling. For this reason it is recommended that the spreading knife and doubling rollers be set at 18 inch to 1 yard apart. When uniting the cloths, the highest possible pressure should be exerted to insure equally strong adherence to both cloths.

Where waterproof doublings or heavier cloths are treated, it is preferable to carry out process in more than one operation. Here the whiting may be reduced or even omitted altogether. Each length of cloth is coated separately on the spreading machine, either one or several times. To prevent the subsequent applications penetrating into the base of the fabric a sharp spreading knife is preferable. A blunt knife may be used for subsequent coats, however. Three to four ounces of the mix per square yard should give good waterproof qualities. The spreads of each length of cloth must be sufficiently dry before they are doubled on the calender to avoid penetration.

Fluorescent American Flag

By fabricating a flag from fluorescent textiles or ordinary stains which often contain fluorescent dyes an American flag of unusual beauty may be obtained, for display purposes in ultraviolet light.

White fluorescing fabric can be prepared by dipping satin or other cloth with a solution made up of buffered fluorescein and quinine or cinchonine.

Red fluorescing fabric can be prepared by dyeing cloth with eosine or rhodamine.

Blue fluorescing fabric is prepared by dyeing cloth with a solution of umbelliferone or Fluorescent Blue G.

Hat Conditioning Material (used after cleaning hats)

This material is used to restore some of "life" and body to a felt hat after cleaning or much wearing. It adds some water-repellency properties and makes it more serviceable in other ways.

Water: 98.

Carnauba or Beeswax: Between 0.2 and 0.5.

Disodium Phosphate: Sufficient to give a buffered solution of pH between 7.50 and 7.80 in final mixture.

Aluminum Stearate: 0.2.
Titanium Dioxide (Finely Ground): 0.5.

A trace of an emulsitying agent to help ingredients stay in solution and suspension. This may be triethanolamine, hexalin or other common ones depending upon availability. Maintenance of proper pH is more important than the particular

emulsifying agent. This solution will probably be purplish. However, various dyes may be added to either mask or make provision for hats on which it would not be suitable. Under certain conditions, this purple color is never evident. The material is applied with a soft cloth pad preferably while hat is on a block. Rub in direction of felt layer, let dry slowly (overnight) and finish in usual manner of pressing, etc.

# CHAPTER TWENTY-ONE

# MISCELLANEOUS

Fireproofing Straw

Straw can be satisfactorily fireproofed by immersion in a solution of 45 g. boric acid and 65 g. borax per liter. Another fireproofing treatment consists in immersing the straw in a solution of 50 g, ammonium phosphate, 25 g. ammonium sulphate, and 25 g. ammonium chloride per liter. Another consists in the use of a solution containing (per liter) 75 g. sodium acetate, 75 g. trisodium phosphate, and 20 cc. pale neutral 28° Bé glycerin. This last mentioned method of treatment has been employed for fireproofing the straw packing for carboys of nitric acid.

# Anti-leak

For Hot-Water Heating Systems Soapmakers' silicate of soda (1 qt. per 1000 gal. water) is used.

Anti-corrosion
For Hot-Water Heating Systems
Formula No. 1
(where considerable gas and air

must be blown from radiator)
Caustic Soda 1/3
Chestnut-Oak Extract 1/3
Water 1/4

One pound of this solution is used to 1000 gal. water.

No. 2

(where waters are very soft—and where salt is present) Sodium Bichromate 30 Sodium Carbonate—Soda
Ash 10
Caustic Soda 1
In natural water use 2 lb. to 1000
gal. water.

In brine use 1 lb. to 5 gal. brine.

To Remove Carbonate Scale (scale that foams when acid is added)

Hydrochloric Acid 2 Chestnut-Oak Extract 1

One part of this mixture to 25 parts of water makes a little over 1% acid strength solution. If stronger solutions are used, some supervision by a competent chemist should be arranged for. For boiling out boilers 2 to 2½ lb. per rated horsepower should be added; all the vents are left open and foaming anticipated.

Treatment for Vacuum or Vapor Heating Systems

Same as for hot-water systems, save that 2 lb. per year is enough—1 lb. added at outset and 1 lb. about three months later.

Leak Sealing, Rust Preventing
Composition
For Hot-Water Systems
U. S. Patent 2,129,459

Flaxseed Meal 5
Potassium Dichromate 7

Stop Leaks for Radiators To stop leaks in automobile or ½ oz. 1 oz. Electric Resistor with Negative Temperature Coefficient U. S. Patent 2,274,592

23

Nickel Oxide

tractor radiators the following prep-

aration is helpful:

Glycerin

Ground Flaxseed

Gry cerm	1 02.	THOREST CARGO	20
Water	5 oz.	Manganic Oxide	47
		Cobaltic Oxide	30
Anti-leak Anti-	freeze		
U. S. Patent 2,2		Composite Resistan	nce
Less than 0.1% of		British Patent 527,0	
		Steatite Dust	
nate is added to alcoho	·1.		$\frac{2}{1}$
		Copper Dust	. 1
Non-corrosive And		Mix together and press i	
Canadian Patent	403,486	with or without firing at a	
To the alcohol is add	ded:	ture below melting point of	of copper.
Sodium Nitrate	0.05-1.0%		
Sodium Molybdate		Heat Resistant Stencil	Film
		U. S. Patent 2,242,3	
Aircraft Engine Ar	ti-freeze	Cellophane or other to	
Ethylene Glycol	94½ g.	absorbent transparent foil	
		with	is coated
Water	- 0	Mineral Black	E
Trihydroxyethylami			5
Phosphate	$2\frac{1}{2}$ g.	Aluminum Powder	34
		Cottonseed Oil	12
Windshield and V		Vegetable Wax	49
.Anti-freeze			
U. S. Patent 2,2	58,184	Adhesion Preventing Con	
Ethylene Glycol	20–60	U. S. Patent 2,262,6	389
Glycerol	8–10	Formula No. 1	
Formaldehyde	2-5	Talc	64
The above prevents i	ice formation	Glycerin	$\frac{1}{2}$
on any exposed surface		Water	$35\frac{1}{2}$
	_ * ',	No. 2	
Dielectric, Trans	former	Soapstone, Powdered	99.8
Formula No		Calcium Chloride,	•
British Patent 5		Powdered	0.2
o-Tolyl Diphenyl	,		
Phosphate	34-73%	Insulating Materia	ds
m-Tolyl Diphenyl	01 .0/0	British Patent 526,51	
Phosphate	66-27%	Formula No. 1	0 11
This is liquid above		41.4 parts by weight o	f a nacta
No. 2	10 0.	containing slaked lime (7	
U. S. Patent 2,2	14.877	dered dehydrated silica g	
Chlorinated Paraffin			
Trichlorbenzene		and transformer oil (14.0 mixed with 100 parts by	
1, 2, 3, 4 Tetrachlor		a mixture containing rosi	
benzene	15–25	oleic acid (18.0), petroleur	n residuai
		The state of the s	

pitch (45.0), and transformer oil (22.0 parts).

# No. 2

A mixture containing rosin (20.0), oleic acid (20.0), castor oil (40.0), and coumarone resin (20 parts) is mixed with a paste containing litharge (20.7), slaked lime (2.6), ground quicklime (7.0), and castor oil (10.0 parts).

# No. 3

Alternatively, a mixture composed of oleic acid (25.0), ester gum (50.0), and castor oil (25.0 parts) is mixed with a paste containing slaked lime (3.3) and castor oil (3.3).

Electrical Insulation Formula No. 1

U. S. Patent 2,259,134
Portland Cement 12 to 18
Asbestos, Long Fiber 7 to 11
Montan Wax 14 to 2

Colloidal Clay Up to 7
Graphite Up to 1

Water sufficient to form

a slurry.

Preferably colloidal clay is used within the limits of 3 to 7 parts and graphite, within the limits of 0.5 to

1 part.

In molding the mixed ingredients a screen of approximately 20 mesh size is placed in the bottom of the mold, the material is flowed thereon, and another screen of approximately the same size is placed on top of the wet mass. Upon the application of pressure the water is freed from the mass, flowing out from a suitable opening in the bottom of the mold, and also from the top of the mold between the punch and the jacket. By using screens in the manner described, the larger

part of the excess water is readily removed from the mass. If water be allowed to remain in the panel, the finished board has poor impact and flexural strength characteristics. On the other hand, it is very desirable to have an excess of water in the mix as it is introduced into the mold. By so doing, the asbestos fibers are not knotted or broken during the molding operation. Instead, they form an interwoven mass which has been found to be essential in obtaining optimum mechanical strength.

The molded parts are air-dried for a suitable period, for instance for about 4 to 5 hours. Thereafter they are placed in an oven in which steam is constantly introduced. The panels are cured in this oven for a suitable period, for example for about 24 hours. After the steam cure they are immersed in warm water (100° to 140° F.) for another suitable interval, for instance for about 24 hours. Following this treatment the panels are baked in a suitable oven, such for example as an electrical oven, at a gradually rising temperature up to approximately 500° F. over a period of, for instance, about 12 hours. All the uncombined water is removed from the panels by this baking treatment, and the components are bonded together to form a hard, rigid mass. The baked panels are sanded to a smooth finish, after which they usually are sprayed or otherwise coated with a suitable lacquer or varnish.

No. 2

British Patent 533,520
Isobutylene Polymer
(Molecular Weight
Above 100,000) 1-2
Bitumen (High Melting) 4-1

A little wax	may be	added to im-
prove working	charact	eristics.

prove working characteristics.	
No. 3	
British Patent 523,383	
Rubber	75
Polystyrene	25
Zinc Oxide	$\frac{3}{4}$
Zinc Laurate	$\frac{3}{4}$
Tetramethylthiuram	
Disulphide	<b>2</b>
This gives an extremely	low
power factor and specific in	iduc-
tive conscity	

Condenser Electroly	
British Patent 531,7	06
Formula No. 1	
Furfuryl Alcohol	64
Ammonium Borate	36
No. 2	
Ammonium Borate	10-40
Acetamide	16-20
Tetrahydrofurfuryl	
Alcohol	40-80

Dry Cell Electr	olyte
Ammonium Chloride	15.0%
Zinc Chloride	30.0%
Calcium Chloride	35.0%
Mercuric Chloride	0.2%
Water, To make	100.0%
mi :	

This gives minimum corrosion of zinc, maximum depolarizing properties and does not dry out on exposure.

# Temporary Gas Shut Off Composition

Gelatin	6
Molasses	2
Phenol (15% Solution)	1/4
Water	913/4

Warm and mix until homogeneous. Apply while just fluid.

Revivitying Spent (	ias Oxide
Add to:	
Spent Iron Oxide	44
Soda Ash	52
Peat	11
Non-dusting Coal 7 Formula No British Patent 5	. 1
Calcium Chloride	100 lb.
Cornstarch (6%	
Gluten)	8 lb.
Water	50 gal.
No. 2	
U. S. Patent 2,2	42,398
Rosin	1
Petroleum	1–9
	-

# Coloring Coal U. S. Patent 2,129,901

Coal free from dust (washed or freshly broken) is treated separately with each of the three following solutions:

1.	Calcium Ferricya-	
	nide	0.413%
2	Ferric Chloride	0.500%

3. Sodium Bisulphite 10.000%

Flare or Lamp Illuminan	ıt
U. S. Patent 2,258,910	
Kerosene	95
Naphthalene	1
Rosin	1
Methanol	1
Caustic Soda (10% Solu-	
tion)	2

Lamp Kerosene Rectifier

This powder is intended for house lamps, etc., to prevent the oil from smoking and having a disagreeable smell, and to increase and brighten the light.

Powdered Naphthalene	52	Motor	Carbon Re	emover
Fine Dry Salt	10		ormula No.	
Powdered Camphor	2		h Patent 5	
Mix thoroughly and put up	in tins		Dichloride	80
or packets. A little is to be a	dded to	Acetone		15
the oil in the lamp or stove,		Cellulose .	Acetate	4
newed when this is consumed		Stearin		1
			No. 2	
Frosting for Inside of Lig	hting	Neutral C	oal Tar Oi	1
$\operatorname{Bulbs}$		(Free fr	om Cresols	(a) 40 cc
U. S. Patent 2,278,25	7	o-Toluidir	ne	15 cc.
Hydrofluoric Acid	23	Diethanol	amine	15 ec.
Ammonium Bifluoride	20	Oleic Acid		15 cc.
Sodium Bicarbonate	4	Ethylene		15 cc.
Alcohol	10	Phosphori		$\frac{1}{2}$ cc.
Water	10	Ethylsilic	ate	$\frac{1}{2}$ cc.
	~~			
	Hydrauli			
	S. Patent		37 0	DT 4
	mula No. 1		No. 3	No. 4
Propylene Glycol Ricinolea			0.50	fl. oz.
Propylene Glycol	4.5	• •	35.0	fl. oz.
Isobutanol	60.0			fl. oz.
Sodium Nitrite	9.0		• •	g.
Potassium Soap	71.0			83.0 g. 27.3 fl. oz.
Ethylene Glycol Ricinoleate		$\begin{array}{c} 32.7 \\ 7.3 \end{array}$	• •	6.0 fl. oz.
Ethylene Glycol	• •	19.0		19.0 g.
Calcium Nitrite	• •		10.0	15.0 g.
Glyceryl Ricinoleate Butanol	• •	• •	55.0	66.7 fl. oz.
Potassium Nitrite	• •	- * *	12.0	g.
Potassium Nitrite	• •	• •	12.0	6.
No. 5	-1	Propylene	Glycol	20.50
Castor Oil, Blown	50		Monoricino	
Ethylene Glycol	16	01,001,11		
Alcohol	26		No. 8	
Hydroxyethylbutylether	11	U.S.	Patent 2,2	55,208
Tricresyl Phosphate	1/2		ylene Glyc	
Diphenylamine	$2\frac{1}{2}$	Polyprop	yleneglycol	mono-
No. 6	-/2	ricinole		3
U. S. Patent 2,249,80	0	Propylene	e Glycol	3
Isobutanol	75	Butanol		11
Glyceryl Monoricinoleate	1		No. 9	
No. 7		U.S.	Patent 2,1	
Isobutanol	56.25	Butanol		55%
Glycerin	13.50	Glycerin		13-15%
	1			

# Protection Against War Chemicals

General Information Concerning the Characteristics, Effects, and Counteraction of the Agents an Enemy Might Use in War

By Walter P. Burn, Lt. Col., C.W.S.

	NITON	un- and lution	with r with obol.	earth,	ution	odium		
Lt. Col., C.W.S.	Pield Neuthalization	Cover with unslaked line and earth; 3% solution of Na <sub>2</sub> SO <sub>3</sub>	Wash down with water. Cover with earth. Alcohol. NaOH spray	Cover with earth, caustic	Alkaline solution	NaSO <sub>3</sub> — sodium sulphite in alcohol solution	Alkali	Alkali
Lt.	Per- SISTENCE	One day to one week; longer if dry or cold	One day to one week; longer if dry or cold	One hour	10 minutes	Open 6 hrs.; woods 12 hrs.	30 minutes	10 to 30 minutes
: Use in War	. Finst Aid [After removal from gassed area]	Gas mask tard with protective oint- and ment, bleach paste, or kerr- protective sene; bather, wash eyes and clothing nose with soda solution	Undress; remove liquid Low- isite with hydrogen peroxide, Ive in glycerine, or kerosene; bathe; wash eyes and nose with soda. Rest and doctor	Gas mask hydrogen peroxide. Iye in protective wash eyes and notes with clothing soda. Rest and doctor	Remove from gassed area. Gas mask Keep quiet and warm. Coffee as stimulant	Gas mask warm. Do not use bandages	Gas mask Keep quiet and warm. Give	Keep guiet and warm, rest in led. Coffee as a stimulant. Loosen clothing. No alcohol or cigarettes
y Might	Pro- TECTION	Gas mask and protective clothing	Gas mask and protective clothing	Gas mask and protective clothing	Gas mask	Gas mask	Gas mask	Gas mask
an Enem	TACTI- CAL CLASS	Hospital case	Hospital	Hospital	Hospital case	First-aid; and hos- pital case	Hospital case	Hospital
Counteraction of the Agents an Enemy Might Use in War	Physiological Effect	Delayed effect. Burns skin or membrane. Inflamma- tion of respiratory tract leading to pneumonia. Eye irritation, conjunctivitis	Burning or irritation of eyes, nasal passages, respir- atory tract, skin. Arsenical poison	Stinging, Causes blisters, sores, palike ralysis of hands, vomiting, pepper Severe on long exposure in nose	Lung irritant	Causes severe coughing, crying and vomiting	Causes coughing. Breathing hurts, eyes water, toxic	Irritation of lungs, occasional vomiting, tears in eyes, doped feeling, Occasionally symptoms delayed; later, collapse, heart failure
ounter	Орок	Garlie, mustard, horse- radish	Gerani- ums	Stinging, like pepper in nose	Highly pungent	Fly- paper, anise	Ensilage, acrid	Musty hay, green corn
	Fовм	Liquid and vapor	Liquid and vapor	Liquid and vapor or gas	Gas	Gas	Gas	Gas
	Names and Symbols	Musrand S(CH2CH2)2(19 Dichlorethyl sulphide	Lawistra CHClCH-AsCla Chlorvinyl-dichlorarsine	Ethyldichloraring C <sub>2</sub> H <sub>5</sub> -AsCl <sub>2</sub>	CHLORINE Clg	CHLORPICHIN CCI <sub>8</sub> NO <sub>3</sub> Nitrochloroform	Drenosgene ClCOOC-Cl <sub>3</sub> Trichlormethyl chloroformate	PHOSGENE COCLE Carbonyl chloride
		•	VESICANTS-	<b>.</b>	STV.	ATIAAI	-гаис	

Collection of the collection o	NAMES AND SYMBOLS	Form	Оров	Physiological Effect	TACTI- CAL CLASS	Pro- TECTION	Frast Arb [After removal from gassed area]	Per- sistence	Field Neutralization
Gas         Fruit Effect         Eyes smart, shut, tears flow. Effect         First-and teadache         First-and teatment         Gas         mask Do not bandage         Wash eyes with boric acid Do not bandage         Several days, weeks in winter           Gas         Coal         Causes sneezing, sick de- polish         First-aid         First-aid         Gas         mask pirm for headache         In minutes           Smoke         Sharp- sarid         Harmless         Smoke         None         First-aid polish         Gas         Mash with soda solution         In minutes           Smoke         Burning         Causes prickling of skin, flow         Smoke         None         Treatment         Treatment         Treatment         Treatment         Treatment         Treatment         Treatment         In minutes           Smoke         Acrid         Harmless         Smoke         None         Treatment	CLORACETOPHENONE C6H6CO-CH2CI		Apple	Makes eyes smart. Shut tightly. Tears flow. Tempo-	First-aid treatment	Gas mask	Wash eyes with cold water or boric-acid solution. Do not bandage. Face wind. For skin, sodium sulphite solution	10 minutes	Strong, hot solu- tion of sodium car- bonate
Gas         Coal Smoke         Coalses sneezing, sick de pressed feeling, headache         First-aid fas mask nose with neo-synephirm or headache         Keep quiet and warm. Loos-neithing pressed feeling, headache         First-aid fas mask nose with neo-synephirm or headache         10 minutes           Smoke         Sharp         Harmless         Smoke         None         Produces no effect requiring of tearnent         None         Produces no effect requiring of tears         While huming           Smoke         Acrid         Harmless         Smoke         Gas mask with soda solution         Minutes           Smoke         Acrid         Harmless         Smoke         None         Produces no effect requiring burning pieces adhere to First-aid needed         None         Produces no effect requiring puintes         10 minutes           Smoke         Burning         Burning burning pieces adhere to First-aid needed         None         Produces no effect requiring pieces adhere to First-aid needed         None         Produces no effect requiring printes         10 minutes           Incental         None         Produces no effect requiring needed         Presk in cloths wet with cop- per sulphate (blue viriol) or per sulphate (blue vir	BROMBENZTI.CTANIDE C6H6CH-BrCN	Gas	Sour	Eyes smart, shut, tears flow. Effect lasts some time.	First-aid treatment	Gas mask	boric acid.	Several days; weeks in winter	Alcoholic sodium hydroxide spray
Smoke         Shoe         Causes sick feeling and treatment bearded         First-aid flas mask polish         First-aid placehing provides bottle         Remove to pure air, keep bleaching-provider bottle         Summer 10 minutes bleaching-provider bottle           Smoke         Sharp         Harmless         Smoke         None         Produces no effect requiring burning burning of teatrs         While bleaching-provider bottle         While bleaching-provider bottle           Smoke         Burning         Cause prickling of skin, flow smoke         Smoke         Gas mask         Wash with soda solution         5 to 10           Smoke         Acrid         Harmless         Smoke         None         Produces no effect requiring pinutes         10 minutes           Smoke         Burning         Burning pieces adhere to First-aid reathment pression and clothing reathment pression water or immerse in water.         10 minutes pression pressi	ADAMSITE (C <sub>2</sub> H <sub>0</sub> ) <sub>2</sub> -NHA <sub>3</sub> Cl Diphenylaminechlorarsine	Gas	` `		دد ا	Gas mask		10 minutes	Bleaching powder solution
Smoke         Sharp- sarid         Harmless         Smoke         None         Produces no effect requiring burning burning         While burning           Smoke         Burning         Acrid         Harmless         Smoke         Rash with soda solution         5 to 10           Smoke         Acrid         Harmless         Smoke         None         Produces no effect requiring         10 minutes           Smoke         Burning         Burning pieces adhere to reatment readed         First-aid         None         Pack in cloths wet with conpersion of the viriol or reatment readed reat for sumerse in water. The reatment readed reat for burn         10 minutes           Incen-diary         None         None         Treat for burn         5 minutes	DIPHENTICHLORARSINE (C6H5)2-AsCl	Smoke	Shoe polish	sick feeling and	(4.	Gas mask	Remove to pure air, keep quiet. Sniff chlorine from bleaching-powder bottle	Summer 10 minutes	Bleaching powder solution
Smoke matches         Description of tears         Cause prickling of skin, flow and clothing         Smoke         Gas mask matches         Wash with soda solution and minutes and produces no effect requiring and produces no effect requiring and clothing pieces adhere to fireatment matches skin and clothing and clothing         Smoke matches         None water in cloths wet with convent matches in water. The strength or pieces adhere to fireatment needed water or immerse in water. The strength or pieces out particles. The strength or matches and produces in water. The strength or matches in water in minutes in water. The strength or matches in water in minutes in water in matches in water. The strength or matches in water in minutes in water in matches in water in minutes in water. The strength or minutes in water in minutes in wate	HC MIXTURE ZN+C <sub>2</sub> Cl <sub>6</sub>	Smoke	Sharp- acrid	Harmless	Smoke	1	Produces no effect requiring treatment	While burning	None needed
Smoke         Acrid         Harmless         Smoke         None         Produces no effect requiring produces no effect requiring produces no effect requiring produces no effect requiring needed produces no effect requiring needed produces no immerse in water.         10 minutes           Incentation         None         5,000° heat ignites materials diary         None         None         Treat for burn         5 minutes	Sulphur Trioxide SO <sub>3</sub> +SO <sub>3</sub> HCl In chlorsulphonic acid	Smoke	Burning matches	Cause prickling of skin, flow of tears		Gas mask	Wash with sods solution	5 to 10 minutes	Alkaline solution
Smoke Burning Burning pieces adhere to First-aid None water or immerse in water 10 minutes water or immerse in water 10 minutes parts or immerse in water 10 minutes and clothing Incen- None 5,000° heat ignites materials Incen- None Treat for severe burn 5 minutes	Титамимтетвасньовие ТіСі	Smoke	Acrid	Harmless	Smoke		no effect requiring	10 minutes	None needed
Incen- None 5,000° heat ignites materials diary needed Treat for severe burn 5 minutes	Wите Ризвновоз	Smoke		Burning pieces adhere to skin and clothing	First-aid treatment			10 minutes	Burns out
	Trermit 8Al+3FeO4	Incen- diary	None	5,000° heat ignites materials	Incen- diary		Treat for severe burn	5 minutes	Quickly cover with dry earth or sand

From Army Ordnance, March-April, 1942.

General Instructions—Protective masks suitable for fire fighting and for mine rescue work are not suitable anti-gas devices. The only masks that are effective against all common war gases are those manufactured according to the Chemical Warfare Service specifications and procurable through the Office of Givilian Defense. General manufacture and public sale of gas masks is prothighed by War Freduction Board's General Limitation Order L-57, March 3.

The following are general rules which apply in all cases.

A. At promptly and quietly; be calm.

B. Put a gas mask on the patient if gas is still present or, if he has a mask on, check to see that his is properly adjusted. If a mask is not available, wet a handkerchief or other cloth and have him breathe through it.

C. Keep the patient at absolute rest; loosen clothing to facilitate breathing. D. Remove the patient of a gas-free place as soon as pressible.

E. Summon medical aid promptly; if possible, send the victim to a hoerital.

F. Do not pennit the patient to smoke, as this causes coughing and, hence,

The importance of proper first aid for gas victims cannot be overemphasized.

exertion.

No. 2

Auto Sound Deadening Compound

U. S. Patent 2,265,770

12

36

12

40

12

Sodium Oleyl Sulphate

Titanium Dioxide

Reclaimed Rubber

Cyclohexanol

Water

20-25%

40 gal.

60 gal.

1 oz.

40 gal.

60 gal.

10%

Diethylene Glycol

Methyl Ricinoleate

Castor Oil No. 3

Sodium Chromate

Alcohol

Castor Oil

Amyl Alcohol

No. 10

No. 11

Sodium Chromate 1 oz.	Asphalt 50
No. 12	Wood Flour 30
Sulphonated Castor Oil	Rosin 8
(80%) 25 gal.	
Alcohol 60 gal.	Air Raid Window Protection
	Strips of old bedsheets or similar
Sodium Chromate 1 oz.	fabric will do a fine job of window-
In place of the above alcohols, the	saving if pasted on with a home-
following may be used: methanol,	made paste like this:
isopropanol, "Cellosolve" or iso-	Wheat Flour 6 oz.
propylether.	Alum, Powdered ½ oz.
No. 13	Corn Syrup ¼ pt.
German Patent 692,303	Water 2 pt.
Formula No. 1	The syrup and the water are
Tritolyl Phosphate 61	mixed and used to make a smooth
Diphenyl Oxide 22	batter of the flour and alum; this is
Biphenyl 5	heated quickly to the active bub-
No. 2	bling point with constant stirring to
Tritolyl Phosphate 55	prevent scorching; or it may be
α Chlornaphthalene 45	cooked on a double boiler. The paste
No. 14	may be preserved with a level tea-
(Non-corrosive)	spoonful of benzoate of soda.
U. S. Patent 2,232,581	Don't use silicate of soda as a
Ethylene Glycol	window stickum; it will eventually
Ricinoleate 32.7 gal.	etch the glass.
Ethylene Glycol 7.3 gal.	MATERIAL PROPERTY AND ADDRESS OF THE PROPERTY ADDRESS OF THE PROPERTY AND ADDRESS OF THE PROPERTY ADDRESS OF THE PROPERTY AND ADDRESS OF THE PROPERTY ADDR
Butyl Alcohol 60.0 gal.	Incendiary Bomb Extinguisher
To each gallon of the above add:	Formula No. 1
Calcium Nitrate 19 g.	British Patent 543,703
Potassium Soap 103 g.	Sand 40-60%
	Borax 60-40%
Anti-mist (Fogging) Compounds	No. 2
British Patent 524,987	Ordinary powdered talc is recom-
Formula No. 1	mended as a cheap efficient extin-
Sodium Oleyl Sulphate 8	guisher. Its covering and adhesive
Titanium Dioxide 24	power is superior to sand or other
Water 68	suggested materials. It will also ex-
	1
	XIV.

tinguish oil and phosphorus incendiaries by preventing access of air.

No. 3

Sprinkled on a bomb, just as sand has been employed, feldspar quickly melts and forms a protective coating which cuts off the supply of air and stops the bomb from burning.

It is superior to mixtures containing salt, pitch, ashes or fine powders, as it does not burn, give off smoke, blow out or scatter appreciably from the intense heat of the incendiary material.

# No. 4

Hardcoal-tar pitch, flaked or granulated, has been recommended by the Bureau of Mines, Department of the Interior, Washington, for extinguishing incendiary bombs. The method is as follows: Let the thermite burn out; about one minute. If the bomb is on metal or concrete or other non-inflammable material spread a layer of the pitch on the bomb with a long handled shovel. Don't throw the pitch. If a flame persists, put on another layer of pitch. Allow the bomb to cool and take it out of the way in a bucket or metal container. If the bomb has fallen on something inflammable like wood, cover the bomb with a layer of pitch, again with a long handled shovel. Then spread a layer near the bomb and roll the bomb on the spread pitch; spread a layer entirely over the bomb. Fires already started may (if the bomb is covered with pitch and out of the way) be put out with a hose or chemical extinguisher. Some bombs contain explosive charges; so protective clothing, goggles, and long handled implements are recommended.

### No. 5

For Explosive Incendiary Bombs
Spray on water, staying behind
an iron shield or wall.

Gun Recoil Fluid	
Glycerin C.P.	gal.
Water, Distilled	gal.
Caustie Soda, C.P.	oz.

Transfer	Liquid	for	New	spa	aper
	Pict	ıres			
Tincture	Green	Soar	1/8	fl.	oz.

i incente Green Soap	78	11.	OZ.
Turpentine	1/8	fl.	oz.
Water, To yield	16	fl.	OZ.

Moistener for	Mime	ograpi	h I	Rolls
Glycerin		2	fl.	OZ.
Water, To yi	$\operatorname{eld}$	1	ga	1.

Preventing Printing Press Static
Use finely powdered mica to dust
off tympan. This works better than
talcum and eliminates offset as well
as static electricity. This is especially useful on high speed presses.

# Preventing Printing Offset Canadian Patent 373,457

The following solution is sprayed through currents of air to facilitate concentration and rapid drying on paper:

Gum Arabic	18 oz.
Glucose	12 oz.
Water	35 oz.
Alcohol	35 oz.

Making Small Animals Transparent For best results use such vertebrates as mice, fish, salamanders, frogs, and snakes. Anything larger than a rat should not be used. It is also important that throughout this technique chemically pure materials are used. Impure chemicals result in discoloration.

1—The animal is first fixed and posed in 40% formalin or alcohol for two days. In this technique the animals are cleared with their skin, hair, and insides unmolested, but in the case of fish and snakes the scales must be removed because they take on the stain. By first fixing the animal in formalin or alcohol the tissues are thus hardened, a process similar to that used by the ancient Egyptians in preparing mummies.

2—Wash the specimen in water and place into a 2% solution of potassium hydroxide (KOH) to which a few drops of 3% hydrogen peroxide has been added. The 2% solution of potassium hydroxide is prepared by adding 2 grams of C.P. KOH pellets to 98 cc. of water. Whenever the solution becomes cloudy or discolored it should be changed. Continue this step until the flesh appears jelly-like and the bones become visible.

3—The animal is now stained with a selective dye, one that stains the bones rather than the tissues of the specimen. The stain for this purpose is alizarine monosulphonate. The stain is prepared by adding very small amounts of the powdered dye to a solution of 2% KOH until a light wine color is obtained. The animal is kept in this stain for two days or until all the bones are stained red and are clearly visible. Do not leave specimen in the stain too long, otherwise overstaining will take place and the tissues as well as the bones will be colored. If this does occur the animal may be destained by placing into a 2% solution of KOH plus a few drops of 3% hydrogen peroxide.

4-At this stage clearing of the | chlorophenate.

specimen is begun by means of glycerin. This may be accomplished by placing the animal into each of the following solutions for at least three days:

- (a) 25 parts glycerin: 75 parts 2% KOH
- (b) 50 parts glycerin: 50 parts 2% KOH
- (c) 75 parts glycerin: 25 parts 2% KOH
- (d) 100% glycerin

5—The animal is now preserved in a fresh bath of pure glycerin to which a crystal of thymol is added to prevent the growth of molds.

6—The final step is the sealing of the container. A cork stopper should never be used. A Bakelite screw cap, glass stopper, or paraffin will do very well. Mount on a white glass background.

Nutrient Broth for Yeast Sucrose 100 g. Peptonum Siccum 20 g. Dipotassium Phosphate 5 g.

Magnesium Sulphate 1 g. Ammonium Sulphate 5 g.

The growth of brewers' yeast increases at least six times in 48 hours in this medium.

Fermentation Mash Sterilizer 0.7 liter of formaldehyde is used per 100 liters of mash.

Medium for Drosophilia	Culture
Water	1000
Tomato Paste	100
Corn Syrup, White	100
Agar, Granulated	20
Moldex	1

Killing Spray Pond Algae Use 30 p.p.m. sodium pentachlorophenate.

# Preventing Mold Growth on Barrels Hungarian Patent 124,005

Wooden wine or other barrels are coated with

Shellac	12	g.
Alcohol	1	ĺ.

# Heating Mixture for Food Containers

U. S. Patent 2,289,007

Sodium Monoxide	30
Aluminum Powder	20
Pumice	20
Water	50

The purpose of this mixture is to create a reaction in the inner can of a container holding one quart of food in its outer compartment, which will raise the temperature of the food from 0° F. to 110° F., thus thoroughly warming the food. The sodium monoxide, aluminum powder and pumice are placed at the bottom of the inner can while the water is placed in the upper section of the can, the two areas being separated by a plate segment. The inner can here should not occupy more than one third of the total volume of the container. Perforation of the plate segment allows the water to drip on to the mixture thus initiating the action. The heat evolution during the reaction is sufficient to raise the temperature of the contents of the can to 110° F.

Self Heating Pad Composition
Iron Filings (150 Mesh) 1 lb.
Cupric Chloride 5 g.
Before use add
Water 15 cc.
and shake well.

# Boiler Compounds Formula No. 1

Soda Ash	76
Trisodium Phosphate	10
Starch	1

and sufficient cutch or dry extract of hemlock, oak or chestnut bark to yield 2% tannin.

# No. 2

± Y	U. 2
Soda Ash	44
Disodium Pho	sphate,
Anhydrous	47
Corn Starch	9

### No. 3

# British Patent 513,386

Diffusii Tatent 919,900	
Graphite, Powdered	85
Aluminum Bronze	9
Zine Dust	3
Tale	3

### No. 4

# U. S. Patent 2,291,146

C. D. I atent 2,231,	140
Sodium Carbonate	7%
Trisodium Phosphate	5%
Borax	3%
Water, To make	100%

# Clarification of Water U. S. Patent 2,251,748

The following composition, in powdered form, is added to the water. It forms a floc with suspended and dissolved solids which settles to the bottom. The clear water is drawn off from the top of the settling tank.

Coal	70
Sodium Aluminum Tannate	20
Ammonium Ferrous Sul-	
phate	5
Magnesium Tannate	5

# Water Softener

# II S Patent 2.102.219

C. N. = 55000000,	
Trisodium Phosphate	20 lb.
Borax	3 lb.
Alum	3 lb.
Water, Hot	6 qt.

Dissolve the above and mix with following solution:

Sodium Aluminate  $\frac{1}{2}$  lb. Water 1 pt.

Boil mixture until it sets to a gel on cooling.

# Conditioned Well Drilling Mud U. S. Patent 2,271,696

Formula No. 1		
Add Flour	1	%
No. 2		
Add Flour		%
Glycol Oleate	0.	1%

No. 3 Add Flour 1 % Glyceryl Monoricinoleate 0.1%

Sculptor's Modeling Composition U. S. Patent 2,214,126

U. D. 1 0000110 2,211,121	•
Sand, Fine	37.5
Aluminum, Powdered	12.5
Talc	12.5
Lacquer	37.5

# Artificial Cat Fish Bait

Obtain several dozen earthworms and pack them in a tin can in the following order. First, place a layer of cut up bath sponge in the bottom of the can, then a layer of earthworms, then another layer of sponge, then earthworms, and so on until the

can is over half full. Cut up the sponge in pieces about ½ inch by ½ inch.

Now set the can away in a warm place and let the whole can of worms and sponge pieces rot. After several weeks, there will be an almost unbearable stench. Use these sponge pieces to bait your hooks when you go fishing for cat fish, and you will be surprised how the fish will take your bait.

# Sensitized Paper to Indicate Exposure of Sterile Solutions, etc., to High Temperatures

Silver Nitrate	15
Potassium Bitartrate	15
Ammonia (28%)	60
Sugar	4
Powdered Acacia	4
Carmine, (No. 40)	1

This yields a red preparation that is applied by brush, to white filter papers. After drying in air, the papers are cut into strips, about 2 or 3 inches long, and ½ inch wide. These sensitized strips are to be stored in glass containers kept in a dark, cool location.

The red color is changed to black when strip has been exposed to the moist heat of an autoclave or steam sterilizer.

A strip of the sensitized paper is placed over the cotton plug in the mouth of a flask of solution subject to sterilization. A strip of coarse gauze is then fastened over cotton and strip. The presence of a black strip, subsequently indicates the contents of flask to have been exposed to high temperature necessary to insure sterility.

Colors Indicating Temperatures

The following inorganic combinations with methenamine (hexamethylene tetramine) and water are agents for indicating temperatures based on color changes:

	Color Change	
	at ° C.	Color Change
Cobalt Chloride: Methenamine: water	35	Rose Blue
Cobalt Bromide: Methenamine: water	40	Rose Blue
Cobalt Iodide: Methenamine: water	50	Rose Green
Cobalt Thiocyanate: Methenamine: water	r 60	Rose Blue
Cobalt Nitrate: Methenamine: water	75	Rose Purple
Nickel Chloride: Methenamine: water	60	Bright Green
		Violet
Nickel Chloride: Methenamine: water	100	Yellow Vio-
		let
Nickel Bromide: Methenamine: water	60	Bright Green
		Blue
Cobalt Sulphate: Methenamine: water	60	Rose Violet

# Universal pH Indicator

Five mg. of thymol blue, 25 mg. of methyl red, 60 mg. of bromothymol blue and 60 mg. of phenolphthalein are dissolved in 75% alcohol to make 100 cc. of solution; this is then neutralized with hundredth-normal sodium hydroxide to produce a green color, but for high and low pH values it can be used directly. This combination shows at whole pH values between 4 and 10 the following distinct color changes: red, orange, yellow-green, blue, indigo and violet. Intermediate color changes are recognizable with an accuracy of 0.5 pH.

To Dissolve Methyl Cellulose
Quickly
Methyl Cellulose 1
Propylene Glycol 1
Water 1
Water, To desired concentration
Add the propylene glycol diluted

with an equal part of water to the methyl cellulose. Mix intimately for about 10 mins. Add half of the water heated to boiling and continue to stir for another 5 minutes. Now add the remaining water and cool as much as possible.

Activator for Zine	Printing Plates
U. S. Patent	2,215,551
Asphalt	5.42
Carbon Black	5.42
Pitch	2.46
Petrolatum	29.90
Turpentine	50.80
Phenol	6.00

Sodium Hexametaphospha	ite
Russian Patent 54,794	
Sodium Dihydrogen	
Phosphate	70
Sodium Hydrogen	
Phosphate	30
Sodium Carbonate	5-7
Fuse at 650-800° C.	

Substitute for Acetic and Formic Acids

Ammonium Sulphate 15 lb. Sulphuric Acid (66°) 25 lb. Water 40 gal.

In textile practice the above replaces 56% acetic or formic acid pound for pound.

Water Resistant Alkali Silicate U. S. Patent 2,234,646 Sodium Silicate (40-42° Bé) ½ gal. Water 1/2 gal. Formaldehyde 1-6fl. oz. Sodium Aluminate (30% Solution)  $\frac{1}{3}$ -1 $\frac{1}{2}$  oz. Sodium Abietate 1-3 OZ. Mix well before use.

Clear Starch Solution Water, Distilled 100 cc. Thymol 0.1 g. Bring to a boil and add Starch mixed to a cream with cold water. Boil for 2-3 minutes. Add Mercuric Iodide if solution is to be kept for a long time.

Syrupy Gasoline

1. Aluminum Cetyl Acetate 2. Oleic Acid. White 3. Gasoline

Rub 1 and 2 into a paste and then stir in 3 warming gently.

# Wax Beakers for Use with Hydrofluoric Acid

Glass beakers or bottles, having outside diameters equal to the inside diameters, desired for the wax beakers and filled with cold water. are dipped into the molten wax (paraffin wax, old hydrofluoric acid bottles, damaged wax beakers, etc.). Then the beakers are held in the air until the wax solidifies from one dipping before the next dipping. Repeated dippings will build up the wax to any desired thickness. The depth to which the beakers are immersed should be greater than the desired height of the beaker. Reinforcement, by a paper band, can be pasted around the wax before the dippings are completed.

The formed vessel is removed from the mold by putting boiling water in the glass vessel, whereby an inside film of the wax is melted. The wax vessel will slip off easily if two holes are made in the bottom of the wax vessel, one at the center and one at the edge; these holes admit air and prevent a vacuum suction. The wax vessel is ready for use after closing the two holes with a warm rod and trimming the top to give the desired height. If the top part of the newly formed wax vessel is too thin, the vessel can be held by the bottom and dipped some more in the molten paraffin. Two vessels can be made simultaneously—one in each hand. Manufacture is faster: (1) out of doors in cold weather:

(2) if the temperature of the molten wax is just above its melting point: and (3) if the water in the beakers, when it gets warm, is changed for cold water.

Artificial Pe	rspiration	
	Acid	Alkaline
	perspiration	perspiration
Sodium Chloride	3.5	3.5
Urea	0.5	0.5
Glucose	0.15	0.15
Di-Sodium Hydrogen Phosphate	0.2	0.2
Ammonium Chloride	Nil	0.8
Ammonia (.880)	Nil	0.4
Acetic Acid (1% Solution)	20 cc.	50 cc.
Distilled Water	to 1000 cc.	to 1000 cc.
pH	5.0	7.5

The amount of 1% acetic acid to be added is that just required to give the pH values indicated.

# DYEING COROZO (IVORY NUT) BUTTONS

One-Color or Uni-Dyeing

First the buttons are soaked. Wooden containers are preferable to metal tanks, since the latter may give off iron causing the buttons to appear spotty. The buttons are soaked in cold water for 12 hours. By this time the albumin contained in the ivory nut is dissolved. Then the buttons are boiled, by way of a steam jet. The albumin will form a white frothy mass which should be removed in order to avoid the forming of veins on the buttons during the dyeing process. In order to check the developing of veins about 3% Monopol-Brilliant-Oil may be added.

For dyeing ivory nut buttons it is advisable to dissolve the dyes in advance.

	~ ~ .			
H	ere	are the proportions:		
C	olor	ant	Wa	ter
1	kg.	Logwood Extract	8	l. '
1	kg.	Yellow Wood		
	(Fu	stic Wood)	8	1.
1	kg.	Catechu	6	1.
1	kg.	Sumac Leaves	8	1.
1	kg.	Logwood Shavings	10	1.

2 kg. Yellow Wood	
Shavings	10 l.
1 kg. Red or Brazil	
Wood or Barwood	
Shavings	10 l.
1 kg. Yellow Oak	
(Quercitron Bark)	
Extract	8 l.
1 kg. Potash Chromate	15 l.
1 kg. Ferric Sulphate	15 l.
The following formulae a	re based
upon 10 l. of water:	

# Light Blue-Gray

3% liter of logwood shavings, ½ liter of yellow wood shavings, ½ liter of sumac leaves, 10 liter of water. Boil buttons in this mixture for 20 minutes, take them out, put them into solution of ½ liter of ferric sulphate to 10 liter of cold water for 4 minutes, take them out; do not rinse. Rub buttons in saw dust.

# Medium Blue-Gray

34 liter of logwood shavings, 14 liter of yellow wood shavings, 1/2 liter of sumac leaves, 10 liter of water. Boil buttons in this mixture for 20 min., take them out, rub them in solution of 1 liter of ferric sulphate to 10 liter of water for 4 min.

Dark Blue-Gray

1.5 liter of logwood shavings, ½ liter of yellow wood shavings, 1 liter of sumac leaves, 10 liter of water. Boil buttons for 20 min., take them out, put them into solution of 1.5 liter of ferric sulphate for 6 min., take them out, rub them.

Light Yellowish Gray

1/8 liter of logwood shavings, 3/8 liter of yellow wood shavings, 1/8 liter of sumac leaves, 10 liter of water. Boil buttons for 20 min., take them out, put them into ferric sulphate solution (10 liter of water to 1/2 liter of ferric sulphate) for 5 min., rub them.

Medium Yellowish Gray

10 liter of water, ¼ liter of logwood shavings, ¾ liter of yellow wood shavings, ¼ liter of sumac leaves. Boil buttons for 20 min., take them out, put them into solution of 10 liter of water to 1 liter of ferric sulphate for 5 min. Rub them.

Dark Yellowish Gray

10 liter of water, ½ liter of yellow wood shavings, 1 liter of sumac leaves. Boil for 20 min. Take them out, put them into solution of 10 liter of water to 1.5 liter of ferric sulphate for 6 min. Rub them.

Reddish Gray

10 liter of water, 1 liter of sumac leaves. Boil buttons for 20 min. Take them out, put them into solution of 10 liter of water to 1 liter of ferric sulphate for 10 min. Rub them.

For darker or lighter coloring add more or less of dyes.

Fashion Colors

For these shades a combination of sumac leaves and yellow oak or yellow oak extract is used. For instance: 10 liter of water, 1.5 liter of sumac leaves, ½ liter of yellow wood extract. Boil buttons for 20 min., take them out, put them into solution of 10 liter of water to ½ liter of ferric sulphate for 2 min., take them out, put them into hot water, rub them. More or less yellow wood extract makes the buttons more or less yellowish. The longer the buttons are allowed to remain in the solution the grayer they become.

# Olive Shades

For these colors yellow oak and yellow wood extract in combination with sumac leaves and logwood extract are widely used. For instance:

10 liter of water, ½ liter of yellow oak or yellow wood extract. In using the above recipes buttons must be thoroughly boiled. Also stirring must not be overlooked, otherwise buttons get spotted. All the buttons dyed in the same bath should be of the same material if the same color is desired. It is, e.g., impossible to dye uniformly small waist coat buttons made of peeled guayaquil and coat buttons made of large hollanders in one batch. Different sorts of nuts give different dyeing effects.

Multi-Colored Buttons

We distinguish between

Speckled or jaspe.
 Imitation Buffalo Horn.

3. Fabric imitation, produced by spraying stripes and checkers.

1. Speckled or Jaspe Buttons

There are two kinds. Those which are sprayed directly with dyes and those which are first sprayed with insulating varnish and later on dyed.

Sprayers used for both methods consist of two thin tubes arranged at right angles like atomizers for flower sprinkling. Buttons are soaked in water for 12 hours, then boiled and finally thoroughly cooled by rinsing in cold water. Then, wet as they are, they are placed on boards, tin sheets or the like and again sprayed with water. Then excess water is removed with a sponge so that all the buttons are equally moist. Now the dye is sprayed on; several different dyes may be sprayed on at the same time and very nice shades may thus be obtained.

For the varnishing method the buttons are boiled, dried in saw dust, placed upon boards and covered with fine dots of varnish. The varnish which is also extensively used in other button spraying methods is a solution of colophony or rosin in alcohol. It is of great importance that it does not peel off.

When the varnish is dry, buttons are dyed in different shades like unicolored ones excepting that all baths must not be warmer than 50° C. After dyeing, varnish is removed in a hot solution of sodium carbonate or ammonia.

# 2. Spraying for Imitation Buffalo Horn

This is done with a spraygun. There is a great variety of material for spraying stencils. Some are etched or pressed copper sheets, some are of braided wire or turpentine soaked string. For imitation buffalo horn fret sawed zinc stencils are most frequently used.

The working method is as follows:
Buttons are soaked for 12 hours,
then thoroughly boiled and cooled
in cold water. Part of them is now
first rubbed in saw dust then well
cleaned by shaking in a bag of

porous material. It is advisable not to prepare more buttons than can be sprayed within an hour. If buttons are exposed to dry air for more than an hour the pores of the ivory nut contract again preventing proper infiltration of the dye.

Boards to place the buttons on should be 1.5 cm. thick. The boards have holes on their upper side into which the buttons fit. The stencils have as many patterns as there are holes in the board. Care must be taken that stencils and button boards match precisely. After spraying the buttons remain on their boards for at least 12 hours allowing the dye to penetrate deeply into the body of the buttons.

Then the buttons, according to the color desired, are put into a ferric sulphate or a potash chromate bath in order to fasten the dye and to prevent its getting off in the polishing process.

If multi-colored buttons are to be made they are sprayed a second time, this time with varnish. For this process stencils must fit particularly well, to the holes, allowing the varnish to penetrate in very delicate lines so that the finished buttons look exactly like natural horn buttons, showing only a few white spots. When the varnish is dry, buttons are dyed in a little lighter shade than that of the spraying dye. Compositions of shades such as brown spray on gray ground or olive spray on greenish ground are very popular and very attractive.

Numerous variations and combinations are possible. We can spray simply with varnish and then dye or we may spray with a lighter shade first and then with a darker one. There are so many methods that there is ample room for the inventiveness of the expert.

In some factories they produce excellent imitations of genuine buffalo horn buttons by scratching off the varnish with a wire brush. The very fine lines thus produced look deceptively like end grains of genuine horn.

3. Producing Stripes and Checkers
Box spraying method:

For this method an airtight wooden box, 3 meters high, 2 meters deep and 2 meters wide is needed. Its bottom is removable. Into this box the boards, covered with buttons (after soaking and boiling), are inserted. The shape of the boards depends on the shape of the stencils available. Then the box is closed airtight. There is a hole in front of the box which can be closed with a flap. Through this hole dye is sprayed in a very fine rain or even as mist. It spreads inside the box and slowly settles upon the buttons. After 20 min. the bottom is pulled out and the stencils are removed.

This method results in a very attractive and uniform coloring. By repeated spraying most beautiful shades and patterns may be obtained that look deceptively like woven fabrics.

# Dyeing of Nacre or Mother-of-Pearl

Quickly and easily a great variety of shades can be laid on nacre. Besides natural shades most beautiful artificial shades and lusters may be produced.

First the objects are treated with a weak pickling solution in order to

remove grease. For this purpose they are put in a solution of 1 part of pure white potash to 10 water; kept therein at a steady temperature for about 1/4 of an hour, drained and repeatedly rinsed and dried. Treated this way, nacre will eagerly absorb dves, particularly those dissolved in alcohol; in a short time it will be colored throughout. On account of the density of the material, coloration turns out rather dark. Weak solutions are therefore advisable. The longer the material is allowed to stay in the bath the deeper the dye will penetrate. It is therefore up to the dyer to dye the whole body equally and uniformly. After dyeing the objects are rinsed in pure water and dried in saw dust.

Often light or irregularly colored gray or gray-black mother-of-pearl is to be blackened. Many shells are colored only around the edge or a few cm. toward the center, the center itself being white.

Nacre is treated in such a way that silver chloride is formed and then exposed to sunlight. A saturated solution of silver chloride in ammonia is used. Put the nacre in and leave the well sealed container for several days in a dark room, shaking the same from time to time. Then put the pieces on blotting paper, expose them to sunshine and after 3 days dark colored nacre is obtained.

Now the finished and polished articles of nacre are put into a glass container and the above solution is poured over them. From time to time the container is shaken in order to change the position of the pieces so that not always the same spots are covered. After 24-60 hours the

pieces are taken out, put on blotting paper and exposed to direct sunlight.

The blackening effect goes rather deep. Disks of about 10 mm. thickness which have been in the solution for 48–60 hours, when broken apart, appear, inside, a uniform dark gray. They may be ground or polished and no white spots will appear. The outer appearance of nacre, dyed this way, is exactly like natural black nacre. The longer the solution and the sunlight are allowed to act on the material, the darker it will turn. Iridescence will be the higher, the more brilliant the original piece of nacre.

It has recently been asserted that admission of air to the solution will produce an even more attractive coloring than exclusion of air.

oring than exclusion of air.

Bronzelike Iridescent Colors

Iridescent shades may be produced by way of coal tar dyes which, besides iridescence, will give the material a very attractive appearance.

Aniline blue will produce a brownish; fuchsine a greenish bronze tone.

Dissolve 1 part of aniline blue in 40 parts of alcohol or 1 part of fuchsine in 45 parts of alcohol and put articles in such solution for ½ hour.

The finished objects should actually look blue or red as the case may be and the bronzelike iridescence should be seen only when they are struck by oblique rays of light.

Coloring Mother of Pearl Buttons
Buttons or other items made of
Mother of Pearl are advisedly prepared for dyeing by first cleansing
of grease and other repellent substances. This is best effected by im-

mersing the material in a 10% solution of potassium hydroxide for 10 minutes at 120° F. and followed by a thorough hot rinsing. Thereafter dyeing is carried out by boiling mildly for 1 to 2 hours in water solution of the selected dyestuffs:

Out of hundreds checked, the following colors give shades of good depth and satisfactory brightness:

Acid Colors

Amacid Yellow M Conc. Amacid Azo Yellow G Conc. Amacid Yellow GNS Naphthol Yellow S Brilliant Milling Yellow 5G Orange Y Conc. Milling Orange PGS Conc. Amacid Neutral Orange G Orange RO Amacid Neutral Orange SGS Brilliant Croceine 3BA Conc. Amacid Milling Scarlet G Fast Red A Conc. Amacid Neutral Red BW Conc. Brilliant Milling Red P2B Acid Rhodamine B Eosine Y Amacid Resorcine Brown G Amacid Neutral Brown RN Conc.

Formyl Violet 3B Ex. Conc. Brilliant Indocyanine 6B Alizarine Leveling Blue CA Amacid Fast Blue BL Brilliant Indocyanine G Amacid Blue A Amacid Fast Green BBF Amacid Black 10BR

The following colors of the Basic class give excellent results as to depth of shade and brightness:

Auramine O Thioflavine T Phosphine 2G Acridine Oranges Rhodamine 6GDN Ex.
Safranine 6B
Safranine Y
Methyl Violets
Rhoduline Blue 6G
Brilliant Rhoduline Blue R
Methylene Blue ZF
Astrophloxin FF Ex.

Basic colors are best applied at 160° F. and never in conjunction with the acid colors.

Manufacture of Artificial Gems
The fact that pieces of suitably colored glass can be made to show a superficial resemblance to precious stones, has led to the manufacture of imitation jewels of all descriptions. The glass used for the purpose possesses greater hardness and density than the ordinary product, and colored to simulate the precious stones. Finally the external shapes of gems are, of course, readily imitated by cutting and grinding the glass.

All the properties mentioned above are imparted to the flux, partly by special treatment, partly by admixtures, but principally by the purity of the substances used. Besides the essential components, lead oxide, minium, etc., are added to the fluxes. These impart greater density to the glass, more luster and specific gravity. But too much lead oxide must be avoided, as it disintegrates the surface and spoils the luster. A great degree of hardness can be obtained by using large proportions of silica, but the flux becomes refractory, to prevent which borax is added.

The raw materials which are necessary for mixing a good flux are as follows:

- 1. Pure silica. It is best to use for this finely powdered rock crystals.
- 2. Pure potash or sodium carbonate.
  - 3. Borax.
- 4. Lead oxide, carbonate or minium.
- 5. A little potassium nitrate, partly to promote the fusion, but especially to destroy by oxidation any carbonaceous impurities which might injure the color.
- 6. A metallic oxide to give color to the flux.

In melting a specific composition an ordinary glass-melting furnace can be employed. The best type of furnace is furnished with a gas-conducting pipe from which four pipes branch off. The upper end of these pipes is bent inward. The gas flame plays under the fire-brick furnace. the thick walls of which form the hearth. The bottom is provided with an opening through which the gases enter into the crucible placed exactly over it, so as to circulate around the actual crucible containing the flux, and resting upon a support of fire-clay and a movable rod. The gases, after playing around the crucible pass out through a hole in the cover and then around and down the walls towards the escape pipe.

The ingredients are separately ground to impalpable powder, sifted through a fine sieve and then weighed. These are then intimately mixed in a mortar and put in a new Hessian crucible and covered with a clay plate. The crucible is next introduced into the furnace and heated by gas flame from bottom. When the mass has been fused the crucible is withdrawn from the

hearth and the clay plate is removed to pour out the molten mass. After allowing to cool to normal temperature the glass is cut into desired shape and polished.

# Fluxes

Rock Crystal	20.23
Sodium Carbonate	14.61
Calcined Borax	10.96
Minium	7.20
Potassium Nitrate	3.65

Powder the ingredients separately and mix. Then fuse the mixture in the manner stated under general process.

A harder flux is obtained by mixing the substances in the following proportions:

oper creator.	
Rock Crystal	43.84
Sodium Carbonate	14.61
Calcined Borax	10.96
Minium	7.20
Potassium Nitrate	1.21

A flux so hard that it will spark when struck with a piece of steel can be prepared from the following substances:

Rock Crystal	10.96
Powdered Glass	29.23
Minium	10.96
Calcined Borax	2.20
Potassium Nitrate	2.43
Arsenic	0.60

Pure flint finely powdered may be used instead of rock crystal, or white powdered glass, but in the latter case some white arsenic must be added to obtain the frit entirely colorless.

These fluxes furnish the "Strass" which is the basis for the manufacture of artificial gems.

-Ru	by	
	I	II
Rock Crystal	29.23	29.23

Dry Sodium		
Carbonate	14.61	14.61
Calcined Borax	10.96	4.84
Saltpeter	5.47	2.43
Copper Oxide	3.65	0.91
Antimony Trisul-	-	
phide	0.50	
Manganese		
Dioxide	0.50	
Minium	10.92	
Sal-Ammoniae		3.65
Sapph	ire	
• •	I	II
Rock Crystal	43.84	29.23
Sodium Carbon-		
ate	21.92	14.61
Borax	7.20	10.96
Minium	7.20	5.47
Potassium Nitrat	e 3.65	1.82
Cobalt Carbonate	0.06	
Copper Carbonat		1.82
Emerc	ald	
Rock Crystal		43.84
Dry Sodium Carl	onate	14.61
Calcined Borax		7.20
Minium		7.20
Saltpeter		2.43
Cobalt Carbonate	е	0.09
Chrome Green		0.30
The above mixt	ure pro	duces
equitiful green cold	-	

beautiful green colored emerald.

As a general rule uranic oxide, which gives yellow colors shading only slightly into green, furnishes an emerald green when used in the following proportions:

36.43
10.96
7.20
3.65
2.43
0.18
0.18
0.18

# Chrysoprase

The following mixture is decidedly the best for imitating the transparent, apple-green color of this stone.

and Stories	
Rock Crystal	43.84
Sodium Carbonate	14.61
Calcined Borax	10.96
Minium	7.20
Saltpeter	1.21
Calcined Bones	7.20
Copper Carbonate	0.12
Ferric Oxide	0.24
Chrome Green	0.36

The above mixture gives dark colored stone.

1 1	200	~	1

Rock Crystal	32.29
Sodium Carbonate	10.96
Calcined Borax	7.20
Minium	5.47
Saltpeter	0.91
Copper Oxide	0.06
Calcined Bones	0.09
Silver Chloride	0.12
Garnet	
Rock Crystal	32.29
Sodium Carbonate	10.96
Calcined Borax	7.93
Minium	5.47
Saltpeter	2.43
Manganese Dioxide	0.36
Ferric Oxide	0.18
~	

If a brighter color is desired add 0.06 part of copper oxide to the mixture.

# Amethyst

Amethyst may be prepared by using manganese dioxide, but not more than 0.06 part of it must be taken for a frit producing about 30 parts of flux. Powdered glass in the proportion of 30 parts, 3.65 parts of potassium nitrate, and some borax and minium give also a good imitation of the amethyst.

Lapıs Lazuu	
Rock Crystal	21.92
Sodium Carbonate	7.20
Calcined Borax	5.47
Minium	3.65
Potassium Nitrate	1.00
Calcined Bones	3.65

Agate

0.12

Cobalt Oxide

Agate can be imitated by allowing fragments of different fluxes to run together, stirring the mass in the meanwhile.

Several varieties of agate are obtained by mixing about 1.82 parts of ferric oxide with 43.84 parts of flux.

The following is another method of producing artificial gems: 2 parts of pure rock crystal, 1 of calcined soda, ¾ of anhydrous borax, 1–16 of lead oxide are rubbed together as intimately as possible, and heated in a crucible for one hour without allowing the mass to become liquid. It is then brought into fusion and kept so for one hour, when it is allowed to congeal. It is then moderately heated for 24 hours, and the resulting flux taken from the crucible, cut and grained.

This forms the base for the flux of the artificial gems.

The following minerals are added as coloring substances:

Blue-Cobalt oxide.

Yellow—Antimony pentoxide.

Green—Cupric oxide.

Red—Purple of cassius.

Violet—Black oxide of manganese.

# Fluorescent Gems

Artificial gems which fluoresce a bright greenish or yellow color under ultraviolet light may be cut from ordinary green glass which contains uranium as a pigment.

By adding small amounts of manganese, chromium, or uranium to fused glass and allowing the metal to dissolve, in the glass, a highly fluorescent substance is produced. This can be cut into cabochon and facet gems suitable for theatrical and advertising effects.

# Artificial Fluorescent Minerals Formula No. 1

Ordinary and slightly porous minerals can be dipped into solutions of fluorescent chemicals, such as sodium salicylate, and allowed to dry. These artificially prepared fluorescent minerals can be used for display purposes and will fool many experts on the subject.

# No. 2

The following mixture is fused in a crucible:

Sodium Nitrate 100 Uranyl Nitrate 0.5

This solid fluoresces a bright yellow to green under ultraviolet light.

# No. 3

Agates can be soaked in kerosene in order to produce a blue-fluorescing stone. After several weeks the kerosene will evaporate and the treatment will have to be repeated.

## No. 4

The following solution can be used for making ordinary stones fluorescent:

Quinine 10
Water 999
Sulphuric Acid 5–8

This solution should not be used on calcareous rocks such as limestone. Fluorescent Sand and Stones

Sand used in advertising, display, and for models may be dyed with fluorescent dyes and illuminated with ultraviolet light. This is especially effective when used in store windows and for small scale demonstrations.

Pebbles of different fluorescent minerals, such as wernerite, dakeite, willemite, calcite, and others, can be mixed and used for a large number and wide variety of show window effects.

# Fluorescent Signs

Glass signs made from tubing filled with a solution of umbelliferone, uranine, or other dye, and under ultraviolet light, may be used in show windows and for advertising as a "cold" source of colored light, as well as to substitute for neon signs.

Small particles of fluorescent minerals can be embedded in a wax backing and made into signs. These are very colorful under ultraviolet light.

# Fluorescent Prospecting Screen

A piece of cardboard is coated with powdered willemite or other brightly fluorescing mineral. When ore containing mercury is heated and placed between the screen and a source of short wave-length ultraviolet light dense dark fumes of mercury vapor will be seen rising from the ore. Other ores and metals do not respond in this way.

# Fluorescent Smoke

When a finely divided phosphor, such as zinc orthosilicate, is blown into a beam of ultraviolet light in an otherwise darkened room, the particles will light up with a bright

green light.

Billows simulating fire can be made by blowing zinc beryllium silicate or other red-fluorescing phosphor or powdered calcite into a beam of ultraviolet light. Dyes should not be used since they stain garments and skin.

"Invisible Thief-Catching Powder"

A substance which is white and unnoticeable in ordinary light, but brightly fluorescent in ultraviolet light may be used to catch thieves. Anthracene, zinc sulphide phosphor, fluorescein, or other such substance may be employed to advantage.

Ordinary powdered tumeric can be dusted on money, food, or other objects. When handled by a guilty person traces of powder will adhere to the hands and clothes and this may be seen in ultraviolet light by the bright yellow fluorescence which is enhanced by treatment with water or chemical reagents.

Old X-ray fluoroscopic screens may be scraped off and the brightly fluorescent powder used for tagging objects. This powder usually glows brightly under short wavelength ultraviolet light, but it should not be used on articles intended for human consumption.

Multi-Purpose Fingerprint Powder When anthracene is dusted over a finger, particles adhere and dissolve slightly in the oil secretion. This fingerprint is self-luminous under ultraviolet light and a photograph may be taken on a multi-colored or irregular object.

The fingerprint can be "lifted" as

usual with colorless scotch tape and photographed under ultraviolet light. The tape itself may fluoresce slightly.

# "Hot Rocks"

In a darkened room lumps of redfluorescing calcite may be used to simulate hot rocks and glowing coals when ultraviolet light (short wavelength) is directed toward the calcite. A person can walk across the red-fluorescing calcite in his bare feet and create a great deal of interest since, in all appearance, he is walking on glowing coals.

# Fluorescent Animals

A small chick or other living animal may be dipped in a solution of neutral acriflavine and allowed to dry. Under long wavelength ultraviolet light, the animal will emit its own light with a striking effect on the audience.

A dog's tail, for example, can be dyed with an organic and fluorescent dye and, under ultraviolet light in darkness, all that may be seen is a luminous wagging tail.

# Fluorescent Moustache

A moustache may be dyed with acriflavine or other fluorescent dye and made to glow with a weird light when illuminated with ultraviolet rays. Long wavelength and filtered ultraviolet light should be employed.

Naturalizing False Teeth and Eyes
The life-like luster of natural
teeth may be simulated in false
teeth by incorporating a small
amount of metallic activator and
according the mixture heat treatment so that a phosphor-like system

is set-up. Porcelain may be used as the base.

Likewise, the life-like luster of the sclera of natural living eyes may be imitated in the same manner.

Dental Investment Composition U. S. Patent 2,247,395 Cristobalite 50–80% Calcium Sulphate  $(\frac{1}{2} H_2O)$  20–50% Calcium Chloride 2% Ammonium Chloride  $\frac{1}{4}$ -3%

Imitation Meerschaum U. S. Patent 2,245,489

Hydrous silicate of magnesium is finely powdered in a ball mill or other suitable grinding device. The grinding should be carried on until an exceedingly fine impalpable powder is produced.

This powder is then thoroughly mixed with sufficient raw egg whites to form a thick, damp paste which can be easily pressed or molded into any desired shape. The preferred portions are 100 grams of egg whites to 144 grams of magnesium silicate. The dampened powder or paste is then placed into molds and pressed

into its final form such as a smoking pipe; a smoking pipe lining; or a cigar or cigarette holder.

The damp pressed articles are then placed in a suitable drier and maintained at a temperature of from 100 to 130° F. for a period of 24 hours. When removed from the drier, it is a hard, light, form-retaining product which can be polished, ground, machined, or carved as desired to produce the finished article.

# Stylus

German Patent 682,661

Red beechwood is impregnated at 50° C. with

Sodium Acetate	25 g.
Sodium Nitrate	20 g.
Potassium Aluminum	
Sulphate	35 g.
Sodium Nitrite	25 g.
Water	3 l.
This stylus will not	break or
eratch in ordinary use.	

Preservative	for	Feathers
Salicylic Acid		10 lb.
Salt		40 lb.
Boric Acid		45 lb.
Potassium Nitr	ate	65 lb.

# CHAPTER TWENTY-TWO

# SUBSTITUTES \*

Selecting the proper substitute is no easy task. Since no material has all the same properties as the original, it cannot be expected that the replacement will give the finished product all of the same characteristics that it originally possessed. A replacement, therefore, that will produce a finished product which will perform almost the same function as the original, without too great a difference, is ordinarily considered satisfactory. For example glycerin, in an anti-freeze, has been satisfactorily replaced by ethylene glycol even though the two products differ in chemical and certain physical properties.

A substitute material, excluding price and availability, must be considered from many angles before it can qualify as a good substitute. Since it cannot have all the same physical and chemical properties as the original material, a compromise must be made. Thus, corn syrup may be suitable, as a glycerin replacement, in a suspending medium, where the former's viscosity is primarily desired; as in certain tooth-pastes. It is not of importance that corn syrup does not lower the freezing point of water or that it is not as hygroscopic as glycerin. Where, however, the last two factors, or others, are important, the use of corn syrup in place of glycerin, is not advisable.

Even when a suitable substitute is found, it may be necessary to modify the original formula by using a smaller or larger amount of the substitute and often, to add one or more other ingredients to balance it. Thus, because corn syrup is more viscous and less hygroscopic than glycerin, it may be necessary to reduce its viscosity by the addition of water and increase its hygroscopicity by means of a compatible hygroscopic salt. Introduction of these two additional ingredients may require considerable testing and aging to avoid subsequent undesirable effects.

Because of the uncertainty of the continued availability of any substitute material, it is advisable to experiment with a number of materials on each problem, so as to have a substitute ready for the substitute used. It means additional work, but is a worth while insurance for continuance in business.

Sometimes it may be desirable to change the composition of a formulation radically or entirely because a suitable substitution cannot be made. Thus flavoring extracts depend on the use of pure alcohol as the solvent for the flavoring ingredients. Since there is no good substitute for alcohol (in food products) available, a formulation without alcohol is indicated, e.g.,

\*This section is a condensation of the book, Substitutes, H. Bennett. Chemical Publishing Co., Inc., Brooklyn, N. Y. (1942).

an emulsion of the flavoring ingredient (e.g. lemon oil) made with an edible gum (gum tragacanth) and water. Of course, the finished product does not look like the original lemon extract, but it can replace it in most of its uses.

Price should not be too great a deterrent in selecting a substitute. Sometimes a substitute will so alter a product as to make it more useful, desirable and salable. An example of this is the use of monoglycollin in place of glycerin. Although the former is more than twice as expensive as the latter, its much greater solvency for certain dyes makes it far more economical to use than the cheaper material which it replaces. In electrolytic condenser manufacture mannitol, at about three times the cost of glycerin, is replacing the latter because it gives a much more desirable product.

In getting outside assistance in finding a substitute, it is important to disclose a problem in its entirety. Reputable manufacturers and consultants hold all communications in strict confidence. Therefore give them the complete formulation, method of manufacture, packaging and a sample of the finished product. Also inform them how and where the finished product is to be used. Only with such complete information can an intelligent recommendation be made.

Product	Substitute or Alternative
Accroides, Gum	Rosin
,	Seed-Lac
	"Vinsol"
Acetaldehyde	Aldol
	Formaldehyde
	Furfuraldehyde
	Glyoxal
Acetamide	Ammonium acetate
	Ethanolamine Acetate
	Formamide
	Urea
Acetanilide	Alum
	Pyramidone
	Zine sulphocarbolate
Acetic Acid	Ammonium sulphate with dilute sulphuric acid
	Boric acid
	Citrie acid
	Formic acid
	Glycollic acid
	Lactic acid
	Levulinic acid
	Phosphoric acid
	Propionic acid
	Pyroligneous acid

Product	Substitute or Alternative
Acetic Acid	. Saccharic acid
	Salt
	Sodium diacetate
Albumen	. Agar
	Alum, potash
	Casein
	Emulsifiers
	Protein, fish
	Protein, soybean
	Resin, natural
	Resins, synthetic
	Thickeners
Alcohol	See Ethyl alcohol
Alkalies	
AIRAITES	tiary, quaternary
	Aminoalcohols
	Ammonium hydroxide
	Barium hydroxide Borax
	Calcium hydroxide
	Calcium oxide
	Lithium hydroxide
	Magnesium hydroxide
	Magnesium oxide
	Nephelin
	Potassium carbonate
	Potassium hydroxide
	Potassium silicate
	Sodium carbonate
	Sodium hydroxide
	Sodium metasilicate
	Sodium orthosilicate
	Sodium pyrophosphate
	Sodium silicate
	Trisodium phosphate
Alkyd Resins	"Flexoresins"
	"Piccolyte" resins
	Resins, synthetic
Almond Oil	Apricot kernel oil
	Benzaldehyde
	Cherry kernel oil
	Mineral oil, refined
	Peach kernel oil
	"Persic" oil
	Vegetable oils

Product	Substitute or Alternative
"Alperox"	Hydrogen peroxide Casein
Alpha Frotein	"G"-protein
Alum	Acetanilide
	Alum, potash
	Aluminum chloride
	Aluminum hydrate
Aluminum Hydrate	Alum
	Ammonia alum
	Copperas
	Ferric sulphate Lime
	Potassium alum
	Sodium aluminate
Aluminum Oleate	Calcium oleate
Aluminum Oleace	Lead oleate
	Magnesium oleate
Aluminum Phosphate	Calcium phosphate
Aluminum Powder	Graphite
	Mica
	Pearl essence
	Sericite
	Slate powder
Aluminum Resinate	Calcium resinate
	Lead resinate
	Magnesium resinate
Aluminum Silicate	Alum, potash Talc
A	Alkalies
Ammonium Compounds	Amides
	Amines
	Ammonium thiocyanate
	Cyanamide
	Dicyandiamide
	Urea
Ammonium Chloride	Manganese chloride
	Zinc chloride
Ammonium Hydroxide	See Alkalies
Ammonium Lactate	Ammonium glycollate
	Glycerin
Ammonium Phosphate	Calcium cyanamid Guano
•	Sodium nitrate
	Dodium muacy

Product	Substitute or Alternative
Ammonium Sulphamate	"Abopon"
	Borax with boric acid
	Sodium chlorate
Ammonium Sulphate	Ammonium phosphate
Ammonium Sulphite	Potassium bisulphite with ammonia
Timinomani Sarpinos	Sodium bisulphite with ammonia
Ammonium Thiocyanate	Ammonium compounds
Timinomani Timooy anado	Sodium chlorate
Amyl Acetate	Butylacetate
1111151 11000000	Fusel oil
Amyl Alcohol	Capryl alcohol
	Fusel oil
	Hexyl alcohol
	Octyl alcohol
	Solvents
	Tetrahydrofurfuryl alcohol
Aniline	σ-Aminodiphenyl
	Furfural
	Pyridin
Anise Oil	"Annol"
Annatto	Dyes, aniline
Antimony	Cadmium
<b>,</b>	Calcium
	Selenium
	Tellurium
Antimony Lactate	Tartar emetic
Antimony Oxide	Tin oxide
	Titanium oxide
Apricot Kernel Oil	Almond oil
Beeswax	"B-Z Wax"
	Ceresin with soap
	Coffee wax
	Flax wax
	"Flexo Wax"
	"Isco 662, 663"
	"Norco Wax 36"
	Sugar cane wax
	Wax, synthetic
Belladonna	Stramonium
Bentonite	Alum, potash
	Clay, colloidal
	Emulsifiers
-	Fillers
	Gums, water dispersible
	Thickeners
The state of the s	

Product	Substitute or Alternative
Benzaldehyde	Bitter almond oil
Benzene Sulphonic Acid	Nitrobenzol Phenolsulphonic acid
Benzine	Petroleum ether
Calcium Sulphide	Barium sulphide
Camel's Hair	"Nylon" fleece
Camphor	Benzyl benzoate
	Camphene
	Dibutyl tartrate
	"Dehydranone"
	Diethyl phthalate
	Esparto wax
	Hexachloroethane
	Menthol Nanhthalana
	Naphthalene Phenol
	Plasticizers
	Resorcinol
	"Tetralin"
	Triphenyl phosphate
Camphor Oil	"Japp-O"
	"Terpesol"
	Turpentine
Candelilla Wax	"Norcowax 72"
Cane Sugar	See Sugar
Capric Acid	"Alox" acids
S 111 1 1	Cocoanut oil fatty acids
Capryl Alcohol	See Octyl alcohol, normal Ammonium bicarbonate
Carbon Dioxide	Carbon tetrachloride
	Methyl chloride
	Nitrogen
	Sodium bicarbonate
Carbon Tetrachloride	Carbon dioxide
	Chloroform
	Ether, petroleum
	Ethylene dichloride with sulphur
	dioxide
	Methyl bromide
	Methyl chloride
	Solvents
"C 1 "	Trichlorethylene
"Carbowax"	Glycerin
Cardamom Oil	Polymerized glycol stearate "Card-O-Mar"
Cardamom Uil	Card-U-Mar

Product	Substitute or Alternative
Carnauba Wax	"Acrawax" Candelilla wax
	Cotton wax, green
•	Esparto wax
	Hydrogenated castor oil
	"Norcowax 350"
	Ouricouri wax
	"Rezowax"
	"Santowax M"
	Stearamides, substituted "Stroba Wax"
	Sugar cane wax
Carob Gum	Sodium alginate
Carragheen	Sodium alginate
Casein	Albumen
	Alum, potash
	Alkyd resins
	"Alpha" protein
	Cellulose esters
	Emulsifiers
	Gluten
	Gums, water dispersible "Proflex"
	"Prosein"
	Resins, natural
	Resins, synthetic
	Shellac
	Thickeners
	Zein
Castor Oil	"Dipolymer"
	"Flexoresin L 1"
	Glycol hexaricinoleate
	Grapeseed oil
	Vegetable oils
Cetyl Alcohol	Lanolin alcohols
	Monostearin
	Oleyl alcohol
	Stearyl alcohol
Cherry Kernel Oil	Almond oil
China Clay	Barytes
	Talc
	Whiting
China Wood Oil	See Tung oil
Chinese Blue	See Iron blue

Product	Substitute or Alternative
Chinese Wax	See Insect wax
Chloramin	Hydrogen peroxide
	Sodium chlorite
Chlorine	Bleaching powder
	Bromine
	Catalysts
	Hydrogen peroxide
	Iodine
	Nitric acid
	Sulphur dioxide
Chloroform	Carbon tetrachloride
Chlorophyll	Dyes, aniline
Chloropierin	"Dry-Ice" with 10% ethylene oxide
	"Ethide"
	Furoylchloride
	Insecticides
	Methyl bromide
Chlororubbers	"Halowax"
	Rubbers, synthetic
Cholesterol	Lanolin alcohols
	Phytosterols
Chondrus	Agar
Chrome Alum	Alum, potash
Chrome Orange	Ochre
	Orange mineral
	Sienna
Chromic Acid	Nitric acid
Chromium Acetate	Aluminum sulphate
Chromium Plating	Cadmium plating
	Nickel and silver plating
	Pearl lacquer
Chromium Sulphate	Ferric sulphate
Cinnamon	Cinnamaldehyde and eugenol with
	powdered nut shells
Citral	Lemongrass oil, Florida
Citric Acid	Acetic acid
	Gluconic acid
	Glycollic acid
	Lactic acid
	Levulinic acid
	Malic acid
	Phosphoric acid Propionic acid
	Saccharic acid
	Dacularie acid

302 TH	E CHEMICAL FORMOLINI
Product	Substitute or Alternative
Citric Acid	Sodium acid sulphate
C10110 11014	Sodium bisulphite
	Sodium diacetate
	Tartaric acid
	Sulphuric acid, dilute
	"Tartex"
	Vinegar
Citronella Oil	
	"Javonella"
Clay	
Clay	Whiting
Clay, Colloidal	
Ciay, Conordai	Kaolin
Clove Oil	"Clovel"
0.000 0.11	Eugenol
Cobalt	<del>-</del>
Cobair	Manganese
	Tantalum
Cobalt Chloride	
Cochineal	
Cocoanut Oil	
Cocoando On	Castor oil
	Castor with cottonseed oils
	Cocoanut oil fatty acids
	Cohune oil fatty acids
	Confectioners' oil, "Crystal"
	Carozo oil
	Coyol oil
	Glyceryl myristate with castor of
	Hydrogenated vegetable oils, par-
	tially
	Lard oil
	Macanilla oil
	Mineral oil with lard oil
	Murumuru oil
	Myristic with ricinoleic acid
	Neatsfoot oil
	"Neo-Fat 13"
	Oleic with ricinoleic acid
	Olive oil with mineral oil
	Oxidized paraffin wax with red of
	Palm kernel oil
	Peanut oil, blown
	Polyhydric alcohol, fatty acid es-
	ters, e.g., Diglycol ricinoleate

Product	Substitute or Alternative
Cocoanut Oil	Rosin with linseed oil
	Tucum oil
	Vegetable oils
	Vegetable oils, blown
Cod Liver Oil	Rice bran oil, purified
	Sardine oil
	Shark liver oil
	Sterols, irradiated animal
a 10"	Tuna liver oil
Cod Oil	Degras
	Herring oil, blown
	Menhaden oil, blown
	Pilchard oil
	Sardine oil, blown
G N. 141	Whale oil
Copper Naphthenate	Copper carbonate, basic
	Copper "mahogany" sulphonate
	Copper oleate
	Creosote
Copper Oxide	Manganese dioxide
Garage Gallant and	Mercuric chloride
Copper Sulphate	Aluminum sulphate
Cork	Asbestos fiber with asphalt or resin
	Bark fiber with asphalt or resin
	binder
	Bran fiber with asphalt or resin
	binder
	"Cushiontone"
	Felt, hair or wool, impregnated
	"Fiberglas"
	"Foamglass"
	"Joinrite"
	Linseed meal
	Millboard soft
	Mineral wool
	"Naturazone"
	Oatmeal
	Palmetto wood
	Paper pulp
	Peat moss
Cream of Tartar	Adipic acid
	Ammonium sulphate
	Mucic acid
	Saecharolactic acid

Product	Substitute or Alternative
Creosote	Coal tar
	Copper chromate
	Copper naphthenate
	Copper oleate
	Copper phosphate
	Copper sulphate
	Cresylic acid
	Pentachlorphenol
	Tar oils
	Zinc chloride
Cresol	Coal tar acids
	Creosote
	Furfural
	Phenol
Cresylic Acid	Creosote
	See Cresol
Degras	Cod oil
	Petrolatum
	"Sublan"
Derris	Devil's shoe-string root
	"Thanite"
Dextrin	"Abopon"
	Adhesives
	Glycerin
	Malt extract
	Sodium silicate
	Sodium sulphate
	Sugar Urea
Dextrose	See Sugar
Diacetone	Acetone
Diacetone	Solvents
Diamond, Industrial	Abrasives
Diamond, industrial	Boron
	Boron carbide
	"Corundum"
	Silicon carbide
Diatomaceous Earth	Carbon, activated
	"Dicalite"
Dibutyl Phthalate	Butyl oleate
	Castor oil
	Castor oil blown
	"Dipolymer"
	"Glaurin"
	Glycol hexaricinoleate

sulphide Quercitron bark Saffron Tannin Turmeric Dyes, Vat	${\bf Product}$	Substitute or Alternative
Plasticizers "Theop" Chlorine Hydrogen peroxide Methyl chloride Dicresyl Carbonate Dicresyl Carbonate Dyes, Aniline  Amaranth Annatto Caramel coloring Chlorophyll Cochineal Coffee grounds Cutch Dragon's blood Fustic Hypernic Indigo Logwood Madder Orchil extract Osage orange extract Pigments, mineral, e.g. sienna Precipitates, chemical e.g. antimot sulphide Queretiron bark Saffron Tannin Turmeric  Dyes, Vat  "A.A.P. Naphthols" Dyes, aniline Precipitate, chemical e.g. lead chr mate Ether, Petroleum  Benzol Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane	Dibutyl Phthalate	2, 5 Hexanediol
Dichloramine		Monoglycollin
Dichloramine		
Hydrogen peroxide Dichlorethylene Methyl chloride Dicresyl Carbonate Glycerin Dyes, Aniline Amaranth Annatto Caramel coloring Chlorophyll Cochineal Coffee grounds Cudbear Cutch Dragon's blood Fustic Hypernic Indigo Logwood Madder Orchil extract Osage orange extract Pigments, mineral, e.g. sienna Precipitates, chemical e.g. antimot sulphide Quercitron bark Saffron Tannin Turmeric "A.A.P. Naphthols" Dyes, Vat "A.A.P. Naphthols" Dyes, aniline Precipitate, chemical e.g. lead chr mate Ether, Petroleum Benzol Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane		
Dichlorethylene Dicresyl Carbonate Dicresyl Carbonate Dyes, Aniline  Amaranth Annatto Caramel coloring Chlorophyll Cochineal Coffee grounds Cudbear Cutch Dragon's blood Fustic Hypernic Indigo Logwood Madder Orchil extract Osage orange extract Pigments, mineral, e.g. sienna Precipitates, chemical e.g. antimor sulphide Quercitron bark Saffron Tannin Turmeric  Dyes, Vat  "A.A.P. Naphthols" Dyes, aniline Precipitate, chemical e.g. lead chr mate Ether, Petroleum  Benzol Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane	Dichloramine	
Dicresyl Carbonate Glycerin  Dyes, Aniline Amaranth  Annatto  Caramel coloring  Chlorophyll  Cochineal  Coffee grounds  Cutch  Dragon's blood  Fustic  Hypernic  Indigo  Logwood  Madder  Orchil extract  Osage orange extract  Pigments, mineral, e.g. sienna  Precipitates, chemical e.g. antimot  sulphide  Quercitron bark  Saffron  Tannin  Turmeric  "A.A.P. Naphthols"  Dyes, Vat  "A.A.P. Naphthols"  Dyes, aniline  Precipitate, chemical e.g. lead chr  mate  Ether, Petroleum  Benzol  Carbon tetrachloride  Ether, ethyl  Ethyl chloride  Isopropyl ether  Pentane	*	
Dyes, Aniline  Amaranth Annatto Caramel coloring Chlorophyll Cochineal Coffee grounds Cudbear Cutch Dragon's blood Fustie Hypernic Indigo Logwood Madder Orchil extract Osage orange extract Pigments, mineral, e.g. sienna Precipitates, chemical e.g. antimor sulphide Quercitron bark Saffron Tannin Turmeric  Dyes, Vat  "A.A.P. Naphthols" Dyes, aniline Precipitate, chemical e.g. lead chr mate Ether, Petroleum  Benzol Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane		
Annatto Caramel coloring Chlorophyll Cochineal Coffee grounds Cutch Dragon's blood Fustic Hypernic Indigo Logwood Madder Orchil extract Osage orange extract Pigments, mineral, e.g. sienna Precipitates, chemical e.g. antimor sulphide Quercitron bark Saffron Tannin Turmeric  Dyes, Vat  "A.A.P. Naphthols" Dyes, aniline Precipitate, chemical e.g. lead chr mate Ether, Petroleum  Benzol Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane	•	
Caramel coloring Chlorophyll Cochineal Coffee grounds Cudbear Cutch Dragon's blood Fustic Hypernic Indigo Logwood Madder Orchil extract Osage orange extract Pigments, mineral, e.g. sienna Precipitates, chemical e.g. antimor sulphide Quercitron bark Saffron Tannin Turmeric Dyes, Vat "A.A.P. Naphthols" Dyes, aniline Precipitate, chemical e.g. lead chr mate Ether, Petroleum Benzol Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane	Dyes, Aniline	
Chlorophyll Cochineal Coffee grounds Cudbear Cutch Dragon's blood Fustic Hypernic Indigo Logwood Madder Orchil extract Osage orange extract Pigments, mineral, e.g. sienna Precipitates, chemical e.g. antimor sulphide Quercitron bark Saffron Tannin Turmeric Dyes, Vat "A.P. Naphthols" Dyes, aniline Precipitate, chemical e.g. lead chr mate Ether, Petroleum Benzol Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane		
Cochineal Coffee grounds Cudbear Cutch Dragon's blood Fustic Hypernic Indigo Logwood Madder Orchil extract Osage orange extract Pigments, mineral, e.g. sienna Precipitates, chemical e.g. antimor sulphide Quercitron bark Saffron Tannin Turmeric  'A.A.P. Naphthols' Dyes, vat "A.A.P. Naphthols" Dyes, aniline Precipitate, chemical e.g. lead chr mate Ether, Petroleum  Benzol Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane		
Coffee grounds Cudbear Cutch Dragon's blood Fustic Hypernic Indigo Logwood Madder Orchil extract Osage orange extract Pigments, mineral, e.g. sienna Precipitates, chemical e.g. antimor sulphide Quercitron bark Saffron Tannin Turmeric Turmeric "A.A.P. Naphthols" Dyes, aniline Precipitate, chemical e.g. lead chr mate Ether, Petroleum  Benzol Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane		
Cutch Dragon's blood Fustic Hypernic Indigo Logwood Madder Orchil extract Osage orange extract Pigments, mineral, e.g. sienna Precipitates, chemical e.g. antimor sulphide Quercitron bark Saffron Tannin Turmeric "A.A.P. Naphthols" Dyes, aniline Precipitate, chemical e.g. lead chr mate Ether, Petroleum  Benzol Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane		
Cutch Dragon's blood Fustic Hypernic Indigo Logwood Madder Orchil extract Osage orange extract Pigments, mineral, e.g. sienna Precipitates, chemical e.g. antimor sulphide Quercitron bark Saffron Tannin Turmeric Dyes, Vat "A.A.P. Naphthols" Dyes, aniline Precipitate, chemical e.g. lead chr mate Ether, Petroleum Benzol Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane		
Dragon's blood Fustic Hypernic Indigo Logwood Madder Orchil extract Osage orange extract Pigments, mineral, e.g. sienna Precipitates, chemical e.g. antimor sulphide Quercitron bark Saffron Tannin Turmeric Dyes, Vat "A.A.P. Naphthols" Dyes, aniline Precipitate, chemical e.g. lead chr mate Ether, Petroleum Benzol Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane		
Fustic Hypernic Indigo Logwood Madder Orchil extract Osage orange extract Pigments, mineral, e.g. sienna Precipitates, chemical e.g. antimor sulphide Quercitron bark Saffron Tannin Turmeric Dyes, Vat "A.A.P. Naphthols" Dyes, aniline Precipitate, chemical e.g. lead chr mate Ether, Petroleum Benzol Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane		
Hypernic Indigo Logwood Madder Orchil extract Osage orange extract Pigments, mineral, e.g. sienna Precipitates, chemical e.g. antimor sulphide Quercitron bark Saffron Tannin Turmeric Dyes, Vat		
Indigo Logwood Madder Orchil extract Osage orange extract Pigments, mineral, e.g. sienna Precipitates, chemical e.g. antimor sulphide Quercitron bark Saffron Tannin Turmeric Dyes, Vat "A.A.P. Naphthols" Dyes, aniline Precipitate, chemical e.g. lead chr mate Ether, Petroleum Benzol Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane		
Logwood Madder Orchil extract Osage orange extract Pigments, mineral, e.g. sienna Precipitates, chemical e.g. antimor sulphide Quercitron bark Saffron Tannin Turmeric Dyes, Vat "A.A.P. Naphthols" Dyes, aniline Precipitate, chemical e.g. lead chr mate Ether, Petroleum Benzol Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane		
Madder Orchil extract Osage orange extract Pigments, mineral, e.g. sienna Precipitates, chemical e.g. antimor sulphide Quercitron bark Saffron Tannin Turmeric Dyes, Vat "A.A.P. Naphthols" Dyes, aniline Precipitate, chemical e.g. lead chr mate Ether, Petroleum Benzol Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane	. " ·	
Orchil extract Osage orange extract Pigments, mineral, e.g. sienna Precipitates, chemical e.g. antimor sulphide Quercitron bark Saffron Tannin Turmeric Dyes, Vat. "A.A.P. Naphthols" Dyes, aniline Precipitate, chemical e.g. lead chr mate Ether, Petroleum Benzol Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane		
Osage orange extract Pigments, mineral, e.g. sienna Precipitates, chemical e.g. antimor sulphide Quercitron bark Saffron Tannin Turmeric Dyes, Vat. "A.A.P. Naphthols" Dyes, aniline Precipitate, chemical e.g. lead chr mate Ether, Petroleum Benzol Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane		
Pigments, mineral, e.g. sienna Precipitates, chemical e.g. antimor sulphide Quercitron bark Saffron Tannin Turmeric Dyes, Vat "A.A.P. Naphthols" Dyes, aniline Precipitate, chemical e.g. lead chr mate Ether, Petroleum Benzol Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane		
Precipitates, chemical e.g. antimor sulphide Quercitron bark Saffron Tannin Turmeric Dyes, Vat "A.A.P. Naphthols" Dyes, aniline Precipitate, chemical e.g. lead chr mate Ether, Petroleum Benzol Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane		
Quercitron bark Saffron Tannin Turmeric Dyes, Vat "A.A.P. Naphthols" Dyes, aniline Precipitate, chemical e.g. lead chr mate Ether, Petroleum Benzol Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane		Precipitates, chemical e.g. antimony
Saffron Tannin Turmeric  Dyes, Vat "A.A.P. Naphthols" Dyes, aniline Precipitate, chemical e.g. lead chr mate  Ether, Petroleum Benzol Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane		
Turmeric  "A.A.P. Naphthols"  Dyes, aniline  Precipitate, chemical e.g. lead chr mate  Ether, Petroleum  Benzol  Carbon tetrachloride  Ether, ethyl  Ethyl chloride  Isopropyl ether  Pentane		•
Dyes, Vat "A.A.P. Naphthols" Dyes, aniline Precipitate, chemical e.g. lead chr mate  Ether, Petroleum Benzol Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane		Tannin
Dyes, aniline Precipitate, chemical e.g. lead chr mate  Ether, Petroleum  Benzol Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane		Turmeric
Dyes, aniline Precipitate, chemical e.g. lead chr mate  Ether, Petroleum  Benzol Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane	Dyes, Vat	"A.A.P. Naphthols"
Ether, Petroleum Benzol Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane		Dyes, aniline
Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane		Precipitate, chemical e.g. lead chromate
Carbon tetrachloride Ether, ethyl Ethyl chloride Isopropyl ether Pentane	Ether, Petroleum	Benzol
Ethyl chloride Isopropyl ether Pentane	,	Carbon tetrachloride
Isopropyl ether Pentane		Ether, ethyl
Pentane		Ethyl chloride
		Isopropyl ether
Ethyl Acctato		Pentane
Edityl Acetate Acctone	Ethyl Acetate	Acetone
Isopropyl acetate	*	
Methyl acetate		Methyl acetate

Substitute or Alternative
Methyl alcohol
Pentane
Propylene glycol
Rum
Solubilizers or emulsifiers "Glyect S533"
"Stago CS"
Sulphonated oils
Solvents
Tetrahydrofurfuryl alcohol
Wine
Iodine
Cryolite
Sodium silicofluoride
Acetaldehyde
Aluminum chloride
Aluminum sulphate
Furfural
Glyoxal
Potassium bichromate
Sodium bichromate
Tannin
Citric acid
Lactic acid
Mucic acid
See Sugar
Casein
Emulsifiers
Gelatin
Gums, water dispersible
Latex
Resins, synthetic
Rosin soap
Casein
Ammonium lactate
Apple syrup
"Aquaresin"
Butylene glycol
Calcium chloride
"Carbowax"
Corn syrup Dextrin
Dicresyl carbonate

Product	Substitute or Alternative
Glycerin	Diglycol oleate Ethylammonium phosphate Glycols "Glycopon" "Glucarine B" Glucose Invert sugar Kerosene Lactic acid Magnesium chloride
	Methyl cellulose
	Methyl sodium potassium phosphate
	Mineral oil
	Nonaethylene glycol ricinoleate Polymerized glycol oleate Sorbitol syrup
	Sugar
	Sulphonated castor oil "Yumidol"
Glyceryl Chlorhydrin	Ethylene chlorhydrin
Glyceryl Phthalate	Glyceryl maleate Monoglycollin
Glycol Diacetate	Monoglycollin
Glycollic Acid	Acetic acid
	Citric acid
	Lactic acid
Glycols	Ethyl potassium phosphate
	Glycerin
Classia	Sorbitol Formaldehyde
Glyoxal	Castor oil
Graphite	"Acrawax"
	Bone black with tale
	Iron oxide
	Metals, powdered
	Mica, powdered
	Paraffin wax Red lead
	Silica black
	Tale
Gum Arabic	See Gum Acacia
Gum Benzoin	See Benzoin
Gum Karaya	Gums, water dispersible
Gum, Locust Bean	Gums, water dispersible

Product	Substitute or Alternative
Gum Tragacanth	
	Thickeners
Gums, Water Dispersible	
	Agar
	Algin
	"Algaloid"
	Ammonium alginate
	Carragheen Casein
	Cherry gum
	Dextrin "Diglycol" stearsts
	"Diglycol" stearate Emulsifiers
	"G" protein
	Gum acacia
	Gum karaya
	Gum tragacanth
	Locust bean gum
	Methyl cellulose
	Pectin
	Quince seed
	Sodium alginate
	Sodium borophosphate
	Soap
Gut	Fiber
	Metal wire
	"Nylon"
	Protein
	Resins, synthetic
Gutta Percha	Balata
	Resins, synthetic
	Rubbers, synthetic
"Halowax"	"Arochlor"
	Chlorinated mineral oil
	Chlorinated paraffin wax
	Chlororubbers
	Resins, synthetic
Hydrofluoric Acid	Aluminum chloride, anhydrous
	Ammonium bifluoride
TT 1 0 11	Phosphoric with chromic acid
Hydrofuramide	Hexamethylenetetramine
Hydrogen	Acetylene
III-i- Deseria	Helium
Hydrogen Peroxide	"Alperox"
	Benzoyl peroxide

Product	Substitute or Alternative
Hydrogen Peroxide	Bleaching powder
	Calcium peroxide
	Chloramine Chlorine
	Dichloramine
	Magnesium peroxide
	Oxalic acid
	Oxygen
	Ozone
	Potassium bichromate
	Potassium chlorate
	Potassium chromate
	Potassium perchlorate
	Potassium permanganate
	Selenium dioxide
	Sodium chlorate
	Sodium chlorite
	Sodium hypochlorite
	Sodium hydrosulphite
	Sodium perborate
	Sodium perchlorate
	Sodium peroxide
	Sulphur dioxide
	Zinc hydrosulphite
	Zinc peroxide
Hydroquinone	Maleic acid
	Naphthol, beta
	Pyrogallol
	Resorcinol Selenium
** 1 '' 11 1	Cyclamen aldehyde
Hydroxycitronellal	Dyes, aniline
Hypernic	Gums, water dispersible
Iceland Moss	Thickeners
T 31	Dyes, aniline
Indigo	"Indolene"
Indol Infusorial Earth	See Diatomaceous Earth
Insecticides	Amines, higher fatty
THISECURCIAES	Bordeaux mixture
	Calcium arsenate
	Castor leaf extract
	Chloropierin
* * *	Cryolite
	"Derex"

Product	Substitute or Alternative
Insecticides	"Ethide"
	Hydrocyanic acid
	Ketones, higher fatty
	Lead arsenate
	"Lethane"
	Methyl bromide
	Naphthalene
	Nicotine
	Paradichlorobenzene
	Paris green
	Phenothiazin
	Phthalonitrile
	Pyrethrum
	Rotenone
	Sodium fluoride
· ·	Sodium silicofluoride
	Sulphur
	Tetrahydrofurfuryl lactate
	"Thanite"
	Tobacco dust
Invert Sugar	Glycerin
Iodine	Bromine
	Chlorine
	Fluorine
Irish Moss	Gum, water dispersible
	Thickeners
Lard	Hydrogenated vegetable or fish oils
	Tallow, refined
Lard Oil	Fish oil
	Mineral oil
	Mustard seed oil
	Polyhydric alcohol fatty acid esters,
	e.g. Diglycol oleate
	Rosin oil
	Vegetable oil
Latex	Blood albumen
	"Dispersite"
	"Emulsion 58-8"
	Gelatin
	Glue
	Methyl cellulose
	Resin emulsions
	"Seatex"
	Vinyl copolymer emulsions
Monoacetin	Monoglycollin

Product	Substitute or Alternative
Monoglycollin	"Carbitol"
	Glycol diacetate
Montan Wax	Lignite wax
	"Monten" wax
	"Norcowax 12A"
	Peat wax
	"Rezo Wax"
	"Santowax"
Morpholine	Ammonia
	Ethylenediamine
	Methylamine
Mucic Acid	Adipic acid
	Gluconic acid
	Saccharic acid
Mucin	Agar
"Nipagen"	"Moldex"
	"Parasept"
	Preservatives
Nitre Cake	Hydrochloric acid
Nitric Acid	Chlorine
	Chromic acid
	Hydrochloric acid
	Hydrogen peroxide
Nitrocellulose	Cellulose esters
	Plastics
	Resins, synthetic
Nitrogen	Vinyl copolymers Ammonia, anhydrous
Nitrogen	Carbon dioxide
NT:1	
Nitromannite	Mercury fulminate
Nutgalls	Gall apples
	Oak galls (oak apples) Tannin
DT . T7	
Nux Vomica	Strychnine hydrochloride "Witco Yellow"
Ochre, French	
Octyl Alcohol, Normal	Hexyl alcohol
01: 4:1	Tributyl phosphate
Oleic Acid	Fatty acids "Indusoil"
OL TALLE	Talloil
Oleyl Alcohol	Cetyl alcohol
Olive Oil	Apricot kernel oil
	"Lenolene"
	Corn oil with crushed green olives

Product	Substitute or Alternative
Olive Oil	Diglycol laurate "Glaurin"
	Grapeseed oil
	Lard oil with mineral oil
	Mineral oil with cocoanut oil
	"Nopco C.P."
	"Olev-ol"
	Peach kernel oil
	Peanut oil, destearinated
	Rice oil
	Vegetable oils
Platinum	Iron containing 42-50% nickel
"Pliofilm"	"Cellophane"
	"Ethocel"
	Plastic films
	Parchment paper
Polystyrene	Cellulose acetopropionate
	Glass, tempered
Polyvinyl Alcohol	"Abopon"
	Gums, water dispersible "Hevealac"
	Methyl cellulose
4.1	Synthetic resin emulsion
	Urea-formaldehyde resins
Pyrogallic Acid	Hydroquinone
Pyrogallol	Hydroquinone
1 9 10 5 4 11 11 11 11 11 11 11 11 11 11 11 11 1	Naphthol, beta
	Pyrogallic acid
	Resorcinol
	"S A 326"
Quartz	Garnet
	Silica, fused
	"Vycor"
Quercitron Bark	Dyes, aniline Gums, water dispersible
Quince Seed	Psyllium seed
Quinine	"Atabrin"
Quinine	Pamaquine naphthoate
	"Promin"
	Quinarine hydrochloride
	Salicin
	Sulphadiazin
Rubber	"Foamglas"
	"Jointite"

Rubber Lead Lead oleate with carbon black Polyvinyl butyral resin with 1% Acrawax C Resins, synthetic "Resistoflex PVA" Rubbers, synthetic "Saffex" Shellac "Tygon" Varnished cambric Vinyl acetate and chloride copolymers "Vinylite" Blood albumen "Cement E C-226" Polyvinyl acetate and copolymer emulsions Resins, synthetic, solutions of Rubber, synthetic solutions "Vinylite" solution	Product	Substitute or Alternative
Polyvinyl butyral resin with 1% Acrawax C Resins, synthetic "Resistoffex PVA" Rubbers, synthetic "Saflex" Shellac "Tygon" Varnished cambric Vinyl acetate and chloride copolymers "Vinylite" Rubber Cement Blood albumen "Cement E C-226" Polyvinyl acetate and copolymer emulsions Resins, synthetic, solutions of Rubber, synthetic solutions "Vinylite" solutions "Vinylite	Rubber	Lead
Polyvinyl butyral resin with 1% Acrawax C Resins, synthetic "Resistoffex PVA" Rubbers, synthetic "Saflex" Shellac "Tygon" Varnished cambric Vinyl acetate and chloride copolymers "Vinylite" Rubber Cement Blood albumen "Cement E C-226" Polyvinyl acetate and copolymer emulsions Resins, synthetic, solutions of Rubber, synthetic solutions "Vinylite" solutions "Vinylite		Lead oleate with carbon black
Resins, synthetic "Resistoflex PVA" Rubbers, synthetic "Saflex" Shellac "Tygon" Varnished cambric Vinyl acetate and chloride copolymers "Vinylite" Blood albumen "Cement E C-226" Polyvinyl acetate and copolymer emulsions Resins, synthetic, solutions of Rubber, synthetic solutions "Vinylite" solutions "Ceramics, pressed "Densite" "Electrite" Vulcanized fiber  Saponin "Foamapin" Soap bark "Virifoam" Slaps, fused hard Sardine Oil Cod oil Rice bran oil Vegetable oils "Cam-O-Sass" "S-O-Frass" Sebacic Acid Maleic acid Seed-Lac Accroides, gum Ester gum, alcohol soluble Resins, synthetic Selenium Antimony Hydroquinone Manganese dioxide Sulphur Tellurium		
"Resistoflex PVA" Rubbers, synthetic "Saflex" Shellac "Tygon" Varnished cambric Vinyl acetate and chloride copolymers "Vinylite" Rubber Cement Blood albumen "Cement E C-226" Polyvinyl acetate and copolymer emulsions Resins, synthetic, solutions of Rubber, synthetic solutions "Vinylite" solutions "Vinylite" solutions Gumarone resin Rubber, Chlorinated Cumarone resin Ceramics, pressed "Densite" "Electrite" Vulcanized fiber Saponin "Foamapin" Soap bark "Virifoam" Slapphire Glass, fused hard Sardine Oil Cod oil Rice bran oil Vegetable oils Sassafras Oil "Cam-O-Sass" "S-O-Frass" Sebacic Acid Maleic acid Seed-Lac Accroides, gum Ester gum, alcohol soluble Resins, synthetic Sulphur Tellurium Tellurium		Acrawax C
Rubbers, synthetic "Saflex" Shellac "Tygon" Varnished cambric Vinyl acetate and chloride copolymers "Vinylite" Blood albumen "Cement E C-226" Polyvinyl acetate and copolymer emulsions Resins, synthetic, solutions of Rubber, synthetic solutions "Vinylite" solutions "Vinylite" solutions "Vinylite" solutions "Vinylite" solutions "Under solutions "Vinylite" solutions "Vinylite" solutions "Under solutions "Vinylite" solutions "Vinylite" solutions "Vinylite" solutions "Vinylite" solutions "Vinylite" solutions "Electrite" Vulcanized fiber "Foamapin" Soap bark "Virifoam" Sapphire Glass, fused hard Sardine Oil Cod oil Rice bran oil Vegetable oils "Cam-O-Sass" "S-O-Frass" Sebacic Acid Maleic acid Seed-Lac Accroides, gum Ester gum, alcohol soluble Resins, synthetic Selenium Antimony Hydroquinone Manganese dioxide Sulphur Tellurium		Resins, synthetic
"Saflex" Shellac "Tygon" Varnished cambric Vinyl acetate and chloride copolymers "Vinylite" Blood albumen "Cement E C-226" Polyvinyl acetate and copolymer emulsions Resins, synthetic, solutions of Rubber, synthetic solutions "Vinylite" solutions  Rubber, Chlorinated Cumarone resin Rubber, Hard Ceramics, pressed "Densite" "Electrite" Vulcanized fiber Saponin "Foamapin" Soap bark "Virifoam" Sap bark "Virifoam" Sapohire Glass, fused hard Sardine Oil Cod oil Rice bran oil Vegetable oils Sassafras Oil "Cam-O-Sass" "S-O-Frass" Sebacic Acid Maleic acid Seed-Lac Accroides, gum Ester gum, alcohol soluble Resins, synthetic Selenium Antimony Hydroquinone Manganese dioxide Sulphur Tellurium		"Resistoflex PVA"
Shellac "Tygon" Varnished cambric Vinyl acetate and chloride copolymers "Vinylite" Rubber Cement Blood albumen "Cement E C-226" Polyvinyl acetate and copolymer emulsions Resins, synthetic, solutions of Rubber, synthetic solutions "Vinylite" solutions "Virylite" solutions "Virylite" solutions "Ceramics, pressed "Densite" "Electrite" Vulcanized fiber "Foamapin" Soap bark "Virifoam" Sapphire Glass, fused hard Cod oil Rice bran oil Vegetable oils Sassafras Oil "Cam-O-Sass" "S-O-Frass" Sebacic Acid Maleic acid Seed-Lac Accroides, gum Ester gum, alcohol soluble Resins, synthetic Selenium Antimony Hydroquinone Manganese dioxide Sulphur Tellurium		Rubbers, synthetic
"Tygon" Varnished cambric Vinyl acetate and chloride copolymers "Winylite"  Rubber Cement		"Saflex"
Varnished cambric Vinyl acetate and chloride copolymers "Winylite"  Blood albumen "Cement E C-226" Polyvinyl acetate and copolymer emulsions Resins, synthetic, solutions of Rubber, synthetic solutions "Vinylite" solutions  Rubber, Chlorinated Cumarone resin Cumarone resin Ceramics, pressed "Densite" "Electrite" Vulcanized fiber Saponin "Foamapin" Soap bark "Virifoam" Sapphire Glass, fused hard Sardine Oil Cod oil Rice bran oil Vegetable oils Sassafras Oil "Cam-O-Sass" "S-O-Frass" Sebacic Acid Maleic acid Seed-Lac Accroides, gum Ester gum, alcohol soluble Resins, synthetic Selenium Antimony Hydroquinone Manganese dioxide Sulphur Tellurium		Shellac
Vinyl acetate and chloride copolymers "Vinylite"  Rubber Cement Blood albumen "Cement E C-226" Polyvinyl acetate and copolymer emulsions Resins, synthetic, solutions of Rubber, synthetic solutions "Vinylite" solutions "Vinylite" solutions Cumarone resin Ceramics, pressed "Densite" "Electrite" Vulcanized fiber "Foamapin" Soap bark "Virifoam" Sapphire Glass, fused hard Sardine Oil Cod oil Rice bran oil Vegetable oils Sassafras Oil "Cam-O-Sass" "S-O-Frass" Sebacic Acid Maleic acid Seed-Lac Accroides, gum Ester gum, alcohol soluble Resins, synthetic Antimony Hydroquinone Manganese dioxide Sulphur Tellurium		"Tygon"
Rubber Cement Blood albumen  "Cement E C-226" Polyvinyl acetate and copolymer emulsions Resins, synthetic, solutions of Rubber, synthetic solutions "Vinylite" solutions  "Unylite" solutions  "Unylite" solutions  "Unylite" solutions  "Unylite" solutions  "Unersite" "Electrite" "Ulcanized fiber "Foamapin" Soap bark "Virifoam" Soap bark "Virifoam" Sapphire Glass, fused hard Sardine Oil Cod oil Rice bran oil Vegetable oils Sassafras Oil "Cam-O-Sass" "S-O-Frass" Sebacic Acid Maleic acid Seed-Lac Accroides, gum Ester gum, alcohol soluble Resins, synthetic Antimony Hydroquinone Manganese dioxide Sulphur Tellurium		Varnished cambric
Rubber Cement Blood albumen "Cement E C-226" Polyvinyl acetate and copolymer emulsions Resins, synthetic, solutions of Rubber, synthetic solutions "Vinylite" solutions "Vinylite" solutions Cumarone resin Rubber, Hard Ceramics, pressed "Densite" "Electrite" Vulcanized fiber Saponin "Foamapin" Soap bark "Virifoam" Sapphire Glass, fused hard Sardine Oil Cod oil Rice bran oil Vegetable oils Sassafras Oil "Cam-O-Sass" "S-O-Frass" Sebacic Acid Maleic acid Seed-Lac Accroides, gum Ester gum, alcohol soluble Resins, synthetic Antimony Hydroquinone Manganese dioxide Sulphur Tellurium		•
Rubber Cement Blood albumen "Cement E C-226" Polyvinyl acetate and copolymer emulsions Resins, synthetic, solutions of Rubber, synthetic solutions "Vinylite" solutions "Vinylite" solutions Cumarone resin Rubber, Hard Ceramics, pressed "Densite" "Electrite" Vulcanized fiber Saponin "Foamapin" Soap bark "Virifoam" Saphire Glass, fused hard Sardine Oil Cod oil Rice bran oil Vegetable oils Sassafras Oil "Cam-O-Sass" "S-O-Frass" Sebacic Acid Maleic acid Seed-Lac Accroides, gum Ester gum, alcohol soluble Resins, synthetic Antimony Hydroquinone Manganese dioxide Sulphur Tellurium		
"Cement E C-226" Polyvinyl acetate and copolymer emulsions Resins, synthetic, solutions of Rubber, synthetic solutions "Vinylite" solutions "Vinylite" solutions Cumarone resin Cumarone resin Ceramics, pressed "Densite" "Electrite" Vulcanized fiber Saponin "Foamapin" Soap bark "Virifoam" Sapphire Glass, fused hard Sardine Oil Cod oil Rice bran oil Vegetable oils Sassafras Oil "Cam-O-Sass" "S-O-Frass" Sebacic Acid Maleic acid Seed-Lac Accroides, gum Ester gum, alcohol soluble Resins, synthetic Antimony Hydroquinone Manganese dioxide Sulphur Tellurium	Duhhan Coment	•
Polyvinyl acetate and copolymer emulsions Resins, synthetic, solutions of Rubber, synthetic solutions "Vinylite" solutions "Vinylite" solutions "Vinylite" solutions  Cumarone resin Cumarone resin Ceramics, pressed "Densite" "Electrite" Vulcanized fiber "Foamapin" Soap bark "Virifoam" Slapphire Glass, fused hard Sardine Oil Cod oil Rice bran oil Vegetable oils Sassafras Oil "Cam-O-Sass" "S-O-Frass" Sebacic Acid Maleic acid Seed-Lac Accroides, gum Ester gum, alcohol soluble Resins, synthetic Antimony Hydroquinone Manganese dioxide Sulphur Tellurium	Rubber Cement	
emulsions Resins, synthetic, solutions of Rubber, synthetic solutions "Vinylite" solutions "Vinylite" solutions  Cumarone resin Rubber, Hard Ceramics, pressed "Densite" "Electrite" Vulcanized fiber "Foamapin" Soap bark "Virifoam" Sapphire Glass, fused hard Sardine Oil Cod oil Rice bran oil Vegetable oils Sassafras Oil "Cam-O-Sass" "S-O-Frass" Sebacic Acid Maleic acid Seed-Lac Accroides, gum Ester gum, alcohol soluble Resins, synthetic Antimony Hydroquinone Manganese dioxide Sulphur Tellurium		
Resins, synthetic, solutions of Rubber, synthetic solutions "Vinylite" solutions  Rubber, Chlorinated Cumarone resin  Rubber, Hard Ceramics, pressed "Densite" "Electrite" Vulcanized fiber "Foamapin" Soap bark "Virifoam" Sapphire Glass, fused hard Sardine Oil Cod oil Rice bran oil Vegetable oils  Sassafras Oil "Cam-O-Sass" "S-O-Frass" Sebacic Acid Maleic acid Seed-Lac Accroides, gum Ester gum, alcohol soluble Resins, synthetic Selenium Antimony Hydroquinone Manganese dioxide Sulphur Tellurium		
Rubber, synthetic solutions  "Vinylite" solutions  Cumarone resin  Cumarone resin  Ceramics, pressed "Densite" "Electrite" Vulcanized fiber  Saponin "Foamapin" Soap bark "Virifoam"  Sapphire Glass, fused hard Sardine Oil Cod oil Rice bran oil Vegetable oils  Sassafras Oil "Cam-O-Sass" "S-O-Frass"  Sebacic Acid Maleic acid Seed-Lac Accroides, gum Ester gum, alcohol soluble Resins, synthetic  Selenium Antimony Hydroquinone Manganese dioxide Sulphur Tellurium		
Rubber, Chlorinated Cumarone resin Rubber, Hard Ceramics, pressed "Densite" "Electrite" Vulcanized fiber "Foamapin" Soap bark "Virifoam" Sardine Oil Cod oil Rice bran oil Vegetable oils Sassafras Oil "Cam-O-Sass" "S-O-Frass" Sebacic Acid Maleic acid Seed-Lac Accroides, gum Ester gum, alcohol soluble Resins, synthetic Selenium Antimony Hydroquinone Manganese dioxide Sulphur Tellurium		
Rubber, Chlorinated Rubber, Hard Ceramics, pressed "Densite" "Electrite" Vulcanized fiber Saponin "Foamapin" Soap bark "Virifoam" Sapphire Glass, fused hard Sardine Oil Cod oil Rice bran oil Vegetable oils Sassafras Oil "Cam-O-Sass" "S-O-Frass" Sebacic Acid Maleic acid Seed-Lac Accroides, gum Ester gum, alcohol soluble Resins, synthetic Selenium Antimony Hydroquinone Manganese dioxide Sulphur Tellurium		"Vinylite" solutions
Rubber, Hard  Ceramics, pressed  "Densite"  "Electrite"  Vulcanized fiber  "Foamapin"  Soap bark  "Virifoam"  Sapphire  Glass, fused hard  Cod oil  Rice bran oil  Vegetable oils  "Cam-O-Sass"  "S-O-Frass"  Sebacic Acid  Maleic acid  Seed-Lac  Accroides, gum  Ester gum, alcohol soluble  Resins, synthetic  Selenium  Antimony  Hydroquinone  Manganese dioxide  Sulphur  Tellurium	Public Chlorinated	
"Densite" "Electrite" Vulcanized fiber "Foamapin" Soap bark "Virifoam" Sapphire Glass, fused hard Sardine Oil Cod oil Rice bran oil Vegetable oils Sassafras Oil "Cam-O-Sass" "S-O-Frass" Sebacic Acid Maleic acid Seed-Lac Accroides, gum Ester gum, alcohol soluble Resins, synthetic Selenium Antimony Hydroquinone Manganese dioxide Sulphur Tellurium		
Saponin "Electrite" Vulcanized fiber "Foamapin" Soap bark "Virifoam" Sapphire Glass, fused hard Sardine Oil Cod oil Rice bran oil Vegetable oils Sassafras Oil "Cam-O-Sass" "S-O-Frass" Sebacic Acid Maleic acid Seed-Lac Accroides, gum Ester gum, alcohol soluble Resins, synthetic Selenium Antimony Hydroquinone Manganese dioxide Sulphur Tellurium	itubbei, ilaid	"Densite"
Saponin "Foamapin" Soap bark "Virifoam" Sapphire Glass, fused hard Sardine Oil Cod oil Rice bran oil Vegetable oils Sassafras Oil "Cam-O-Sass" "S-O-Frass" Sebacic Acid Maleic acid Seed-Lac Accroides, gum Ester gum, alcohol soluble Resins, synthetic Selenium Antimony Hydroquinone Manganese dioxide Sulphur Tellurium		
Saponin "Foamapin" Soap bark "Virifoam" Sapphire Glass, fused hard Sardine Oil Cod oil Rice bran oil Vegetable oils Sassafras Oil "Cam-O-Sass" "S-O-Frass" Sebacic Acid Maleic acid Seed-Lac Accroides, gum Ester gum, alcohol soluble Resins, synthetic Selenium Antimony Hydroquinone Manganese dioxide Sulphur Tellurium		
Soap bark "Virifoam"  Sapphire Glass, fused hard  Sardine Oil Cod oil Rice bran oil Vegetable oils  Sassafras Oil "Cam-O-Sass" "S-O-Frass"  Sebacic Acid Maleic acid Seed-Lac Accroides, gum Ester gum, alcohol soluble Resins, synthetic  Selenium Antimony Hydroquinone Manganese dioxide Sulphur Tellurium	Sanonin	
Sapphire Glass, fused hard Sardine Oil Cod oil Rice bran oil Vegetable oils Sassafras Oil "Cam-O-Sass" "S-O-Frass" Sebacic Acid Maleic acid Seed-Lac Accroides, gum Ester gum, alcohol soluble Resins, synthetic Selenium Antimony Hydroquinone Manganese dioxide Sulphur Tellurium	Saponini	
Sapphire Glass, fused hard  Sardine Oil Cod oil  Rice bran oil  Vegetable oils  Sassafras Oil "Cam-O-Sass"  "S-O-Frass"  Sebacic Acid Maleic acid  Seed-Lac Accroides, gum  Ester gum, alcohol soluble  Resins, synthetic  Selenium Antimony  Hydroquinone  Manganese dioxide  Sulphur  Tellurium		
Sardine Oil Cod oil Rice bran oil Vegetable oils Sassafras Oil "Cam-O-Sass" "S-O-Frass" Sebacic Acid Maleic acid Seed-Lac Accroides, gum Ester gum, alcohol soluble Resins, synthetic Selenium Antimony Hydroquinone Manganese dioxide Sulphur Tellurium	Sapphire	Glass, fused hard
Rice bran oil Vegetable oils  Sassafras Oil  "Cam-O-Sass"  "S-O-Frass"  Sebacic Acid  Maleic acid  Seed-Lac  Accroides, gum  Ester gum, alcohol soluble  Resins, synthetic  Antimony  Hydroquinone  Manganese dioxide  Sulphur  Tellurium		
Sassafras Oil  "Cam-O-Sass"  "S-O-Frass"  Sebacic Acid  Maleic acid  Accroides, gum  Ester gum, alcohol soluble  Resins, synthetic  Antimony  Hydroquinone  Manganese dioxide  Sulphur  Tellurium		Rice bran oil
Sassafras Oil  "Cam-O-Sass"  "S-O-Frass"  Sebacic Acid  Maleic acid  Accroides, gum  Ester gum, alcohol soluble  Resins, synthetic  Antimony  Hydroquinone  Manganese dioxide  Sulphur  Tellurium		
Sebacic Acid Seed-Lac Maleic acid Accroides, gum Ester gum, alcohol soluble Resins, synthetic Antimony Hydroquinone Manganese dioxide Sulphur Tellurium	Sassafras Oil	
Seed-Lac Accroides, gum Ester gum, alcohol soluble Resins, synthetic  Selenium Antimony Hydroquinone Manganese dioxide Sulphur Tellurium		"S-O-Frass"
Seed-Lac Accroides, gum Ester gum, alcohol soluble Resins, synthetic  Selenium Antimony Hydroquinone Manganese dioxide Sulphur Tellurium	Sebacic Acid	Maleic acid
Ester gum, alcohol soluble Resins, synthetic Antimony Hydroquinone Manganese dioxide Sulphur Tellurium		
Resins, synthetic Antimony Hydroquinone Manganese dioxide Sulphur Tellurium		
Selenium Antimony Hydroquinone Manganese dioxide Sulphur Tellurium		
Manganese dioxide Sulphur Tellurium	Selenium	and the second s
Manganese dioxide Sulphur Tellurium		Hydroquinone
Tellurium		
		Sulphur
Selenium Dioxide Hydrogen peroxide		Tellurium
	Selenium Dioxide	Hydrogen peroxide

Product	Substitute or Alternative
Sesame Oil	Diglycol dilaurate
	Peanut oil
	Sunflower seed oil
Shellac	Alkyd resins
	"Bullzite"
	Batavia gum
	Casein
	Copal, alcohol soluble
	"Elastolac"
	Ester gum with plasticizer
	Gelatin
	Glass with "Vinylite" coating
	Glyceryl phthalate Gum accroides
	Gum kauri
	Polyvinyl chloride
	"Protoflax"
• *	Resins, synthetic
Silica Gel	Agar
	Aluminum hydroxide
	Calcium chloride
	Carbon, activated
	Sodium alumino-silicate
Sodium Alginate	Agar
	Emulsifiers
	"G" protein
	Gelatin
	Gums, water dispersible Thickeners
Sadium Allerd Sulphata	"Wetanol"
Sodium Alkyl Sulphate	Alum, potash
Sodium Aidinnate	Aluminum hydrate
	Copperas with slaked lime
Sodium Antimony Fluoride	Tartar emetic
Sodium Benzoate	Preservatives
Sodium Bichromate	Aluminum sulphate
	Formaldehyde
	Hydrogen peroxide
	Tannin
Sodium Bisulphite	Acetic acid
	Catalysts
	Potassium metabisulphite
	Sodium hyposulphite
Suet	Tallow, edible

$\mathbf{Product}$	Substitute or Alternative
Sugar	Apple juice, concentrated Calcium chloride
	Dextrin
	"Diglycol" stearate with water and
	saccharin
	Glycerin
	Glycols
	Glucose
	Gum, water dispersible
	Honey
	Invert sugar
	Lactose
	Magnesium chloride
	Malted barley
	Malt syrup
	Molasses
	"Nulomoline"
	Saccharin
	Sorghum
	"Sweetose"
C Colore Downt	Urea G. Garagelanian
Sugar Coloring, Burnt	See Caramel coloring
Sulphated Fatty Alcohol	Emulsifiers
Calabanatad Conton Oil	Wetting agents ("Wetanol")
Sulphonated Castor Oil	Emulsifiers Glycerin
	Naphthenic soaps
	Polyglycol fatty acid esters with
	or without wetting agents, e.g.
	nonaethylene glycol oleate
	Sulphonaphthenic soaps
	Sulphonated olive oil
	Sulphonated tall oil
	Sulphonated vegetable oil
Sulphonated Cocoanut Oil	Sulphonated castor oil
Sulphonated Olive Oil	Diglycol monoricinoleate
	Diglycol oleate
	Emulsifiers
	Glyceryl mono-oleate
	Sulphonated castor oil
Sulphonated Red Oil	Sulphonated castor oil
Sulphonated Tallow	Sulphonated castor oil
Sulphur Dioxide	Chlorine
	Hydrogen peroxide
	Methyl chloride

Product	Substitute or Alternative
Talc	Soapstone
	"Stroba" wax
	Wax, synthetic
	Zinc, stearate
Tallow	Fatty acids
	Garbage grease
	Glyceryl oleo-stearate
	Hydrogenated vegetable oil
	Lard
	Lubricating grease
	Petrolatum
	Soap
	Stearin
	Vegetable oils
M-11 0:1	Whale oil with stearin
Tallow Oil	Menhaden oil
Tannic Acid	Alum
	Ammonium bichromate
	Dyewoods
	Formaldehyde Potassium bichromate
	Sodium bichromate
4 8	"Syntans"
Tannin	Dyes, aniline
	Formaldehyde
	Lignin sulphonates
	"Maratan"
Tartaric Acid	Acetic acid
	Citric acid
	Saccharolactic acid
	Sodium acid sulphate
	Sulphuric acid
Tellurium	Antimony
	Sulphur
Tetrachlorethylene	Trichlorethylene
Tetrahydrofurfuryl Alcohol	Ethyl alcohol
	Trichlorethylene
"Tetralin"	Turpentine
Thickeners	Agar
	Albumen
	Ammonium caseinate
	Ammonium stearate
	Arrowroot
	Bentonite
Contraction of the Contract of	Blood, dried

Product	Substitute or Alternative
Thickeners	Casein
	Clay
	"G" protein
Titanium Dioxide	Glue "Celite No. 340"
Trantum Dioxide	Tin oxide
Titanium Tetrachloride	Silicon tetrachloride
Toluol	"Enn Jay" solvents
	Hydrogenated petroleum fractions "Nevsol"
	"Notol 1"
	Solvent
	"Solvesso 1"
	Tollac solvent
Tonka Beans	Coumarin
	"Tonka-Mel"
Triacetin	Butyl "Carbitol"
	"Carbitol"
	Plasticizers
Trichloracetic Acid	Triglycollin Salicylic acid
Trichlorethylene	"Dresinate"
Titomore only tone	Mineral spirits
	Naphtha, petroleum (340–410° F.)
	Soap with solvent
	Solvents
	Tetrahydrofurfuryl alcohol
Tricresyl Phosphate	Diglycol oleate
	"Glaurin"
m: 11 1 1	Sperm oil
Triethanolamine	Alkalies
	Alkyl amines e.g. amylamine Amino alcohols e.g. aminomethyl
	propanol
	Emulsifiers
	Glycerin
	"Glyco S489"
	"Trigamine"
Tripoli	Diatomaceous earth
Trisodium Phosphate	Alkalies
Tritolyl Phosphate	See Tricresyl phosphate
Tung Oil	Castor oil, dehydrated
	"Kellsey" "Kellin"
* **	Linseed oil, polymerized
	Linseed on, polymerized

Product	Substitute or Alternative
Tung Oil	Synthetic resin solutions Vegetable oil
Zein	Casein "G" protein
Zinc Oleate	Calcium oleate Lead oleate
	Magnesium oleate
Zine Oxide	Barium sulphate "Bolted King White"
	Titanium dioxide with talc or kaolin Whiting
Zinc Perborate	Sodium perborate
Zinc Peroxide	Hydrogen peroxide
	Sodium peroxide Zinc perborate
Zinc Stearate	=
21110 20041400	*
	Graphite
	Magnesium stearate
	Tale
Zinc Sulphate	Alum, potash
Zinc Stearate	Aluminum stearate Barium sulphate, purified Graphite Magnesium stearate Stearic acid Talc

### TABLES

Weights and Measures Troy Weight

24 grains = 1 pwt. 20 pwts. = 1 ounce12 ounces = 1 pound

Apothecaries' Weight

20 grains = 1 scruple 3 scruples = 1 dram 8 drams = 1 ounce 12 ounces = 1 pound

The ounce and pound are the same as in Troy Weight.

Avoirdupois Weight  $27^{11}/_{32}$  grains = 1 dram 16 drams = 1 ounce 16 ounces = 1 pound 2000 lbs. = 1 short ton 2240 lbs. = 1 long ton

Dry Measure
2 pints = 1 quart
8 quarts = 1 peck
4 pecks = 1 bushel
36 bushels = 1 chaldron

Liquid Measure
4 gills = 1 pint
2 pints = 1 quart
4 quarts = 1 gallon
31½ gals. = 1 barrel
2 barrels = 1 hogshead
1 teaspoonful = ½ oz.
1 tablespoonful = ½ oz.
16 fluid oz. = 1 pint

Circular Measure
60 seconds = 1 minute
60 minutes = 1 degree
360 degrees = 1 circle

Long Measure 12 inches = 1 foot 3 feet = 1 yard  $5\frac{1}{2}$  yards = 1 rod 5280 feet = 1 stat. mile 320 rods = 1 stat. mile Square Measure
144 sq. in. = 1 sq. ft.
9 sq. ft. = 1 sq. yard
30'4 sq. yds. = 1 sq. rod
43,560 sq. ft. = 1 acre
40 sq. rods = 1 rood
4 roods = 1 acre
640 acres = 1 sq. mile

Metric Equivalents Length 1 inch = 2.54 centimeters 1 foot = 0.305 meter 1 yard = 0.914 meter 1 mile = 1.609 kilometers 1 centimeter = 0.394 in. 1 meter = 3.281 ft. 1 meter = 1.094 yd. 1 kilometer = 0.621 mile

Capacity

1 U. S. fluid oz. = 29.573 milliliters

1 U. S. liquid qt. = 0.946 liter

1 U. S. dry qt. = 1.101 liters

1 U. S. gallon = 3.785 liters

1 U. S. bushel = 0.3524 hectoliter

1 U. S. bushel = 0.3524 hectoliter

1 U. S. bushel = 0.3524 hectoliter

1 U. S. bushel = 0.364 U. S. fluid ounce

1 liter = 1.057 U. S. liquid qt.

1 liter = 0.908 U. S. dry qt.

1 liter = 0.264 U. S. gallon

1 hectoliter = 2.838 U. S. bu.

1 Cu. centimeter = .061 cu. in.

1 liter = 1000 milliliters or 100 cu. c.

Weight 1 grain = 0.065 gram 1 apoth. scruple = 1.296 grams 1 av. oz. = 28.350 grams 1 troy oz. = 31.103 grams 1 troy lb. = 0.454 kilogram 1 troy lb. = 0.373 kilogram 1 gram = 15.432 grains 1 gram = 0.772 apoth. scruple 1 gram = 0.035 av. oz. 1 gram = 0.035 troy oz. 1 kilogram = 2.205 av. lbs. 1 kilogram = 2.679 troy lbs.

A	Blackberries	9994
Approximate pH Values		3.2-3.6
The following tables give approxi-	Bread, white	5.0 - 6.0
mate pH values for a number of sub-	Butter	6.1 - 6.4
stances such as acids, bases, foods,	Cabbage	5.2 - 5.4
biological fluids, etc. All values are	Carrots	4.9 - 5.3
rounded off to the nearest tenth and	Cheese	4.8 - 6.4
are based on measurements made at	Cherries	3.2-4.0
25° C.	Cider	2.9-3.3
pH Values of Acids	Corn	6.0 - 6.5
Hydrochloric, N 0.1	Crackers	6.5 - 8.5
Hydrochloric, 0.1N 1.1	Dates	6.2 - 6.4
Hydrochloric, 0.01N 2.0	Eggs, fresh white	7.6 - 8.0
Carladania M	Flour, wheat	5.5 - 6.5
Sulphuric, N 0.3	Gooseberries	2.8-3.0
Sulphuric, 0.1N 1.2	Grapefruit	3.0-3.3
Sulphuric, 0.1N       1.2         Sulphuric, 0.01N       2.1		
Orthophosphoric, 0.1N 1.5	Grapes	3.5 - 4.5
Sulphurous, 0.1N 1.5	Hominy (rye)	6.8 - 8.0
Oxalic, 0.1N 1.6	Jams, fruit	3.5 - 4.0
Tartaric, 0.1N	Jellies, fruit	2.8 - 3.4
Malia 0 1 NT	Lemons	2.2 - 2.4
Malic, 0.1N	Limes	1.8 - 2.0
Citric, 0.1N 2.2	Maple Syrup	6.5-7.0
Formic, 0.1N 2.3	wapie Syrup	
Lactic, 0.1N	Milk, cows	6.3-6.6
Acetic, N 2.4	Olives	3.6–3.8
Acetic, 0.1N 2.9	Oranges	3.0 - 4.0
Acetic, 0.1N 2.9 Acetic, 0.01N 3.4	Oysters	6.1 - 6.6
Benzoic, 0.1N 3.1	Peaches	3.4 - 3.6
Alama O 1 NT 9 0	Pears	3.6 - 4.0
Alum, 0.1N 3.2	Peas	5.8-6.4
Carbonic (saturated) 3.8	Dialiton dill	3.2-3.6
Hydrogen Sulphide, 0.1N 4.1	Pickles, dill	
Arsenious (saturated) 5.0	Pickles, sour	3.0-3.4
Hydrocyanic, 0.1N 5.1	Pimento	4.6 - 5.2
Boric, 0.1N 5.2	Plums	2.8 - 3.0
	Potatoes	5.6 - 6.0
pH Values of Bases	Pumpkin	4.8 - 5.2
Sodium Hydroxide, N 14.0	Raspberries	3.2 - 3.6
Sodium Hydroxide, 0.1N 13.0	Rhubarb	3.1 - 3.2
Sodium Hydroxide, 0.01N 12.0	Salmon	6.1-6.3
Potassium Hydroxide, N 14.0	Sauerkraut	3.4-3.6
Potassium Hydroxide, 0.1N 13.0	Chrisen	
Potassium Hydroxide, 0.01N 12.0	Shrimp	6.8-7.0
	Soft Drinks	2.0 - 4.0
Lime (saturated)	Spinach	5.1 - 5.7
Sodium Metasilicate, 0.1N 12.6	Squash	5.0 - 5.4
Trisodium Phosphate, 0.1N 12.0	Strawberries	3.0 - 3.5
Sodium Carbonate, 0.1N 11.6	Sweet Potatoes	5.3 - 5.6
Ammonia, N 11.6	Tomatoes	4.0-4.4
Ammonia, 0.1N	Tuna	5.9-6.1
Ammonia, 0.01N 10.6		
Potassium Cyanide, 0.1N 11.0	Turnips	5.2-5.6
	Vinegar	2.4-3.4
Magnesia (saturated) 10.5	Water, drinking	6.5 - 8.0
Sodium Sesquicarbonate, 0.1N . 10.1	Wines	2.8-3.8
Ferrous Hydroxide (saturated) 9.5		
Calcium Carbonate (saturated) 9.4	pH Values of Biologic Mate	rials
Borax, 0.1N 9.2		
Sodium Bicarbonate, 0.1N 8.4	Blood, plasma, human	7.3-7.5
pH Values of Foods	Spinal Fluid, human	7.3 - 7.5
-	Blood, whole, dog	6.9 - 7.2
Apples 2.9–3.3	Saliva, human	6.5 - 7.5
Apricots 3.6-4.0	Gastric Contents, human	1.0-3.0
Asparagus 5.4-5.8	Duodenal Contents, human .	4.8-8.2
Bananas 4.5–4.7	Feces, human	4.6-8.4
Beans 5.0–6.0		
	Urine, human	4.8-8.4
Beers 4.0-5.0	Milk, human	6.6-7.6
Beets 4.9–5.5	Bile, human	6.8 - 7.0

A Institution from the manufacture of the second state of the second sec

# Interconversion Tables and Chart for Units of Volume and Weight, and Energy

ม่มหม่นในสมในสมในสมในสมในสมในสมในสมในสมในสมในส	
. 15. 15. 15. 15. 15. 15. 15. 15. Tadionaleus de contracte de la contracte de	MULTIPLY BY
reterational treatment and the same of the	
c Juntanhantalantantantanhantan	

TO CONVERT				t			WIC	MULTIPLY BY	, T	Ī	Ī				1
Cu.in. Cu.ft. Co.76. 51.0t.	Ca. R. Ca. Yd.	Co. 76. 51.0c.	7. Z		£2	Peur	-1	e sta	Oz. Trey	Oz. Trey Oz. Av. Lb. Trey	Lb. Yeoy	15.44.	66. or 6.	Lit. of Kir.	
1,00000 0,5787 0,214 55411 034634 017314 004324 252.891 526857 578031 043904 036121 16.3671 006387 04190	.0,5787 .0,2143 .554112	.0,2143 .554112	.554112	12	.034632	.017310	.004329	252.891	.526857	.578037	.04390	.036127	16.3871	.016387	.041639
1728.00 1.00000 .037037 957.509 59.8442 29.9221 7.48052 436996 910.408 998.848 75.8674 62.4280 28316.9 28.316 .028317	1.00000 .037037 957.505	.037037 957.505	957.505		59.8442	29.9221	7.48052	436996	910.408	998.848	75.8674	62.4280	28316.9	28.3169	.028317
46656.0 27.0000 1.00000 22822.6 1615.79 807.896 201.974 117990 1.24881.0 26968.9 2048.42 1685.56 764556 764.556 764555	27.0000 1.00000 25852.6	1.00000 25852.6	25852.6	-	1615.79	807.896	201.974	117990,	24581.0	26968.9	2048.42	1685.56	764556	764.556	.764556
1.80469 001044 0.43868 1.00000 062500 031250 001813 456.390 950813 1.04318 079234 065199 29.5736 029573 0.02957	. 001044 .0,3868 1.00000	.043868 1.00000	1.00000	•	062500	.031250	.007813	456.390	.950813	1.04318	.079234	.065199	29.5736	.029573	.0,2957
28.8750 016710 0.6189 16.0000 1.00000 .500000 1.126000 135000 135000 136.6908 1.26375 1.06318 473.177 473177 0.4732	1 0000.01 6818,0. 017910.	.0 4189 16.0000 1	16.0000 1	-	00000	.500000	.125000	7302.23	15.2130	16.6908	1.26775	1.04318	473.177	.473177	.0,4732
57,7500 033420 001238 22,0000 2,00000 1,00000 250000 1460,48 30,4260 33,3816 2,53550 2,08635 946,354 346354	.033420 .001238 32.0000 2	.001238 32.0000 2	32.0000 2	2	00000	1.00000	.250000	1460.45	30.4260	33.3816	2.53550	2.08635	946.354	.946354	.019463
231.000 , 133.681 , 004951   128.000   8.00000   4.00000   1.00000   58417.9   121.704   133.527   10.1420   8.34541   3185.42   3.78542   .003785	.133681 .004951 128.000 8	.004951 128.000 8	128.000 8	00	00000	4.00000	1.00000	58417.9	121.704	133.527	10.1420	8,34541	3785.42	3.78542	.003785
0.03954 .0.2288 .0.48475 .002191 .0.4369 .0.46850 .0.4712 1.00000 .002083 .004786 .0.4178 .0.6479 .0.6479 .0.6479	. 0,2288 .0,8475 .002191 .0	.0,8475 .002191 .0	. 002191	۱9	1369	.0,6850	.0,1712	1.00000	.002083	.002286	.0 1736	,0 i1428	.064799	.0,6479	.0 16479
1.89805 0.01098 0.4068 1.05173 0.05733 0.03260 0.00001 0.000 1.0000 0.0914 083333 0.0571 31.1035 0.031104	0. 51173 . 0 4068 1.05173 . 0	.0,4068 1,05173 .0	0. 67170.1	6	65733	.032867	.008217	480.000	1.00000	1.09714	.083333	.068571	31.1035	.031104	.0,3110
1,72999 ,001001 ,0,3708 ,958608 ,059913 ,029957 ,007489 437,500 ,911457 1.00004 ,075956 ,062500 28,3495 ,028350 ,0,2835	.0. 809826. 8012.0. 100100.	.0. 809886. 8028.0.	.958608 .0.	é	59913	.029957	.007489	437,500	.911457	1.00000	.075955	.062500	28.3495	.028350	.0,2835
22.7766 013181 0 4882 12.6208 .788800 .394400 .998600 5760.00 12.0000 13.1657 1.00000 .822857 373.242 .373242	.013181 .0,4882 12.6208 .78	.0,4882 12.6208 .78	12.6208 .78	18	8800	.394400	009860	5760.00	12.0000	13.1657	1.00000	.822857	373.242	.373242	.0 ,3732
27.6799 016018 0.5933 15.3378 958611 479306 119826 7000.0d 14.5833 16.0000 1.21528 1.00000 453.593 453593 0.45359	36. 8755.33 15.3378 .95	26, 8755, 15, 3378, .95	15.3378 .95	.95	1198	.479306	.119826	7000.00	14,5833	16.0000	1.21528	1.00000	453.593	.453593	.0.4536
.061024 0,3531 0,1308 033814 002113 001057 0,12642 15.4323 032151 035274 002679 002205 1.00000 001000 000001	.0,3531 .0,1308 .033814 .00	.0,1308 .033814 .00	.033814 .00	8	2113	.001057	.0,2642	15.4323	.032151	.035274	.002679	.002205	1.00000	.00100	100000
Liver or Keg. 61.0237 .035315 .001308 33.8140 2.11337 1.05669 .264172 15432.3 32.1507 35.2739 2.67923 2.20462 1000.00 1.00000 .001000	.035315 .001308 33.8140 2.1	.001308 33.8140 2.1	33.8140 2.1	2.	11337	1.05669	.264172	15432.3	32.1507	35.2739	2.67923	2.20462	1000.00	1.00000	.001000
61023.7 35.3146 1.30795 33814.0 2113.37 1056.69 264.172 1543201 32130.7 32273.9 2679.23 2204.62 10000001 1000.001 1.00000	35.3146 1.30795 33814.0 211	1.30795 33814.0 211	33814.0 211	21	3.37	1056.69	264.172	154320,	32150.7	35273.9	2679.23	2204.62	1000001	1000.00	1.00000
Note. The small subnumeral following a zero indicates that the zero is to be taken that number of times; thus, 0,1428 is equivalent to .0001428.	numeral following a zero indi	following a zero indi	a zero indi	걸	Cates	that the	zero is to	be taken	that nu	nber of t	imes; thu	s, .0,142	8 is equin	ralent to	.0001428.
Values used in constructing table: .: 1 gal. = 8.34541 lb. 1 inch = 2.540001 cm. 1 cu. in. = 16,387083 cc. = 16.387083 g H3 O at .: 1 lb. av. = 27.679886 cu. in. H3O at 4°C. 4°C. = 39°P.	ing table:	7083 g H, O at .:	7, 0 at ∴	• • •	1 5 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1 lb. av. = 453.5926 g.	5926 g. I 1b. 79886 cu.	in. H.10	at 4°C.	. 4	1 lb. av 1 gallor 31 cu. in.	1 lb. av. = 7000 grains. .: 1.gallon = 58417.87 grains. 231 cu. in. = 1 gallon = 3785.4162 g.	rains. 87 grains 1 = 3785.4	162 g.	

OL					MU	MULTIPLY BY					
FROM	B. T. U.	P. C. U.	Cat,	Ft. Lbs.	Ft. Tons.	Kg. M.	HP Hrs.	KW Hrs.	Joules	Lbs. C	Lbs. H <sub>1</sub> O
B.T.U.	1.00000	. 555556	.251996	778.000	.389001	107.563	.0,3929	.062931	1055.20	.0,6876	.001031
P.C.U.	1.80000	1.0000	45.3593	1400.40	.700202	193.613	.0,7072	.0,5276	1899.36	.0,1238	.001855
Colories	3.96832	2.20462	1:00000	3091.36	1.54368	426.844	.001559	.001163	4187.37	.0,2729	.004089
Pt. Lbs.	.001285	.0,7141	.0,3239	1.00000	.000500	.138255	.0,5050	.0,3767	1.35625	0,8840	.0,1325
Pt. Tons	2.57069	1.42816	.647804	2000.00	1.00000	276.511	.001010	.0,7535	2712.59	.0,1768	. 002649 .
Kg. M.	.009297	.005165	.002343	7.23301	.003617	1.00000	.0,3653	.0,2725	9.81009	.046394	.0,9580
HP Hrs	2544.99	.141388	641.327	1980000,	990.004	273747	1.00000	,746000	2685473	.175044	2.62261
KW Hrs.	3411.57	1895.32	859.702	2654200	1327.10	366959	1.34041	1,00000	3599889	.234648	3.51562
Joules	.0,9477	.0,5265	.0,2388	.737311	.0,3687	.101937	.043724	.0,2778	1.00000	.0,6518	.0,9766
Lbs. C.	14544.0	8080.00	3665.03	113150,	5657.63	1564396	5.71434	4.26285	153470,	1.00000	14.9876
Lbs. HrO	.970,400	539,111	244.537	754971	377.487	104379	.381270	.284424	1023966	.066744	1.00000

'TP. C. U." refers to the "pound-centigrade unit." The ton used is 2000 pounds. "Lbs. C" refers to pounds of carbon oxidized, 100% efficiency equivalent to the corresponding number of heat units. "Lbs H.O" refers to pounds of water evaporated at 100°C. "212"R, at 100% efficiency

By the use of the foregoing table about 330 interconversions among twenty-six of the standard engineering units of measure can be directly estimated from the alignment chart to three significant figures or calculated by simple multiplication to six figures. The multiplier factor given in the table is located on the center scale "A" giving the point which when aligned with any number point on "CI" determines the product on

"C." Imperfections in the scale due to lack of precision in printing should be checked at intervals along "A" scale by actual division of "C" by "C1," the lines being left out so that the reader can do this. A line scratched on a transparent celluloid triangle gives the best medium for making alignments.

dium for making alignments.

When volume and weight interconversions are given, water is the medium the calculations are based upon. By the introduction of specific gravity factors the median can be changed, giving the weight of any volume dian material, etc.

Courtesy of Chemical and Metallurgical Engineering.

CONVERSION OF TH	ERMOMETER	READINGS
------------------	-----------	----------

										-	
F°	C°	F°	C°	F°	C°	F۰	C°	F°	C°	$\mathbf{F}^{\circ}$	C°
	—40.00 —38.89 —37.78 —36.67 —35.56	30 31 32 33 34	$     \begin{array}{r}       -1.11 \\       -0.56 \\       0.00 \\       0.56 \\       1.11     \end{array} $	80 81 82 83 84	26.67 27.22 27.78 28.33 28.89	250 255 260 265 270	121.11 123.89 126.67 129.44 132.22	500 505 510 515 520	260.00 262.78 265.56 268.33 271.11	900 910 920 930 940	482.22 487.78 493.33 498.89 504.44
$-28 \\ -26$	-34.44 -33.33 -32.22 -31.11 -30.00	35 36 37 38 39	1.67 2.22 2.78 3.33 3.89	85 86 87 88 89	29.44 30.00 30.56 31.11 31.67	275 280 285 290 295	135.00 137.78 140.55 143.33 146.11	525 530 535 540 545	273.89 276.67 279.44 282.22 285.00	950 960 970 980 990	510.00 515.56 521.11 526.67 532.22
-18 $-16$ $-14$	—28.89 —27.78 —26.67 —25.56 —24.44	40 41 42 43 44	4.44 5.00 5.56 6.11 6.67	90 91 92 93 94	32.22 32.78 33.33 33.89 39.44	300 305 310 315 320	148.89 151.67 154.44 157.22 160.00	550 555 560 565 570	287.78 290.55 293.33 296.11 298.89	1000 1050 1100 1150 1200	537.78 565.56 593.33 621.11 648.89
- 8 - 6 - 4	-23.33 $-22.22$ $-21.11$ $-20.00$ $-18.89$	45 46 47 48 49	7.22 7.78 8.33 8.89 9.44	95 96 97 98 99	35.00 35.56 36.11 36.67 37.22	325 330 335 340 345	162.78 165.56 168.33 171.11 173.89	575 580 585 590 595	301.67 304.44 307.22 310.00 312.78	1250 1300 1350 1400 1450	676,67 704,44 732,22 760,00 787,78
1 2 3	—17.78 —17.22 —16.67 —16.11 —15.56	50 51 52 53 54	10.00 10.56 11.11 11.67 12.22	100 105 110 115 120	37.78 40.55 43.33 46.11 48.89	350 355 360 365 370	176.67 179.44 182.22 185.00 187.78	600 610 620 630 640	315.56 321.11 326.67 332.22 337.78	1500 1550 1600 1650 1700	815.56 843.33 871.11 898.89 926.67
6 7 8	—15.00 —14.44 —13.89 —13.33 —12.78	55 56 57 58 59	12.78 13.33 13.89 14.44 15.00	125 130 135 140 145	51.67 54.44 57.22 60.00 62.78	375 380 385 390 395	190.55 193.33 196.11 198.89 201.67	650 660 670 680 690	343.33 348.89 354.44 360.00 365.56	1750 1800 1850 1900 1950	954.44 982.22 1010.00 1037.78 1065.56
11 12 13	-12.22 $-11.67$ $-11.11$ $-10.56$ $-10.00$	60 61 62 63 64	15.56 16.11 16.67 17.22 17.78	150 155 160 165 170	65.56 68.33 71.11 73.89 76.67	400 405 410 415 420	204.44 207.22 210.00 212.78 215.56	700 710 720 730 740	371.11 376.67 382.22 387.78 393.33	2000 2050 2100 2150 2200	1093.33 1121.11 1148.89 1176.67 1204.44
16 17 18	- 9.44 - 8.89 - 8.33 - 7.78 - 7.22	65 66 67 68 69	18.33 18.89 19.44 20.00 20.56	175 180 185 190 195	79.44 82.22 85.00 87.78 90.55	425 430 435 440 445	218.33 221.11 223.89 226.67 229.44	750 760 770 780 790	398.89 404.44 410.00 415.56 421.11	2250 2300 2350 2400 2450	1232.22 1260.00 1287.78 1315.56 1343.33
21 22 23	- 6.67 - 6.11 - 5.56 - 5.00 - 4.44	70 71 72 73 74	21.11 21.67 22.22 22.78 23.33	200 205 210 215 220	93.33 96.11 98.89 101.67 104.44	450 455 460 465 470	232.22 235.00 237.78 240.55 243.33	800 810 820 830 840	426.67 432.22 437.78 443.33 448.89	2500 2550 2600 2650 2700	1371.11 1398.89 1426.67 1454.44 1482.22
25 26 27 28 29	- 3.89 - 3.33 - 2.78 - 2.22 - 1.67	75 76 77 78 79	23.89 24.44 25.00 25.56 26.11	225 230 235 240 245	107.22 110.00 112.78 115.56 118.33	485 490	246.11 248.89 251.67 254.44 257.22	850 860 870 880 890	454.44 460.00 465.56 471.11 476.67	2750 2800 2850 2900 2950	1510.00 1537.78 1565.56 1593.33 1621.11

# ALCOHOL PROOF AND PERCENTAGE TABLE

	D			Per cent	
	Per cent		~		<b>T</b>
U. S.	$\mathbf{Alcohol}$	Per cent	U. S.	${f Alcohol}$	Per cent
Proof	by Volume	Alcohol	$\mathbf{Proof}$	by Volume	Alcohol
at 60° F.	at $60^{\circ}$ F.	by Weight	at 60° F.	at 60° F.	by Weight
N.	0.0	0.00	57	28.5	-
0 1 2 3 4 5 6 7 8 9		0.00	58	29.0	23,82
1	0.5				43.82
2	1.0	0.80	59	29.5	
<u></u>		0.00	60	30.0	24.67
3	1.5				24.07
4	2.0	1.59	61	30.5	
2		2.00	62	31.0	25.52
Ð	2.5				20.02
6	3.0	2.39	63	31.5	-
177	3.5		64	32.0	26.38
Ž.				02.0	20.56
8	4.0	3.19	65	32.5	-
o o	4.5		66	33.0	27.24
- 0		4.00		33.5	
10	5.0	4.00	67		-
11	5.5	-	68	34.0	28.10
40		4.00	69	34.5	
12	6.0	4.80			
13	6.5		70	35.0	28.97
14	7.0	5.61	71	35.5	
14		9.01			
15	7.5	·	72	36.0	29.84
15 16	8.0	6.42	73	36.5	
10		0.44			20.50
17	8.5	· ·	74	37.0	30.72
18	9.0	<b>7.2</b> 3	75	3 <b>7.</b> 5	
10		1.20			01.00
19	9.5		76	38.0	31.60
20	10.0	8.05	77	38 <b>.</b> 5	
20		0.00	78		32,48
21 22	10.5			39.0	34.48
22	11.0	8.86	79	39.5	-
00		0.00	80	40.0	33.36
23 24	11.5				99,90
24	12.0	9.68	81	40.5	-
25	12.5		82	41.0	34.25
20		40.00			04.20
26	13.0	10.50	83	41.5	
27	13.5		84	42.0	35.15
20		11.00			00.10
28	14.0	11.32	85	42.5	-
29	14.5		86	43.0	36.05
29 30		12.14	87	43.5	
30	15.0	12.14			
31	15.5		88	44.0	36 <b>.</b> 96
32 33 34	16.0	12.96	89	44.5	
04		12.50			05.00
33	16.5	-	90	<b>45.0</b>	37.86
34	17.0	13.79	91	45.5	-
35		20.10	$9\overline{2}$	46.0	90 70
30	17.5	-		40.0	3 <b>8.7</b> 8
36	18.0	14.61	93	46.5	
37	18.5		94	47.0	39.70
01		4 7 4 4			55.10
38	19.0	<b>15.44</b>	95	47.5	
38 39	19.5		96	48.0	40.62
40		16.27			10.02
40	20.0	10.27	97	48.5	
41	20.5		98	49.0	41.55
42	21.0	17.10	99	49.5	22.00
42		17.10			
43	21.5		100	50.0	42.49
AA	22.0	17.93	101	50.5	
43 44 45		T1.90			10.10
45	22.5		102	51.0	43.43
46	23.0	18.77	103	51.5	
400		10.11			44.00
47	23.5	*	104	52.0	44.37
48	24.0	19.60	105	<b>52.5</b>	
40	0/ 5	20.00			AF 99
49	24.5		106	53.0	45.33
50 51	25.0	20.44	107	53.5	***************************************
51	25.5		108	54.0	46.28
57		24.00			40.40
52 53	26.0	21.28	109	<b>54.5</b>	
53	26.5		110	55.0	47.24
F.4		00 10			T1.4T
54	27.0	22.13	111	<b>55.5</b>	
55	27.5	-	112	<b>56.0</b>	48.21
56	28.0	22.97			10.22
90	40.U	44.91	113	56.5	TARREST TO THE PARTY OF THE PAR

	Per cent	-		Per cent	<b></b>
U.S.	Alcohol	Per cent	U.S.	Alcohol	Per cent
	by Volume	Alcohol	Proof	by Volume	Alcohol
Proof	at 60° F.	by Weight	at 60° F.	at 60° F.	by Weight
at 60° F.	57.0	49.19	158	79.0	72.38
114		40.10	159	79.5	***************************************
115	5 <b>7.</b> 5	50.17	160	80.0	73.53
116	58.0	90.11	161	80.5	
117	58 <b>.</b> 5	51.15	162	81.0	74.69
118	59.0	91.10	163	81.5	-
119	59.5	52.15	164	82.0	75.86
120	60.0	52.15	165	82.5	
121	60.5	F9.1E	166	83.0	77.04
122	61.0	53.15	167	83.5	
123	61.5	F 4 4 F	168	84.0	78.23
124	62.0	54.15	169	84.5	
125	62.5		170	85.0	79.44
126	63.0	55.16		85.5	
127	63.5		171	86.0	80.62
128	64.0	56.18	172	86.5	
129	64.5		173		81.90
130	65.0	57.21	174	87.0	01.00
131	65.5		175	87.5	83.14
132	66.0	58.24	1.76	88.0	00.14
133	66.5		177	88.5	04.41
134	67.0	59.28	178	89.0	84.41
104	67.5		179	89.5	07.00
135	68.0	60.32	180	90.0	85.69
136		00.02	181	90.5	
137	68.5	61.38	182	91.0	86.99
138	69.0	01.00	183	91.5	
139	69.5	62.44	184	92.0	88.31
140	70.0	04.44	185	92.5	
141	70.5	CO 51	186	93.0	89.65
142	71.0	63.51	187	93.5	-
143	71.5	04.50	188	94.0	91.02
144	72.0	64.59	189	94.5	
145	72.5		190	95.0	92.42
146	73.0	65.67	191	95.5	
147	73.5		192	96.0	93.85
148	74.0	66.77	193	96.5	-
149	74.5		193	97.0	95.32
150	75.0	67.87		97.5	
151	75.5		195	98.0	96.82
152	76.0	68.92	196		00.00
153	76.5		197	98.5	
154	77.0	70.10	198	99.0	98.38
155	77.5		199	99.5	
156	78.0	71.23			100.00
157	78.5		200	100.0	
191		ma	Potassiur	n Acid Ph	thalate-So-
	Buffer Syste	ino como com-	dium l	Hydroxide	5.0
The follo	owing table gi	ves some com-	Cocondar	v Sodium Cit	trate o.v
mon buffer	r systems and	the approxi-	Cambania	Acid_Ricarbo	nate 0.0
mate pH o	of maximum b	uffer capacity.	Primary	Phosphate-	Secondary
			Phosph	nate	6.8
			Primary	nate Phosphate-S	odium Hy-
			drovid	Α	0.0
the value	given, for	Concentrations	Romic A	cid-Borax	0.0
	stair II I moia	Γ.	Dorox		J
Claracacil -	Sodium Unit	oride - fly-	1 Th A	H WILLIAM F.	voroxide J.A
drochlo	mic Acid	2.0	Digarhar	ate_Carhonat	e 10.4
Dotoecinm	Acid Phti	nalate-riy-	Soconde	arw Phosona	a te-bourum
المام مسلم	ria Acid	2.0		wide	
The same of the same	Dotoecium (il	trate o		Countries of W	A. Taylor & Company
Acetic Ac	cid-Sodium A	cetate 4.6	•	Coursesy of Pr.	*** - =0.00
Accide 11					

## REFERENCES AND ACKNOWLEDGMENTS

Abrasive & Cleaning Methods
Agr. Gaz. N. S. Wales
Allg. Oes. v. Gettzeitung
Aluminum Co. of Amer.
Amer. Cyanamid & Chem. Corp.
Amer. Druggst
Amer. Dyestuff Reporter
Amer. Electrop. Society
Amer. Gum Importers' Ass'n
Amer. Paint Jol.
Amer. Perfumer
Amer. Photography
Amer. Wool & Cotton Reporter
Analyst
Anal. Fis. Quim.
Ault & Wiborg Varnish Wks. Handbook

Baker's Helper
Bakers Review
Baker's Weekly
Behr Manning Corp.
Better Enameling
Boonton Molding Co.
Bottler & Packer
Boyce Thompson Inst.
Brewers' Tech. Review
Brick & Clay Record
Br. Jol. Dent. Science
Brit. Jol. of Photography
Brit. Medical Jol.
Bull. Imp. Hyg. Lab.
Bulletin of Imperial Institute
Bull. Soc. Franc. Phot.

Camera Camera (Luzern) Canadian Jol. of Med. Technology Canadian Textile Jol. Canner Cement & Cement Mfr. Ceramic Age Chemical Abstracts Chemical Analyst Chemical Industries Chemical Products Chemical Weekblad Chem. Zent. Chemist & Druggist Chr. Hansen's Lab. Cleaning & Dyeing World Combustion Confectioner's Jol. Consumers' Guide Cramer's Manual

Dairy World
Damsk. Tids. Farm
Dental Items
Dental Lab'y Review
Devt. Part. Zeitung
Drug & Cosmetic Industry
Druggists Circular
Drugs, Oils, & Paints
DuPont Rubber Bulletins

Eastman Kodak Co. Electric Journal

Farbe u. Lacke
Farben Zeitung
Farming S. Africa
Fein Mechanic v. Prazision
Fettchem, Umschan
Fils & Tissus
Flavours
Foous
Food Manufacture
Fruit Products Jol.

Gelatin, Leim, Klebstoffe General Abrasive Co. Glass Industry Graphic Arts Monthly

Hawaiian Planters' Record Hercules Powder Co. Bulletins Hide & Leather

Ice Cream Review
India Rubber World
Indian Lac Research Inst.
Indian Soap Jol.
Indiana Acad. of Sciences
Industrial Chemist
Industrial Finishing
Instruments
Intern'l Salt Co.
Int'l Tin Res. & Dev. Council
Iowa State College Bull.

- J. Amer. Dental Assn. J. Amer. Medical Assn.
- J. Chem. Eng.
- J. Chinese Chem. Soc.
- J. Federation Curriers
- J. Federation Light Leather Tanners
- J. Res. Nat. Bur. Standards
- J. Rubber Industry
- J. Russ. Rubber Ind.

Jol. Soc. Leather Trades Jol. Soc. Rubber Ind. Japan Jol. Tech. Physics Jol. of Technical Methods (I.A.M.M.)

Keram Steklo Khimstroi Kozhevenna-Obuvnaya Prom. Kunstdunger, Und Leim

Lakokras, Ind. Leather Trades Review Leather Worker Les Mat. Grasses Lithographic Tech. Foundation

Malayan Agric. Jol.
Manufacturing Chemist
Meat
Meat Merchandising
Melliand
Metal Industry
Metall und Erz
Metallurg
Metallurgist
Metallurgist
Metals & Alloys
Mich. Agric. Exp. Sta.
Milk Dealer
Mineralogist
Monatschr. Textil-Ind.
Monsanto Chem. Co.
Munic. Eng. San. Record

Nat'l Butter & Cheese Jol. Nat'l Provisioner Nickelsworth Nitrocellulose

Ober Flachen Tech. Oil & Color Trades Jol. Oil & Soap

Pacific Rural Press
Paint Technology
Paper Trade Jol.
Parfum Mod.
Peinture, Pigments, Vernis
Phar. Acta Helva
Pharmaceutical Jol.
Phot. Abstracts

American Colloid Co. Army Ordnance Cowles Laundry Tips Electrochemical Society Indiana Farmer's Guide Photo Art Monthly Phot. Ind. Phot. Korr. Photog. Kronik Phot. Rev. Photo Rundschau Physics Phytopathology Pix Plater's Guide Book Portland Cement Assn. Power Practical Druggist Practical Everyday Chemistry Printing Industry Prob. Edelmetalle Process Engr. Mo. Proc. World Petroleum Congress

Rayon & Mell. Tex. Monthly Refiner & Nat. Gas Mfr. Rev. Aluminum Rev. Amer. Electro Society Rock Products

Science
Sharpless Solvents Corp.
Silver Technologist
Shoe and Leather Journal
Soap
Soap Gazette & Perfumer
Solvent News
Sovet-Sakhar
Spirits
Steel
Synthetic & Applied Finishes

Textile Colorist Textile Mfr. Textile Recorder

Univ. Nebr. Agric. Coll. Bull. U. S. Department of Agriculture U. S. Bureau of Mines U. S. Bureau of Standards

Veneers and Plywood

Z. Elektrochem. Zeit. Unters. Lebensm.

### ADDENDA

Industrial & Eng. Chemistry Manufacturing Confectioner New York Physician Phila. Quartz Co.

### TRADE-NAME CHEMICALS

During the past few years, the practice of marketing raw materials, under names which in themselves are not descriptive chemically of the products they represent, has become very prevalent. No modern book of formulae could justify its claims either to completeness or modernity without numerous formulae containing these so-called "Trade Names."

Without wishing to enter into any discussion regarding the justification of "Trade Names" the Editors recoming the transportant containing the second of the containing the conta

"Trade Names," the Editors recognize the tremendous service rendered to commercial chemistry by manufacturers of "Trade Name" products, both in

the physical data supplied and the formulation suggested.

Deprived of the protection afforded their products by this system of nomenclature, these manufacturers would have been forced to stand helplessly by while the fruits of their labor were being filched from them by competitors who, unhampered by expenses of research, experimentation and promotion, would be able to produce something "just as good" at prices far below those of the original producers.

That these competitive products were "just as good" solely in the minds of the imitators would only be evidenced in costly experimental work on the part of the purchaser and, in the meantime, irreparable damage would have been done to the truly ethical product. It is obvious, of course, that under these circumstances, there would be no incentive for manufacturers to develop

new materials.

Because of this, and also because the "Chemical Formulary" is primarily concerned with the physical results of compounding rather than with the chemistry involved, the Editors felt that the inclusion of formulae containing various trade name products would be of definite value to the producer of finished chemical materials. If they had been left out many ideas and processes would have been automatically eliminated.

As a further service the better known "trade name" products are included

with the list of chemicals and supplies.

# CHEMICALS AND SUPPLIES: WHERE TO BUY THEM\*

Numbers on right refer to list of suppliers on pages directly following this list. Thus to find out who supplies borax look in left hand column, alongside borax, on page 591. The number there is 34. Now turn to page 603 and find number 34. Alongside is the supplier, American Potash & Chemical Corp., New York, N. Y.

Product No.	Product No.
A	Albasol
A-Svrup	Albatex
Aacagum	Alberit
Abalyn	Albertol
Abietic Acid	Albinol
Abopon	Albolit 53
Accelerator 808195	Albolith387
Accelerator 833	Albone C
Accelerators, Vulcanization195	Albron 11
Acceloid	Albumen
Accroides	Albusol344
Acelose	Alcohol, Denatured449
Acetaloid 2	Alcohol, Pure
Acetamide	Aldehol
Acetic Acid140	Aldol392
Acetic Anhydride	Aldydal294
Acetoin	Alfalate322
Acetol	Alframine
Acetone	Alginic Acid313
Acetnhenetidin	Alizarin
Acetyl Cellulose.see Cellulose Acetate	Alkalies148
Acetyl Salicylic Acid368	Alkaloids
Acidolene349	Alkanet
Acids, Fatty540	Alkanol195
Acimul251	Alkyd Resins409
Acrawax	Alloxan 88
Acriflavine 1	Almond Oil342
Acrolite	Aloes413
Acrxyeol	Aloin
Acrylic Resins450	Aloxite
Acryloid450	Alperox
Acrysol450	Alpha Naphthol
Acto507	Alphasol23
Adeps Lanaesee Lanolin	Altax
Adheso Wax251	Alugel
A.D.M. No. 100 Oil	Alumina
Aerogel	Aluminum
Aerosol	Aluminum Acetate392
Agar	Aluminum Bronze Powder549
Agene	Aluminum Chloride 99
Agerite Powder559	Aluminum Hydrate121
Akcocene	Aluminum Oleate479
Aktivin8	Aluminum Silicate580
Albacer	Aluminum Stearate229
Alba-Floc550	Aluminum Sulphate513
Albalith387	Alums
* Please see addenda p. 602. 5	89

Product No.	Product No.
Alundum	Aquarex195
Alvar478	Aquarome
Amandol	Aquasol
Amberette	Arachis Oilsee Peanut Oil
Amberlac	Arapali450
Amberol	Araskleen
Ambreno	Aratone
Amco Acetate316	Archer-Daniels No. 635 44
Amerine	Archer-Daniels-Midland Oil 44
Ameripol254	Arctic Syntex144
Amerith	Aresklene
Ameroid	Areskiene
Amidine	Aridex195
Aminostearin251	Arlex
Aminox	Aroflex519
Ammoniac Resin	Arolite
Ammonium Bichromate431	Arosol
Ammonium Bifluoride269	
Ammonium Carbonate586	Arsenic
Ammonium Carbonate	Artisil
Ammonium Laurate251	Asbestine
Ammonium Linoleate251	Asbestos429
Ammonium Nitrate	Ascarite
Ammonium Oleate	Asetoform
Ammonium Persulphate 92	Aseptex
Ammonium Phosphate521	Asphalt 65
Ammonium Stearate251	Asphaltum 9
Ammonium Sulphate 60	Astrinite
Ammonium Sulphite	Astrulan 28
Ammonium Sulphoricinoleate251	Atrapol406
Amyl Acetate	Aurosal
Anchoracel 2n	Avirol
Angstrol190	Avitex198
Anhydrone	Avonac379
Aniline Chloride	Azo 30
see Aniline Hydrochloride	В
Aniline Dyes240 Aniline Hydrochloride99	-
Aniline Hydrochloride 99	Badex
Aniline Oil	Bakelite 56
Ansol	Bakers' Plasticizer 5' Balsams
Anthraquinone	Darisams
Antidolorin	Barak
Antimony	Bardex 6
Antimony Ovide 283	Barite see Baryte
Antimony Oxide 283 Antimony Sulphide 223 Antimony Trioxide	Barium Carbonate 6
Antimony Trioxide	Barium Carbonate
see Antimony Oxide	Barium Peroxide
Anti-Oxidants	Barium Silico Fluoride2
Anti-scorch	Barium Sulphate 6
Antox	Barium Sulphide17
Apco	Baroid
Anocthinner	Barretan 6
Appramine	Bartyl24
Aquadag	
Aqualoid309	Barytes
	Barytes
Aqualube251	Barytes
Aquamel251	Barytes
Aquamel	Barytes
Aquamel251	Barytes

Product No.	Product No.
Beckolin	Butyl Alcohol (Normal)434
Beckophen	Butyl Aldehyde
Beckosol	Butyl Amine
Deckosoi	Butyl Carbitol106
Beeswax192	Dutyl Carbitol
Beetle Resin	Butyl Cellosolve106
Bellaphan311	Butyl Lactate
Bensapol588	Butyl Propionate 96
Bentonite	Butyl Stearate316
Benzaldehyde	Butyric Ether396
Benzidine236	
Benzine 32	$\mathbf{C}$
Rongogaine	Cadalyte
Benzocaine	Cadmium
Benzol	Cadmolith128
Benzoi	
Benzoyl Peroxide335	Cajuput Oil292
Benzyl Cellulose 6	Calagum251
Bergamot Oil407	Calcene148
Beryllium 72 Beryllium Salts 223	Calcium Arsenate85
Bervllium Salts223	Calcium Carbonate330
Reta Naphthol	Calcium Carbonate (Precipitated) 360
Regitene384	Calcium Chloride
Beutene	Calcium Chloride (Anhydrous)213 Calcium Cyanamid23
Bismuth	Calcium Cyanamid
Bismuth Subnitrate388	Calcium Fluoride238
Bitumensee Asphaltum	Calcium Hydroxide
Bitumensee Asphartum	see Lime, Hydrate
Black Leaf539	Calaire Orda
Blanc Fixe291	Calcium Oxidesee Lime
Blandol494	Calcium Phosphate433
Blankit240	Calcium Polysulphide98
Bleaching Powder	Calcium Propionate251
Blendene251	Calcium Stearate
Blood Albumen370	Calcium Stearate
Bludtan123	see Plaster of Paris
Boea	Calcium Sulphide (Luminous) 29
Bole	Calcorid
Bonderite411	Calcolac
Bondogen559	Calcoloid 99
Bondogen	Calcozine
Bone Ash	Calgon
Bone Black484	Calgorite100
Bone Glue	Calomel590
Bone Meal	Calorite
Bone Oil532	Calorite
Borax	Camphor
Bordeaux Mixture	Camphor Oil342
Rordow 188	Candelilla Wax
Boric Acid 83	Capillary Syrup see Glucose Syrup
Borol	Cantax
Retanical Products 414	Caramel Color
Bresin	Caraway Oil
Brisgo	Carbasol107
Bromine	Carbitol106
Bromo "Acid"	Carbofrax109
Bromo-Fluorescein	Carbolac
Bromo-Fluorescelli	Carbolic Acidsee Phenol
Bronze Powder	Carbolic Oil
Brosco	Carbolic Oil
Rurgundy Pitch	Carbolineum
Butacita	Carbon, Activated305
Butalvde	Carbon Bisulphide
Rutey	Carbon Black547
Butohen	Carbon, Decolorizing169
Rutyl Acetate	Carbon Tetrachloride395
Butyl Acetyl Ricinoleate150	Carbonex 68
Langi ricciyi rizoniorodo	

Product No.	Product No.
Carboraffin	Chromic Oxide see Chromium Oxide
Carboseal	Chromium Oxide283
Carbowax	Chromium Sulphate360
Carboxide	Cinchophen
Cardamom Seed390	Cinelin
Carmine444	Citral
Carmine444	Citrene
Carnauba Wax	Citric Acid
Carragheensee Irish Moss	Citronella Oil
Casco	
Casein	
Castile Soap	Clay
Castor Oil 57	Clovel
Castor Oil, Blown 57	Coal Tar165
Castor Oil, Sulphonated588	Coal Tar Colors
Castrolite454	Coal Tar Oil
Catalin	Cobalt Acetate 90
Catalno	Cobalt Chloride354
Catylon270	Cobalt Driers354
Caustic Soda351	Cobalt Linoleate354
CCH351	Cobalt Naphthenate401
Celascour	Coblac
Celeron	Cocoa Butter
Celite	Cocoa Butter
Cellit	Coconut Butter
Cellon	Coconut Oil 59
Cellosolve	Coconut Oil Fatty Acid 5
Celluloid	Cod Liver Oil451
Celluloid Scrap476	Codite
Cellulose Acetate	Collodion160
Cellulose Nitrate361	Collodion Woolsee Pyroxylin
Cellulose Nitrate	Colloresin240
Cement417	Colombony and Darin
Censteric	Color Lad
Ceraflux	Color L34
Cercon	Colors, Dry
Cerelose	Colors, Oil Soluble
Cereps	Colza Oilsee Rapeseed Oil
Ceresalt	Cominol
Ceresin Wax482	Condensite
Cerol	Congo Resinsee Resins, Natural
Cetamin	Conoco
Cetec241	Convertit400
Cetyl Alcohol290	Copal 23
Chalk, Precipitated135	Copal, Esterified226
Charcoal439	Copper Carbonate160
China Clay         525           China Wood Oil         63	Copper Chloride
China Wood Oil	Copper Cyanide
Chloramine 1	Copper Nitrate 62
Chlorasol106	Copper Oxides
Chlorex106	Copper Sulphate
Chlorinated Rubber276	Coppercide
Chlorine (Liquid)208	Corn Oil 30
Chloroform	Corn Sugar
Chlorophyll	Corn Syrup
Chloropicrin 41	Cosmic Black
Chlorosol106	Cotton Seed Oil
Cholesterin	Cotton Seed Oil, Hydrogenated 435
Cholesterin	Coumarin355
Chremnitz White	Coumarone Resin
Chrome Alum564	Cream of Tartar269
Chrome Green	Creasate 816
Chrome Yellow 40	Creosote
Chromic Acid	Cresols
CHICHIA FILIU ALLEGA ALLEGA ALLEGA ALLEGA	OLUBUAD

Product No.	Product No.
Cresophan	Dipentene
Cresylic Acid	Diphenyl
Cromodine	Dinhenyl, Chlorinated 368
Cryolite	Diphenyl Oxide
Cryptone387	Diphenyl Phthalate368
Crysalba	Discolite
Cumar	Disodium Phosphate565
Cupric Chloride see Copper Chloride	Disperso
Curbay Binder552	Distoline
Curgon471	Dowicide188
Cuttle Fish Bone	Dow-metal188
Cyclamal239	Download 188
Cycline368	Dow plasticizers         188           D. P. G.         368
Cyclohexylamine195	Drierite
Cyclohexanol195	Driers (Paint and Oil)401
Cyclonol195	Driers, Varnish
Cymanol296	Drop Black
Cymanor	Dry Ice
$\mathbf{D}$	Dulux
Dammar Gum331	Duolith
Dapol247	Dupanol
Darco	Duphax
Darvan	Duphonol
Daxad	DuPont Rubber Red195
Deceresol	Duprene
Degras	Duraplex
Deo-base	Durez
Deramin	Durite
Derris Extract472	Durophene471
Derris Root 73	Dutox195
Derris Root 73	Dyestuffs
Derris Root       73         Devolite       471         Dextrins       370	Dutox       195         Dyestuffs       379         Dynax       195
Derris Root       73         Devolite       471         Dextrins       370         Dextrose       162	Dyestuffs
Derris Root       73         Devolite       471         Dextrins       370         Dextrose       162         Diacetin       316	Dyestuffs
Derris Root       73         Devolite       471         Dextrins       370         Dextrose       162         Diacetin       316         Diafnam       442	Dyestuffs
Derris Root       73         Devolite       471         Dextrins       370         Dextrose       162         Diacetin       316         Diafoam       442         Diakonn       295	Dyestuffs
Derris Root       73         Devolite       471         Dextrins       370         Dextrose       162         Diacetin       316         Diafoam       442         Diakonn       295         Diamond K Linseed Oil       499	Dyestuffs
Derris Root       73         Devolite       471         Dextrins       370         Dextrose       162         Diacetin       316         Diafoam       442         Diakonn       295         Diamond K Linseed Oil       499         Diamyl Phthalate       552	Dyestuffs
Derris Root       73         Devolite       471         Dextrins       370         Dextrose       162         Diacetin       316         Diafoam       442         Diakonn       295         Diamond K Linseed Oil       499         Diamyl Phthalate       552         Diastafor       504	Dyestuffs
Derris Root       73         Devolite       471         Dextrins       370         Dextrose       162         Diacetin       316         Diafoam       442         Diakonn       295         Diamond K Linseed Oil       499         Diamyl Phthalate       552         Diastafor       504         Diastase       526	Dyestuffs
Derris Root       73         Devolite       471         Dextrins       370         Dextrose       162         Diacetin       316         Diafoam       442         Diakonn       295         Diamond K Linseed Oil       499         Diamyl Phthalate       552         Diastafor       504         Diastase       526         Diatol       552	Dyestuffs       379         Dynax       195         E       East-India Gum       23         Eastman Products       202         Egg, Dried       430         Egg Yolk       515         Elaine       210         Elemi       552         Emulphor       240
Derris Root     73       Devolite     471       Dextrins     370       Dextrose     162       Diacetin     316       Diafoam     442       Diakonn     295       Diamond K Linseed Oil     499       Diamyl Phthalate     552       Diastafor     504       Diastase     526       Diatol     552       Diaton     586	Dyestuffs       379         Dynax       195         E       E         East-India Gum       23         Eastman Products       202         Egg, Dried       430         Egg Yolk       515         Elaine       210         Elemi       552         Emulphor       240         Emulsifier L83A       251
Derris Root       73         Devolite       471         Dextrins       370         Dextrose       162         Diacetin       316         Diafoam       442         Diakonn       295         Diamond K Linseed Oil       499         Diamyl Phthalate       552         Diastafor       504         Diastase       526         Diatol       552         Diatomaceous Earth       586         Dibutyl Cellosolve Phthalate       368	Dyestuffs   379   Dynax   195   E
Derris Root       73         Devolite       471         Dextrins       370         Dextrose       162         Diacetin       316         Diafoam       442         Diakonn       295         Diamond K Linseed Oil       499         Diamyl Phthalate       552         Diastafor       504         Diastase       526         Diatol       552         Diatomaceous Earth       586         Dibutyl Cellosolve Phthalate       368         Dibutyl Tartrate       312	Dyestuffs       379         Dynax       195         E       E         East-India Gum       23         Eastman Products       202         Egg, Dried       430         Egg Yolk       515         Elaine       210         Elemi       552         Emulphor       240         Emulsifier L83A       251         Emulsone       251         Emulsone B       251
Derris Root       73         Devolite       471         Dextrins       370         Dextrose       162         Diacetin       316         Diafoam       442         Diakonn       295         Diamond K Linseed Oil       499         Diamyl Phthalate       552         Diastafor       504         Diastase       526         Diatol       552         Diatomaceous Earth       586         Dibutyl Cellosolve Phthalate       368         Dibutyl Tartrate       312         Dibutyl Typhthalate       312         Dibutyl Typhthalate       316	Dyestuffs       379         Dynax       195         E       E         East-India Gum       23         Eastman Products       202         Egg, Dried       430         Egg Yolk       515         Elaine       210         Elemi       552         Emulphor       240         Emulsifier       L83A       251         Emulsone       251         Emulsone B       251         Eosin       440
Derris Root       73         Devolite       471         Dextrins       370         Dextrose       162         Diacetin       316         Diafoam       442         Diakonn       295         Diamond K Linseed Oil       499         Diamyl Phthalate       552         Diastafor       504         Diastase       526         Diatol       552         Diatomaceous Earth       586         Dibutyl Cellosolve Phthalate       368         Dibutyl Tartrate       312         Dibutylphthalate       316         Dicalite       180	Dyestuffs       379         Dynax       195         E       E         East-India Gum       23         Eastman Products       202         Egg, Dried       430         Egg Yolk       515         Elaine       210         Elemi       552         Emulphor       240         Emulsifier       L83A       251         Emulsone       251         Emulsone       251         Eosin       440         Ephedrine       360
Derris Root       73         Devolite       471         Dextrins       370         Dextrose       162         Diacetin       316         Diafoam       442         Diakonn       295         Diamond K Linseed Oil       499         Diamyl Phthalate       552         Diastafor       504         Diastase       526         Diatol       552         Diatomaceous Earth       586         Dibutyl Cellosolve Phthalate       368         Dibutyl Tartrate       312         Dibutylphthalate       316         Dicalite       180         Dichlorbenzol       284	Dyestuffs       379         Dynax       195         E       E         East-India Gum       23         Eastman Products       202         Egg, Dried       430         Egg Yolk       515         Elaine       210         Elemi       552         Emulphor       240         Emulsifier L83A       251         Emulsone       251         Emulsone B       251         Eosin       440         Ephedrine       360         Epsom Salt       238
Derris Root         73           Devolite         471           Dextrins         370           Dextrose         162           Diacetin         316           Diafoam         442           Diakonn         295           Diamond K Linseed Oil         499           Diamyl Phthalate         552           Diastafor         504           Diastase         526           Diatol         552           Diatol         552           Diatouraceous Earth         586           Dibutyl Cellosolve Phthalate         368           Dibutyl Tartrate         312           Dibutylphthalate         316           Dicalite         180           Dichlorbenzol         284           Dichlorethylene         195	Dyestuffs       379         Dynax       195         E       E         East-India Gum       23         Eastman Products       202         Egg, Dried       430         Egg Yolk       515         Elaine       210         Elemi       552         Emulphor       240         Emulsifier L83A       251         Emulsone       251         Emulsone B       251         Eosin       440         Ephedrine       360         Epsom Salt       238         Erinoid       33         Erio Chrome Dves       235
Derris Root         73           Devolite         471           Dextrins         370           Dextrose         162           Diacetin         316           Diafoam         442           Diakonn         295           Diamond K Linseed Oil         499           Diamyl Phthalate         552           Diastafor         504           Diastase         526           Diatol         552           Diatomaceous Earth         586           Dibutyl Cellosolve Phthalate         368           Dibutyl Tartrate         312           Dibutylphthalate         316           Dicalite         180           Dichlorbenzol         284           Dichlorethylene         195           Dichlorethylether         106	Dyestuffs       379         Dynax       195         E       E         East-India Gum       23         Eastman Products       202         Egg, Dried       430         Egg Yolk       515         Elaine       210         Elemi       552         Emulphor       240         Emulsifier L83A       251         Emulsone       251         Emulsone B       251         Eosin       440         Ephedrine       360         Epsom Salt       238         Erinoid       33         Erio Chrome Dves       235
Derris Root         73           Devolite         471           Dextrins         370           Dextrose         162           Diacetin         316           Diafoam         442           Diakonn         295           Diamond K Linseed Oil         499           Diamyl Phthalate         552           Diastafor         504           Diastase         526           Diatol         552           Diatol         552           Diatomaceous Earth         586           Dibutyl Cellosolve Phthalate         368           Dibutyl Tartrate         312           Dibutyl phthalate         316           Dicalite         180           Dichlorbenzol         284           Dichlorethylene         195           Dichlorethylether         106           Diethanolamine Lactate         251	Dyestuffs
Derris Root         73           Devolite         471           Dextrins         370           Dextrose         162           Diacetin         316           Diafoam         442           Diakonn         295           Diamond K Linseed Oil         499           Diamyl Phthalate         552           Diastafor         504           Diastase         526           Diatol         552           Diatol         552           Diatomaceous Earth         586           Dibutyl Cellosolve Phthalate         368           Dibutyl Tartrate         312           Dibutyl phthalate         316           Dicalite         180           Dichlorbenzol         284           Dichlorethylene         195           Dichlorethylether         106           Diethanolamine Lactate         251	Dyestuffs       379         Dynax       195         E       E         East-India Gum       23         Eastman Products       202         Egg, Dried       430         Egg Yolk       515         Elaine       210         Elemi       552         Emulphor       240         Emulsifier L83A       251         Emulsone       251         Emulsone B       251         Eosin       440         Ephedrine       360         Epsom Salt       238         Erinoid       33         Erio Chrome Dyes       235         Escolite       163         Essential Oils       152         Essential Fseso       507
Derris Root         73           Devolite         471           Dextrins         370           Dextrose         162           Diacetin         316           Diafoam         442           Diakom         295           Diamond K Linseed Oil         499           Diamond K Linseed Oil         552           Diastafor         504           Diastase         526           Diatol         552           Diatol         552           Diatolyl         Cellosolve Phthalate           Dibutyl         Cellosolve Phthalate         368           Dibutyl         Tartrate         312           Dibutylphthalate         316           Dicalite         180           Dichlorethylene         195           Dichlorethylene         195           Dichlorethylether         106           Diethylcarbonate         552           Diethylene Glycol         106           Diethyl Phthalate         560	Dyestuffs       379         Dynax       195         E       E         East-India Gum       23         Eastman Products       202         Egg, Dried       430         Egg Yolk       515         Elaine       210         Elemi       552         Emulphor       240         Emulsifier L83A       251         Emulsone       251         Eosin       440         Ephedrine       360         Epsom Salt       238         Erinoid       33         Erio Chrome Dyes       235         Escolite       163         Essential Oils       152         Esso       507         Ester Gum       329
Derris Root         73           Devolite         471           Dextrins         370           Dextrose         162           Diacetin         316           Diafoam         442           Diakonn         295           Diamond K Linseed Oil         499           Diamyl Phthalate         552           Diastafor         504           Diastase         526           Diatol         552           Diatomaceous Earth         586           Dibutyl Cellosolve Phthalate         368           Dibutyl Tartrate         312           Dibutylphthalate         316           Dicalite         180           Dichlorbenzol         284           Dichlorethylene         195           Dichlorethylether         106           Diethanolamine Lactate         251           Diethylcarbonate         552           Diethyl Phthalate         560	Dyestuffs       379         Dynax       195         E       E         East-India Gum       23         Eastman Products       202         Egg, Dried       430         Egg Yolk       515         Elaine       210         Elemi       552         Emulphor       240         Emulsifier       L83A       251         Emulsone       251         Emulsone       251         Eosin       440         Ephedrine       360         Epsom Salt       238         Erinoid       33         Erio Chrome Dyes       235         Escolite       163         Essential Oils       152         Esso       507         Ester Gum       329         Esterol       409
Derris Root         73           Devolite         471           Dextrins         370           Dextrose         162           Diacetin         316           Diafoam         442           Diakonn         295           Diamond K Linseed Oil         499           Diamyl Phthalate         552           Diastafor         504           Diastase         526           Diatol         552           Diatol         552           Diatomaceous Earth         586           Dibutyl Cellosolve Phthalate         368           Dibutyl Tartrate         312           Dibutyl Phthalate         316           Dicalite         180           Dichlorbenzol         284           Dichlorethylene         195           Dichlorethylether         106           Diethylcarbonate         552           Diethyl Phthalate         560           Diethyl Phthalate         560           Diegestase         345           Diglycol         120	Dyestuffs       379         Dynax       195         E       E         East-India Gum       23         Eastman Products       202         Egg, Dried       430         Egg Yolk       515         Elaine       210         Elemi       552         Emulphor       240         Emulsifier L83A       251         Emulsone       251         Eosin       440         Ephedrine       360         Epsom Salt       238         Erinoid       33         Erio Chrome Dyes       235         Escolite       163         Essential Oils       152         Esso       507         Ester Gum       329         Estersol       562         Estersol       552
Derris Root         73           Devolite         471           Dextrins         370           Dextrose         162           Diacetin         316           Diafoam         442           Diakonn         295           Diamond K Linseed Oil         499           Diamyl Phthalate         552           Diastafor         504           Diastase         526           Diatol         552           Dibutyl Cellosolve Phthalate         368           Dibutyl Phthalate         316           Dichlorehyle         180           Dichlorehylene         195           Dichlorethylene         195           Dichlorethylether         106           Diethylcarbonate         251           Diethyl Phthalate         560           Digestase         345           Diglycol Laurate         251           Diglycol Laurate         251	Dyestuffs       379         Dynax       195         E       E         East-India Gum       23         Eastman Products       202         Egg, Dried       430         Egg Yolk       515         Elaine       210         Elemi       552         Emulphor       240         Emulsifier L83A       251         Emulsone       251         Eosin       440         Ephedrine       360         Epsom Salt       238         Erinoid       33         Erio Chrome Dyes       235         Escolite       163         Essential Oils       152         Esso       507         Ester Gum       329         Estersol       552         Ethavan       368
Derris Root         73           Devolite         471           Dextrins         370           Dextrose         162           Diacetin         316           Diafoam         442           Diakom         295           Diamond K Linseed Oil         499           Diamyl Phthalate         552           Diastafor         504           Diastase         526           Diatol         552           Diatol         552           Diatol         552           Diatol         552           Diatolate         368           Dibutyl Cellosolve Phthalate         368           Dibutyl Tartrate         312           Dibutylphthalate         316           Dicalite         180           Dichlorbenzol         284           Dichlorethylene         195           Dichlorethylether         106           Diethylcarbonate         552           Diethyl Phthalate         560           Diethyl Phthalate         560           Diethyl Phthalate         560           Diethyl Phthalate         251           Diethylesol Cleate         251      <	Dyestuffs   379   Dynax   195
Derris Root         73           Devolite         471           Dextrins         370           Dextrose         162           Diacetin         316           Diafoam         442           Diakom         295           Diamond K Linseed Oil         499           Diamyl Phthalate         552           Diastafor         504           Diastase         526           Diatol         552           Diatol         552           Diatolyl         Cellosolve Phthalate           Dibutyl Cellosolve Phthalate         368           Dibutyl Tartrate         312           Dibutylphthalate         316           Dicalite         180           Dichlorbenzol         284           Dichlorethylene         195           Dichlorethylene         195           Dichlorethylene         106           Diethylcarbonate         552           Diethyl Phthalate         560           Diethyl Phthalate         251           Diglycol Laurate         251           Diglycol Stearate         251           Diglycol Stearate         251           Diglycol Stearate	Dyestuffs       379         Dynax       195         E       E         East-India Gum       23         Eastman Products       202         Egg, Dried       430         Egg Yolk       515         Elaine       210         Elemi       552         Emulphor       240         Emulsifier L83A       251         Emulsone       251         Eosin       440         Ephedrine       360         Epsom Salt       23         Erinoid       33         Erino Chrome Dyes       235         Escolite       163         Essential Oils       152         Esso       507         Ester Gum       329         Esterol       409         Estersol       552         Ethavan       368         Ether       106         Ethox       561
Derris Root         73           Devolite         471           Dextrins         370           Dextrose         162           Diacetin         316           Diafoam         442           Diakonn         295           Diamond K Linseed Oil         499           Diamyl Phthalate         552           Diastafor         504           Diastase         526           Diatol         552           Diatol         552           Diatol         552           Diatol         586           Dibutyl Cellosolve Phthalate         368           Dibutyl Tartrate         312           Dibutyl Phthalate         316           Dicalite         180           Dichlorebenzol         284           Dichlorethylether         196           Diethylcarbonate         251           Diethylene Glycol         106           Diethyl Phthalate         560           Diettyl Phthalate         560           Diegestase         345           Diglycol Claurate         251           Diglycol Oleate         251           Diglycol Stearate         251	Dyestuffs   379   Dynax   195     E
Derris Root         73           Devolite         471           Dextrins         370           Dextrose         162           Diacetin         316           Diafoam         442           Diakonn         295           Diamond K Linseed Oil         499           Diamyl Phthalate         552           Diastafor         504           Diastase         526           Diatol         552           Diatol         268           Dibutyl Cellosolve Phthalate         368           Dibutyl phthalate         316           Dicalite         180           Dichlorethylene         195           Dichlorethylene         195           Dichlorethylether         106           Diethylene Glycol         106      <	Dyestuffs       379         Dynax       195         E       E         East-India Gum       23         Eastman Products       202         Egg, Dried       430         Egg Yolk       515         Elaine       210         Elemi       552         Emulphor       240         Emulsifier L83A       251         Emulsone       251         Emulsone B       251         Eosin       440         Ephedrine       360         Epsom Salt       238         Erinoid       33         Erio Chrome Dyes       235         Escolite       163         Essential Oils       152         Esso       507         Ester Gum       329         Esterol       409         Estersol       552         Ethavan       368         Ether       106         Ethox       561         Ethyl Acetate       361         Ethyl Cellulose       276
Derris Root         73           Devolite         471           Dextrins         370           Dextrose         162           Diacetin         316           Diafoam         442           Diakonn         295           Diamond K Linseed Oil         499           Diamyl Phthalate         552           Diastafor         504           Diastase         526           Diatol         552           Diatol         552           Diatol         552           Diatol         586           Dibutyl Cellosolve Phthalate         368           Dibutyl Tartrate         312           Dibutyl Phthalate         316           Dicalite         180           Dichlorebenzol         284           Dichlorethylether         196           Diethylcarbonate         251           Diethylene Glycol         106           Diethyl Phthalate         560           Diettyl Phthalate         560           Diegestase         345           Diglycol Claurate         251           Diglycol Oleate         251           Diglycol Stearate         251	Dyestuffs   379   Dynax   195     E

Table   187   Gelatin   4		
Section   Sect	No.	Product No.
Section   Sect	Tthe Destal	Gelatin 4
Sthylene Diamine	stnyi Protoi	Gelloid
Section   Sect	Sthylamine	Geloway
Strict   S	Sthylene Diamine	Gologone 58
Carabog   Cara	Ethylene Dichloride	Gelozoffe
Diagroil   248   Geranium Lake   38   Glauher Salt   38   G	Ethyleneglycol	
Direct   Commons   Commo	Encelyntus Oil	Gelva Resin47
Dilan	1100000 440	Geraniol31
Stron	Errian	
F	France 1	Geranium Oil46
F	Euresoi	Gilsonite38
F	SXUON	Ginseng32
Pabroil	ימן	Glandular Products
Carallog		Classhoon
Sactolac	Fabroil	Glassiteeti 20
Falba Absorption Base   221   Falkide   214   Falkovar   214   Falkovar   215   Feetcol   215   Ferric Chloride   216   Ferric Chloride   209   Ferric Chloride   209   Ferro Chrome   209   Ferro Chrome   209   Ferro Silicon   209   Ferrous Chloride   366   Ferro Silicon   209   Ferrous Chloride   366   Ferro Silicon   209   Ferrous Chloride   366   Ferro Silicon   209   Ferrous Chloride   306   Ferrous Chloride   306   Ferrous Chloride   306   Fileron   218   Fileron   219   Fileron   219   Fileron   219   Filtrol   219   Filtrol   219   Filtrol   219   Fish Glue   214   Fixalt   356   Fixtan   593   Fixatan   593   Fixatan   593   Fixatan   593   Filexoresin   251   Filexoresin   251   Filexoresin   251   Formaldehyde   279   Formal Acid   478   Formica   224   Formica   225   Formic Acid   478   Formica   226	Factolac	Glauber Sait
Falkide         214         Accessed         214         Accessed         Access	Folks Absorption Base441	Glucarine
Falkovar	Polkido 214	Glucose4
Seectol	Faikide	Glue16
Section   155   Glutrin   4   4   4   5   6   6   6   6   6   6   6   6   6	Pairoval 455	Glumide
Ser-ox   See   Iron Chloride   See   Iron Chloride   See   Iron Chloride   See   Iron Chloride   Serric Chloride   See   Iron Chloride   Serro Chrome   209   Serro Chrome   209   Serro Silicon   209   See   Serro Silicon   209   See   Serro Silicon   209   See	reectol	Glutrin4
Ser-ic Chloride   see Iron Chloride   Serric Chloride   see Iron Chloride   Serro Chrome   209   Serro Chrome   209   Serro Silicon   209   Serrous Chloride   see Iron Chloride   Seerro Silicon   218   Serro Chrome   229   Serrous Chloride   see Iron Chloride   Seerrox   513   Serrox   514   Serrox   515   Serrox   51	eldspar	Glycerawax
Serric Chloride	Fer-ox	Clycorin 1.
Serric Chrome	Parrie Chloride see Iron Unioride	Chronol
Serro Chrome	Corrigin	Claracted Mana Stagesta
Serro Manganese   209	Torra Chrome	Glyceryi Mono Stearate2
Serrous Chloride   See Iron Chloride   Glyceryl Tristearate   Clycory	Form Manganese	Glyceryl Phthalate
Serrous Chloride   See Fron Chloride   See Fron Chloride   See Fron Chloride   See Fron Chloride   See Fiberlon   See Ethylene   See Film   Scrap   See Ethylene   See Film   See Film   See Film   See Film   See Film   See Film   See Formaldehyde   See Formaldehydehydehydehydehydehydehydehydehydehy	Towns Ciliaan	Glyceryl Stearate
Serior   15	Formers Chloride see Iron Chloride	Glyceryl Tristearate2
Ciberlon   218	513	Glyco Wax A2
Section   Sect	rerrox 218	Glyco Wax B
Fillers	iberion	Glycol see Ethylene Glyc
Glycol Distearate   Glycol Distearate   Glycol Distearate   Glycol Distearate   Glycol Distearate   Glycol Piltrol   Sish Glue   Sish Glycol Stearate   Glycolac   Glycomel   Glycomel   Glycomel   Glycomel   Glycomine   Glycomine   Glycomine   Glycomine   Glycomine   Glycoride   Glycoride   Glycoride   Glycoride   Glycosterin   Glycosterin   Glycosterin   Glycosterin   Glyptal   Graphite   Graphi	Filac	Clycol Bori Borata
Filhr Scrap         287           Filter-Cel         306           Filtrol         219           Fish Glue         278           Fish Oil         214           Fixalt         368           Fixtan         256           Flavine         593           Flavine         293           Flavors         293           Flavors         306           Flexoresin         293           Flexoresin         293           Flexoresin         251           Gold Chloride         Graphite           Graphite         Graphite           Fluorspar         251           Flormalin         see Formaldehyde           Formalin         see Formaldehyde           Formamide         251           Formica         224           Formica         224           Formica         224           Formica         478           Formor         478           Freson         367           Friction         Black Pulp           Fusel Oil         552           Fyrex         565           Gum Elemi         Gum Karaya	Fillers	Clared Distants
Filtrol	Film Scron	Glycol Distearate
Filtrol         219         Glycol Stearate         278         Glycolac         278         Glycolac         Glycomel         278         Glycomel         Glycomine         Glycomine         Glycoride         Glycoride         Glycoride         Glycoride         Glycoride         Glycoride         Glycosterin         Graphite <t< td=""><td>Filter_Cal</td><td>Glycol Oleate</td></t<>	Filter_Cal	Glycol Oleate
Fish Glue         218         Glycolac           Fixalt         368         Glycomel           Fixtan         256         Glycomine           Flavine         593         Glycopon           Flavors         293         Glycosterin           Flavors         293         Glycosterin           Flaxseed         80         Glycosterin           Flexoresin         251         Gold Chloride           Fluorspar         281         Graphite           Formalin         see Formaldehyde         Graphite           Formaldehyde         279         Ground Nut Oil         see Peanut           Formica         224         Guai-a-phene         Guantal           Formica Acid         478         Gum Batu         Gum Batu           Freon         317         Gum Benzoin           Friction Black Pulp         200         Gum Copal         Gum Dammar           Fyrex         565         Gum Karaya         Gum, Locust Bean           Gum, Locust Bean         Gum Manila         Gum Martic           Gallic Acid         595         Gum Martic           Gallic Acid         452         Gum Sqndarac           Gamboge         452         Gum Tra	Filtrol	Glycol Phthalate
Fixalt         368           Fixata         368           Fixatan         256           Flavors         293           Flaxseed         80           Flectol         455           Flexoresin         251           Flexoresin         281           Flexoresin         281           Flexoresin         251           Flexoresin         281           Flexoresin         281           Flexoresin         281           Flexoresin         281           Gold Chloride         Graphite           Graphite         Graphite           Guantal         Ground Nut Oil         see Peanut           Gum Batu         Gum Benzoin           Gum Benzoin         Gum Dammar           Gum Legum         Gum Legum           Gum         Locust <t< td=""><td>Figh Clue</td><td>Glycol Stearate</td></t<>	Figh Clue	Glycol Stearate
Fixalt         368         Glycomel           Fixtan         256         Glycomine           Flavine         593         Glycoride           Flavors         293         Glycoride           Flaxseed         80         Glycosterin           Flectol         455         Glyptal           Flexoresin         251         Gold Chloride           Fluorspar         281         Graphite           Formalin         see Formaldehyde         Graphite           Formapin         251         Graphite           Formaldehyde         279         Ground Nut Oil         see Peanut           Formica         224         Guai-a-phene         Guantal           Formica Acid         478         Gum Batu         Gum Batu           Freon         317         Gum Benzoin         Gum Dammar           Fuller's Earth         460         Gum Dammar         Gum Locust Bean           Gum, Locust Bean         Gum Manila         Gum Mastic           Galagum         251         Gum Mastic           Galic Acid         452         Gum Sandarac           Gamboge         452         Gum Tragacanth	Fish Oil	Glycolac
Fixtan	368	Glycomel
Flavine	256	Glycomine
Flavors   293   Glycoride   Glycosterin	ixtan	Glyconon
Flaxseed	Flavine	Glycoride
Flectol 455 Flexoresin 251 Fluorspar 281 Formalin see Formaldehyde Formalin 195 Formaldehyde 279 Formanide 195 Formica 224 Formica 224 Formic Acid 565 Formvar 478 Freon 317 Freon 317 Freon 317 Freon 401 Frynex 565 Fyrex 565 Galagum 6 Galagum 251 Galagum 251 Galagum 251 Galagum 251 Galagum 251 Galagum 3251 Galagum 3251 Galagum 3251 Galagum 3251 Gamboge 452 Gambage 452 Gam Mariaa Gum Martic Gum Sandarac Gum Myrrh Gum Sandarac Gum Myrrh Gum Sandarac Gum Mariaa Gum Martic Gum Sandarac Gum Tragacanth	Flavors293	Clycogtowin
Flectol         455         Gryptal           Flexoresin         251         Gold Chloride           Fluorspar         281         Graphite           Formalin         251         Graphite, Colloidal           Formapin         251         Graphite, Colloidal           Formadehyde         279         Ground Nut Oil         see Peanut           Formamide         195         Ground Nut Oil         see Peanut           Ground Arabic         Guantal         Guantal         Gum Arabic         Gum Batu         Gum Batu         Gum Batu         Gum Copal         Gum Copal         Gum Copal         Gum Dammar         Gum Elemi         Gum Elemi         Gum Elemi         Gum Elemi         Gum Karaya         Gum Manila         Gum Manila         Gum Mastic         Gum Mastic         Gum Myrrh         Gum Myrrh         Gum Sandarac         Gum Sandarac         Gum Tragacanth         Gum Tragacant	Flaxseed80	Glycosterin
Flexoresin         251         Gold Chloride           Fluorspar         281         Graphite           Formalin         251         Graphite           Foamapin         251         Graphite           Formaldehyde         279         Ground Nut Oil         see Peanut           Formanide         195         Guai-a-phene         Guai-a-phene         Guantal         Guantal </td <td>Flectol405</td> <td>Glyptal</td>	Flectol405	Glyptal
Fluorspar Formalin see Formaldehyde Formaldehyde 279 Formamide 195 Formica 224 Formica 224 Formica 478 Formwar 317 Freon 317 Freon 317 Friction Black Pulp 200 Fuller's Earth 460 Fusel Oil 552 Fyrex 565 Galagum Galaic 251 Galagum 251 Gallic Acid 452 Gamboge 452 Gambage 195 Gamphite, Colloidal Graphite,	Flexoresin	Gold Chloride
Formalin         see Formaldenyde         Graphite, Collidar           Foamapin         251           Formaldehyde         279           Formanide         195           Formica         224           Formic Acid         565           Formwar         317           Freon         317           Friction Black Pulp         200           Fuller's Earth         460           Fusel Oil         552           Fyrex         565           Galagum         251           Gallic Acid         595           Gamboge         452           Gamboge         195           Gum Tragacanth	Fly owen on	Graphite
Foamapin         251           Formaldehyde         279           Formamide         195           Formica         224           Formic Acid         565           Formvar         478           Freon         317           Friction Black Pulp         200           Fuller's Earth         460           Fusel Oil         552           Gum Elemi           Fyrex         565           Galagum         251           Gallic Acid         452           Gamboge         452           Gamboge         195           Gum Tragacanth	Formalin see Formaldehyde	Graphite, Colloidal
Formaldehyde         279         Ground Nut Oil         see Peanut           Formanide         195         Guai-a-phene         Guantal           Formica         224         Guantal         Guantal         Guantal           Formic Acid         565         Guantal         Guanta	Formanin 251	Grapeseed Oil
Formamide 195 Formica 224 Formica 224 Formic Acid 565 Formwar 478 Freon 317 Friction Black Pulp 200 Fuller's Earth 460 Fyrex 565 Galagum Galagum 251 Galagum 251 Gallic Acid 452 Gamboge 452 Gam Batu Gum Benzoin Gum Copal Gum Copal Gum Dammar Gum Karaya Gum Locust Bean Gum Manila Gum Mastic Gum Martic Gum Sandarac Gum Sandarac Gum Tragacanth	roamapin	Ground Nut Oilsee Peanut
Formica 224 Formica 565 Formor Acid 478 Formor 478 Freon 317 Friction Black Pulp 200 Fuller's Earth 460 Fusel Oil 552 Fyrex 6 Galagum Galagum 251 Gallic Acid 595 Gamboge 452 Graffiel 595 Gam Arabic Gum Batu Gum Benzoin Gum Copal Gum Copal Gum Elemi Gum Karaya Gum, Locust Bean Gum Manila Gum Mastic	Formaldenyde	Guai-a-nhene
Formic Acid	Formamide	Cuental
Formic Acid         565         Gum Arabic         Gum Batu         Gum Batu         Gum Batu         Gum Batu         Gum Batu         Gum Copal         Gum Dammar         Gum Locust Bean         Gum Locust Bean         Gum Manila         Gum Mastic         Gum Mastic         Gum Mastic         Gum Mastic         Gum Myrrh         Gum Myrrh         Gum Sandarac         Gum Sandarac         Gum Tragacanth	Formica <sup>224</sup>	Gualitai
Formwar         478         Gum Battu           Freon         317         Gum Benzoin           Friction Black Pulp         200         Gum Copal           Fuller's Earth         460         Gum Dammar           Fusel Oil         552         Gum Elemi           Fyrex         Gum Karaya         Gum, Locust Bean           Galagum         251         Gum Manila           Gallic Acid         595         Gum Myrrh           Gamboge         452         Gum Sandarac           Gardirol         195         Gum Tragacanth	Formic Acid	Gum Arabic
Freon         317         Gum Belizoli         Gum Copal         Gum Dammar	Formyrar 418	Gum Batu
Friction Black Pulp       200       Gum Copar         Fuller's Earth       460       Gum Elemi         Fusel Oil       552       Gum Karaya         Fyrex       Gum, Locust Bean       Gum Manila         Galagum       251       Gum Mastic         Gallic Acid       595       Gum Myrh         Gamboge       452       Gum Sandarac         Gordinal       195       Gum Tragacanth	Frann 317	Gum Benzoin
Fuller's Earth       460       Gum Dammar         Fusel Oil       552       Gum Elemi         Fyrex       655       Gum Karaya         Galagum       251       Gum Manila         Gallic Acid       595       Gum Myrrh         Gamboge       452       Gum Sandarac         Gradial       195       Gum Tragacanth	Friction Black Puln	Gum Copal
Fusel Oil 552 Fusel Oil 5552 Fyrex 565 Gum Elemi Gum Karaya Gum, Locust Bean Gum Manila Gum Mastic Gum Mastic Gum Myrrh Gum Mastic Gum Myrrh Gum Sandarac Gum Tragacanth	Thelland Forth	Gum Dammar
Galagum         251         Gum Manila           Gallic Acid         595         Gum Mastic           Gamboge         452         Gum Sandarac           Gardiol         195         Gum Tragacanth	Fuller's Earth	Gum Elemi
Galagum	Fusei Oil	
Galagum	Fyrex	Cum Locust Rean
Galagum		
Gallic Acid	G.	Gum Maniia
Gallic Acid	Galagum	Gum Mastic
Gamboge	Collie Acid	dum myttm
Cardinal	Cambaga402	Gum Sandarac
237 Gums, Varnish	Candinal 195	Gum Tragacanth
	Gastex237	Gums, Varnish

Product No.	Product No.
Gutta Percha	Product No.
	Iron Oxide
Gypsum553	Iron Sulphate
Ħ	Isocholesterolsee Cholesterin
	Isohol
Halex 89	Isolene
Halowax262	Isoline
Harcol	Isomerpin195
Harveg272	Isophan
Harvite	Isopropyl Acetate
Haskelite	Tanana Alaska
	Isopropyl Alcohol
Heliozone195	Isopropyl Ether
Hemlock Bark528	Ivory Black 79
Henna Leaves414	T .
Herbs139	J
Hercolyn276	Japan Wax
Hercusol	Jasmogene
Herkolite241	Jointex
Heveatex277	OULD
Hexamethylenetetramine279	К
	T/aimita 000
Hexone	Kainite
Hexyl Alcohol106	Kalite559
Hyamine450	Kaolin
Hydralite C240	Kapsol
Hydrated Limesee Lime	Karo162
Hydristear583	Kellogg KVO
Hydrochloric Acid	Kellogg Varnish Oil
Hydrochloric Acid238 Hydrofluoric Acid250	Keltone
Hydrogen Peroxide573	Kerol
Hardmannatod Figh Oil 400	Kerosene
Hydrogenated Fish Oil492	Kerosene. Deodorized
Hydromalin251	Kerosene, Deodorized482
Hydromel	Ketanol195
Hydronol195	Ketonone
Hydropel151	Kilfoam 20
Hydroquinone202	Kolineum
Hydroresin	Kopol71a
Hydrowax	Koreon
Hygropon251	Koreon 374   Kronisol 561
	Kronitex
I	Kryocide
Ichthyol360	1223 00120
Idalol	. L
TO TIT 940	Laboratory Farrinment
IG Wax240 IG Wax O240	Laboratory Equipment, 118, 129, 132, 206, 221, 386, 470
IG Wax 0240	
Igepon	Lacquer Blue40
Ignex251	Lacquers
Indian Red	Lactac
Indigisols	Lactic Acid 43
Indigo 437	Lactoid 89
Indium 72 Indolylacetic Acid 360	Lactol Spirits
Indolvlacetic Acid	Lake Colors
Indur441	Lamp Black
T J	Lanette Wax
Indusoil296 Infusorial Earth	Lanolin
infusorial Earth	Lard Oil
see Diatomaceous Earth	Lard Oil
Insect Wax, Chinese451	Latac
Invadine	Latex277, 384
Invert Sugar	Laurex
Todine388	Lauric-Ol249
Iridium 58	Lauryl Alcohol
Irish Moss414	Lauryl Sulphonate
Iron Ammonium Citrate468	Lavekol
Iron Chloride	Lavender Oil558
Tron Omoride	1 201011101 011 11111111111111111111111

Product No.	Product
Lavene	Mahogany Soaps4
Lead Acetate238	Makalot1
Lead Arsenate238	Maleic Acid3
Lead Borate354	Manganar1
Lead and Its Oxides199	Manganese
Lead Oleate479	Manganese Dioxide
Lecithin 28	Manhaden Oil
Lecivit	Manila Gum29
Lemenone	Manjak
Lemon Juice. Concentrated375	Mannitol
Lemon Oil292	Manol4
Lemonal558	Manox34
Leonil 23	Mapico
Le Page's Cement457	Mapromin4
Leptyne425	Mapromol4
Lerbinia	Marble Dust20
Lethane450	Marcol
Leucosol	Marlite4
Leucotrope W	Marseilles Soapsee Castile Soa
Leukanol450	Mazola10
Leukonin269	Melamac
Lewisol329	Mellittis24
Licorice339	Menthol28
Lime417	Menthone
Lime, Hydrated298	Menthyl Salicylate2
Limestone467	Mercurous Nitrate5
Lindol116	Mercury28
Lingasan275	Mercury Compounds59
Linoleic Acid251	Merpentine1
Linseedsee Flaxseed	Merpol19
Linseed Oil 80	Mersol36
Litex529	Mertanol30
Litharge199	Merusol50
Lithium Chloride352	Methacrylic Acid19
Lithium Salts352	Methalate C23
Lithoform	Methanol
Lithopone320	Methasol29
Locust Bean Powder194	Methicol24
Lognite593	Methocel18
Logwood Extract	Methox50
Lorinol	Methyl Abietate
Lorol195	Methyl Acetate10
Lubrisol494	Methyl Acetone1
Lucidol335	Methyl Amyl Ketone
Lufax450	Methyl Anthranilate2
Lumarith	Methyl Cellosolve
Luminol202	Methyl Cellosolve Acetate2
Luxene 56	Methyl Ethyl Ketone10
Lycopodium355	Methyl Hexalin
Lynsol	Methyl Isobutyl Ketone
Lysol326	Methyl Orange
M	Methyl Parasept
	Methyl p-Hydroxybenzoate2' Methyl Salicylate
Mabelite	Methyland
Mafos351	Methylanol
Magnesia110	Methylate
Magnesite	Motol
Magnesium Carbonate360	Metol
Magnesium Chloride586	Metro-Nite
Magnesium Hydroxide348	Metso4
Magnesium Powder	Mica44 Micoid3
Magnesium Silicate580	Milcold3

Product No.	Product No.
Migasol	Nitro-cottonsee Nitrocellulose
Milcol	Nopco
Milk Gloss251	
Milk Sugar344	
Mineral Oilsee Paraffin Oil	Nu-Char
Mineral Oilsee Parainin Oil	Nulomoline400
Mineral Rubber	Nuodex401
Mineral Seal Oil507	Nusoap401
Mineral Spirits	0
Miniumsee Lead Oxide	
Mirasol107	Ochres490
Moldex251	Octyl Acetate106
Moldslip251	Octyl Alcohol106
Molybdenum141	Oil, Citronella292
Molybdenum Compounds141	Oil, Mineral505
Molybdenum Oxide141	Oil, Olive325
Monex384	Oil, Redsee Oleic Acid
Monoamylamine Oleate251	Oil Root Beer C474
Monoethanolamine Lactate251	Oilate401
Monolite241	Oildag 3
Montan Color	Oilsolate
Montan Wax	Oiricuri Wax 87
Morpholine	Oiticica Oil303
Mowilith	Olate
Mulsene	Olein
Muriatic Acidsee Hydrochloric Acid	Oleoresins
Warrane Acidsee Hydrochioric Acid	Oleyl Alcohol
Mycoban195 N	Olive Oil
27 7	Olive Oil Substitute
Naccolene379	Olive Oil, Sulphonated454
Naccon379	
Nacconol379	Ondulum
Naphtha172	Opal Wax
Naphthalene	Orange Oil454
Naphthalene, Chlorinated262	Oroco453
Napthenic Acid	Ortho Dichlorbenzene284
Napoleum Spirits	Ortho-phenylphenate188
Narobin	Orthosil420
National Oil Red379	Osmo-Kaolin225
Neatsfoot Oil381	Ouricuri Wax186
Nekal240	Oxalic Acid374
Nelgin	Oxgall385
Neolan137	Oxygen131
Neomerpin195	Oxynone455
Neoprene	Oxyquinoline Sulphate74
Neozone D	Ozokerite Wax518
Neutroleum233	
Neville Resin385	P
Nevindene	Palm Kernel Oil 59
Nevindene	Palm Oil586
Nevinoi 160	Palmitic Acid
Nickel Chloride	Panoline
Nickel Sulphate	Para Aminophenol
Nicotine	Parachlormetacresol368
Nicotine Sulphate323	Parachol
Nicotinic Acid 99	Paracide284
Nigrosine 99	
Ninabenzyl461	Para-dor188
Ninagen	Paradura409
Nipasol461	Paraffin, Chlorinated
Nitramon	Paraffin Oils469
Nitre Cake	Paraffin Wax403
Nitric Acid	Para-flux261
Nitrohenzol	Paralac
Nitrocellulose196	Paraldehyde279

	70 7 1
Product No.	Product No.
Paramet	Plexigum
Paranol	Plexite
Data Diagram 1 27	Plextol
Para-Phenylenediamine 37	
Parapont195	Plioform255
Parasept	Pliolite
Paris Black	Pliowax
Paris Green177	Pollonas
Paris White	Pollopas
raris white	Polycol
Parlon	
Paroil 12	Polyrin251
Peachol	Polystyrene
Peanut Oil207	Polyvinyl Acetate
Pearl Essence	Polyzime
reari Essence	
Pectin	Ponolith320
Peerless Clay	Pontalite195
Pegopren	Pontianak Resin363
Pentacetate477	Pontol
Pentalyn	Potash, Caustic393
Destayii	Potassium Abietate
Pentasol477	
Pentrol312	Potassium Carbonate542
Peppermint Oil342	Potassium Chlorate542
Peptone	Potassium Chloride 34
Perchloron	Potassium Dichromate431
Description	Potassium Hydroxide360
Perfume Bases293	Detassium riyuroxide
Perilla Oil308	Potassium Iodine
Permosalt	Potassium Iodine
Permosalt A251	Potassium Nitratesee Saltpetre
Perone	Potassium Oleate
Perrol	Potassium Palmolate251
rerroi	Potassium Perchlorate542
Perspex	
Petrex275	Potassium Permanganate111
Petrobenzol	Potassium Silicate
Petrohol502	Potassium Tartrate
Petrolatum419	Prague Powder
Petrolene	Prestabit
Petroleum Ether489	Proflex251
Petroleum Jelly	Proofit
Petroleum Spirits	Propylene Oxide106
Pharmasol	Protectoid116
Phenac23	Protovac
Dhamal 16	Provatol
Phenol	
Phenoi-Formaldenyde Resins191	Proxate
Phenolic Resin440	Prussian Blue
Phenothiazine	Prystal 17
Phenothiazine	Puerine349
Phisol	Pumice
Dhahamhama 570	Psyllium Seeds
Phobophene579	rsymum seeds
Phosphoric Acid565	Pylam Red436
Phosphorus300	Pyrax
Phosphotex	Pyrefume414
Phthalic Anhydride368	Pyrethol353
Piccolyte418	Pyrethrum414
Pigment Colors 40	Pyrethrum Extract356
Figure Colors 40	Tyrethrum Extract
Pine Oil244	Pyridin319
Pine Tar496	Pyrosee Pyrogallic Acid
Pitch438	Pyrosee Pyrogallic Acid Pyrogallic Acid598
Plaskon	Pyrolusite 190
Plastacele	Pyrolusite
Plaster of Paris580	I yroxymi Solutions200
Plastogen559	Q
Plastopal294 Plaz471	Quakersol41
Plaz	Quebracho 24

Product No.	Desident St.
Product No.	Product No.
Quince Seed	Schultz Silica
Quinine Bisulphate258	Solonium
	Selenium
Quinine Hydrochloride360	Sellatan A
Quinoline 68	Sellatan A
	Serinol310
$\mathbf{R}$	Sermor
<del></del>	Serrasol
Raisin Seed Oil444	Shellac 595
Rancidex	Shellac Wax
	Onemac wax
Rapeseed Oil 63	Sherpetco
Rapidase572	Sicapon
Rauzene	Siennas
Toduzene	
Rayox559	Silex580
Red Oil119	Silica 67
Red Squill	Silica Black
Redmanol	Silicon 72
Reogen	Silvatol
Resin DA 1	Silver
Resin R-H-35	
Resin N-H-50	Silver Cyanide160
Resinox442a	Silver Nitrate
Resins. Natural	Slaked Limesee Lime
Resins, Synthetic440	Soap
Desire of	
Resipon	Soda Ash179
Resoglaz 6	Soda, Caustic351
Resorcin416	Soda, Sal
Revertex	Sodium Acetate
	C I Al
Rezidel251	Sodium Alginate313
Rezinel	Sodium Aluminate
Rezyl 23	Sodium Arsenite
	Sodium Benzoate284
Rhodium58	
Rhonite450	Sodium Bicarbonate
Rhoplex450	Sodium Bichromate431
Rhotex450	Sodium Bisulphite256
Rochelle Salts	Sodium Boratesee Borax
Rochelle Saits444	Soulum Doratesee Dorax
Rodo559	Sodium Borophosphate251
Rose Water336	Sodium Carbonate493
Roseol342	Sodium Chlorate404
Rosin	Sodium Chlorite351
ROSIN	G. T. Character
Rosin Oil	Sodium Choleate183
Rosoap A251	Sodium Cyanide195
Rotenone535	Sodium Fluoride
Dubhor 201	Sodium Hydrosulphite454
Rubber201 Rubber Hydrochloride347	
Rubber Hydrochloride341	Sodium Hydroxide360
Rubber Latex334	Sodium Hypochlorite174
Rubber Resin	Sodium Hypochlorite Liquid447
Rubber Resin	Sodium Hyposulphite256
D 1:1: G 1	Codium Tannel Culphoto 951
Rubidium Salts340	Sodium Lauryl Sulphate251
4.0A3	Sodium Metaphosphate 94
S	Sodium Metasilicate423
"S" Syrup423	Sodium Nitrate 70
S Syrup	Sodium Nitrite
Saccharine279	
Sal Soda136	Sodium Oleate251
Salicylic Acid188	Sodium Oxalate
	Sodium Perborate195
Salt371	Cadima Dhambata
Salt Cake	Sodium Phosphate521
Saltpetre164	Sodium Propionate251
Santicizers	Sodium Pyrophosphate565
Cantalana 920	Sodium Resinate408
Santobane	G. I Giliata
Santomask	Sodium Silicate423
Santox	Sodium Silico Fluoride256
Conomino 137	Sodium Stannate
Dapailline	Sodium Stannate
Saponin309	Collina Calabata
Savolin251	Sodium Sulphate238

Product No.	Product No.
Product No.	Sunoco Spirits520
Sodium Sulphite358	
Sodium Tungstate 62	Superphosphate566
Soligen 6	Surfex435
Solox	Suspendite
0.1	Suspensone
Solozone195	
Solux195	Syncrolite309
Solvent Naphtha 68	Syntex144
Solvesso507	Synthane
Solwax	Synthenol499
O. 1.1.1	Dynamonor
Sorbitol251	${f T}$
Sorbitol Laurate251	
Sorbitol Oleate251	Talc
Sorbitol Stearate251	Talcum see Talc
Soya Protein249	Talloil
Soya Protein	
Soybean Flour500	Tallow
Soybean Oil499	Tamol450
Sperm Oil	Tanax
Spermaceti517	Tannic Acid595
Speron	Tantalum
Speron	Tamanum
Spindle Oil507	Tar Acid Oil
Squill414	Tartar Emetic 43
SRA Black	Tartaric Acid
Stacol	Tea Seed Oil
Stannic Chloridesec Tin Chloride	Teglac
Stannic Unioridesee I'm Unioride	
Stannous Chloridesee Tin Chloride	Tegofan471
Starch512	Telloy559
Staybellite	Tellurium559
Stearacol251	Tellurium Oxide
Stearic Acid	Tenex
Stearic Acid	
Stearin577	Tenite
Stearin Pitch	Tepidone
Stearite586	Tergitol
Stearol427	Terpineol
Stearoricinol	Tetrachlorethane
Stearoricinoi	
Stearyl Alcohol444	Tetrachlorethylene
Stoddard Solvent172	Tetrahydronaphthalene195
Storax342	<b>Tetralin</b>
Stripolite454	Tetrone
Stripper, T. S	Textac
Ottober, 1. O OFG	
Strontium Nitrate256	Textone351
Strychnine422	Thallium Sulphate309
Styraxsee Storax	Thermoplex
Styrene	Thiocarbamilid
Styrex188	Thionex
California An	
Sulfanilamide	Thiourea
Sulfanole574	Thorium Salts576
Sulfatate251	Thymol
Sulfo Turk A251	Tidolith548
Sulfo Turk B	Timonex
Sulfo Turk C	Tin546
Sulfogene195	Tin Chloride
Sulphonated Castor Oil 93	Tin Oxide
Sulphonated Coconut Oil454	Tinctures
	Tintite
Sulphonated Fatty Alcohol251	Mikewissas Dismid.
Sulphonated Mineral Oil251	Titanium Dioxide
Sulphonated Olive Oil588	Titanium Tetrachloride513
Sulphoricinol	Titanox
Sulphur	Ti-Tone
Sulphur Chloride513	Ti-Tree Oil
Sulphur Unioride	
Sulphur Dioxide	Toluene
Sulphuric Acid361	Toluol
Sulphurized Oils501	Toners
Building City	1 TOTAL

CHEMICALS AND SOTTME	5. WHERE TO BOT TILL
3.7	37.
Product No.	Product No. 104
Tonsil	Varcum
Tornesit	Varcum
Triacetin392	Varnish
Triamylamine	Varnolene507
Tributyl Citrate	Varsol507
maishlorethylene	Varsoi
This long	Vaso
m-iavogy/ Phosphate	Vat Colors
Triethanolamine	Vatsol
Triethanolamine Lactate251	Vegetable Colors437
Triethanolamine Naphtenate251	Vegetable F Wax517
Triethanolamine Oleate251	Vermiculite
Triethanolamine Phthalate251	Vermilion217
Triethanolamine Stearate251	Victron
Trigamine	Vinanac 0
Trigamine Stearate	Vingol
Trihydroxyethylamine	Winyl Acatata
see Triethanolamine	Vinyl Chloride
Trikalin	17:nyz]ita
Triphenylguanidine	Timifoon
Triphenylphosphate368	Tricoomim 201
Tripoli	Vigeoloid
Trisodium Phosphate	Transport 0
Triton	Within see Sulphuric Acid
	TT M D Nanhtha
Tung Oilsee China Wood Oil	Vololovi
	Voiciay Vultex570
Ti	w
Maralrolono	
Thursday and the second	Water Glass see Sodium Silicate
Marriager Dad (III)	Wax L33
Marrows Owing	Wax, Synthetic
M	Wetanol
Marino Chinetitiite	White Arsenic
Manus andring (Vanice)	White Arsenic
Musualla (14)	1 TT71.:Limm
mt-h-all Rose	Witch Hazel Extract181
Typaphor Black238	TTT - J Dicerm
	1 TV and Oil see China Wood Oil
U	177-01 Wow
Uformite	Wyo-Jel591
	t and the second
TILLERAND	X
T711	X-13238
TT 1	1 77 1
Unilith 548	17
TT CALTONE	V-10mol
Unyte	1 37-1-1
Uranium Nitrate	Xynomine406
Urea455	Y
Ureka C	1 504
Ursulin Uversol269	Yeast504
	Yelkin453
v	Z
Valex95	30
TT Janu	195
3	1 20 301
Vanilin	y   Zimate
Venzyme	

No.	Product
Product.	1 -
inc	
ima Cambanata	Zine Burbiase
the Ohlamida	Vane Silli) illue
Channets	7 imagnium
the Technical Te	7 7 Tirronium Oxide
ima Orrida	7 7 inov
Car Deginete	. 1
inc Silicofluoride269	7   Zopaque
AD:	DENDA
A.A.P. Naphthols	Nisha Pagin
A main amount hall thromatically a a a a a a a a a a a a a a a a a a	, , , ,
A - 1 1	4 1 20202
A1	4 1 1 001 0 1
0-1	1100023
D D T No 7	D1: 1:4-
Olam No 22	I limited
D	1 1 Olymorized
Timeral man A	1 1 2013 1 2113
Emarilation A30'/6A	1 1 1013
The sale of SASY	I I I TOUDMOLE
Tith and	O Ittleoran
Tillamo Irm	0   Danticizes
Till arrayray (	1 Dantonio
Classian	1 Dantomerso
Clarent Cohocoto	0   Santowax
71 1	II DUASO OD
	Standard Viscous Oil
C Dwotom	
TT	I Stroba ii all
TT other long discourable	o Dallatata
TT	O LEIPEROI
T	O Theop
77 D Cam	71 11 000
77 -11:	11-011
77 - 11 4	19   Tysemice
Transfer	Jo   Wax, Intology
Marriage	00   111000 2 0220
N Clo E	gi i iumiuoi
Nitroethane1	50 Zinol

## SELLERS OF CHEMICALS AND SUPPLIES

No.	Name	Address
1.	Abbott Laboratories	North Chiagge III
2.	Acetate Products Corn	Landon Prodond
3.	Acheson Colloids Corp.	Port Huron Mich
4.	Acheson Graphite Corp	Niggora Falls N V
5.	Acme Oil Corp	Chicago III
6.	Acme Oil Corp. Advance Solvents & Chem. Corp.	New York N V
7.	Ajax Metal Co	Philadelphia Pa
8.	Aktivin Corp	New York N Y
9.	Aktivin Corp. Allied Asphalt & Mineral Corp.	New York N Y
10.	Alpha Lux Co., Inc.	New York N V
11.	Aluminum Co. of America	Pittsburgh, Pa.
12.	Amecco Chemicals, Inc.	Rochester, N. Y.
13.	American Active Carbon Co	
14.	American Agar Co., Inc.	San Diego, Calif.
15.	American Aniline Products, Inc	New York, N. Y.
16.	American-Brit. Chem. Supplies, Inc.	New York, N. Y.
17.	American Catalin Corp	New York, N. Y.
18.	American Cellulose Co	Indianapolis, Ind.
19.	American Chemical Paint Co.	
20.	American Chemical Products Co	Rochester, N. Y.
21.	American Chlorophyll, Inc.	New York, N. Y.
22.	American Colloid Co	Chicago, Ill.
23.	American Cyanamid & Chem. Co	New York, N. Y.
24.	American Dyewood Co	New York, N. Y.
25.	American Fluoride Corp	New York, N. Y.
26.	American Insulator Corp	New Freedom, Pa.
27.	American Lanolin Corp.	Lawrence, Mass.
28.	American Lecithin Corp.  American Luminous Products Co	New Iork, N. I.
29. 30.	American Maize Products Co	Now York N V
31.	American Metal Co.	Now York N V
32.	American Mineral Spirit Co.	New York N Y
33.	American Plastics Corp.	New York, N. Y.
34.	Amorican Potech & Chem Corn	New York, N. Y.
35.	American Smelting & Refining Co.	New York, N. Y.
36.	American Zinc Co	New York City
37.	Amido Products Co	New York, N. Y.
38.	Anchor Chemical Co	Manchester, England
39.	Anderson Prichard Oil Corn	. Oklahoma City, Okla,
40.	Anshacher-Siegle Corn	Rosebank, New York
41.	Angul Chem Co	Marinette, Wis.
42.	Antwerp Naval Stores Co., Inc.  Apex Chem. Co.  Archer-Daniels-Midland Co.	Boston, Mass
43.	Apex Chem. Co	New York, N.
44.	Archer-Daniels-Midland Co	Minneapolis, Minn.
45.	Arkansas Co	New York, N. Y.
46.	Armour & Co	Chicago, III.
47.	Asbury Graphite Mills	Asbury Park, N. J.
48.	Atlantic Gelatine Co	Woburn, Mass.
49.	Atlantic Refining Co. Atlantic Research Associates	Philadelphia, Pa.
50.	Atlantic Research Associates	Newtonville, Mass.
51.	Atlas Import Co.	
52.	Atlas Powder Co.	Augebrae Cormons
53.	Augsburger, Kunst Fabrik	Augsburg, Germany
	603	

No.	Name	Address
54.	Autoxygen, Inc	New York, N. Y.
<b>55.</b>	Badcock, Robert & Co	New York, N. Y.
<u>56.</u>	Bakelite Corp.	New York, N. Y.
57.	Baker Castor Oil Co. Baker & Co., Inc.	Jersey City, N. J.
58.	Baker, Franklin Co	Hobolton N. J.
59. 60.	Paker, Franklin Co	New York N V
61.	Baker, H. J. & Bro. Baker, J. E., Co.	York Po
62.	Baker, J. T. Chem. Co.	Philipsburg, N. J.
63.	Balfour, Guthrie & Co., Ltd.	New York, N. Y
64.	Barada & Page Inc	Kansas City Mo
65.	Barber Asphalt Co	Philadelphia, Pa.
66.	Barium Reduction Corp.	Charleston, W. Va.
67.	Barnsdall Tripoli Corp	Seneca, Mo.
68. 69.	Barrett Co. Barry, E. J., Inc.	New York N. Y.
70.	Rattolla & Ranwick	New York N V
71.	Battelle & Renwick Battleboro Oil Co.	Battleboro, N. C.
71a.	Beck. Koller & Co	Detroit, Mich
72.	Belmont Smelting & Refining Wks	Brooklyn, N. Y.
73.	Benkert, W. & Co., Inc. Benzol Products Co.	New York, N. Y.
74.	Benzol Products Co	Newark, N. J.
75. 76.	F. C. Bersworth Labs.	Framingnam, Mass.
77.	Beryllium Corp. of America Bick & Co., Inc.	Reading Pa
78.	Bilhuher-Knoll Corp.	New York, N. Y.
79.	Binney & Smith	New York, N. Y.
80.	Bisbee Linseed Co. Bohme, A. G., H. Th.	Philadelphia, Pa.
81.	Bohme, A. G., H. Th.	Chemnitz, Germany
82.	Bopf-Whittam Corp	Linden, N. J.
83. 84.	Borax Union, Inc.	. San Francisco, Calif.
85.	The W. H. Bowdlear Co. Bowker Chem. Corp.	New York N V
86.	Bradley & Baker	New York, N. Y.
87.	Brazil Oiticica, Inc. British Drug Houses, Ltd.	New York, N. Y.
88.	British Drug Houses, Ltd	London, England
89.	British Xylonite Co.	London England
90.	Brooke, Fred L., Co. Bud Aromatic Chemical Co., Inc.	Chicago, Ill.
91. 92.	Buffalo Electro Chem. Co., Inc.	New York, N. Y.
93.	Rurkard-Schier Chem. Co., Inc	Chattanoora Tann
94.	Burkard-Schier Chem. Co. Buromin Corp.	Pittshurgh. Pa.
95.	Bush, W. J. & Co., Inc	New York, N. Y.
96.	C. P. Chemical Solvents, Inc.	New York, N. Y.
97.	Cabot, Godfrey L., Inc.	Boston, Mass.
98. 99.	Calcium Sulphide Corp. Calco Chemical Co.	Damascus, Va.
100.	Calcon Inc	Dittaband Da
101.	Calgon, Inc. Calif. Fruit Growers' Exchange	Ontario Calif
102.	Campbell, C. W. Co., Inc.	New York, N. Y.
103.	Campbell, John & Co	New York, N. Y.
104.	Campbell Rex & Co	London, England
105.	Carbic Color & Chemical Co	New York, N. Y.
106.	Carbide & Carbon Chem. Corp	New York, N. Y.
107.	Carbogen Chemical Co	Garwood, N. J.
108. 109.	Carbolincum Wood Preserving Co	Nicesya Folla N V
110.	Carey, Philip Co.	Tookland Ohio
111.	Carus Chem. Co., Inc.	I.a Salle III
112.	Casein Mfg. Co.	New York. N. Y.
113.	Casein Mfg. Co. The Casein Mfg. Co. of Amer. Inc.	New York, N. Y.
114.	Celanese Corp. of America	New York, N. Y.

No.	Name	Address
115.	Cellonwerke	Charlottenburg, Germany
116.	Celluloid Corp.	Newark N J
117.	Celluloid Corp	New York N V
118.	Lentral Scientific Co	Chicago and Ill
119.	Century Stearic Acid Wks. Century Stearic Acid & Candle Wks. Ceramic Color & Chem. Mfg. Co.	New York N Y
120.	Century Stearic Acid & Candle Wks	New York N V
121.	Ceramic Color & Chem Mfg Co	Morr Drighton Da
122.	Cerro de Pasco Copper Corp. Champion Paper & Fibre Co.	Now Voult N V
123.	Champion Paner & Fibre Co	Contan N C
123.	Chanlin-Ribbo	Name Wante N. V.
125.	Chaplin-Bibbo	New lork, N. 1.
125. 126.	Charabrayah Wife Co., Inc.	
	Chesebrough Mfg. Co.	New York, N. Y.
127.	Chemical & Pigment Co.	Baltimore, Md.
128.	Chemical & Pigment Co., Inc.	Scranton, Pa.
129.	Chemical & Pigment Co., Inc. Chemical Publ. Co., Inc. Chemical Solvents, Inc.	Brooklyn, N. Y.
130.	Chemical Solvents, Inc.	New York, N. Y.
131.	Chenev Chem. Co	
132.	Chicago Apparatus Co	Chicago, Ill.
133.	Chicago Copper & Chem. Co	Blue Island, Ill.
134.	Chipman Chem. Co., Inc. Chrystal, Charles B. Co., Inc. Church & Dwight Co., Inc. Ciba Co., Inc.	Bound Brook, N. J.
135.	Chrystal, Charles B. Co., Inc.	New York, N. Y.
136.	Church & Dwight Co., Inc.	New York, N. Y.
137.	Ciba Co., Inc.	New York, N. Y.
138.	Cinelin Co	Indianapolis, Ind.
139.	Clarke, John & Co	New York, N. Y.
140.	The Cleveland-Cliffs Iron Co	
141.	Climax Molybdenum Co	New York, N. Y.
142.	Clinton Co	
143.	Coleman & Rell Co	Norwood Ohio
144.	Colgate-Palmolive-Peet Co	Chicago Ill
145.	Colgate-Palmolive-Peet Co	Jersey City N J
146.	Colgate-Palmolive-Peet Co. Colledge, E. W., Inc.	Claveland Ohio
147.	Colonial Passan Oil Co	Everett Mass
148.	Colonial Beacon Oil Co. Columbia Alkali Corp. Commercial Solvents Corp. Commercial Solvents Corp.	Now Vork N V
	Columbia Alkan Corp.	Now Vork N V
149.	Commercial Solvents Corp.	Towns Houte Ind
150.	Commercial Solvents Corp	Description N. V.
151.	Commonwealth Color & Chem. Co	Name Name of the N
152.	Compagnie Duvai	
153.	Conewango Refining Co	warren, Pa.
154.	Consolidated Chem. Sales Corp	Newark, N. J.
155.	Consolidated Feldspar Corp	Trenton, N. J.
156.	Commercial Solvents Corp.  Commonwealth Color & Chem. Co.  Compagnie Duval  Conewango Refining Co.  Consolidated Chem. Sales Corp.  Consolidated Feldspar Corp.  Continental Diamond Fibre Co.	New York, N. Y.
157.	Continental Diamond Fibre Co	Bridgeport, Pa.
158.	Continental Oil Co	
159.	Cook Swan Co., Inc.	New York, N. Y.
160.	Cooper, Charles & Co	New York, N. Y.
161.	Coopers Creek Chem. Co	W. Conshohocken, Pa.
162.	Continental Diamond Fibre Co. Continental Oil Co. Cook Swan Co., Inc. Cooper, Charles & Co. Coopers Creek Chem. Co. Corn Products Refining Co. Cowles Detergent Co. Croton Chem. Corp. Crowley Tar Products Co. Crystal, Charles B. Co., Inc. Cudeby Packing Co.	New York, N. Y.
163.	Cowles Detergent Co	Cleveland, Ohio
164.	Croton Chem. Corp.	Brooklyn, N. Y.
165.	Crowley Tar Products Co	New York. N. Y.
166.	Crystal, Charles B. Co., Inc.	New York, N. Y.
167.	Cudahy Packing Co	
168.	Danco, Gerard J.  Darco Sales Corp.	New York, N. Y.
	Dance Color Corn	New York, N. Y.
169.	Darling & Co	Chicago III
170.	Davison Chem. Corp.	Raltimora Md
171.	T T O.1 Comm	Linicago III
172.	Deep Rock Oil Corp	Ct Tarie Wa
173.	C. P. De Lore Co	Politimore 3/13
174.	Deep Rock Oil Corp. C. P. De Lore Co. Delta Chem. Mfg. Co. Delta Chem. & Iron Co.	Dailinore, Md.
175.	Delta Chem. & Iron Co	Donner Cal-
176.	Denver Fire Clay Co	

000		
	Name	Address
No.		New York, N. Y.
177.	Devoe & Raynolds Co.  Dewey & Almy Chem. Co.  Diamond Alkali Co.	Boston, Mass
178.	Dewey & Almy Chem. Co	Pittchurch Pa
179.	Diamond Alkali Co. Dicalite Co.	New York, N. Y.
180.	Dicalite Co	Hegey Conn
181.	Dickinson, E. E. Co	Malden W Va
182.	Dickinson, J. Q. & Co	Detroit Mich
183.	Dickinson, J. Q. & Co. Difco Laboratories, Inc.	Detroit Mich
184.	Digestive Ferments Co	Son Francisco Calif
185.	Difco Laboratories, Inc. Digestive Ferments Co. Marshall Dill Distributing & Trading Co.	Now York N. Y
186.	histring the Leading Co	Morry Voulz N V
187.	Dodge & Olcott Co.  Dow Chemical Co.  Drakenfeld, B. F. & Co.	Midland Wich
188.	Dow Chemical Co	Mary Voyl, N V
189.	Drakenfeld, B. F. & Co. Dreyer, P. R. Co. Dreyfus Co., L. A.	Now York N Y
190.	Drever, P. R. Co	Poschank N V
191.	Drevfus Co., L. A.	Chicago III
192.	Imiry. A. C. & Co., Inc.	Morry Vorly N V
193.	Drury, A. C. & Co., Inc. Ducas, B. P. Co. Duche, T. M. & Sons Duche, T. M. & Namours & Co.	Now Vont N V
194.	Duche, T. M. & Sons	Wilmington Dol
195.	Duche, T. M. & Sons	Dowlin N I
196.	DuPont, E. I., de Nemours & Co.  E. I. DuPont de Nemours & Co., Inc.  Durite Plastics	Dhiladalahia Da
197.	Durite Plastics	Philadelphia, ra.
198.	Durite Plastics	Cincipacti Obio
199.	Dynamit, A. G. The Eagle-Picher Lead Co.	Cincinnati, Onlo
200.	The Eagle-Picher Lead Co. Eakins, J. S. & W. R., Inc.	Name Verly N. I.
201.	Eakins, J. S. & W. R., Inc.	Desharten N V
202.	Earle Bros. Eastman Kodak Co.	Rochester, N. 1.
202.	Eastman Kodak Co. Economic Materials Co.	Clarreland Obje
204.	Economic Materials Co.  Eff Laboratories, Inc.	Treserrand, Onto
205.	Eff Laboratories, Inc Egyptian Lacquer Co	Nearley, N. S.
206.	Firmer & Amend	New IOIK, N. I.
207.	Egyptian Lacquer Co. Eimer & Amend Elbert & Co.	New Tork, N. 1.
208.	Elbert & Co. Electro Bleaching Gas Co.	New Iork, N. 1.
209.	Electro Bleaching Gas Co. Electro-Metallurgical Co.	Circinati Ohio
210.	Electro-Metallurgical Co.  Emery Industries, Inc.	Name Vanis N V
211	Empire Distilling Corp	New York, N. 1.
212	Enterprise Animal Oil Co	Philadelphia, Fa.
213	Emery Industries, Inc. Empire Distilling Corp. Enterprise Animal Oil Co. Fales Chem. Co., Inc.	.Cornwall Landing, N. 1.
214	Fales Chem. Co., Inc.	Pittsburgh, ra.
215	Falk & Co	No. Unicago, III.
216	Fansteel Metallurgical Corp. Felton Chemical Co.	Mary Varia N V
$\frac{210}{217}$	Felton Chemical Co. Fezandie & Sperrle, Inc.	New IOIK, N. I.
218	Fezandie & Sperrie, Inc	Indian Orchard, Mass.
219	Fiberloid Corp. Filtrol Co. Fishbeck, Chas. Co.	No. Los Angeles, Calli.
220	Fishbeck, Chas. Co	Dittahungh Pa
$\frac{221}{221}$	Fishbeck, Chas. Co	Now York N V
222	Fisher Scientific Co	Dhiladalphia Pa
223	Florasynth Laboratories	Cincinnati Ohio
224	Foote Mineral Co	Norr Vords N V
225	Formica Insulation Co. Fougera, E. & Co.	Zanilwarth N J
226	Fougera, E. & Co. France, Campbell & Darling France, American Chemical Wks.	Comlete dt N I
227	Franco-American Chemical Wks	Now Vowl N V
228	Frank-Vliet Co.	Produm N V
229	Frank-Viet Co. Franks Chem. Products Co., Inc.	Now Vork N Y
230	Franks Chem. Products Co., Inc. French Potash Co.	Cincinnati Ohio
231	). French Potash Co. L. Alex Fries & Bro.	New York, N. Y.
232	Fries Bros	Norr Vork N V
238	2. Fries Bros	Now Von N V
234	3. Fritzchie Bros. 4. Garrigues, Stewart & Davies, Inc.	New Lork, N. 1.
23	4. Garrigues, Stewart & Davies, Inc. 5. Geigy Co., Inc.	New IOIK, N. I.
23	5. Geigy Co., Inc. 6. General Aniline Works, Inc.	New IOTK, IN. I.
23	6. General Aniline Works, Inc. 7. General Atlas Carbon Co.	New York N V
23	7. General Atlas Carbon Co. 8. General Chemical Co.	
40	· · · · · · · · · · · · · · · · · · ·	

	No.	Name	Address
		a 15 a	2100,000
	239.	General Drug Co	New York, N. Y.
	240.	General Dyestuffs Corp.	New York N Y
	241.	Conoral Electric Co	Dittagald Mass
		General Electric Co. General Electric Co. General Magnesite & Magnesia Co.	Pittsneid, Mass.
	242.	General Electric Co	Schenectady, N. Y.
	243.	General Magnesite & Magnesia Co.	Philadelphia Pa
	244.	General Naval Stores Co.	Now Vowle N V
		Centeral traval bioles co	New TORK, IN. I.
	245.	General Plastics Corp. General Plastics, Inc.	London, England
	246.	General Plastics, Inc.	No. Tonawanda, N. Y.
	247.	Girdler Corp	Louisville War
		Cincades Dilamento Tor	Louisville, A.y.
	248.	Givaudan-Delawanna, Inc.	New York, N. Y.
	249.	Glidden Co	Cleveland Ohio
	250.	Globe Chem. Co	Cincinnati Ohio
		Globe Olicin. Oo.	Omemnati, Oniq
	251.	Glyco Products Co., Inc.	Brooklyn, N. Y.
	252.	Goldschmidt, A. G., Th.	Essen Germany
	253.	Goldschmidt Corp.	Now Varie N V
		Goldschinder Corp.	IVEW TOLK, IV. I.
	254.	Goodrich, B. F., Co. Goodyear Tire & Rubber Co.	Akron, Ohio
	255.	Goodvear Tire & Rubber Co	Akron, Ohio
	256.	Craccolli Chamical Co	Claveland Ohio
		Glasselli Olicinicai Ou	Oleverand, Onio
	257.	Grasselli Chemical Co. W. S. Gray Co.	New York, N. Y.
	258.	Greeff, R. W. & Co.	New York, N. Y.
	259.	Griffith Laboratories	Chicago III
		Communication of the contraction	37 37 37 37 37
	260.	Gross, A. & Co	New York, N. Y.
	261.	Hall, C. P. & Co. Halowax Corp.	Akron, Ohio
	262.	Haloway Corn	Now York N Y
		TT	3T 371- 37 37
	263.	Hammil & Gillespie, Inc.	New York, N. Y.
	264.	Hamilton, A. K.	New York, N. Y.
	265.	Hamilton, A. K. Hammond Drierite Co.	Vellow Springs, Ohio
		Handy & Harman	Now Vorle N. V
	266.	Handy & Harman	INEW LOFK, IV. I.
	267.	Hardy, Charles, Inc. Harrison Mfg. Co.	New York, N. Y.
	268.	Harrison Mfg. Co.	Rahway, N. J.
	269.	Harshaw Chemical Co	Cleveland Ohio
		TI D J C	Mann Vanla M V
	270.	Hart Products Corp. Haskelite Mfg. Corp.	New York, N. 1.
	271.	Haskelite Mfg. Corp	
	272.	Haveg Corp. Hegeler Zinc Co.	Newark, Del.
	273.	Haves Colp. Co	Danwillo III
		negeler zinc co	ar ar ar ar
	274.	Heine & Co. Hercules Powder Co.	New York, N. 1.
	275.	Hercules Powder Co	New York, N. Y.
	276.	Hercules Powder Co	Wilmington Del
		TT	The land Brown
	277.	Heveatex Corp. C. B. Hewitt & Bro.	meirose, mass.
	278.	C. B. Hewitt & Bro	New York, N. Y.
	279.	Heyden Chemical Works Hill Bros. Chem. Co. Hillside Fluor Spar Mincs	New York, N. Y.
		TI'I Day Chara Co	Log Angeles Calif
	280.	Hill Bros. Chem. Co	Los Aligeies, Calli.
	281.	Hillside Fluor Spar Mincs	
	282.	Holland Aniline Dve Co.	Holland, Mich.
	283.	O. Hommel Co. Hooker Electro-Chemical Co. Hopkins, J. L. & Co.	Pittshurgh Pa
		O. Hollimer Co.	Man Want M
	284.	Hooker Electro-Chemical Co	New Tork, N. I.
	285.	Hopkins, J. L. & Co	New York, N. Y.
	286.	Howd Color Products	Sandlisky Unio
		TT T. M & C.	Dumbank Calif
	287.	Horn Jefferys & Co. Horner, James B., Inc.	, Durbank, Cani.
	288.	Horner, James B., Inc.	New York, N. Y.
p	289.	Huisking Chas I. & Co., Inc.	New York, N. Y.
		Trummed Chemical Co. Inc.	Now York N V
	290.	nummer Onemical Co., inc.	37 37 1 37 37
	291.	Huisking, Chas L. & Co., Inc. Hummel Chemical Co., Inc. Hurst, Adolph & Co., Inc.	New York, N. Y.
	292.		
		Hymes, Lewis Associates I. G. Farbenindustrie	New York N V
	293.	riymes, Lewis Associates	Dan Issant C
	294.	I. G. Farbenindustrie	rankiurt, Germany
	295.		
		Industrial Cham Salas Co	New York N V
	296.	THURSTINI OHEIR. Dates OU.	Morr Vonly Mr W
	297.	Innes, U. G., Corp.	INEW TORK, IN. I.
	298.	Imperial Chem. Industries Industrial Chem. Sales Co. Innes, O. G., Corp. Innis Speiden Co. Internal Pulp Corp.	New York, N. Y.
	299.	Innis Speiden Co. International Pulp Corp. International Selling Corp.	New York. N. Y.
		Tutanational Colling Com	New York N V
	200.	Infernational Dennis Corb	THE CALL TOTAL STEE BE

		A 1.1
No.	Interstate Color Co., Inc	Address
301.	Interstate Color Co., Inc.	New York, N. Y.
302.	Iowa Soda Products Co	Council Blums, Ia.
303.	Jackson, L. N. & Co.  Jacobson, C. A.  W. Va. Univer	
304.	Jacobson, C. A	Tolodo Obi
305.	The Jennison-Wright Co. Johns-Manville Corp.	
306.	Johns-Manville Corp.	Dittahumah Da
307.	Jones & Laughlin Steel Corp.	
308.	Jones, S. L. & Co.	New York N V
309. 310.	T-1: Mr. C.	Philadelphia Pa
311.	Jones, S. L. & Co.  Jungmann & Co.  Kali Mfg. Co.  Kalle & Co.  Kay Fries Chem., Inc.  Kelco Co.  Winning Co.	eshaden Rierich Germany
312.	Very Fries Chem Inc	New York, N. Y
313.	Walco Co	San Diego, Calif
314.		
315.	Kentucky Color & Chem Co	Louisville, Kv.
316.	Kessler Chem Corn	
317.		
318.	H. Kohnstamm & Co	New York, N. Y.
319.	Koppers Products Co	
320.	Kinetic Chem., Inc.  H. Kohnstamm & Co.  Koppers Products Co.  Krebs Pigment & Color Corp.	$\dots$ Newark, N. J.
321.	Kuhlman, Etabls.  Kurt, Albert, G. M. B. H.  Lattimer-Goodwin Chem. Co.	Paris, France
322.	Kurt, Albert, G. M. B. H.	Amoneburg, Germany
323.	Lattimer-Goodwin Chem. Co	Grand Junction, Onio
324.	Laxseed Co. Leghorn Trading Co., Inc. Lehn & Fink Corp.	New York, N. Y.
3 <b>2</b> 5.	Leghorn Trading Co., Inc.	Now York, N. 1.
326.	Lehn & Fink Corp	Waladan Patamaan N T
327. 328.	Theo. Leonhard Wax Co., Inc. Lewis, C. H. & Co.	Now York N V
329	Lewis, C. fl. & Co	Providence R I
330.	Limestone Products Corn of Amer	Newton N J
331.	Lewis, C. H. & Co. Lewis, John D., Inc. Limestone Products Corp. of Amer. Lincks, Geo. H. Liquid Carbonic Corp. Litter, D. H., Co. Littlejohn & Co., Inc. Lucidol Corp. Geo. Lueders & Co. Lundt & Co. Maas & Waldstein MacAndrews & Forbes Co. Mackay, A. D. Magnetic Pigment Co.	New York, N. Y.
332.	Liquid Carbonic Corp.	
333.	Litter, D. H., Co.	New York, N. Y.
334.	Littlejohn & Co., Inc.	New York, N. Y.
335.	Lucidol Corp	Buffalo, N. Y.
336.	Geo. Lueders & Co	New York, N. Y.
337.	Lundt & Co.	New York, N. Y.
338.	Maas & Waldstein	Newark, N. J.
339.	MacAndrews & Forbes Co	New York, N. Y.
340.	Mackay, A. D.	New York, N. Y.
341. 342.	Magnetic Pigment Co.	New IOFK, N. I.
343.	Magnetic Pigment Co. Magnus, Mabee & Reynard, Inc. Makalot Corp. Mallinckrodt Chemical Works	Roston Mass
344.	Mallinckrodt Chemical Works	St Louis Mo
345.	Malt Diastase Co	Brooklyn N. Y.
346.	Malt Diastase Co. Manchester Oxide Co.	Manchester, England
347.	Marbon Corp. Marine Magnesium Prod. Corp.	Gary. Ind.
348.	Marine Magnesium Prod. Corp	.S. San Francisco, Calif.
349.	Martin, Dennis Co	Newark, N. J.
350.	Martin, L. Co. Mathieson Alkali Co.	New York, N. Y.
351.	Mathieson Alkali Co	New York, N. Y.
35 <b>2.</b>	Maywood Chem. Works	Maywood, N. J.
353.	McCormick & Co.	
354.	The McGean Chem. Co.	Cleveland, Ohio
355.	McKesson & Robbins, Inc.	New York, N. Y.
35 <b>6.</b> 35 <b>7.</b>	McLaughlin, Gormley, King & Co	Winneapolis, Winn.
358.	Mearl Corp. Mechling Bros. Chem. Co.	Comdon N T
359.	E. Meer & Co., Inc.	Now York N V
360.	Merck & Co.	Rehway N I
361.	Merrimac Chemical Co.	Roston Mass
362,	Metro-Nite Co.	Milwaukee. Wis.
4 1 -		

No.	Name	Address
363.	Meyer & Sons, J.	Philadelphia Pa
364.	Mica Insulator Co.	New York N Y
365.	Mica Insulator Co. Michel Export Co.	New York N Y
366.	Michigan Alkali Co	New York, N. Y.
367.	Miller, Carl F., Co.	Soattle Wash
368.	Monsanto Chem. Works	St. Louis Mo.
369.	Woore-Wunger	New York N Y
370.	Morningstar, Nicol. Inc.	New York, N. Y.
371.	Morton Salt Co	Ohionea Til
372.	Murphy Varnish Co	Newark, N. J.
373.	Murphy Varnish Co.  Mutual Chem. Co. of Amer.  Mutual Chem. Co. of America	New York, N. Y.
374.	Mutual Chem. Co. of America	New York, N. Y.
375.	Mutual Citrus Products Co	Ananeim, Calif.
376.	National Aulminate Corp	
377.	Nat'l Ammonia Co., Inc.	Philadelphia, Pa.
379.	Nat'l Ammonia Co., Inc. Nat'l Aniline & Chem. Wks. National Lead Co. National Oil Products Co.	New York, N. Y.
380.	National Lead Co	New York, N. Y.
381.	National Oil Products Co.	
382.	Nat'l Pigments & Chem. Co	St. Louis, Mo.
383.	National Rosin Oil & Size Co.	New York, N. Y.
384. 385.	Naugatuck Chem. Co.	Naugatuck, Conn.
	Neville Co.	Pittsburgh, Pa.
386.	Neville Co. N. J. Laboratory Supply Co. N. J. Zinc Co. The N. Y. Quinine & Chem. Wks., Inc. Newmann-Buslee & Wolfe, Inc.	Newark, N. J.
387. 388.	The N V Origins & Cham When To-	New York, N. Y.
	Marrana Duales & Walfe Inc.	Chiange III
390. 391.		
391. 392.	Nigget Cham Co	Niegore Folla N V
393.	Niagara Alkali Co	Now York N V
394.	Niagara Chamicals Corn	Niacara Falla N V
395.	Niacet Chem. Co. Niagara Alkali Co. Niagara Chemicals Corp. Niagara Smelting Corp. The Northwestern Chem. Co. Norton Co.	Niagara Falls N Y
396.	The Northwestern Chem Co.	Wauwatosa. Wis.
397.	Norton Co.	Worcester, Mass.
398.		
399.	Novadel-Agene Corp. Nulomoline Co.	Newark, N. J.
400.	Nulomoline Co	New York, N. Y.
401.	Nuodex Products, Inc.	Elizabeth, N. J.
402.	Ohio-Apex, Inc. Oil States Petroleum Co.	Nitro, W. Va.
403.	Oil States Petroleum Co	New York, N. Y.
404.	Oldbury Electro-Chem. Co	New York, N. Y.
405.	Olive Branch Minerals Co	
406.	Onyx Oil & Chem. Co	
407.	Orbis Products Corp	New York, N. Y.
408.	Papermakers' Chem. Corp	Wilmington, Del.
409.	Paramet Chem. Corp. Parke, Davis & Co. Parker Rust Proof Co. Patent Chemicals, Inc.	Long Island City, N. 1.
410.	Parke, Davis & Co	Detroit, Mich.
411.	Parker Rust Proof Co	Now Vont N V
412. 413.	Patent Unemicals, Inc.	Now York N V
414.	Peek & Velsor, Inc. Penick, S. B. & Co.	New York N V
414.	Penn. Alcohol Corp.	Philadelphia Pa
416.	Penn. Coal Products Co.	Petrolia. Pa
417.	PennDixie Cement Corp.	New York City
418.	Penn. Industrial Chem. Corp.	Clairton. Pa.
419.	Penn Refining Co	Butler. Pa.
420.	Dame Calt Mar Ca	Philadelphia Pa
421.	Pfaltz-Bauer, Inc.	New York, N. Y.
422.	Pfaltz-Bauer, Inc. Pfizer, Chas. & Co., Inc. Phila. Quartz Co.	New York, N. Y.
423.	Phila. Quartz Co	Philadelphia, Pa.
424.	Philipp Bros	New York, N. Y.
425.	Philipp Bros. Pittsburgh Plate Glass Co.	Pittsburgh, Pa.
426.	Plaskon Corp.	Toledo, Ohio
		•


	No.	Name	Address
	427.	Dirmonth Owner Take	New York, N. Y.
	428.	Pollopas, Ltd. Powhatan Mining Corp.	London, England
	429.	Powhatan Mining Corp	Woodlawn, Baltimore, Md.
	430.	Pray, W. P. Prior Chem. Corp.	New York, N. Y.
	431.	Prior Chem. Corp	New York, N. Y.
	432.	Procter & Gamble Co.	
	433. 434.	Provident Chem. Wks	Dhiladalphia Da
	435.	Pure Calcium Products Co.	Painegville Objo
	436.	Pulam Products Co	New York N. Y
	437.	Rangom I. E. Co	New York N V
	438.	Robert Rauh, Inc.	Newark, N. J.
	439.	Robert Rauh, Inc. Read, Chas. L. & Co., Inc. Reichhold Chemicals, Inc.	New York, N. Y.
	440.	Reichhold Chemicals, Inc	Detroit, Mich.
	441.	Relly Tar & Unem. Corp.	
	442.	Resinous Prod. & Chem. Co	Norm World City
	442a. 443.	Resinox Corp	New fork City
	444.	Revertex Corp.  Revson, R. F. Co.	New York N V
	445.	Rhone-Poulene Inc	Paris, France
	446.	Richards Chem. Works	Jersey City, N. J.
	447.	Riverside Chem. Co	No. Tonawanda, N. Y.
	448.	Robeson Process Co	New York, N. Y.
	449.	Rogers & McClellan	Boston, Mass.
	450.	Rohm & Haas Rosenthal, H. H., Co. Ross, Frank B., Co., Inc.	
	451. 452.	Rosenthal, H. H., Co.	Now York N. 1.
	452. 453.	Ross-Rowe, Inc.	New York N V
	454.	Rovce Chem Co	Carlton Hill, N. J.
	455.	Rubber Service Labs. Co.	Akron. Ohio
	456.	Rubber Service Labs. Co. Russel', W. R. & Co.	New York, N. Y.
	457.	Russia Cement Co	Gloucester, Mass
	458.	Ryland, H. C., Inc. Saginaw Salt Products Co. Salomon, L. A. & Bro.	New York, N. Y.
	459. 460.	Salamon I. A & Bro	New York N V
	461.	Samuelson & Co. P.	London, England
	462.	Sandoz Chem. Works	
	463.	Scheel, Wm. H.	
	464.	Schimmel & Co	New York, N. Y.
	464a.	Schliemann Co., Inc.	New York City
	465. 466.	Schofield-Daniel Co. Scholler Bros., Inc.	Philadalphia Pa
	467.	F. E. Schundler & Co.	Joliet III
	468.	Schuylkill Chem Co	Philadelphia Pa
	469.	Schwabacher, S. & Co., Inc.	New York, N. Y.
	470.	Schwabacher, S. & Co., Inc. Scientific Glass Apparatus Co. Scott, Bader & Co.	Bloomfield, N. J.
	471.	Scott, Bader & Co.	London, England
	472.	Seacoast Laboratories	New York, N. Y.
	473. 474.	Seeley & Co., Inc.	Now York, N. 1.
	475.	Seldner & Enequist, Inc.	Brooklyn N V
	476.	Serinsky, Moses Co.	Indianapolis Ind.
	477.	Sharples Solvents Corp.	Philadelphia Pa
	478.	Shawinigan, Ltd. Shepherd Chem. Co.	New York, N. Y.
	479.	Shepherd Chem. Co	Norwood, Cincinnati, Ohio
	480.	Sherka Chem. Co., Inc.	Bloomfield, N. J.
	482.	Sherwood Petroleum Co	Linglewood, N. J.
	483. 484.	Siemon Colors, Inc.	Names N. I.
	485.	Siemon & Co	Bridgeport, Conn.
1	486.	Silica Products Co	
	487.	Silver, Geo., Import Co	New York, N. Y.
		ACTION AND ADDRESS OF THE ACTION AND ADDRESS	

=			
i	No.	Name	Address
45	88.	Sinclair Refining Co	Olmstead, Ill.
	89.	Skelly Oil Co.	
	90	Smith Chem. & Color Co	Brooklyn, N. Y.
	91	Smith & Nichols, Inc.	New York, N. Y.
	92.	Smith, Werner G., Co. Solvay Sales Corp.	Cleveland, Ohio
	93.	Solvay Sales Corp.	New York, N. Y.
	94.	Sonneborn, L., Sons	New York, N. Y.
	95.	Southern Mica Co	Franklin, N. C.
	96.	Southern Mica Co. Southern Pine Chem. Co.	Jacksonville, Fla.
	97.	Southwark Mfg. Co	Camden, N. J.
7	98.	Sparhawk Co	Sparkhill, N. Y.
1	99.	Sparhawk Co	Buffalo, N. Y.
	ሰሰ	A E Staley Mfor Co	Decatur, III.
	01.	Stamford Rubber Supply Co	Stamford, Conn
	02.	Stanca Distributors	New York, N. Y.
	03.	Stanco Distributors Standard Alcohol Co.	New York N. Y.
	04.	Standard Brands, Inc.	New York N Y.
	05.	Standard Oil Co. of Calif	San Francisco, Calif.
	ue. 06.	Standard Oil Co. of Calif. Standard Oil Co. of Indiana	Chicago III.
	06. 07.	Standard Oil Co. of N. J.	New York, N. Y.
	07. 08.	Standard Oil Co. of N. J. Standard Oil Co. of N. Y.	New York N. Y.
	08.	Standard Silicata Ca	Pittsburgh Pa.
	10.	Standard Silicate Co. Standard Ultramarine Co.	Huntington W. Va.
	10.	Standard Ottianiai ine Co	New York City
	11.	Standard Utramarine Co. Stanley Co., John T. Starch Products Co. Stauffer Chem. Co. Stauffer Chem. Co. of Texas	New York N Y
	12.	Startin Products Co	New York N Y.
	13.	Staurer Chem. Co. of Toron	Freenort Texas
	14.	Stein, Hall & Co.	New York N Y
	16.	Stokes & Smith Co	New York N Y
	17.	Strani & Pitsen	New York N Y
	18.	Stokes & Smith Co. Strahl & Pitsch Strohmeyer & Arpe Co. Strock & Wittenberg Corp. Sun Oil Co.	New York N Y
	19.	Stroock & Wittenberg Corp	Philodelphia Pa
þ	20.	Sun Ull Co	New York N Y
5	21.	Swann Chemical Co. Synfleur Scientific Labs. Synthane Corp.	Monticello N Y
	22.	Synneur Scientific Labs	Oaks Pa.
Ð	23.	The Synthetic Products Co.  Taintor Trading Co.	Cleveland Ohio
	24.	The Synthetic Products Co	Now York N Y
	25.	Taintor Trading Co. Takamine Laboratory, Inc.	Clifton N J
	26.	Takamine Laboratory, Inc.	Chicago III
	27.	Tamms Silica Co	Grand Ranide Mich
	28.	Tanners Supply Co	Now York N Y
	29.	Tanners Supply Co. Tannin Corp. C. Tennant & Sons Co. of N. Y.	Now York N Y
	30.	C. Tennant & Sons Co. of N. 1.	Wingenort Tonn
	31.	Tenn. Eastman Corp. Texas Chem. Co. Texas Mining & Smelting Co.	Houston Toyas
	32.	Texas Chem. Co.	Larado Tayas
	33.	Texas Mining & Smelting Co	Dhiladalahia Pa
	34.	Thomas, Arthur H., Co.	St Louis Mo
	35.	Thorocide, Inc.	New York N Y
	36.	Thurston & Braidich	Niegara Falle N V
	537.	Titanium Alloy Mig. Co	Nour Vorle N V
F	538.	Titanium Pigments Co	TACM TOTY' TA' T'
			Lonierrillo Kar
-	539.	Tobacco By-Products & Chem. Corp	Louisville, Ky.
	539. 540.	Tobacco By-Products & Chem. Corp.  Trask, Arthur C., Co.	Louisville, Ky. Chicago, Ill.
100	539. 540. 541.	Tobacco By-Products & Chem. Corp.  Trask, Arthur C., Co.  Trojan Powder Co.	Louisville, Ky. Chicago, Ill. Allentown, Pa. Ridgefield N J
TO 100 100 100	539. 540. 541. 542.	Tobacco By-Products & Chem. Corp.  Trask, Arthur C., Co.  Trojan Powder Co.  Turner, Joseph & Co.	Louisville, Ky. Chicago, Ill. Allentown, Pa. Ridgefield, N. J.
To the to the	539. 540. 541. 542. 543.	Tobacco By-Products & Chem. Corp. Trask, Arthur C., Co. Trojan Powder Co. Turner, Joseph & Co. Uhe, George Co.	Louisville, Ky. Chicago, Ill. Allentown, Pa. Ridgefield, N. J. New York, N. Y.
To the the tree to	539. 540. 541. 542. 543.	Tobacco By-Products & Chem. Corp. Trask, Arthur C., Co. Trojan Powder Co. Turner, Joseph & Co. Uhe, George Co. Uhlich, Paul Co.	Louisville, Ky. Chicago, Ill. Allentown, Pa. Ridgefield, N. J. New York, N. Y. New York, N. Y. Log Appelor Celif
To the the tree to	539. 540. 541. 542. 543.	Thomas, Arthur H., Co. Thorocide, Inc. Thurston & Braidich Titanium Alloy Mfg. Co. Titanium Pigments Co. Tobacco By-Products & Chem. Corp. Trask, Arthur C., Co. Trojan Powder Co. Turner, Joseph & Co. Uhe, George Co. Uhlich, Paul Co. Union Oil Co.	Louisville, Ky. Chicago, Ill. Allentown, Pa. Ridgefield, N. J. New York, N. Y. New York, N. Y. Los Angeles, Calif.
TO THE COUNTY OF THE PARTY OF	539. 540. 541. 542. 543. 544. 545.	Tobacco By-Products & Chem. Corp. Trask, Arthur C., Co. Trojan Powder Co. Turner, Joseph & Co. Uhe, George Co. Uhlich, Paul Co. Union Oil Co. Union Smelting & Refining Co., Inc.	Louisville, Ky. Chicago, Ill. Allentown, Pa. Ridgefield, N. J. New York, N. Y. New York, N. Y. Los Angeles, Calif. Newark, N. J.
the training and the con-	539. 540. 541. 542. 543. 544.	Tobacco By-Products & Chem. Corp. Trask, Arthur C., Co. Trojan Powder Co. Turner, Joseph & Co. Uhe, George Co. Uhlich, Paul Co. Union Oil Co. Union Smelting & Refining Co., Inc. United Carbon Co.	Louisville, Ky. Chicago, Ill. Allentown, Pa. Ridgefield, N. J. New York, N. Y. New York, N. Y. Los Angeles, Calif. Newark, N. J. Charleston, W. Va.
The tree are not not any and are	539. 540. 541. 542. 543. 544. 545.	Union Smelting & Refining Co., Inc. United Carbon Co.	Louisville, Ky. Chicago, Ill. Allentown, Pa. Ridgefield, N. J. New York, N. Y. New York, N. Y. Los Angeles, Calif. Newark, N. J. Charleston, W. Va. Trenton, N. J. Newark, N. J.

		A Jdmana
No.	Name	Address
549.	U. S. Bronze Powder Works, Inc.	Chicago III
550.	U. S. Bronze Powder Works, Inc. U. S. Gypsum Co. U. S. Industrial Alcohol Co.	New York, N. Y
551.	U. S. Industrial Alcohol Co	New York N Y
552.	U. S. Industrial Chem. Co	Now Vork N V
553.	U. S. Phosphoric Prod. Corp	New York, N. Y
554.	U. S. Rubber Products, Inc.	New York, N. Y.
555.	U. S. Phosphoric Prod. Corp. U. S. Rubber Products, Inc. U. S. Smelting, Refining & Mining Co.	St. Louis, Mo.
556.	Utan Glisonite Co.	Chicago III
557.	van Allen, L. R. & Co.	Now York N V
558.	Van-Ameringen Haebier, Inc.	New York, N. Y.
559.	vanderbilt, R. 1., Co.	Jersey City, N. J.
560.	van Dyk & Co., Inc.	Chicago, Ill
561.	Van Schaack Bros. Chem. Co. Varcum Chem. Corp.	Niagara Falls, N. Y.
562.	Varcum Chem. Corp.	
563. 564.	Varcum Chem. Corp. Verley, Albert & Co. Verona Chem. Co. Victor Chem. Works	Newark, N. J.
565.	Verona Chem Works	
566.	Victor Chem. Works Virginia-Carolina Chem. Corp.	Richmond, Va.
567.	Virginia-Carolina Chem. Corp. Virginia Smelting Works	W. Norfolk, Va.
568.	Virginia Smelting Works	Pittsburgh, Pa.
570.	Vultex Chem. Co	Campriage, Mass.
571.	Vitro Mfg. Co. Vultex Chem. Co. Waldo, E. M. & F., Inc.	Nuirkirk, Mu.
572.	Waldo, E. M. & F., Inc. Wallerstein Co., Inc.	Nov. Vowl. N V
573.	Wallerstein Co., Inc. The Warner Chem. Co. Warwick Chem. Co. Warwick Chem. Co.	West Warwick R I
574.	Warwick Chem. Co	New York N Y
575.	Welch, Holme & Clark Co	Gloucester, N. J.
576.	Warwick Chem. Co. Welch, Holme & Clark Co. Welsbach & Co. Werk, M., Co.	Cincinnati, Ohio
577.	Werk, M., Co.	
578.		
579.	Westinghouse Elec. & Mig. Co	New York, N. Y.
580.		
581.	Wilches-Martin-Wilches Co.	New York, N. Y.
582. 583.		
584.		
585.		
586.		
587.		
588.	Wolf, Jacques & Co	
589.		
590.	Wood Flour, Inc. Wood Ridge Mfg. Co.	Wood Klage, N. J.
591.	Wood Ridge Mfg. Co. Wyodak Chem. Co. Young, J. S. & Co.	Uleveland, Unio
593.	Young, J. S. & Co	Now Vork N V
595.	Young, J. S. & Co. Zinsser, Wm. & Co.	Recolded N V
596.		
	ADDENDA	
597.	Borne-Scrymser Co	New York, N. Y.
598.	Hycar Corp.	Akron, O.
599.		Cleveland, O.

# WHERE TO BUY CHEMICALS OUTSIDE THE UNITED STATES

Argentina, Buenos Aires—M. Goetz, Rincón 332
Australia, Adelaide—Robert Bryce & Co., Pty., Ltd.,
73-75 Wakefield Street
——, Melbourne, C1—Robert Bryce & Co., Pty., Ltd.,
526 Little Bourke Street
———, Sydney—Robert Bryce & Co., Pty., Ltd., 188-190 Kent Street
Bolivia, La Paz—M. Romulo Vildoso, Calle Potosi 137
Brazil, Sao Paulo—Empresa Comercial Mercur Ltda.,
Caixa Postale 4232
Canada, Montreal—Chemicals, Ltd., 384 St. Paul St., W.
——, Toronto 2—Canada Colors & Chemicals, Ltd.,
1090 King St., West
, Vancouver, B. C.—Shanahan's Ltd., Foot of Campbell Avenue
Chile, Santiago—Bernardo Dornblatt, Clasificador 195B
Cuba, Havana—Raul Guillent,
215 Bank of Nova Scotia Bldg., P. O. Box 1133
England, London—Rex Campbell & Co., Ltd.,
7, Idol Lane, Eastcheap, E. C. 3
India, Calcutta—Kaisers Trading Company, 159 Lower Chitpore Rd.
Mexico, Mexico D. F.—R. Koestinger,
J. M. Velasco, 119, Insurgentes, Mixcoac
New Zealand, Wellington—Robert Bryce & Co., Pty., Ltd.,
19 Lower Tory Street
South Africa, Johannesburg—Philip Elzas & Co.,
Sweden, Huddinge—E. Landerholm
Switzerland, Zurich—Oswald E. Boll, Dufourstrasse 157
Uruguay, Montevideo—Compania Industrial Alfa, Lda., Porongos 2228
Venezuela, Caracas—A. G. Bulgaris, Apartado 1752



${f A}$	Adhesive—Continued
	Window Glass 20
Abrasive Paste, Dental417	Wood Joining 27
Wheel416	Adobe Preservative331
Wheel, Bonded416	Agar, Dissolving446
Wheel, Impregnant for416	Agate, Artificial550
Accroides, Substitute for555	Air Filter, Coating for
Acetaldehyde, Substitute for555	Raid Protection, Window536
Acetamide, Substitute for555	Aircraft Cleaner
Acetanilide, Substitute for555	Airship Fabric, Coating524
Acetic Acid, Substitute for555	Albumen, Substitute for556
Acid Wax Émulsion 86	Alcohol Resistant Finish319
Acne Lotion	Rubbing 70
Salve 76	Alfalfa Snout Beetle Poison 97
Acrawax Emulsion 84	Algae, Killing Spray Pond538
Acrylic Resins438	Alkalies, Substitutes for556
Activator, Nicotine Spray100	Alkyd Resins, Substitute for556
Adhesion Preventing (see also	Alloys
Anti-Stick)	Almond Oil, Substitute for556
of Rubber to Cloth, Increasing434	"Alperox," Substitute for557
Adhesive (see also Caulking, Ce-	Alum, Substitute for557
ment, Glue, Gum, Mucilage,	Aluminum Alloy, Sea Water Re-
ment, Glue, Gum, Mucilage, Paste, Putty and Seal)12, 17	sistant
Alkali Resistant	Anodizing204
Aluminum to Paper 29	Coating Iron230
Bitumen to Rubber 27	Coloring204, 205
Canvas to Wall 30	Coppering
Cellophane	Hydrate, Substitute for557
Celluloid	Oleate, Substitute for557
Chloroprene to Metal 28	Phosphate, Substitute for557
Cork to Metal 30	Powder, Substitute for557 Pre-Painting Treating of330
Envelope	Pre-raining Treating of330
Fiber Container	Protective Coating for225
Flexible Metal	Resinate, Substitute for557 Silicate, Substitute for557
Flypaper Ribbon	Silvering207
Laminating Luminous 27	Amethyst, Artificial550
Lithographer's 20	Ammonium Chloride, Substitute
Metal to Cork 30	for 55%
Mirror 22	Compounds, Substitute for557 Hydroxide, Substitute for557
Mirror	Hydroxide, Substitute for557
Paper to Glass 20	Lactate, Substitute for557
Plywood 19	Phosphate, Substitute for557
Polythene to Metal or Ceramic 28	Sulphamate, Substitute for558
Pressure327	Sulphate, Substitute for558
Pressure Sensitive 27	Sulphite, Substitute for558
Stiffening 27	Thiocyanate, Substitute for558
Tape Remover 77	Ammunition Primer430
Thermoplastic26, 437	Amyl Acetate, Substitute for558
Tissue Paper to Aluminum 29	Alcohol, Substitute for558
Transparent 18	Analgesic Salve
Vacuum 24	Aniline, Substitute for558
Water Insoluble	Animal Remedies111
Water Soluble 17	Anise Oil, Substitute for558
Wax 24	Annatto, Substitute for558
AT AT	5

Annealing Metal244	Beverages	25
Anodizing Aluminum204	Fluorescent15	٤ō
Ant IIII Destruction 101	Oranga	Š
Ant Hill Destruction	Orange Stabilizing Alcoholic S	) J
Poison8	Stabilizing Alcoholic	52
Repellent101	Tracer15	50
Repellent	Binders, Core24	12
Anti-Corrosion, Radiator529	Bird Food	ç
Anti-Dim Compounds536	Blackening Iron and Steel21	ıč
Anti-Fogging Compounds536	Black-Out Paint	20
Anti Energy 16 520	Diack-Out Faint	20
Anti-Freeze	Bleach, Disinfectant	18
Anti-Leak, Radiator529 Antidote, Universal Poison74	Fur	38
Antidote, Universal Poison 74	Laundry	14
Antimony. Substitute for558	Photographic34	
Lactate, Substitute for558	Wood Floor	
Oxide, Substitute for558	Blooching Animal Fiber 16	30
Antiseptic, Abrasion	Bleaching, Animal Fiber46 Benzoyl Peroxide18	70
Antiformin Type 79	Denzoyi Feroxide	57
Andiorini Lype	Bristles15	
Non-Alcoholic Iodine 79	Cotton	
Apparatus3	Fats	37
Apple Juice	Fruit	16
Apricot Kernel Oil, Substitute for .558	Horsehair18	
Aralac, Dveing	Laundry46	
Aralac, Dyeing		
Amoratic Waters 59	Oils	56
Aromatic Waters	Perborate	Jä
Artificial Leather Coating326 Asphalt, Artificial445	Peroxide	37
Asphalt, Artificial445	Silk457, 46	59
Increasing Softening Point of 445	Sulphur Dioxide16	30
Aspirin, Improved	Textile	),9
Aspirin, Improved	Textone50	
Astringent, Facial 45	Wool	30
Athlete's Foot Salve63, 76		
Aumete a root paive	Blood Clotter	('1
Atmete s Foot Barve	Blow-Fly Destroyer, Sheep11	12
	Blood Clotter  Blow-Fly Destroyer, Sheep11  Dressing, Sheep11	12
B	Blow-Fly Destroyer, Sheep	12
В	Blow-Fly Destroyer, Sheep	12
B Baby Powder 52	Blow-Fly Destroyer, Sheep	12 12 33 74
B Baby Powder 52	Blow-Fly Destroyer, Sheep	12 12 13 74
B Baby Powder 52	Blow-Fly Destroyer, Sheep	12 12 13 74
Baby Powder	Blow-Fly Destroyer, Sheep	12 12 13 14 13 14
Baby Powder	Blow-Fly Destroyer, Sheep       11         Dressing, Sheep       11         Blue Print, Glass       38         Sensitizer       37         Bluing Iron       21         Laundry       1         Laundry Tablet       46         Steel       21	12 12 74 13 14 13
Baby Powder	Blow-Fly Destroyer, Sheep	12 12 74 13 14 13 14 13
Baby Powder 52 Skin Oil 45 Bait, Artificial Cat Fish 540 Baking Powder 9 Balloon Fabric, Coating 524 Perbunan 435	Blow-Fly Destroyer, Sheep	12 12 74 13 14 13 14 13
B Baby Powder 52 Skin Oil 45 Bait, Artificial Cat Fish 540 Baking Powder 9 Balloon Fabric, Coating 524 Perbunan 435 Banana Leaf Spot Control 97	Blow-Fly Destroyer, Sheep       11         Dressing, Sheep       11         Blue Print, Glass       38         Sensitizer       37         Bluing Iron       21         Laundry       1         Laundry Tablet       46         Steel       21         Boat Plug Compound       22         Boiler Compounds       16, 58	12 12 13 14 13 14 13 14 13 14 13 14 13 14 14 14 14 14 14 14 14 14 14 14 14 14
B  Baby Powder	Blow-Fly Destroyer, Sheep       11         Dressing, Sheep       11         Blue Print, Glass       38         Sensitizer       37         Bluing Iron       21         Laundry       1         Laundry Tablet       46         Steel       21         Boat Plug Compound       2         Boiler Compounds       16,58         Treatments       52	12 74 13 14 13 14 13 14 13 14 13 14 14 15 16 16 16 16 16 16 16 16 16 16 16 16 16
B  Baby Powder	Blow-Fly Destroyer, Sheep       11         Dressing, Sheep       11         Blue Print, Glass       38         Sensitizer       37         Bluing Iron       21         Laundry       1         Laundry Tablet       46         Steel       21         Boat Plug Compound       2         Boiler Compounds       16,58         Treatments       52         Tube Cleaner       48	12 12 13 14 13 14 13 14 13 14 13 14 13 14 13 14 13 14 14 14 14 15 16 16 16 16 16 16 16 16 16 16 16 16 16
B  Baby Powder	Blow-Fly Destroyer, Sheep       11         Dressing, Sheep       11         Blue Print, Glass       38         Sensitizer       37         Bluing Iron       21         Laundry       1         Laundry Tablet       46         Steel       21         Boat Plug Compound       2         Boiler Compounds       16,58         Treatments       55         Tube Cleaner       48         Bonbon Coating, Maple       12	12 74 13 14 13 14 13 14 13 14 13 14 13 14 14 14 14 14 14 14 14 14 14 14 14 14
B  Baby Powder	Blow-Fly Destroyer, Sheep       11         Dressing, Sheep       11         Blue Print, Glass       38         Sensitizer       37         Bluing Iron       21         Laundry       1         Laundry Tablet       46         Steel       21         Boat Plug Compound       2         Boiler Compounds       16, 58         Treatments       52         Tube Cleaner       48         Bonbon Coating, Maple       12         Braid Flexibilizer       50	12 12 13 14 13 14 13 14 13 14 13 14 13 14 13 14 13 14 13 14 14 15 16 16 16 16 16 16 16 16 16 16 16 16 16
B  Baby Powder 52 Skin Oil 45 Bait, Artificial Cat Fish 540 Baking Powder 9 Balloon Fabric, Coating 524 Perbunan 435 Banana Leaf Spot Control 97 Bandage, Waterproof 77 Bath Powder, Foaming 52 Salts 51 Bating Hides 153 Battery Electrolyte 532	Blow-Fly Destroyer, Sheep       11         Dressing, Sheep       11         Blue Print, Glass       38         Sensitizer       37         Bluing Iron       21         Laundry       1         Laundry Tablet       46         Steel       21         Boat Plug Compound       2         Boiler Compounds       16, 58         Treatments       52         Tube Cleaner       48         Bonbon Coating, Maple       12         Braid Flexibilizer       50         Brake Block Composition       44	12 74 13 14 13 14 14 14 14
B  Baby Powder 52 Skin Oil 45 Bait, Artificial Cat Fish 540 Baking Powder 9 Balloon Fabric, Coating 524 Perbunan 435 Banana Leaf Spot Control 97 Bandage, Waterproof 77 Bath Powder, Foaming 52 Salts 51 Bating Hides 153 Battery Electrolyte 532	Blow-Fly Destroyer, Sheep       11         Dressing, Sheep       13         Blue Print, Glass       38         Sensitizer       35         Bluing Iron       21         Laundry       1         Laundry Tablet       46         Steel       21         Boat Plug Compound       2         Boiler Compounds       16, 55         Treatments       52         Tube Cleaner       48         Bonbon Coating, Maple       12         Braid Flexibilizer       50         Brake Block Composition       44         Lining Impregnant       44	12 12 13 14 13 14 14 15 14 14 15
B  Baby Powder 52 Skin Oil 45 Bait, Artificial Cat Fish 540 Baking Powder 9 Balloon Fabric, Coating 524 Perbunan 435 Banana Leaf Spot Control 97 Bandage, Waterproof 77 Bath Powder, Foaming 52 Salts 51 Bating Hides 153 Battery Electrolyte 532	Blow-Fly Destroyer, Sheep       11         Dressing, Sheep       11         Blue Print, Glass       38         Sensitizer       37         Bluing Iron       21         Laundry       1         Laundry Tablet       46         Steel       21         Boat Plug Compound       2         Boiler Compounds       16,55         Treatments       52         Tube Cleaner       48         Bonbon Coating, Maple       12         Braid Flexibilizer       50         Brake Block Composition       44         Lining Impregnant       44         Brass, Corrosion Proofing       23	12 12 12 13 14 13 14 14 15 13 14 14 15 13 14 15 16 16 17 17 17 17 17 17 17 17 17 17 17 17 17
B  Baby Powder 52 Skin Oil 45 Bait, Artificial Cat Fish 540 Baking Powder 9 Balloon Fabric, Coating 524 Perbunan 435 Banana Leaf Spot Control 97 Bandage, Waterproof 77 Bath Powder, Foaming 52 Salts 51 Bating Hides 153 Battery Electrolyte 532 Beakers, Wax 542 Bearing (see Metal)	Blow-Fly Destroyer, Sheep       11         Dressing, Sheep       11         Blue Print, Glass       38         Sensitizer       37         Bluing Iron       21         Laundry       1         Laundry Tablet       46         Steel       21         Boat Plug Compound       2         Boiler Compounds       16,55         Treatments       52         Tube Cleaner       48         Bonbon Coating, Maple       12         Braid Flexibilizer       50         Brake Block Composition       44         Lining Impregnant       44         Brass, Corrosion Proofing       23	12 12 12 13 14 13 14 14 15 13 14 14 15 13 14 15 16 16 17 17 17 17 17 17 17 17 17 17 17 17 17
B  Baby Powder 52 Skin Oil 45 Bait, Artificial Cat Fish 540 Baking Powder 9 Balloon Fabric, Coating 524 Perbunan 435 Banana Leaf Spot Control 97 Bandage, Waterproof 77 Bath Powder, Foaming 52 Salts 51 Bating Hides 153 Battery Electrolyte 532 Beakers, Wax 542 Bearing (see Metal)	Blow-Fly Destroyer, Sheep       11         Dressing, Sheep       11         Blue Print, Glass       38         Sensitizer       37         Bluing Iron       21         Laundry       1         Laundry Tablet       46         Steel       21         Boat Plug Compound       2         Boiler Compounds       16,55         Treatments       52         Tube Cleaner       48         Bonbon Coating, Maple       12         Braid Flexibilizer       50         Brake Block Composition       44         Lining Impregnant       44         Brass, Corrosion Proofing       23	12 12 12 13 14 13 14 14 15 13 14 14 15 13 14 15 16 16 17 17 17 17 17 17 17 17 17 17 17 17 17
Baby Powder 52 Skin Oil 45 Bait, Artificial Cat Fish 540 Baking Powder 9 Balloon Fabric, Coating 524 Perbunan 435 Banana Leaf Spot Control 97 Bandage, Waterproof 77 Bath Powder, Foaming 52 Salts 51 Bating Hides 153 Battery Electrolyte 532 Beakers, Wax 542 Bearing (see Metal) Alloy 251 Porous Metal 250	Blow-Fly Destroyer, Sheep   11	12 $12$ $13$ $14$ $14$ $15$ $14$ $15$ $14$ $15$ $14$ $15$ $14$ $15$ $15$ $14$ $15$ $15$ $15$ $15$ $15$ $15$ $15$ $15$
B  Baby Powder	Blow-Fly Destroyer, Sheep   11	12 $12$ $13$ $14$ $14$ $15$ $14$ $15$ $14$ $15$ $14$ $15$ $14$ $15$ $15$ $15$ $15$ $15$ $15$ $15$ $15$
B  Baby Powder 52 Skin Oil 45 Bait, Artificial Cat Fish 540 Baking Powder 9 Balloon Fabric, Coating 524 Perbunan 435 Banana Leaf Spot Control 97 Bandage, Waterproof 77 Bath Powder, Foaming 52 Salts 51 Bating Hides 153 Battery Electrolyte 532 Beakers, Wax 542 Bearing (see Metal) Alloy 251 Porous Metal 250 Bedbug Exterminator 8, 108 Beeswax, Substitute for 558	Blow-Fly Destroyer, Sheep   11	128374 $138374$ $13839$ $13839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14839$ $14$
B  Baby Powder 52 Skin Oil 45 Bait, Artificial Cat Fish 540 Baking Powder 9 Balloon Fabric, Coating 524 Perbunan 435 Banana Leaf Spot Control 97 Bandage, Waterproof 77 Bath Powder, Foaming 52 Salts 51 Bating Hides 153 Battery Electrolyte 532 Beakers, Wax 542 Bearing (see Metal) Alloy 251 Porous Metal 250 Bedbug Exterminator 8, 108 Beeswax, Substitute for 558	Blow-Fly Destroyer, Sheep   11	12 12 12 13 14 13 14 14 15 13 14 14 15 16 16 17 18 18 18 18 18 18 18 18 18 18 18 18 18
Baby Powder 52 Skin Oil 45 Bait, Artificial Cat Fish 540 Baking Powder 9 Balloon Fabric, Coating 524 Perbunan 435 Banana Leaf Spot Control 97 Bandage, Waterproof 77 Bath Powder, Foaming 52 Salts 51 Bating Hides 153 Battery Electrolyte 532 Beakers, Wax 542 Bearing (see Metal) Alloy 251 Porous Metal 250 Bedbug Exterminator 8, 108 Beeswax, Substitute for 558 Bell Metal 251 Bell Metal 251 Belladonna, Substitute for 558	Blow-Fly Destroyer, Sheep   11	12 12 12 13 14 13 14 14 15 13 14 14 15 16 16 17 18 18 18 18 18 18 18 18 18 18 18 18 18
Baby Powder 52 Skin Oil 45 Bait, Artificial Cat Fish 540 Baking Powder 9 Balloon Fabric, Coating 524 Perbunan 435 Banana Leaf Spot Control 97 Bandage, Waterproof 77 Bath Powder, Foaming 52 Salts 51 Bating Hides 153 Battery Electrolyte 532 Beakers, Wax 542 Bearing (see Metal) Alloy 251 Porous Metal 250 Bedbug Exterminator 8, 108 Beeswax, Substitute for 558 Bell Metal 251 Bell Metal 251 Belladonna, Substitute for 558	Blow-Fly Destroyer, Sheep   11	12 12 12 13 14 13 14 14 15 13 14 14 15 16 16 17 18 18 18 18 18 18 18 18 18 18 18 18 18
B Baby Powder 52 Skin Oil 45 Bait, Artificial Cat Fish 540 Baking Powder 9 Balloon Fabric, Coating 524 Perbunan 435 Banana Leaf Spot Control 97 Bandage, Waterproof 77 Bath Powder, Foaming 52 Salts 51 Bating Hides 153 Battery Electrolyte 532 Beakers, Wax 542 Bearing (see Metal) Alloy 251 Porous Metal 250 Bedbug Exterminator 8, 108 Beeswax, Substitute for 558 Bell Metal 251 Belladonna, Substitute for 558 Belt Dressing, Anti-Static 184	Blow-Fly Destroyer, Sheep   11	12121121121121121121121212121212121212
B Baby Powder 52 Skin Oil 45 Bait, Artificial Cat Fish 540 Baking Powder 9 Balloon Fabric, Coating 524 Perbunan 435 Banana Leaf Spot Control 97 Bandage, Waterproof 77 Bath Powder, Foaming 52 Salts 51 Bating Hides 153 Battery Electrolyte 532 Beakers, Wax 542 Bearing (see Metal) Alloy 251 Porous Metal 250 Bedbug Exterminator 8, 108 Beeswax, Substitute for 558 Bell Metal 251 Belladonna, Substitute for 558 Belt Dressing, Anti-Static 184	Blow-Fly Destroyer, Sheep   11	12121121121121121121121212121212121212
Baby Powder 52 Skin Oil 45 Bait, Artificial Cat Fish 540 Baking Powder 9 Balloon Fabric, Coating 524 Perbunan 435 Banana Leaf Spot Control 97 Bandage, Waterproof 77 Bath Powder, Foaming 52 Salts 51 Bating Hides 153 Battery Electrolyte 532 Beakers, Wax 542 Bearing (see Metal) Alloy 251 Porous Metal 250 Bedbug Exterminator 8, 108 Beeswax, Substitute for 558 Bell Metal 251 Belladonna, Substitute for 558 Belt Dressing, Anti-Static 184 Edge Coloring 157 Bentonite, Substitute for 558	Blow-Fly Destroyer, Sheep   11	12121121121121121121121212121212121212
Baby Powder 52 Skin Oil 45 Bait, Artificial Cat Fish 540 Baking Powder 9 Balloon Fabric, Coating 524 Perbunan 435 Banana Leaf Spot Control 97 Bandage, Waterproof 77 Bath Powder, Foaming 52 Salts 51 Bating Hides 153 Battery Electrolyte 532 Beakers, Wax 542 Beakers, Wax 542 Bearing (see Metal) Alloy 251 Porous Metal 250 Bedbug Exterminator 8, 108 Bedbug Exterminator 8, 108 Bell Metal 251 Belladonna, Substitute for 558 Belt Dressing, Anti-Static 184 Edge Coloring 157 Bentonite, Substitute for 558 Benzaldehyde, Substitute for 559	Blow-Fly Destroyer, Sheep   11	12121212121212121212121212121212121212
Baby Powder 52 Skin Oil 45 Bait, Artificial Cat Fish 540 Baking Powder 9 Balloon Fabric, Coating 524 Perbunan 435 Banana Leaf Spot Control 97 Bandage, Waterproof 77 Bath Powder, Foaming 52 Salts 51 Bating Hides 153 Battery Electrolyte 532 Beakers, Wax 542 Beakers, Wax 542 Bearing (see Metal) Alloy 251 Porous Metal 250 Bedbug Exterminator 8, 108 Beeswax, Substitute for 558 Bell Metal 251 Belladonna, Substitute for 558 Belt Dressing, Anti-Static 184 Edge Coloring 157 Bentonite, Substitute for 558 Benzaldehyde, Substitute for 559 Benzene Sulphonic Acid, Substi-	Blow-Fly Destroyer, Sheep   11	12121212121212121212121212121212121212
Baby Powder 52 Skin Oil 45 Bait, Artificial Cat Fish 540 Baking Powder 9 Balloon Fabric, Coating 524 Perbunan 435 Banana Leaf Spot Control 97 Bath Powder, Foaming 52 Salts 51 Bating Hides 153 Battery Electrolyte 532 Beakers, Wax 542 Bearing (see Metal) Alloy 251 Porous Metal 250 Bedbug Exterminator 8, 108 Beeswax, Substitute for 558 Bell Metal 251 Bell Metal 251 Bell Beladonna, Substitute for 558 Belt Dressing, Anti-Static 184 Edge Coloring 157 Bentonite, Substitute for 558 Benzaldehyde, Substitute for 559 Benzene Sulphonic Acid, Substitute for 559 Benzene Sulphonic Acid, Substitute for 559	Blow-Fly Destroyer, Sheep	12121121121121121121121212121212121212
Baby Powder 52 Skin Oil 45 Bait, Artificial Cat Fish 540 Baking Powder 9 Balloon Fabric, Coating 524 Perbunan 435 Banana Leaf Spot Control 97 Bandage, Waterproof 77 Bath Powder, Foaming 52 Salts 51 Bating Hides 153 Battery Electrolyte 532 Beakers, Wax 542 Beakers, Wax 542 Bearing (see Metal) Alloy 251 Porous Metal 250 Bedbug Exterminator 8, 108 Beeswax, Substitute for 558 Bell Metal 251 Belladonna, Substitute for 558 Belt Dressing, Anti-Static 184 Edge Coloring 157 Bentonite, Substitute for 558 Benzaldehyde, Substitute for 559 Benzene Sulphonic Acid, Substi-	Blow-Fly Destroyer, Sheep   11	12121121121121121121121121121212121212

Burnishing Baths, Iron212	Casein—Continued
Baths, Steel212	Solution307, 404
Butter, High-Melting131	Substitute for
Buttons, Dyeing543	Textile Fibers
	Casket Finishing319
C	Cast Iron, Soldering247
~	Casting Mold, Precious Metal242
Cable Coating, Electric310	Castor Oil, Substitute for560
Impregnating Compound442	Caterpillar Spray, Walnut100
Sheathing, Electric310	Cattle Feed, Molasses
Cacao Butter Substitute 75	Marker171
Cadmium Plating, Stripper for223	Caulking. See also Adhesive, Ce-
Cake, Macaroon Cup124	ment, Glue, Gum, Mucilage, Paste, Putty and Seal
Calamine Lotion	Apple Putty and Seal
Calcimine Coater301	Asphalt
Calcium Iodoxybenzoic Acid 80 Sulphide, Substitute for559	Cautions
Calculations 9	Comont Con also Adhesive Class
Calculations	Cement. See also Adhesive, Glue, Gum, Mucilage, Paste, Putty
Calico Finishing	and Seal
Calorizing Metals245	Cement. See Concrete
Camal's Hair Substitute for 559	Acid Proof
Camel's Hair, Substitute for559 Camouflage Paint288	Advertim 19
Camphor, Substitute for559	Aquarium 12 Asphalt Roofing 27
Oil, Substitute for559	Celluloid to Wood or Cloth 27
Cans, Coating for Beer270	Cellulose Acetate 27
Canary Food	Coating
Candelilla Wax Emulsion 84	Coating
Wax, Substitute for559	Dental 25
Candles 12	Floor Hardener 12
Candy Flavor Retention, Hard121	Furnace Patching192
Fruit119	Glass 29
Emit Telly 120 (	Glass or Metal28
Cane Sugar, Substitute for559	Heat Insulating190
Cannon Crackers 427 (	Household 31
Sponging Fluid	Hycar 26
Capric Acid, Substitute for559	Light Weight191
Capryl Alconol, Substitute for 339	Linoleum325
Caramel Base	Nitrocellulose
Sauce	Oil Well
Carbon Black, Colloidal	Photoengraving389
Dioxide, Substitute for559	Pipe Leak
Disulphide Fumigation101	Plastic Coating for284 Polyvinyl Chloride Coating 24
Paper, Fluorescent169	Personal 100
Paper Inks	Refractory
Paper, invisible writing103	Ruhhar 25
Remover, Engine	Rubber
Tetrachloride Substitute for 559	Shoe
Tetrachloride, Substitute for559 Carbonate Scale, Removing529	Slow Setting
"Carbonate Scale, itemoving	Sound Insulating190
"Carbowax," Substitute for559 Carburizing Steel245 Cardamom Oil, Substitute for559	Stone Table 28
Cardamom Oil Substitute for559	Stripfilm389
Carminative	Stripfilm
Carnauba Wax Emulsion 85	Thermosetting
Wax, Substitute for560	Vinyl Coating
Carob Gum, Substitute for560	Waterproof Glass 29
Carragheen, Substitute for560	Cereal. Dried Fruit
Carrot Inice	Cesspool Deodorant
Carroting, Fur	Cetyl Alcohol, Substitute for 560
Cascades, Pyrotechnic423	Chalk, Fluorescent
Casein, insolubilizing 10	Tailor's
Paint, Waterproof261	Charred Documents, Deciphering.338

Cheese, Caciocavallo	Clay, Substitute for
Cheddar	Colloidal, Substitute for562
Cream	Cleaner (see also Spot Removers) 13
Italian	Abrasive451
Limburger132	Acid Emulsion550
Molding136	After Buffing492
Pecorino Romano	Aircraft494
Processed	Appliance490
Provole	Auto Paste400
Provolone	Auto Polish and Cleaner398
Relish132	Beer Pipe
Sausage	Boiler Tube489
Sharp	Bottle480
Sheen Wilk	Brass491
Smoked	Bronze
Spread, Processed132	Brush
"Supply"	Cannon494
Chemical Resistant Coating262	Chromic Acid480
Cherry Juice34	Cloth Shoe Top477
Kernel Oil, Substitute for560	Concrete Floor487
Laurel Water 52	Dairy Bottle
Chest Rub8	Dairy Utensil481
Chewing Gum	Denture
Activated Charcoal123	Dish
Base	Dog114
Chicken Chigger Control 103	Emulsion Base
Feather Mite Control103	Engine Carbon494
Feed106	Floor. See Floor Treatments
Reviver107	Furniture485
Scratch Grain106	Garage Floor487
Chigger Control100	Glass,
China Clay, Substitute for560	Grease
Wood Oil, Substitute for560	Grease and Dirt487
Chinch Bug Control 99	Hand
Chinese Blue, Substitute for561 Wax, Substitute for560	Household 13
Wax, Substitute for560	Industrial Hand451
Chloramine, Substitute for561	Jelly450 Kerosene-Oleic Acid-Benzol469
Chlorine, Substitute for561	Kerosene-Oleic Acid-Benzol469
Chloroform, Substitute for561	Leather Glove
Chlorophyll, Substitute for561	Magnesium
Chloropicrin, Substitute for561	Marble
Chlororubbers, Substitute for561	Mechanic's Hand
Chocolate Fudge Drink131	Metal
Cholesterol, Substitute for561	Metal Panel490
Chondrus, Substitute for561	Milk Pipe
Chrome Alum, Substitute for561	Oil
Orange, Substitute for561	Paint
Pickle	Paint Brush
Chromic Acid, Substitute for561	Painted Surface
Chromium Acetate, Substitute for .561	Photographic Negative389
Plating, Substitute for561	Photographic Tray
Sulphate, Substitute for561	Pipe 5
Cinnamon, Artificial143	Plater's
Substitute for561	Porcelain
Citral, Substitute for561	Porcelain Crucible
Citric Acid, Substitute for561, 562	Rifle
Citronella Oil, Substitute for562	Rno
Citrus Potato Leaf Hopper In-	Rug       477         Soak       488         Steel Plate       494
secticide	Steel Plate 404
Thrip Spray 97	Straw Hat
Clarification 4	Tin
Clarifying Powder, Fruit Juice146	Transparent Sheet450
The state of the s	

Cleaner—Continued	Coloring—Continued
Wall486	Temper213
Wall Paper 13	m:
Wall raper	Tin
Watch	Zinc
Waterless Hand451	Concrete. See Cement
Window	Coating
Windshield494	Floor Finish321
Wire488	Fluorescent 192 Porous Light 191
Woodwork	Porous Light
Cleaning Fluid. See Cleaner	Quick Setting191
Laboratory Glassware480	Surface Hardener192
Metal244	Condenser Electrolyte532
Nickel Alloy197	Container Coating, Food437
Rusty Instruments239	Container Coating, Food457
Desity Instruments	Coating, Wood or Metal263
Rusty Tools238	Compounding 3
Cleanser. See Cleaner	Paper Milk
Liquid Cosmetic 41	Coolant, Metal Cutting. See Cutting
Clove Oil, Substitute for562	Oil
Coal, Coloring532	Copper, Age Hardening250
Non-Dusting532	Coloring 9
Tar, Synthetic 74	Coloring
Coating. See Lacquer, Paint, Var-	Descaling253
nish	Etching
Water Resistant261	Hot Working250
G.1-14 Generalitate for	Manhahamata Calastituta for E69
Cobalt, Substitute for	Naphthenate, Substitute for 563
Chloride, Substitute for562	Oxide, Substitute for563
Cochineal, Substitute for562	Sulphate, Substitute for563
Cocktail, Tomato Juice 37	Core Binders242
Cocktail, Tomato Juice 37 Cocoa Butter Substitute 75	Cork, Substitute for563
Malt Powder 9	Corn Borer Spray, European 97
Powder, Sweet 9	Ointment
Cocoanut Oil, Substitute for .562, 563	Corrosion Prevention Coating237
Codling Moth Spray, Pear100	Preventive184
Codliver Oil Emulsion 75	Cosmetics 40
Ointment 68	Stockings 53 Cottonseed Oil Emulsion
Ointment         68           Substitute for         563           Colchicine Plant Emulsion         102	Cottonseed Oil Emulsion 87
Colchising Plant Emulsion 109	Cracked Heel Treatment, Horse116
Colloidal Insecticide 98	Crayon, Cattle Marking171
	Erasable181
Colors. See Dyeing	Fluorescent180
Basic Printing517	riuorescent
Fugitive Wool509	Glass172
Temperature Changing541	Laboratory Marking172
Coloring. See Dyeing, Staining	Marking 9 Soluble Textile 181
Aluminum204, 205	Soluble Textile
Aluminum Powder205	Textile Marking181
Belt Edges	Textile Marking181 Cream, Aluminum Chloride42
Brass	Antisentic 42
Brass, Black	Artificial Whipping
Bronze	Brushless Shaving7, 40, 58
Chromium210	Cleansing 2 Cold 41
Coal532	Cold 41
Copper	Cosmetic 40
Iron	Dermal41, 65
Two Dlock 179	Emolliant 41
Iron, Black	Emollient
Iron Blue Black219	Foundation 41
Lead	Train 55
Metals	Hair 55
Nickel	Honey41
Paint	Liquefying
Silver222	Liquid Cosmetic 41
Slides and Films367	Liquid Cosmetic 41 Neutralizers, Dairy 181
Steel	Non-Greasy Cold
Steel Blue220	"Nourishing" 41

620

Cream—Continued	Diacetone, Substitute for564
Powder	Diamond, Industrial, Substitute
Salt Cosmetic	for564 Diatomaceous Earth, Substitute
Vanishing	for
Vanishing         6, 42           Vitamin Cold         41	Diazo Printing
Creosote, Substitute for564	Dibutyl Phthalate, Substitute for327, 564, 565
Cresol Disinfectant, Saponified 78 Substitute for	Dichloramine, Substitute for565
Cresylic Acid, Substitute for564	Dichlorethylene, Substitute for565
Culture Medium, Drosophilia538	Dicresyl Carbonate, Substitute
Currency, Marking	for 565
Curry Powder, Indian143 Cutting Oil Base185	Die Casting Treatment, Mag-
Outling On Base	nesium
D	Dill Flavor
	Directions, Mixing 1
Dairy Utensil Cleaners481	Dishwashing Compounds478
Dandruff Treatment, Animal113	Disinfectant, Cresol8, 78 Poultry House105
Decalcomania, "Cellophane"310	Powder 79
Deciphering Charred Documents338	Seed
Decolorizing	Shoe 79
Degras, Substitute for564	Dissolving 4 Distemper. See Paint, Water
Degreaser, Leather	Dog Coat Dressing114
Metal	Ear Wax Treatment
Degreasing Compounds487	Foods
Metal         237           Dehairing, Hide         156	Remedies113, 114
Delusterant, Hosiery	Wash114 Dope. See Lacquer
Demulsifier, Petroleum 94	Doughnut Glaze, Silver123
Dental Alloy252	Dressings, Salad
Hydrocolloid446 Impression Hydrocolloid446	Drier, Paint
Investment553	Drilling Fluid, Well
Mold. Refractory	Dry Cell Electrolyte
Paste, Abrasive	Cleaning (see Stain Removers) .477 Cleaning Fluid (see also
Waxes	Cleaning Fluid (see also
Denture Alloy	Cleaner)
Cleaner 60	Dubbing, Leather
Plastic	Dyes, Aniline, Substitute for565
Powder	Identification of
Hygienic	Logwood Speck506
Perspiration 51	Oxidizing Bath, Vat
Spray 8	Reducing Bath, Vat507
Depilatories	Soap. Hair 57
Derris, Substitute for	Stain Solvent
Descaling Copper253	Dyeing. See Coloring, Staining
Metal243	Aluminum
Stainless Steel	Black-Out Cloth
Detergents. See Cleaners	Bristles
Degreasing487	Glove Leather
Detonator, Primary430	Horsehair
Developer, Photographic 16 Dextrin, Substitute for 564	Ivory Button
Dextrose, Substitute for	Khaki 508   Synthetic Wool 508
Dhobie Itch Ointment 68	Vat Color

${f E}$	Emulsion—Continued
	Orthophenylphenol 79
Earache Remedy, Animal113	Paint304
Ear Drops	Paper Sizing 336
Mange Treatment, Animal114	Paper Sizing
Mange Headment, Ammai14	Dissolute Oil 207
Treatment, "Swimming-Pool" 70	Piccolyte-Oil307
Eczema Ointment, Embalmers' 80	Pine-Needle Oil
Treatment, Animal114	Pine Oil 87
Eggs, Removing Gloss From108	Plant Growth 86
Eggshells, Removing148	Polish396
Electric Contact Alloy249, 250	Polyvinyl 89
There Allers 250	Polyvinyl
Fuse Alloy	Resin-Wax 90
Insulation. See Insulation	Resin-wax
Resistors530	Salt Stable 87
Electroplating. See Plating	Santowax 84
Electropolishing Copper236	Sesame Oil 88
Embalming Fluid 79	Shellac
Emerald, Artificial549	Soluble Oil. See Soluble Oil
Emulaifor 91	Sulfanilamide 67
Emulsifier 91 Lacquer 93	Sulfathiazole
Lacquer	Synthetic Resin 89
Rosin Soap 90	Synthetic Resin
Emulsion 84	Synthetic Wax 84
Acid Cleaning450	Tetralin 91
Acid Pine Oil 89	Toluol87, 88
Acid Stable85, 87	Vinyl Resin 89
Acid Wax	Waterproofing 91
Acrawax 84	Wax
Agricultural86	Wax-Resin 90
Amyl Acetate 87	Enamel. See also Paint
Amyl Acetate	Architectural297
Anise Uii	Automobile
"Aquaplex"	Automobile
Anise Oil 88 "Aquaplex" 306 Benzene 89	Flat
Renzvi Benzoate	Floor
Breaking Petroleum 94	Gloss300
Candelilla Wax84, 404 Carnauba Wax85, 396, 403, 404	Insulating
Carnauha Wax85, 396, 403, 404	Nail. See Lacquer, Finger Nail
Castor Oil	Naval White Inside274
Cleaning	Non-Yellowing296
Cleaning Race 91	Semi-Gloss303
Codliver Oil	Synthetic 297
Colchicine	White
Copper Naphthenate	Engraving, Photo375
Copper Naphthenate	Enteric Coating
Core Binder242	Enteric Coating
Cottonseed Oil 87	Ephedrine Spray
Cumar 89	Eradicator, Ink
Cutting Oil. See Cutting Oil	Eraser, Rubber
Dammar165	Essential Oils, Spice
Die Lubricant 91	Hitch Stainless Steel
Disinfectant 79	Etching Brass
Elemi 90	Bronze377
Ester Gum-Oil305	Electrolytic
Flexalyn	Glass380
Flexalyli 95	Inconel202
Fruit Coating85	Intaglio375
Glass Wool Coating523	Lead
Hard Water Stable 87	Lead
Kerosene-Pine Oil 88	Magnesium
Lacquer 91	Metals
Lime Stable 88	Molybdenum378
Metal Cleaning489	Monel
Metal Protective	Name Plate
Mineral Oil	Nickel
Nitrocellulose 92	Nickel Plating
Oil98, 396	Nickel Plating
UII	A ALOUGIAGOIA MALAGORA DE ALTO CONTROL DE LA

Etching-Continued	Firebrick, Insulating190
Plastic	Fireproof Plaster332
Reagents	Fireproofing
Relief	Canvas 15
Resist	Light Fabrics
Silver	Paper
Stainless Steel379	Straw
Stainless Steel Color225	Wood
Steel	Fixing Bath, Photographic 16
Zine Engraving 225	Flameproofing. See Fireproofing
Zinc Engraving	Flare, Distress
Ethyl Acetate, Substitute for565	Illuminant
Alcohol, Substitute for566	Illuminant
Cellulose Film327	Flash Lamp, Photo395
Cellulose Plastic438	Flashlight Powder395
Experimentation	Flavor, Imitation Raspberry 33
Explosives429	Non-Alcoholic 33
Mining430	Orange 33
Safety	Pickle143 Retention, Hard Candy121
Eye Drops	Vanilla (Artificial) 9
Lotion	Vanilla Bean
1001011	Flock Finishing322
${f F}$	Flock Finishing322 Floor Cleaners. See Floor Treat-
Fabrics, Doubled526	ments
Face Powders 46	Coverings, Cleaning. See Floor
Facial Astringent 45	Treatments
Farm Specialties	Hardener192
Fat Liquor, Hide	Oil
Feather, Numida Effect on158 Preservative	Treatments
Feed, Chicken	Wax. See Polishes
_ Dog	Flooring Base446
Felt. Insectproof	Flower Pots, Pyrotechnic423
Fence Post, Preserving331 Ferrotype Polish394	Fluorescent Animals
Ferrotype Polish	Beverage
Fertilizer, Cheap118	Cellophane336
Conservatory	Chalk
Garden	Concrete
Retting525	Documents
Fiberboard, Compressed446	Finger Prints394
Waterproofing 14	Flag
Figuring Proportions 2	Food
Filler Crack	Gems550
Sho(	Hair
Film, Coloring	Ink
Ethyl Cellulose	Lamp Coatings
Stripping Gelatin389	Leather
Filtering 4	Nail Lacquer 50
Finger Waving, Hair 56	Paint
Fingerprint Powder, Fluorescent552	Paper336
Fingerprinting, Photographic394 Fining Powder, Fruit Juice146	Plaster
Fining Powder, Fruit Juice146	Powders
Fire Crackers	Powders, Improving Life of 294
Gerb Starting423	Screen
Kindler 15	Smoke
Pyrotechnic Port419, 420, 421	Soap
Pyrotechnic Starting419	Wood
Smokeless Tableau421	Fluorine, Substitute for566
	A CONTRACTOR OF THE PROPERTY O

Fluorspar, Substitute for566	G
Flushing Oil, Crankcase185	Œ
Flux, Aluminum247	Galvanized Iron, Pre-Painting
Arc Welding247	Treating of
Brazing247	Iron, Primer for266 Garden Fertilizer116
Cast Iron Welding248	
Copper Soldering248 Hard Metal Soldering246	Specialties 95
Magnesium248	Gargle, Throat 60 Garnet, Artificial
Non-Acid	Gas Protection, War534
Non-Oxidizing248	Seal, Temporary532
Soldering	Seal, Temporary532 Gasket Grease186
Steel Brazing248	Neoprene445
Welding	Paste
Fly Bait, Walnut Husk100	Gasoline, Syrupy
Lure, Fruit	Gelatin Film, Stripping389 Gems, Artificial548
Preparations	Geranium Oil, Synthetic 53
Sprays 8	Gerbs, Pyrotechnic
Foil, Improved Tin251	Germicidal Base
Synthetic310	Germicide, Cesspool
Transfer310	0il
Transparent	Glace, Doughnut
Food, Fluorescent	Glass, Etching380
Tagging	Flux, Acid Resisting188
Tracer	Frosting
Foot Powder 7	Infra-Red Absorbing189
Formaldehyde Deodorant 79	Luminescent309
Substitute for	Scratch Remover
Foundry Core Binder242	Silver Plating
Sand Binder	Glaze, Decorative Glassware189
Fountains, Pyrotechnic	Transparent Red189
Glass309	Glazing Brick189
Fruit Bars, Dried145	Fur
Cereal, Dried146	Thread
Coating Emulsion 85	Gloss on
Coating Wax397	Gluconic Acid, Substitute for566
Hormone for Seedless102	Glucose, Substitute for566
Juices         33           Juices, Blended         35	Glue (see also Adhesive, Caulking,
Preservation146	Cement, Gum, Mucilage, Paste,
Preserve Thickener146	Putty and Seal)
Purée, Ice Cream126	Bindery
Sulphured146	Bookbinders         18           Bottle Labelling         21
Fudge Icing	Casein
	Enamel, Etching383
Funigating Food	Flexible
Fungus Destroyer	Insolubilizing 18
Carroting	Machine
Conditioner163	Non-Warp 22
Glazing	Plywood
Gloss	Purifying
Lubricant	Substitute for
Lustering         163           Non-Curling         164	Tablet
Softener163	Tightwrap 22
Softening Dyed	Tube 21
Fuse, Electric	Gluten, Substitute for566
Railway421	Glycerin, Substitute for566, 567

Glyceryl Chlorhydrin, Substitute for	"Halowax," Substitute for       568         Hand Lotion. See Lotion, Hand       186         Hardening Copper, Age       250         Harness Oil       186         Hat Conditioner       527         Hay Fever Treatment       71         Heat Generating Salts       56         Treating, Metal       244, 245         Heating       3         Mixture, Food Container       539         Hemostatic       77         Hiccup Treatment       71         Hide Dehairing       156         Honey Oil, Paint       317         Horn, Dyeing       545         Horse Gall Treatment       116         Intestinal Parasite Remedy       116         Liniment       116         Remedies       116
Grassnopper Poison 98	Remedies
Transparent Lubricant	Horsehair, Bleaching
Grease-Proof Compound263	Hydrogen, Substitute for568 Peroxide, Substitute for568, 569
Grinding 4	Peroxide, Substitute for568, 569
	Hydroquinone, Substitute for569 Hydroxycitronellal, Substitute for.569
Cement. Glue. Mucilage. Paste.	Hypernic, Substitute for569
Putty and Seal	Hypo Eliminator
Arabic Solution166	Hypochlorite Deodorant 78
Arabic, Substitute for567	
Benzoin, Substitute for567 Chewing123	I
Chewing	Ice Cream, Fruit Purée for126
Chewing       123         Envelope       21         Karaya, Substitute for       567	Ice Cream, Fruit Purée for126 Milk Chocolate129
Chewing       123         Envelope       21         Karaya, Substitute for       567         Locust Bean, Substitute for       567	Ice Cream, Fruit Purée for       126         Milk Chocolate       129         Mixes for       129
Chewing	Ice Cream, Fruit Purée for
Chewing	Ice Cream, Fruit Purée for       126         Milk Chocolate       129         Mixes for       129         Iceland Moss, Substitute for       569         Icing, Butter Cream       126         Cream-Type       125
Chewing	Ice Cream, Fruit Purée for       126         Milk Chocolate       129         Mixes for       129         Iceland Moss, Substitute for       569         Icing, Butter Cream       126         Cream-Type       125         Fudge       122
Chewing       123         Envelope       21         Karaya, Substitute for       567         Locust Bean, Substitute for       567         Solution       170         Tragacanth, Substitute for       568         Water Dispersible, Substitute for       568         Gun Lubricant       11	Ice Cream, Fruit Purée for       126         Milk Chocolate       129         Mixes for       129         Iceland Moss, Substitute for       569         Icing, Butter Cream       126         Cream-Type       125         Fudge       122         Marshmallow Cake       125
Chewing       123         Envelope       21         Karaya, Substitute for       567         Locust Bean, Substitute for       567         Solution       170         Tragacanth, Substitute for       568         Water Dispersible, Substitute for       568         Gun Lubricant       11         Recoil Fluid       537	Ice Cream, Fruit Purée for       126         Milk Chocolate       129         Mixes for       129         Iceland Moss, Substitute for       569         Icing, Butter Cream       126         Cream-Type       125         Fudge       122         Marshmallow Cake       125         Impetigo Lotion       65         Incendiary Bomb Extinguishers       536
Chewing	Ice Cream, Fruit Purée for       126         Milk Chocolate       129         Mixes for       129         Iceland Moss, Substitute for       569         Icing, Butter Cream       126         Cream-Type       125         Fudge       122         Marshmallow Cake       125         Impetigo Lotion       65         Incendiary Bomb Extinguishers       536         Indigo, Substitute for       569
Chewing       123         Envelope       21         Karaya, Substitute for       567         Locust Bean, Substitute for       567         Solution       170         Tragacanth, Substitute for       568         Water Dispersible, Substitute for       568         Gun Lubricant       11         Recoil Fluid       537         Gunpowder, Smokeless, Flashless       430         Gut, Substitute for       568         Gutta-Percha, Substitute for       568	Ice Cream, Fruit Purée for       126         Milk Chocolate       129         Mixes for       129         Iceland Moss, Substitute for       569         Icing, Butter Cream       126         Cream-Type       125         Fudge       122         Marshmallow Cake       125         Impetigo Lotion       65         Incendiary Bomb Extinguishers       536         Indigo, Substitute for       569         Indol, Substitute for       569
Chewing	Ice Cream, Fruit Purée for       126         Milk Chocolate       129         Mixes for       129         Iceland Moss, Substitute for       569         Icing, Butter Cream       126         Cream-Type       125         Fudge       122         Marshmallow Cake       125         Impetigo Lotion       65         Incendiary Bomb Extinguishers       536         Indigo, Substitute for       569         Indol, Substitute for       569         Infra-Red Absorbing Glass       189
Chewing       123         Envelope       21         Karaya, Substitute for       567         Locust Bean, Substitute for       567         Solution       170         Tragacanth, Substitute for       568         Water Dispersible, Substitute for       568         Gun Lubricant       11         Recoil Fluid       537         Gunpowder, Smokeless, Flashless       430         Gut, Substitute for       568         Gutta-Percha, Substitute for       568	Ice Cream, Fruit Purée for       126         Milk Chocolate       129         Mixes for       129         Iceland Moss, Substitute for       569         Icing, Butter Cream       126         Cream-Type       125         Fudge       122         Marshmallow Cake       125         Impetigo Lotion       65         Incendiary Bomb Extinguishers       536         Indigo, Substitute for       569         Indol, Substitute for       569         Infra-Red Absorbing Glass       189         Infusorial Earth, Substitute for       569
Chewing       123         Envelope       21         Karaya, Substitute for       567         Locust Bean, Substitute for       568         Solution       170         Tragacanth, Substitute for       568         Water Dispersible, Substitute for       568         Gun Lubricant       11         Recoil Fluid       537         Gunpowder, Smokeless, Flashless       430         Gut, Substitute for       568         Gutta-Percha, Substitute for       568         Gypsy Moth Spray       97	Ice Cream, Fruit Purée for       126         Milk Chocolate       129         Mixes for       129         Iceland Moss, Substitute for       569         Icing, Butter Cream       126         Cream-Type       125         Fudge       122         Marshmallow Cake       125         Impetigo Lotion       65         Incendiary Bomb Extinguishers       536         Indigo, Substitute for       569         Indol, Substitute for       569         Infra-Red Absorbing Glass       189         Ingredients, Quality of       1         Inhibitor, Metal Corrosion       239
Chewing       123         Envelope       21         Karaya, Substitute for       567         Locust Bean, Substitute for       567         Solution       170         Tragacanth, Substitute for       568         Water Dispersible, Substitute for       568         Gun Lubricant       11         Recoil Fluid       537         Gunpowder, Smokeless, Flashless       430         Gut, Substitute for       568         Gypsy Moth Spray       97         H       Hair, Bleaching Animal       158         Cream       55	Ice Cream, Fruit Purée for       126         Milk Chocolate       129         Mixes for       129         Iceland Moss, Substitute for       569         Icing, Butter Cream       126         Cream-Type       125         Fudge       122         Marshmallow Cake       125         Impetigo Lotion       65         Incendiary Bomb Extinguishers       536         Indigo, Substitute for       569         Infosorial Earth, Substitute for       569         Ingredients, Quality of       1         Inhibitor, Metal Corrosion       239         Polymerization       436
Chewing       123         Envelope       21         Karaya, Substitute for       567         Locust Bean, Substitute for       567         Solution       170         Tragacanth, Substitute for       568         Water Dispersible, Substitute for       568         Gun Lubricant       11         Recoil Fluid       537         Gunpowder, Smokeless, Flashless       430         Gut, Substitute for       568         Gutta-Percha, Substitute for       568         Gypsy Moth Spray       97         H       Hair, Bleaching Animal       158         Cream       55         Dressing       41	Ice Cream, Fruit Purée for
Chewing       123         Envelope       21         Karaya, Substitute for       567         Locust Bean, Substitute for       567         Solution       170         Tragacanth, Substitute for       568         Water Dispersible, Substitute for       568         Gun Lubricant       11         Recoil Fluid       537         Gunpowder, Smokeless, Flashless       430         Gut, Substitute for       568         Gutta-Percha, Substitute for       568         Gypsy Moth Spray       97         H       Hair, Bleaching Animal       158         Cream       55         Dressing       41	Ice Cream, Fruit Purée for
Chewing       123         Envelope       21         Karaya, Substitute for       567         Locust Bean, Substitute for       568         Solution       170         Tragacanth, Substitute for       568         Water Dispersible, Substitute for       568         Gun Lubricant       11         Recoil Fluid       537         Gunpowder, Smokeless, Flashless       430         Gut, Substitute for       568         Gutta-Percha, Substitute for       568         Gypsy Moth Spray       97         H       Hair, Bleaching Animal       158         Cream       55         Dressing       41         Dye       57         Dye, Removing       57	Ice Cream, Fruit Purée for       126         Milk Chocolate       129         Mixes for       129         Iceland Moss, Substitute for       569         Icing, Butter Cream       126         Cream-Type       125         Fudge       122         Marshmallow Cake       125         Impetigo Lotion       65         Incendiary Bomb Extinguishers       536         Indigo, Substitute for       569         Indol, Substitute for       569         Infra-Red Absorbing Glass       189         Ingredients, Quality of       1         Inhibitor, Metal Corrosion       239         Polymerization       436         Injection Molding Compound       439         Ink, Aqueous Printing       167         Brass Etching       179
Chewing       123         Envelope       21         Karaya, Substitute for       567         Locust Bean, Substitute for       567         Solution       170         Tragacanth, Substitute for       568         Water Dispersible, Substitute for       568         Gun Lubricant       11         Recoil Fluid       537         Gunpowder, Smokeless, Flashless       430         Gut, Substitute for       568         Gypsy Moth Spray       97         H       Hair, Bleaching Animal       158         Cream       55         Dressing       41         Dye       57         Dye, Removing       57         Dyeing Animal       158         Dyeing Soap       57	Ice Cream, Fruit Purée for
Chewing       123         Envelope       21         Karaya, Substitute for       567         Locust Bean, Substitute for       568         Solution       170         Tragacanth, Substitute for       568         Water Dispersible, Substitute for       568         Gun Lubricant       11         Recoil Fluid       537         Gunpowder, Smokeless, Flashless       430         Gut, Substitute for       568         Gutta-Percha, Substitute for       568         Gypsy Moth Spray       97         H       Hair, Bleaching Animal       158         Cream       55         Dressing       41         Dye       57         Dye, Removing       57         Dyeing Animal       158         Dyeing Soap       57         Fixatives       55	Ice Cream, Fruit Purée for
Chewing       123         Envelope       21         Karaya, Substitute for       567         Locust Bean, Substitute for       567         Solution       170         Tragacanth, Substitute for       568         Water Dispersible, Substitute for       568         Gun Lubricant       11         Recoil Fluid       537         Gunpowder, Smokeless, Flashless       430         Gut, Substitute for       568         Gutta-Percha, Substitute for       568         Gypsy Moth Spray       97         H       Hair, Bleaching Animal       158         Cream       55         Dressing       41         Dye       57         Dye, Removing       57         Dyeing Animal       158         Dyeing Soap       57         Fixatives       55         Lacquer       55	Ice Cream, Fruit Purée for
Chewing       123         Envelope       21         Karaya, Substitute for       567         Locust Bean, Substitute for       567         Solution       170         Tragacanth, Substitute for       568         Water Dispersible, Substitute for       568         Gun Lubricant       11         Recoil Fluid       537         Gunpowder, Smokeless, Flashless       430         Gut, Substitute for       568         Gutta-Percha, Substitute for       568         Gypsy Moth Spray       97         H       Hair, Bleaching Animal       158         Cream       55         Dressing       41         Dye       57         Dye, Removing       57         Dyeing Animal       158         Dyeing Soap       57         Fixatives       55         Lacquer       55	Ice Cream, Fruit Purée for
Chewing       123         Envelope       21         Karaya, Substitute for       567         Locust Bean, Substitute for       567         Solution       170         Tragacanth, Substitute for       568         Water Dispersible, Substitute for       568         Gun Lubricant       11         Recoil Fluid       537         Gunpowder, Smokeless, Flashless       430         Gut, Substitute for       568         Gutta-Percha, Substitute for       568         Gypsy Moth Spray       97         H       Hair, Bleaching Animal       158         Cream       55         Dressing       41         Dye       57         Dye, Removing       57         Dyeing Soap       57         Fixatives       55         Lacquer       55         Restorer, Dog       114         Rinse, Blond       57         Straightener       56	Ice Cream, Fruit Purée for
Chewing       123         Envelope       21         Karaya, Substitute for       567         Locust Bean, Substitute for       567         Solution       170         Tragacanth, Substitute for       568         Water Dispersible, Substitute for       568         Gun Lubricant       11         Recoil Fluid       537         Gunpowder, Smokeless, Flashless       430         Gut, Substitute for       568         Gutta-Percha, Substitute for       568         Gypsy Moth Spray       97         H       Hair, Bleaching Animal       158         Cream       55         Dressing       41         Dye       57         Dye, Removing       57         Dyeing Animal       158         Dyeing Soap       57         Fixatives       55         Lacquer       55	Ice Cream, Fruit Purée for
	for

Ink—Continued	Javelle Water 14
Glassware	Jelly, Pectin
Hectograph Ribbon166	Juice, Apple
T. J. I. I.	Comment 100
Indelible	Carrot 38
Intaglio Printing168	Cherry 34
Invisible	Grape 33
Lantern Slide171	Plum 35
Laundry Marking9, 169	Pulpy Berry 35
Leather	Pulpy Berry 35 Raspberry 34 Rhubarb 37
Meat Stamping	Rhuharh 37
Multigraph	Sauerkraut 37
Parachute Marking170	Storage of
Parachute Marking	m
Pass-Out Fluorescent170	Tomato 36
Photostat168	
Printing	K
Pyrographic169	Kapok, Flameproofing497
Raised Printing	
Rayon Printing	Kerosene Purifier
Removable Marking	Kier Boiling, Cotton Goods525
Remover 14	
Rotary Heliogravure167	$\mathbf{L}$
	Lacquer, Airplane326
Secret	Dacquer, Airpiane
Silk Screen170	Brass323
Stamp-Pad166	Christmas Ornament325
Sympathetic169	Cloth326
Textile Printing	Emulsion 91
Thermoplastic168	Ethyl Cellulose324, 325
Thermo-Setting Printing167 Thinner171	Finger Nail327
Thinner 171	Fluorescent325
Transfer	Furniture324, 327
	Glass Fiber325
Typewriter Ribbon	Glued Surface326
White	
Writing 9	Hair 55
Insect Bite Remedy 77	Metal324
Repellents 8	Nail 49
Repellent, Animal100	Nitro Starch326
Repellent, Animal100 Insecticidal Dust97	Paper326
Insecticide Activator, Nicotine100	Pigmented302, 326
Agricultural (see also Emulsion,	Polyvinyl Acetal326
Agricultural) 97	Remover 14
Colloidal 98	Rubbing324
Crop Dusting 97	Solvent324
Gherkin 98	Textile Printing518
Glierkili	Wood324
Home Made 98	Laminating. See Fabrics, Doubled
Midge 78	Tamm Illuminant 529
Silverfish 78 Spreader 98	Lamp Illuminant
Spreader 98	Lances, Pyrotechnic426
Substitute for	Lapis Lazuli, Artificial550
Substitute for	Lapping Compound (see also Pol-
Insulation	ishes)417
Cable435	Lard. Substitute for
Heat190	Oil, Substitute for570
Invert Sugar, Substitute for570	Latex. See Rubber Latex
Iodine Antiseptic, Non-Alcoholic 79	Stabilizer433
Mild Tincture of 79	Substitute for
G-1 stitut for	Laundry Bleaching469
Substitute for	"Propha" AEA
Iodized Oils80	"Breaks"454
Irish Moss, Substitute for570	Compounds
Iron, Corrosion Proofing240	Detergents
1	Gloss
	Stain Removers455
Japanese Beetle Lure100	Starch
Beetle Spray100	Washing451

	Lavender Oil, Synthetic 53	Lubricant—Continued
	Laxative Emulsion	Glass Mold189
	Lead Castings, Cleaning223	Gyroscope Bearing182
	Coating Iron	Metal Drawing183
	Leaf Roller Moth Spray, Plum 97	Metal Working185
	Leak Sealers, See Anti-Leak	Nickel Drawing188
	Leather, Artificial	Non-Gumming Oil185
	Conditioner	Nylon509
	Deglazing	Pipe Thread183
	Degreaser	Rolling Strip Steel183
	Dressing, Military402	Rustproofing184
	Dubbing	Stop-Cock184
	Dyeing Glove	Textile
	Finish, Antique	Threaded Fitting
	Fluorescent	Vinyon509
	Preservative	Wire Drawing
	Stain, Black	Wood
	Tanning151	Luminescent Glass309
	Waterproofing	Lamp Coatings
	Lice Control, Unicken	Lure, Japanese Beetle100
	Treatment, Head	Lusterizing, Rug508
	Lights, Pyrotechnic	M
	Limed Oak Finish321	Macaroon Cup Cake124
	Liming, Hide	Magret Renellent
	Liniment 7	Maggot Repellent 80 Magic Serpent, Pyrotechnic423, 428
	Acetone	Writing Pad 180
	Analgesic	Magnesium Alloys Corrosion
	Anodyne 70	Magnesium Alloys, Corrosion Proofing
	Anodyne	Die Casting Treatment198
	Horse	Magnet, Permanent25
	Stimulating	Malted Milk Powder
	Stimulating	Malted Milk Powder
	oleum	Manifolding Paper, Coating for 168
	Linseed Oil, Heavy Kettle-Bodied.316	Manure, Reinforced
	Lipstick. Coloring	Substitute for118
	Fluorescent 48	Marble, Artificial
	Liquid	Marble, Artificial
	Litho Plate Sensitizer374	Chocolate Dipping125
	Washout	Filler
	Lithographer's Adhesive 20	Mascara, Liquid 4
	Lithographic Etch	Mash, Chicken100
	Plate Conditioner375	Sterilizer, Fermentation53
	Locust Poison 99	Mask, Beauty 4
	Lotion, Acne	Mask, Beauty 44 Masking Coating, Glass 30 Match, Non-Poisonous Safety 42
	After-Shave 58	Water, Non-Poisonous Safety423
	Calamine	Waterproof
	Face 3	Matte Finish, Brass213
	Gum Massaging	Mayonnaise14
	Hand	Maal Powder Purotechnic 419
	Mouth 60	Meal Powder, Pyrotechnic418 Measuring and Weighing
	Poison Ivy	Meat Curing Brine 14
	Skin 45	Meat and Vegetable Stew Army
	Lubricant	Meat Curing Brine
	Anti-Seize	Mechanic's Hand Paste 450
	Chassis	Meerschaum, Imitation55
	Dental	Meringue, Cinnamon12
	Die Member	Metagelatin384
	Diesel	Metals
	Drawing Die	Annealing
	Driving Journal	Bearing, Powdered
	Fiber	Bell
g.		the state of the s

Metals—Continued	Mucin, Substitute for571
Calorizing245 Casting, Mold for Precious	Mustard Gas Protectives 62
Metal242	N
Casting, Smooth Finish242	
Cleaning244	Nail Enamel. See Lacquer, Nail Varnish Remover 50
Coated Fabrics523	Wax, Liquid
Coloring	Naphthenic Miscible Oil 92
by220	"Naturalizing" False Teeth and
Corrosion. See Corrosion	Eyes
Corrosion, Preventing237	Nematode Destroyer100
Degreasing237	Neoprene Gasket445 Nickel Alloy, Bright Annealing 241
Descaling	Brightener
Heat Treating244, 245	"Nipagen." Substitute for571
Lacquer	Nitre Cake, Substitute for571 Nitric Acid, Substitute for571
Lacquer324 Plating. See Plating	Nitric Acid, Substitute for 571 Nitrocellulose Emulsion 92
Plating, Removal	Substitute for
Porous	Nitrogen, Substitute for571
Quenching	Nitromannite, Substitute for571 Non-Ferrous Metals, Etching176
Rustproofing. See Rustproofing Sheet, Non-Sticking251	Non-Ferrous Metals, Etching176
Temper Coloring	Non-Sticking Fabrics521
Methacrylate Denture438	Noodles, Soy
Methods of Using the Recipes 3	Nutgalls, Substitutes for
Methyl Cellulose, Dissolving541 Micro-Identification, Textile500	Nuts, Removing Skins from148 Nux Vomica, Substitute for75, 571
Midge Insecticide	Nux Vomica, Substitute for75, 571
Mildewproofing	0
Removing	
Milk, Fudge	Oat Seed Treatment
Stimulator, Cow	Octyl Alcohol, Normal, Substitute
Silvering	for
Silvering	Offset. Preventing537
Mite, Control of Harvest103	Oil, Baby Skin
Mixing	Cutting. See Cutting Oil
Compounds444	Emulsion, Acid
Mold Growth, Preventing Barrel539	Miscible 92
Precious Metal Casting242	Proof Compound
Refractory Dental243 Molding Compositions. See Plastics	Slushing. See Slushing Oil
Material 11	Soluble
Money Marking Paper 171	Well Cement
Monoacetin. Substitute for	Ointment, Acne
Monogivcollin, Substitute for 311	Allantoin
Montan Wax, Substitute for571 Morpholine, Substitute for571	Antisentic 2
Mosquito Repellent8, 77, 100	Antiseptic
Spray	Base 62
Spray	Base, Emulsified 63 Cod Liver Oil 68
Moths, Destroying	Dhobie Itch
Mothproofing	Dry Skin
Mouthwash	Embalmers' Eczema 80
Dog	Eye 61
Mucic Acid, Substitute for571	Poison Gas
Mucilage. See also Adhesive, Caulk-	Scabies
ing, Cement, Glue, Gum, Paste, Putty and Seal	Sulfathiazole 67
Secret Message 19	Zinc Peroxide 68

Oiticica Oil, Limed Rosin316	Paint—Continued
Oleic Acid, Substitute for571	Repairing Plastic193
Oleyl Alcohol, Substitute for571	Resin Water308
Oleyi Alcohol, Substitute 101	Rust Preventive271
Olive Oil, Substitute for 509, 571, 572	Self-Priming Flat279
Opal, Artificial550	Geni Elet Creen Incide Nevel 974
Orange Beverage 39	Semi-Flat Green Inside Naval274
Flower Water 52	Semi-Paste278
Orthophenylphenol Emulsion 79	Ship Bottom
Oxidizing Brass209	Silicate
	Smoke Stack273
<b>P</b>	Stipple
Packing, Neoprene445	Stripper484
Paint (see also Enamels)254	Structural Matal 279
raint (see also Enamers)204	Structural Metal272 Thinning275, 276
Aging Water Glass303 Anti-Corrosive263, 272	Thinning
Anti-Corrosive263, 272	Thixotropic Flat286
Anti-Fouling. See Paint, Ship	Tinting Metal269
Bottom	Traffic
Asbestos Shingle274	Vehicles for
Black-Out	Water261, 303
Boat Bottom273	Water Tank Interior274
Boot-Topping272	White Canvas273
Brush Cleaner486	White Lead285
Brush Preserver486	White Naval
Camouflage	Wood Undercoat300
Camounage	Yellow Marking Boat274
Casein	Deinting Down Carefood 210
Cement	Painting Damp Surfaces310 Farm Implements271
Chemical Resistant261	Farm implements271
Compass Bowl270	Floor
Copper Oxide273	Golf Balls285
Deck273	Linoleum
Drier319	Linoleum
Eggshell Flat	Plaster Statue
Emulsion	Plywood283
Exterior Wood275	Paper
Firencof 260	Alkaliproof338
Fireproof	Casein Coating for335
Flat Wall278	Fluorescent
Flat White Inside Naval274	"Glassine"
	Greaseproof33
Fluorescent	Greaseproof
Formulation287	Insectproof335
Fume-Proof275 Galvanized Iron271	Moistureproofing
Galvanized Iron	Pest Resistant335
Glass288	Pulp Board337
Gloss	Pulp, Waterproofing335
Glossy Green Inside Naval274	Self-Sealing Waxed337
Green Naval	Sizing
Grinding Liquid317	Softening
Heat Resistant	Temperature Indicating540
Hot Metal271	Translucent33
Inside White Naval274	Transparent 33
Inside White Submarine274	Transparent
Luminous	Waterproof
Metal Finishing268	Waterproofing 14 Waxed 33
Metal Philishing	Waxeu
Metal Primer	Paraffin Wax Emulsion 84
Metal Protective270	Passivation, Stainless Steel258
Naval	Paste. See also Adhesive, Caulk-
Oil	ing, Cement, Glue, Gum, Muci-
Outside House275, 286	lage. Putty and Seal
Outside White273	Belting 2'
Preservative273	Bench 25
Ready Mixed277	Dry
Red Lead273	Dry 19 Envelope 22
Remover	Gasket 20

Paste—Continued	Picture Transfer Fluid	
Library 22	Pie, Caramel Custard	126
Paperhanger's	Dough	124
Tin	Pigeon Remedy107,	108
Patching, Porcelain Enamel295	Pigments, Camouflage Paint	290
Peach Borer Spray 97	Disperser for	433
Pectin Dressing, Therapeutic 72	Fluorescent	290
Emulsions with 88	Infra-Red	299
Soap448	Luminescent Ceramic	
Using         72           Penetrating Oil         11	Military Enamel	298
Penetrating Oil 11	Military Paint	290
Peppermint Water 52	Suspending	328
Perfume, Deodorant Cream 53	White Paint	328
Formaldehyde 79	Pill Coating	73
Hypochlorite 78	Polishing Pin Wheels Pipe Coating, Acid Resisting.	74
Oils, Synthetic 53	Pin Wheels	422
Solid 53	Pipe Coating, Acid Resisting	$^{263}$
Permanent Waving 55	Corrosion-Proof Thread Compound	$^{240}$
Peroxide Bleaching	Thread Compound	270
Perspiration, Artificial543	Waterproofing	270
Petroleum Jelly187	Pistons, Tin Coating Aluminum	234
Petroleum Jelly	Pitch, Synthetic Brewer's	445
Phonograph Records. See Record Photo Flash Lamp395	Plant Growth Emulsion	86
Photo Flash Lamp395	Growth Stimulant	118
Photoengraving375	Plaster, Building	191
Cement	Fireproof	332
Glue Enamel	Fluorescent	191
Glue Ink Top385	of Paris, Fast Setting Patching	76
Resist385	Patching	12
Sensitive Coating385	Rapid Drying	191
Photographic Bleach349	Plastic	142
Coloring. See Photographic Ton-	Cast	139
ing	Coating4	140
Desensitizers373, 374	Etching	378
Developers	Ethyl Cellulose4	138
Direct Reversal348	Luminous4	
Fixers	Optical Lens4	
Flashlight Powder395	Self-Hardening4	138
Glass Cleaner	Silver Plating	228
Hardening Baths369-371	Styrene4	139
Hints	Vegetable Cellulose4	138
Intensifiers349–353	Wall Board4	140
Negative Cleaner389	Wood Dough	12
Overexposures, Saving395	Wood Pulp4	
Printing, Diazo394	Plater's Stripping Solution2	224
Printing on Wood394	Plating, Antique Iron	230
Redeveloper	Brass	226
Reducers	Cadmium2	226
Ston Roths 368 369	Copper	227
Stop Baths 368, 369 Toning 357–367	on Glass2	236
Photogravure Sensitizer374	on Glass, Silver	227
Photolithographic Sensitizer374	Gold	วัสด
Pickle Color, Preserving Green143	Green Gold	229
Dill	Lead	231
Diamen 1/2	Molybdenum Bronze	226
Flavor	Nickel	233
Hide	Non-Conductor	736
Trace 1	Non-Electric	290
Inconel	on Plastics	350
Monel	on Plastics	200
Nickel	Platinum	333
Nickel Alloy	Silver	200
Stainless Steel	Tin	100
Sterling Silver	LIII	104

Plating—Continued	Preserve Thickener, Fruit146
Touch-Up	Primer, Ammunition
White Gold	Automobile Enamel302
Zinc	Baking
Platinum, Substitute for 572 "Pliofilm," Substitute for	Metal261
"Phofilm," Substitute for	Paint
Plum Juice	Plaster332
Plush, Printing on	Red Lead270
Plywood Adnesive	Wood 261 278
Painting	Wood
Gas Protectives	Direct Textile
Ivy Protective	Metallic Textile512
Polish	Plate Activator, Zinc541
Aircraft Metal401	Resist, Textile
Aluminum401	Roller, Thiokol436
Automobile	Textile
Ferrotype394	Thickener, Textile
Floor	Prophylactic Capsules 74
Furniture	Protein (Alpha), Substitute for 557
Jewelry401	Pulverizing
Linoleum	Pumpernickel Bread123
Metal	Purees, Fruit
Metal Burnishing400	Putty (see also Adhesive, Caulking,
Metal Roller401 Nail. See Lacquer, Nail	Cement, Glue, Gum, Mucilage,
Nail. See Lacquer, Nail	Paste and Seal)
Non-Rubbing	Bakelite
Oil	Magnesium Joining 29
Paste Shoe         397           Patent Leather         402	Pyorrhea Tooth Powder 60
Plastics	Pyrogallic Acid Substitute for 579
Shoe	Pyrogallic Acid, Substitute for572 Pyrogallol, Substitute for572
Silver401	Pyrotechnics
Transparent Sheet 450	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
Wax	Q
Wax	
num	Quartz, Substitute for572
Polymerization Inhibitor436	Quenching, Metal
Polystyrene Resin436	Quercitron Bark, Substitute for 572
Substitute for572	Quick Match, Military430
Polyvinyl Alcohol, Plasticized433	Quince Seed, Substitute for572
Alcohol, Substitute for572	Quinine, Substitute for572
Butyral Coating	R
Porcelain Enamel, Patching295	ĸ
Protective Coating for264 Potatoes, Improved French-Fried.148	Radiator Corrosion, Inhibitor of 239
Poultice Antiphlogistic 62	Rain Pyrotechnic 42
Poultice, Antiphlogistic 62 Poultry Favus Treatment	Rain, Pyrotechnic
House, Disinfection of105	Raspberry Juice 34
Lime Granules	Rat Food, Experimental11
Pickle	Lure
Smoked140	Poison
Powder, Bahy	Rayon Scourings
Base, Liquid	Record Coating, Phonograph303
Black429	Phonograph
Cellular Smokeless430	Phonograph
Explosive	Remover. Paint and Varnish33
Face	Stain (see also Cleaners)39
Fluorescent Face	Resin. See also Rosin
Glenn's Liquid	Acrylic43
Tooth	Casting Phenolic43
Praliné Crunch	Casting Thermosetting43 Polystyrene43
Processorita Tavila Hiber 521	I POINTETTITONO 13

	1
Resin—Continued	Sassafras Oil, Substitute for573
Raised Printing Base168	Sauerkraut
Synthetic	Juice
Synthetic Varnish436	Carona Dranatachnia
Dynunctic variasii	Saxons, Pyrotechnic423
Water White Synthetic436	Scabies Ointment
Resist, Etching	Treatments
	Scouring, Rayon470, 505
Rhubarb Juice 37	Screw Threads, Coating for270
Rifle Cleaner494	Worm Remedy, Livestock 112
Ringworm Treatment 63	Scrooping Compounds, Textile521
Treatment, Animal115	Scurf Pomade
Treatment, Cattle	Scurf Pomade
Roach Destruction101	Cement, Glue, Gum, Mucilage,
Road Markers, Night294	
	Paste and Putty
Roman Candles	Engine Joint
Roofing Composition192	Food Container
Rose Water 52	Gas Tight Valve 30
Rosin. See also Resin	Metal Container Dope 19
Opaque436	Metal Thread Connection 28
Plasticized 90	Oil and Vapor Proof 19
Soap 90	Vacuum Tube
Rotproofing Sandbags496	Sealer, Wood
Rouge, Compact 47	Sebacic Acid, Substitute for573
Fluorescent Face	Seed Disinfectant
Rub, Athletic	Treatment, Pea
Rubber431	Seed-Lac, Substitute for573
Rine 424 495	Solonium Substitute for 579
Buna	Selenium, Substitute for573 Dioxide, Substitute for573
Cement, Substitute for573	Cold Tracking Commonitions 200
Chlorinated, Substitute for573 Eliminating Tack in434	Self Heating Compositions539
Eliminating Tack in434	Serpents, Pyrotechnic423, 428
Eraser432	Sesame Oil. Substitute for574
Hard, Substitute for573	Shampoo, Coal Tar
Latex, Artificial433	Shaving Cream, Brushless 7, 40, 58
Leather-like	Sheen Blow-Fly Dressing112
Plant	Dip
Plant	Sheepskin Treatment, Pre-Tan-
Preserving	ning
Reclaiming	Shellac, Ammonia397
Reclaiming Synthetic436	Aqueous
Reconditioning Agi	Molding Compound439
Reconditioning	Solutions, Thinning329
Crosthotia 490, 494, 490, 494	Substitute for574
Dynunetic	Wester Dilutable 200
Rugs, Refinishing Fiber or Grass522	Water Dilutable329
Rust Inhibitor, Cutting Oil 185	Shoe Cement
Preventing	Disinfectant 79
Remover	Dressing, White 10
Remover, Textile	Filler445
Rustproofing, Lubricant184	Polish
Y NE ( ) 1	Stiffener445
	Waterproofing 10
S	Shot. Lead
	Signal. Distress
Salad Dressings145	Silica Gel. Substitute for574
Dressing, Non-Fattening145	Silicate, Waterproof262
Salt, Free Flowing	Water Resistant Alkali542
Sickness Cure, Cattle	Silver Pickling, Sterling196
Sandstone, Chemically Resistant. 191	Tarnish, Inhibitor of242
Machinella	Townsming 94E
Machinable191	Tempering
Santowax Emulsion 84	Silverfish Elimination101
Saponin, Substitute for573	Insecticide
Sapphire, Artificial549	Sisal, Retting525
Substitute for573	Softening525
Sardine Oil Substitute for 573	Size, See Sizing

Sizing (see also Paper, Textiles) 502	Solder—Continued
Duck (Awning)502	Wire Fabric246
Logwood Textile502	Zinc Aluminum Alloy246
NI1 FOO	Soldering Cast Iron247
Nylon502	
Rayon502	Flux (see Flux)
Thermoplastic	Fluxes
Skin Blemish Covering 44 Lotion, See Lotion, Skin	Iron Tip248
Lotion, See Lotion, Skin	Metal to Ceramics247
Protectives	Soluble Oil
Sky Rockets	Oil, Non-Foaming185
Sky Rockets	Colvent Dunlicator 200
Slides, Coloring367	Solvent, Duplicator328 Ethyl Cellulose328
Slug Bait100	Etnyl Cellulose
Slushing Oil, Steel Protective185	Lacquer327
Smoke, Pyrotechnic429	Sound Deadener536
Screens, Military429	Sparklers, Pyrotechnic428
Snail Bait100	Snark Pot. Pyrotechnic429
Snuff, Antiseptic	Spice Equivalents, Essential143
Soap (see also Cleaners)13, 448	Oils142, 143
Soap (see also Cleaners)13, 440	Pickle
Anti-Perspirant449	Pickie
Automobile494	Spider Spray, Red100
Break	Spoilage 4
Builders	Sponges, Self Sterilizing158
Cheap	Spot Remover (see Stain Remover) 14
Cocoanut Oil448	Spotting Mixture, Cleaner's468
Fluorescent449	Spray Agricultural. See Emulsion,
r luorescent	Agricultural
Leather449	Agricultural
Liniment of Soft 70	Fly 8 Stain Remover (see also Clean-
Liquid	Stain Remover (see also Clean-
Mechanic's Hand	ers)390
Non-Gelling Liquid450	Acriflavin456
Pad	Argyrol
Paste	Balsam
Pectin448	Benzoin Tincture457
Peculi440	Carbon457
Pumice449	Carpon457
Rosin	Cement457
Saddle13, 449	Chocolate457
Scabies 69	Cocoa
Soapless449	Coffee457
Soft448	Dye
Solution, Stock	Fish Oil459
Sulphur	Gentian Violet
Tartile 470	Glue
Textile	
Tincture of Green	Grass
Transparent448	Grease460
Waste Fat448	Grease Spot468
Wool Thrower's470	Hand451
Soda, Textile	Ichthyol
Sodium Alginate, Substitute for574	Indelible Pencil461
Alkyl Sulphate, Substitute for 574	India Ink461
Aluminata Substitute for 574	Ink
Aluminate, Substitute for574 Antimony Fluoride, Substitute	Iodine
Antimony Fluoride, Substitute	
for	Lacquer
Benzoate, Substitute for574	Laundry455
Bichromate, Substitute for574	Leather
Bisulphite, Substitute for574	Lime Soap
Hexametaphosphate	Medicine
Solder, Aluminum246	Mercurochrome
Gold249	Metallic
To distant	Methylene Blue465
Indium	With Jan
Non-Tarnishing Jeweler's249	Mildew
Precious Metal249	Miscellaneous
Soft246	Mud464
Tin-Free	Nail Polish

Stain Remover—Continued	Substitutes—Continued
Oil459, 464	Tinfoil
Ointment	Wool Grease
Paint464	Suet, Substitute for574
Perspiration464	Sugar, Substitute for578
Picric Acid465	Coloring, Burnt, Substitute for 578
Polished Glass481	Vinegar Solution
Printing Ink465	Sulfanilamide Emulsion 67
Prontosil	Ointment 66
Red Clay	Sulfathiazole Emulsion67, 88
Red Clay	Sulphated Fatty Alcohol Substi-
Rouge	tute for
Rust	Sulphonated Castor Oil Substitute
Scarlet Red	for
Scorch	Cocoanut Oil, Substitute for575
	Olive Oil, Substitute for575
Shoe Polish	Dod Oil Cabatitute for 575
Silver	Red Oil, Substitute for575
Silver Compound456	Tallow, Substitute for575
Smoke	Sulphur, Colloidal 98
Stone	Dioxide Bleach
Tannin	Dioxide Bleaching160
<u>Tar</u> 465	Dioxide, Substitute for575
Tea Stain467	Sunburn Preventive 46 Sun-Tan Powder 47
Textile Mill470	Sun-Tan Powder 47
Verdigris	Suppositories
Water Spot468	Surgical Dressing Remover, Pain-
Yellow Stain468	less
Staining. See Coloring, Dyeing	Waterproof
Stainless Steel, Passivation of253	Sweeping Compound487
Stains, Wood319	Sweetener, Sugarless
Starch, Laundry470	Syrup de Gomme 166
Solution, Clear542	Sugarless 73
Stars, Pyrotechnic	Dagazioss (
Static, Preventing537	
Bracic, Freventing	l res
Stool Diving 10	$\cdot$ T
Steel, Bluing	
Carburizing245	
Carburizing	Tablet, Activated Carbon 74
Carburizing	Tablet, Activated Carbon 74
Carburizing       245         Cutting Cold       252         Hardening       245         Removing Brittle Surface       253	Tablet, Activated Carbon 74
Carburizing       245         Cutting Cold       252         Hardening       245         Removing Brittle Surface       253	Tablet, Activated Carbon 74
Carburizing       245         Cutting Cold       252         Hardening       245         Removing Brittle Surface       253         Tempering       244         Stencil, Heat Resistant       530	Tablet, Activated Carbon 74 Binder, Medicinal 73 Lubricant 74 Polishing, Medicinal 74 Talc. Substitute for 576
Carburizing       245         Cutting Cold       252         Hardening       245         Removing Brittle Surface       253         Tempering       244         Stencil, Heat Resistant       530         Sheet, Heat Resisting       181	Tablet, Activated Carbon 74 Binder, Medicinal 73 Lubricant 74 Polishing, Medicinal 74 Talc, Substitute for 576 Tallow, Substitute for 576
Carburizing       245         Cutting Cold       252         Hardening       245         Removing Brittle Surface       253         Tempering       244         Stencil, Heat Resistant       530         Sheet, Heat Resisting       181	Tablet, Activated Carbon       74         Binder, Medicinal       73         Lubricant       74         Polishing, Medicinal       74         Talc, Substitute for       576         Tallow, Substitute for       576         Oil. Substitute for       576
Carburizing       245         Cutting Cold       252         Hardening       245         Removing Brittle Surface       253         Tempering       244         Stencil, Heat Resistant       530         Sheet, Heat Resisting       181         Stereotype Mat       337         Sterilizer, Metal Cleaner and       489	Tablet, Activated Carbon 74 Binder, Medicinal 73 Lubricant 74 Polishing, Medicinal 74 Talc, Substitute for 576 Tallow, Substitute for 576 Oil, Substitute for 576 Tannic Acid. Substitute for 576
Carburizing       245         Cutting Cold       252         Hardening       245         Removing Brittle Surface       253         Tempering       244         Stencil, Heat Resistant       530         Sheet, Heat Resisting       181         Stereotype Mat       337         Sterilizer, Metal Cleaner and       489         Stiffener, Shoe       445	Tablet, Activated Carbon 74 Binder, Medicinal 73 Lubricant 74 Polishing, Medicinal 74 Talc, Substitute for 576 Tallow, Substitute for 576 Oil, Substitute for 576 Tannic Acid. Substitute for 576
Carburizing       245         Cutting Cold       252         Hardening       245         Removing Brittle Surface       253         Tempering       244         Stencil, Heat Resistant       530         Sheet, Heat Resisting       181         Stereotype Mat       337         Sterilizer, Metal Cleaner and       489         Stiffener, Shoe       445         Textile       521	Tablet, Activated Carbon       74         Binder, Medicinal       73         Lubricant       74         Polishing, Medicinal       74         Talc, Substitute for       576         Tallow, Substitute for       576         Oil, Substitute for       576         Tannic Acid, Substitute for       576         Acid Jelly       66         Tannin, Substitute for       576
Carburizing       245         Cutting Cold       252         Hardening       245         Removing Brittle Surface       253         Tempering       244         Stencil, Heat Resistant       530         Sheet, Heat Resisting       181         Stereotype Mat       337         Sterilizer, Metal Cleaner and       489         Stiffener, Shoe       445         Textile       521         Stinking Smut Spray, Wheat       98	Tablet, Activated Carbon 74 Binder, Medicinal 73 Lubricant 74 Polishing, Medicinal 74 Talc, Substitute for 576 Tallow, Substitute for 576 Oil, Substitute for 576 Tannic Acid, Substitute for 576 Acid Jelly 66 Tannin, Substitute for 576 Tanning, Chrome 152
Carburizing       245         Cutting Cold       252         Hardening       245         Removing Brittle Surface       253         Tempering       244         Stencil, Heat Resistant       530         Sheet, Heat Resisting       181         Stereotype Mat       337         Sterilizer, Metal Cleaner and       489         Stiffener, Shoe       445         Textile       521         Stinking Smut Spray, Wheat       98	Tablet, Activated Carbon       74         Binder, Medicinal       73         Lubricant       74         Polishing, Medicinal       74         Talc, Substitute for       576         Tallow, Substitute for       576         Oil, Substitute for       576         Tannic Acid, Substitute for       576         Acid Jelly       66         Tannin, Substitute for       576         Tanning, Chrome       152         Hide       151
Carburizing       245         Cutting Cold       252         Hardening       245         Removing Brittle Surface       253         Tempering       244         Stencil, Heat Resistant       530         Sheet, Heat Resisting       181         Stereotype Mat       337         Sterilizer, Metal Cleaner and       489         Stiffener, Shoe       445         Textile       521         Stinking Smut Spray, Wheat       98         Stockings, Cosmetic       53	Tablet, Activated Carbon       74         Binder, Medicinal       73         Lubricant       74         Polishing, Medicinal       74         Talc, Substitute for       576         Tallow, Substitute for       576         Oil, Substitute for       576         Tannic Acid, Substitute for       576         Acid Jelly       66         Tannin, Substitute for       576         Tanning, Chrome       152         Hide       151         Leather       151
Carburizing         245           Cutting Cold         252           Hardening         245           Removing Brittle Surface         253           Tempering         244           Stencil, Heat Resistant         530           Sheet, Heat Resisting         181           Stereotype Mat         337           Sterilizer, Metal Cleaner and         489           Stiffener, Shoe         445           Textile         521           Stinking Smut Spray, Wheat         98           Stockings, Cosmetic         53           Stomach Tablet, Anti-Acid         74	Tablet, Activated Carbon       74         Binder, Medicinal       73         Lubricant       74         Polishing, Medicinal       74         Talc, Substitute for       576         Tallow, Substitute for       576         Oil, Substitute for       576         Tannic Acid, Substitute for       576         Acid Jelly       66         Tannin, Substitute for       576         Tanning, Chrome       152         Hide       151         Leather       151
Carburizing         245           Cutting Cold         252           Hardening         245           Removing Brittle Surface         253           Tempering         244           Stencil, Heat Resistant         530           Sheet, Heat Resisting         181           Stereotype Mat         337           Sterilizer, Metal Cleaner and         489           Stiffener, Shoe         445           Textile         521           Stinking Smut Spray, Wheat         98           Stockings, Cosmetic         53           Stomach Tablet, Anti-Acid         74           Stone, Artificial         190	Tablet, Activated Carbon       74         Binder, Medicinal       73         Lubricant       74         Polishing, Medicinal       74         Talc, Substitute for       576         Tallow, Substitute for       576         Oil, Substitute for       576         Tannic Acid, Substitute for       576         Acid Jelly       66         Tannin, Substitute for       576         Tanning, Chrome       152         Hide       151         Leather       151         Vegetable       151         Tapeworm Control, Sheep       112
Carburizing         245           Cutting Cold         252           Hardening         245           Removing Brittle Surface         253           Tempering         244           Stencil, Heat Resistant         530           Sheet, Heat Resisting         181           Stereotype Mat         337           Sterilizer, Metal Cleaner and         489           Stiffener, Shoe         445           Textile         521           Stinking Smut Spray, Wheat         98           Stockings, Cosmetic         53           Stomach Tablet, Anti-Acid         74           Stone, Artificial         190           Straw Textile Fibers         522	Tablet, Activated Carbon       74         Binder, Medicinal       73         Lubricant       74         Polishing, Medicinal       74         Talc, Substitute for       576         Tallow, Substitute for       576         Oil, Substitute for       576         Tannic Acid, Substitute for       576         Acid Jelly       66         Tannin, Substitute for       576         Tanning, Chrome       152         Hide       151         Leather       151         Vegetable       151         Tapeworm Control, Sheep       112         Tarnish Prevention       241
Carburizing         245           Cutting Cold         252           Hardening         245           Removing Brittle Surface         253           Tempering         244           Stencil, Heat Resistant         530           Sheet, Heat Resisting         181           Stereotype Mat         337           Sterilizer, Metal Cleaner and         489           Stiffener, Shoe         445           Textile         521           Stinking Smut Spray, Wheat         98           Stockings, Cosmetic         53           Stomach Tablet, Anti-Acid         74           Stone, Artificial         190           Straw Textile Fibers         522           Stripper, Paint         484	Tablet, Activated Carbon       74         Binder, Medicinal       73         Lubricant       74         Polishing, Medicinal       74         Talc, Substitute for       576         Tallow, Substitute for       576         Oil, Substitute for       576         Tannic Acid, Substitute for       576         Acid Jelly       66         Tannin, Substitute for       576         Tanning, Chrome       152         Hide       151         Leather       151         Vegetable       151         Tapeworm Control, Sheep       112         Tarnish Prevention       241
Carburizing         245           Cutting Cold         252           Hardening         245           Removing Brittle Surface         253           Tempering         244           Stencil, Heat Resistant         530           Sheet, Heat Resisting         181           Stereotype Mat         337           Sterilizer, Metal Cleaner and         489           Stiffener, Shoe         445           Textile         521           Stinking Smut Spray, Wheat         98           Stockings, Cosmetic         53           Stomach Tablet, Anti-Acid         74           Stone, Artificial         190           Straw Textile Fibers         522           Stripper, Paint         484           Stripping Compounds         483	Tablet, Activated Carbon       74         Binder, Medicinal       73         Lubricant       74         Polishing, Medicinal       74         Talc, Substitute for       576         Tallow, Substitute for       576         Oil, Substitute for       576         Tannic Acid, Substitute for       576         Acid Jelly       66         Tannin, Substitute for       576         Tanning, Chrome       152         Hide       151         Leather       151         Vegetable       151         Tapeworm Control, Sheep       112         Tarnish Prevention       241         Removal       197         Tartaric Acid, Substitute for       576
Carburizing         245           Cutting Cold         252           Hardening         245           Removing Brittle Surface         253           Tempering         244           Stencil, Heat Resistant         530           Sheet, Heat Resisting         181           Sterotype Mat         337           Sterilizer, Metal Cleaner and         489           Stiffener, Shoe         445           Textile         521           Stinking Smut Spray, Wheat         98           Stockings, Cosmetic         53           Stomach Tablet, Anti-Acid         74           Stone, Artificial         190           Straw Textile Fibers         522           Stripper, Paint         484           Stripping Compounds         483           Tin from Brass         225	Tablet, Activated Carbon       74         Binder, Medicinal       73         Lubricant       74         Polishing, Medicinal       74         Talc, Substitute for       576         Tallow, Substitute for       576         Oil, Substitute for       576         Tannic Acid, Substitute for       576         Tannin, Substitute for       576         Tanning, Chrome       152         Hide       151         Leather       151         Vegetable       151         Tapeworm Control, Sheep       112         Tarnish Prevention       241         Removal       197         Tartaric Acid, Substitute for       576         Tear Gas Cleaner       62
Carburizing         245           Cutting Cold         252           Hardening         245           Removing Brittle Surface         253           Tempering         244           Stencil, Heat Resistant         530           Sheet, Heat Resisting         181           Stereotype Mat         337           Sterilizer, Metal Cleaner and         489           Stiffener, Shoe         445           Textile         521           Stinking Smut Spray, Wheat         98           Stockings, Cosmetic         53           Stomach Tablet, Anti-Acid         74           Stone, Artificial         190           Straw Textile Fibers         522           Stripper, Paint         484           Stripping Compounds         483           Tin from Brass         225           Stylus, Wood         553	Tablet, Activated Carbon       74         Binder, Medicinal       73         Lubricant       74         Polishing, Medicinal       74         Talc, Substitute for       576         Tallow, Substitute for       576         Oil, Substitute for       576         Tannic Acid, Substitute for       576         Acid Jelly       66         Tannin, Substitute for       576         Tanning, Chrome       152         Hide       151         Leather       151         Vegetable       151         Tapeworm Control, Sheep       112         Tarnish Prevention       241         Removal       197         Tartaric Acid, Substitute for       576         Telephone Membrane Coating       329
Carburizing         245           Cutting Cold         252           Hardening         245           Removing Brittle Surface         253           Tempering         244           Stencil, Heat Resistant         530           Sheet, Heat Resisting         181           Stereotype Mat         337           Sterilizer, Metal Cleaner and         489           Stiffener, Shoe         445           Textile         521           Stinking Smut Spray, Wheat         98           Stockings, Cosmetic         53           Stomach Tablet, Anti-Acid         74           Stone, Artificial         190           Straw Textile Fibers         522           Stripper, Paint         484           Stripping Compounds         483           Tin from Brass         225           Stylus, Wood         553           Styrene Plastic         439	Tablet, Activated Carbon 74 Binder, Medicinal 73 Lubricant 74 Polishing, Medicinal 74 Talc, Substitute for 576 Tallow, Substitute for 576 Oil, Substitute for 576 Tannic Acid, Substitute for 576 Acid Jelly 66 Tannin, Substitute for 576 Tanning, Chrome 152 Hide 151 Leather 151 Vegetable 151 Tapeworm Control, Sheep 112 Tarnish Prevention 241 Removal 197 Tartaric Acid, Substitute for 576 Tear Gas Cleaner 62 Telephone Membrane Coating 329 Television Screen 294
Carburizing         245           Cutting Cold         252           Hardening         245           Removing Brittle Surface         253           Tempering         244           Stencil, Heat Resistant         530           Sheet, Heat Resisting         181           Stereotype Mat         337           Sterilizer, Metal Cleaner and         489           Stiffener, Shoe         445           Textile         521           Stinking Smut Spray, Wheat         98           Stockings, Cosmetic         53           Stomach Tablet, Anti-Acid         74           Stone, Artificial         190           Straw Textile Fibers         522           Stripper, Paint         484           Stripping Compounds         483           Tin from Brass         225           Stylus, Wood         553           Styrene Plastic         439           Substitutes         554-578	Tablet, Activated Carbon 74 Binder, Medicinal 73 Lubricant 74 Polishing, Medicinal 74 Talc, Substitute for 576 Tallow, Substitute for 576 Oil, Substitute for 576 Tannic Acid, Substitute for 576 Acid Jelly 66 Tannin, Substitute for 576 Tanning, Chrome 152 Hide 151 Leather 151 Vegetable 151 Tapeworm Control, Sheep 112 Tarnish Prevention 241 Removal 197 Tartaric Acid, Substitute for 576 Tear Gas Cleaner 62 Telephone Membrane Coating 329 Television Screen 294
Carburizing         245           Cutting Cold         252           Hardening         245           Removing Brittle Surface         253           Tempering         244           Stencil, Heat Resistant         530           Sheet, Heat Resisting         181           Stereotype Mat         337           Sterilizer, Metal Cleaner and         489           Stiffener, Shoe         445           Textile         521           Stinking Smut Spray, Wheat         98           Stockings, Cosmetic         53           Stomach Tablet, Anti-Acid         74           Stone, Artificial         190           Straw Textile Fibers         522           Stripper, Paint         484           Stripping Compounds         483           Tin from Brass         225           Stylus, Wood         553           Styrene Plastic         439           Substitutes         554-578           Acetic Acid         542	Tablet, Activated Carbon 74 Binder, Medicinal 73 Lubricant 74 Polishing, Medicinal 74 Talc, Substitute for 576 Tallow, Substitute for 576 Oil, Substitute for 576 Tannic Acid, Substitute for 576 Acid Jelly 66 Tannin, Substitute for 576 Tanning, Chrome 152 Hide 151 Leather 151 Vegetable 151 Tapeworm Control, Sheep 112 Tarnish Prevention 241 Removal 197 Tartaric Acid, Substitute for 576 Tear Gas Cleaner 62 Telephone Membrane Coating 329 Television Screen 294 Tellurium, Substitute for 576 Temperature Indicators, Colored 541
Carburizing         245           Cutting Cold         252           Hardening         245           Removing Brittle Surface         253           Tempering         244           Stencil, Heat Resistant         530           Sheet, Heat Resisting         181           Stereotype Mat         337           Sterilizer, Metal Cleaner and         489           Stiffener, Shoe         445           Textile         521           Stinking Smut Spray, Wheat         98           Stockings, Cosmetic         53           Stomach Tablet, Anti-Acid         74           Stone, Artificial         190           Straw Textile Fibers         522           Stripper, Paint         484           Stripping Compounds         483           Tin from Brass         225           Stylus, Wood         553           Styrene Plastic         439           Substitutes         554-578           Acetic Acid         542           Cacao Butter         75	Tablet, Activated Carbon       74         Binder, Medicinal       73         Lubricant       74         Polishing, Medicinal       74         Talc, Substitute for       576         Tallow, Substitute for       576         Oil, Substitute for       576         Tannic Acid, Substitute for       576         Tannin, Substitute for       576         Tanning, Chrome       152         Hide       151         Leather       151         Vegetable       151         Tapeworm Control, Sheep       112         Tarnish Prevention       241         Removal       197         Tartaric Acid, Substitute for       576         Telephone Membrane Coating       329         Television Screen       294         Tellurium, Substitute for       576         Temperature Indicators, Colored       541         Measurement       3
Carburizing         245           Cutting Cold         252           Hardening         245           Removing Brittle Surface         253           Tempering         244           Stencil, Heat Resistant         530           Sheet, Heat Resisting         181           Stereotype Mat         337           Sterilizer, Metal Cleaner and         489           Stiffener, Shoe         445           Textile         521           Stinking Smut Spray, Wheat         98           Stockings, Cosmetic         53           Stomach Tablet, Anti-Acid         74           Stone, Artificial         190           Straw Textile Fibers         522           Stripper, Paint         484           Stripping Compounds         483           Tin from Brass         225           Stylus, Wood         553           Styrene Plastic         439           Substitutes         554-578           Acetic Acid         542           Cacao Butter         75           Formic Acid         542	Tablet, Activated Carbon       74         Binder, Medicinal       73         Lubricant       74         Polishing, Medicinal       74         Talc, Substitute for       576         Tallow, Substitute for       576         Oil, Substitute for       576         Tannic Acid, Substitute for       576         Tannin, Substitute for       576         Tanning, Chrome       152         Hide       151         Leather       151         Vegetable       151         Tapeworm Control, Sheep       112         Tarnish Prevention       241         Removal       197         Tartaric Acid, Substitute for       576         Telephone Membrane Coating       329         Television Screen       294         Tellurium, Substitute for       576         Temperature Indicators, Colored       541         Measurement       3
Carburizing         245           Cutting Cold         252           Hardening         245           Removing Brittle Surface         253           Tempering         244           Stencil, Heat Resistant         530           Sheet, Heat Resisting         181           Stereotype Mat         337           Sterilizer, Metal Cleaner and         489           Stiffener, Shoe         445           Textile         521           Stinking Smut Spray, Wheat         98           Stockings, Cosmetic         53           Stomach Tablet, Anti-Acid         74           Stone, Artificial         190           Straw Textile Fibers         522           Stripper, Paint         484           Stripping Compounds         483           Tin from Brass         225           Stylus, Wood         553           Styrene Plastic         439           Substitutes         554-578           Acetic Acid         542           Cacao Butter         75           Formic Acid         542           Manure         118	Tablet, Activated Carbon       74         Binder, Medicinal       73         Lubricant       74         Polishing, Medicinal       74         Talc, Substitute for       576         Tallow, Substitute for       576         Oil, Substitute for       576         Tannic Acid, Substitute for       576         Acid Jelly       66         Tannin, Substitute for       576         Tanning, Chrome       152         Hide       151         Leather       151         Vegetable       151         Tapeworm Control, Sheep       112         Tarnish Prevention       241         Removal       197         Tartaric Acid, Substitute for       576         Telephone Membrane Coating       329         Television Screen       294         Tellurium, Substitute for       576         Temperature Indicators, Colored       541         Measurement       3         Metal Color       220
Carburizing         245           Cutting Cold         252           Hardening         245           Removing Brittle Surface         253           Tempering         244           Stencil, Heat Resistant         530           Sheet, Heat Resisting         181           Stereotype Mat         337           Sterilizer, Metal Cleaner and         489           Stiffener, Shoe         445           Textile         521           Stinking Smut Spray, Wheat         98           Stockings, Cosmetic         53           Stomach Tablet, Anti-Acid         74           Stone, Artificial         190           Straw Textile Fibers         522           Stripper, Paint         484           Stripping Compounds         483           Tin from Brass         225           Stylus, Wood         553           Styrene Plastic         439           Substitutes         554-578           Acetic Acid         542           Cacao Butter         75	Tablet, Activated Carbon       74         Binder, Medicinal       73         Lubricant       74         Polishing, Medicinal       74         Talc, Substitute for       576         Tallow, Substitute for       576         Oil, Substitute for       576         Tannic Acid, Substitute for       576         Tannin, Substitute for       576         Tanning, Chrome       152         Hide       151         Leather       151         Vegetable       151         Tapeworm Control, Sheep       112         Tarnish Prevention       241         Removal       197         Tartaric Acid, Substitute for       576         Telephone Membrane Coating       329         Television Screen       294         Tellurium, Substitute for       576         Temperature Indicators, Colored       541         Measurement       3

Tetrahydrofurfuryl Alcohol, Sub-	Varnish—Continued
stitute for	Furniture314
"Tetralin," Substitute for576	General Utility
Textile Finishes497-499	Infra-Red315
Printing. See Printing, Textile	Interior Spar318
Thermoplastics	Length, Increasing316
Thickener, Starch-Tragacanth519	Metal
Substitute for	Mixing
Thief Catching Powder	Modified Phenolic314
Thinner, Paint	Paper319
Thickel Printing Roller	Phenolic
Thrip Control, Flax 97	Quick Drying314
Throat Gargle bu	Remover, Furniture485
Spray, Sulfanilamide 67 Tablet, Sore	Rubbing314
Tablet, Sore	Spar316 Tinplate Baking315
Tile, Cement Floor	Vehicle for Floor
Wall	Water Tank (Interior)316
Tinfoil, Improved	Wrinkle Finish321
Substitute	Vegetable Juices 37
Copper	Velvet, Artificial
Tinplate, Protective Coating of 233	Crush Proof520
Titanium Diovide Substitute for 577	Vinegar Solution, Sugar143
Titanium Dioxide, Substitute for577 Tetrachloride, Substitute for577	Vinylite, Heat Stable437
Toluol, Substitute for577	Vitreous Enamel, Improving Adhe-
Tomato, Improving Firmness of148	sion of
Juice 36	
"Tonic." Hair 55	W
Juice       36         "Tonic," Hair       55         Tonka Beans, Substitute for       577	•
Tools, Cleaning Rusty238	Waffle Mix
Tempering243	Wall Coating, Protective284
Tooth Paste 59	Repairing Rough
Powder	Walnuts, Cracking148
Toothache Drops 61	War Chemicals, Protection
Torches, Parade418	Against
Tourbillions422	Warehouse, Fumigating101
Transfer Coating310	Washing, Laundry451
Transformer Dielectric530 Transparentizing Small Animals537	Watch Cleaner
	Water, Clarifying539
Tree Canker Salve	Glass, Water Resistant542
Triacetin, Substitute for577 Triangles, Pyrotechnic423	Waterproofing
Trichloracetic Acid, Substitute for .577	Canvas
Trichlorethylene, Substitute for . 577	Compound
Tricresyl Phosphate, Substitute	Emulsion
for577	Fiber Board 14
Triethanolamine, Substitute for 577	Leather
Tripoli, Substitute for	Membrane
Trisodium Phosphate, Substitute	Paper 14
Trisodium Phosphate, Substitute for577 Tritolyl Phosphate, Substitute for 577	Pipe270
Tritolyl Phosphate, Substitute for .577	Shoes 10
Tung Oil, Substitute for577, 578	Water-Repellent. See Waterproof-
Type Metal, Reclaiming253	ing
Typewriter Ribbon Ink165	Water Softener540
	System, Rust Inhibitor for241
V	Wax Adhesive       24         Bright-Drying       397, 402
77 17	Bright-Drying397, 402
Varnish	Carving
Baking	Coppler's Inread
Bodying	Dental
Congo315   Exterior Spar319	Emulsion
	Floor (goo also Polishes)
Four Hour	Floor (see also Polishes) 11

	140
Wax—Continued       12         Grafting       443         Impression       442         Insulating       444         Jeweler's       444         Nail       50         Non-Blocking, Hot Melt       442         Non-Oxidizing       442         Polishes. See Polishes       11         Self Polishing       397         Slow Burning       442         Sticky Non-Oxidizing       442         Synthetic       422         Weathered Wood Effect       322         Weed Killers       95         Weighting       4         Weighting, Textile       521         Welding, Bronze to Iron       248         Flux       247         Rod, Brass       248         Rod Coating, Steel       249         Rod, Copper       248         Tip Alloy       250	Wood, Artificial       .440         Finishes       .322         Flour, Molded       .441         Post Preservation       .188         Preservative       .331         Wool, Chlorinating       .523         Grease Substitute       .186         Immunized       .523         Non-Felting       .523         Non-Shrinking       .523         Wrinkle Finish       .321         X       X         X-Ray Meal, Barium       .76         Y       Yeast Binder       .73         Yeast, Improved       .126         Yeast Nutrient       .538         Z       Z         Zein, Substitute for       .578         230
Tip Alloy       230         Wheel Cases, Pyrotechnic       423         Whitewash, Disinfectant       262         Waterproof       261         Window Cleaning       481         Protection, Air Raid       536         Wine, Cornmeal       32         Grape       32         Mint       32	Zinc Coating Iron

### USEFUL REFERENCE BOOKS \*

VARNISH MAKING Symposium PLASTIC MOULDING D. A. Dearle PLASTICS IN INDUSTRY Plastes MAKING AND MOULDING OF PLASTICS. L. M. T. Bell RUBBER AND ITS USE H. L. Fisher RUBBER LATEX H. P. and W. H. Stevens FOOD MANUFACTURING S. Blumenthal	3.00 6.00 4.00 5.00 5.00 2.25 2.00 7.50
PRINCIPLES AND PROCESSES OF LIGHT LEATHER MANUFACTURE	$6.50 \\ 4.25$
CLEANERS . W. D. John COSMETIC FORMULARY . H. Bennett DRUG AND SPECIALTY FORMULAS . E. J. Belanger HAIR DYES AND HAIR DYEING . H. S. Redgrove and J. Bari-Wools BASIC LABORATORY PRACTICE . N. C. Sprague VEGETABLE DYES . E. M. Mariet PRACTICAL EMULSIONS . H. Bennett . EMBALMING FLUIDS . S. Mendelsohn CASEIN AND ITS USES . H. Hadert	4.25 3.75 6.00 5.00 3.50 2.00 5.00 4.00 3.00 10.00 2.50
CATIONS	3.25 5.00 2.00
GLUE AND GELATIN	2.25 4.00 1.25 3.75 4.00 4.00 3.75 5.00
* These and other technical books may be obtained from The Chemical 1	Pub-

\* These and other technical books may be obtained from The Chemical Publishing Co., Inc., Brooklyn, N. Y., U.S.A.

and the second of the second contract of the	